

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**


Sealed items rate tender on form 6&8 are invited by the Executive Engineer HPPWD Kotla Behar Division Kotla Behar for the following works from the approved and eligible contractors enlisted with HPPWD Department so as to reach in this office on dated 6.9.2023 up to 10.30AM and the same will be opened on the same day at 11.30 AM in the presence of contractors /firms or their authorized representative. The application for purchase of tender forms will be received up to 2.00 PM on dated 5.9.2023 and tender forms can be obtained from this office against cash payment (nonrefundable) on 4.9.2023 from 10.00 AM to 2.00 PM and no tender form shall be issued by the post. The amount of earnest money in shape of FDR of any nationalized bank in HP duly pledged in the Name of Executive Engineer HPPWD Kotla Behar Division Kotla Behar

The conditional tender and tender received without earnest money (FDR) will be rejected and if holiday declared by the Govt. on the above date due to any reasons the tender shall be received and opened on the next working day. The undersigned reserved the right to rejected tender without assigned any reasons, .

Sr No	Name of work	Estimated cost	Earnest money	Time Limit	Cost of tender form	Form No
1	Repair & Maintenance on Muhin Suhin Road (SH:- Repair of pot holes in between km 0/0 to 1/00 ,1/00 to 2/00 & 2/00 to 2/090)	424699	9000	One Month	350	6&8
2	Repair & Maintenance on Muhin Suhin Road (SH:- Repair of pot holes in between km 2/090 to 2/190,2/190 to 2/290 & 2/290 to 3/00	324173	6000	One Month	350	6&8
3	Repair & Maintenance on Pir Saluhi to Nouri Road (SH:- Repair of Pot holes in between km 3/00 to 4/00	302316	6000	One Month	350	6&8
4	Repair & Maintenance on Harpukhar to Chanouta Road (SH:- Repair of pot holes in between km 3/00 to 4/00 & 6/00 to 7/00	415316	8000	One Month	350	6&8
5	Repair & Maintenance on Kaloha to Lahari Nichali (SH:- Repair of pot holes in between km 0/0 to 2/00	302316	6000	One Month	350	6&8
6	Repair & maintenance on Rakkar Chaplah Upper Bharoli Tikkar Shantla Road (SH:- Repair of pot holes in between km 7/00 to 8/00)	296089	6000	One Month	350	6&8
7	Repair & maintenance on nakki Khad to garli Road (SH:- Repair of pot holes in between km 0/00 to 0/870)	333263	6000	One Month	350	6&8
8	Repair & maintenance on Chalali to sukhra Road (SH:- Repair of pot holes in between km 0/0 to 2/150	444754	9000	One Month	350	6&8
9	Repair & maintenance on Kaloha Pragpur Dhaliara Dada Siba Sansarpur Terrace Road (SH:- Repair of pot holes in between km 31/200 to 33/200	495710	10000	One Month	350	6&8
10	Repair & maintenance on Saw Mil to Village Gurnawar km 0/0 to 3/0 (SH:- Repair of pot holes in between km 2/0 to 3/0	266255	5000	One Month	350	6&8
11	Repair & maintenance on Karoo to Tiamal Road km 0/0 to 3/500 Km 0/0 to 2/160 (SH:- Repair of pot holes in between km 0/0 to 2/600	282060	6000	One Month	350	6&8
12	Repair & maintenance on Swan Khad to Kahanpur Km	226445	5000	One Month	350	6&8

	0/0 to 3/500 (SH:- :- Repair of pot holes in between km 2/0 to 3/0					
13	Repair & maintenance on Balgahr Chatwal landiara Road km 0/0 to 4/250 (SH:- :- Repair of pot holes in between km 0/0 to 4/0	315050	6000	One Month	350	6&8
14	Repair & maintenance on Kotla Bassi Malot Seul Road km 2/0 to 6/825 (SH:- :- Repair of pot holes in between km 2/0 to 4/0	298800	6000	One Month	350	6&8
15	Repair & maintenance on Kaloha Pragpur Dhaliara Dada siba Sansarpur Terrace Road (section Terrace) (SH:- :- Repair of pot holes in between km 33/200 to 60/920	333210	6000	One Month	350	6&8
16	Restoration of Rain Damage on Various Road Under HPPWD Sub Division Pragpur (SH:- Painting and writing of sign board ,km stone, culverts Rain shelters ect	484025	10000	Three Month	350	6&8

1) Certified that tender of above works are being called in Exigency of public interest ,


Executive Engineer,
Kotla Behar Division HPPWD.,
Kotla Behar


NO.PWD/KB/CB/TENDER 2023-24 2362-66 DATED 23/8/2023

Copy to the F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla -2 for favour of information please.

Copy to the Engineer-in-Chief HPPWD Shimla for information please.

Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of information please.

Copy to the Superintending Engineer 9th Circle HPPWD Nurpur for favour of information please.


Executive Engineer,
Kotla Behar Division HPPWD.,
Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO. 1
Estimate Cost :- Rs. 4,24,699/-
Earnest Money :-Rs. 9000/-
Time Limit :-One Months.

Name of work :- Repair & Maintenance on Muhin Suhin road (SH: Repair of Pot Holes in between Km. 0/00 to 1/00 , 1/00 to 2/000 & 2/00 to 2/090)

Sr. No.	Description of Item	Quantity	Rate in		Unit	A
			Figures	Words		
1	Providing laying, spreading by manual/mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, stone aggregates of Grading-III, 53mm to 22.4mm (fifty three to twenty two point four millimetre) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (eighty to hundred) kN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	5.13 Cubic Metre			Per Cubic Metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	1279.14 Square meter			* Per square meter	
TOTAL						

Executive Eng
Kotla Behar D
HPWD, Kota

SCHEDULE OF QUANTITY

JOB NO. 2
Estimate Cost :- Rs. 3,24,173/-
Earnest Money :-Rs. 6000/-
Time Limit :-One Months.

Name of work:- Repair & Maintenance on Muhin Suhin road (SH: Repair of Pot Holes in between Km. 2/090 to 2/190 , 2/190 to 2/290 & 2/290 to 3/00)

Sr. No.	Description of Item	Quantity	Rate in		Unit	A
			Figures	Words		
1	Providing laying, spreading by manual/mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, stone aggregates of Grading-II, 53mm to 22.4mm (fifty three to twenty two point four millimetre) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (eighty to hundred) kN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	10.78 Cubic Metre			Per Cubic Metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1504.2, 503 and 508.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	939.41 Square meter			Per square meter	
TOTAL						

SCHEDULE OF QUANTITY

JOB NO. 3
Estimate Cost :- Rs. 3,02,316/-
Earnest Money :- Rs. 6000/-
Time Limit :- One Months.

Name of work:- Repair & Maintenance on Pir saluhi to Nouri road (SH: Repair of Pot Holes in between Km. 3/00 to 4/00)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Ar
			Figures	Words		
1	Providing laying, spreading by manual/mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, stone aggregates of Grading-III, 53mm to 22.4mm (fifty three to twenty two point four millimetre) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (eighty to hundred) kN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	13.32 Cubic Metre			Per Cubic Metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1, and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	858.48 Square meter			Per square meter	
TOTAL						

SCHEDULE OF QUANTITY

Name of work:- Repair & Maintenance on Harpukhar to Chanouta road (SH: Repair of Pot Holes in between Km. 3/00 to 4/00 & 6/00 to 7/00)

JOB NO. 4
Estimate Cost :- Rs. 4,15,316/-
Earnest Money :-Rs. 8000/-
Time Limit :-One Months.

Sr. No.	Description of Item	Quantity	Rate in		Unit	
			Figures	Words		
1	Providing laying, spreading by manual/mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, stone aggregates of Grading-II, 53mm to 22.4mm (fifty three to twenty two point four millimetre) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (eighty to hundred) kN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	8.95 Cubic Metre			Per Cubic Metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1504.2, 503 and 508.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	1229.70 Square meter			Per square meter	
TOTAL						


Executive Engineer
Kota Behar District
HPPWD Kota

SCHEDULE OF QUANTITY

Name of work:- Repair & Maintenance on Kaloha to Lohari Nichli (SH: Repair of Pot Holes in between Km. 0/0 to 2/00)

Sr. No.	Description of Item	Quantity	Rate in		Unit	A
			Figures	Words		
1	Providing laying, spreading by manual/mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, stone aggregates of Grading-III, 53mm to 22.4mm (fifty three to twenty two point four millimetre) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (eighty to hundred) kN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals.	13.32 Cubic Metre			Per Cubic Metre	
2	The rate is including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1. and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	858.48 Square meter			Per square meter	
TOTAL						

SCHEDULE OF QUANTITY

Name of work:- Repair & Maintenance on Rakkar Chaplah Upper Bharoli Tikkar Shantla road (SH: Repair of Pot Holes in between Km. 7/00 to 8/00)

JOB NO. 6
Estimate Cost :- Rs. 2,96,089
Earnest Money :-Rs. 6000/-
Time Limit :-One Months.

Sr. No.	Description of Item	Quantity	Rate in		Unit
			Figures	Words	
1	Providing laying, spreading by manual/mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, stone aggregates of Grading-III, 53mm to 22.4mm (fifty three to twenty two point four millimetre) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (eighty to hundred) kN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	20.75 Cubic Metre			Per Cubic Metre
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1. and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	799.31 Square meter			Per square meter
TOTAL					

SCHEDULE OF QUANTITY**Name of work:- Repair & Maintenance on Nakki Khad to Garli road (SH: Repair of Pot Holes in between Km. 0/00 to 0/870)**

Sr. No.	Description of Item	Quantity	Rate in		Unit	Am
			Figures	Words		
1	Providing laying, spreading by manual/mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, stone aggregates of Grading-III, 53mm to 22.4mm (fifty three to twenty two point four millimeter) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (eighty to hundred) KN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two millimeter) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals.	4.92 Cubic Metre			Per Cubic Metre	
2	The rate is including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimeter) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	998.90 Square meter			Per square meter	
TOTAL						

SCHEDULE OF QUANTITY

Name of work:- Repair & Maintenance on Chalali to Sukhar road (SH: Repair of Pot Holes in between Km. 0/00 to 2/150)

JOB NO. 8
Estimate Cost :- Rs. 4,44,754/-
Earnest Money :- Rs. 9000/-
Time Limit :- One Months.

Sr. No.	Description of Item	Quantity	Rate in		Unit
			Figures	Words	
1	Providing laying, spreading by manual/mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, stone aggregates of Grading-III, 53mm to 22.4mm (fifty three to twenty two point four millimetre) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (eighty to hundred) kN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.49 Cubic Metre			Per Cubic Metre
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	1349.68 Square meter			Per square meter
TOTAL					

Executive Eng
Kotla Behar D
HP&WD Kotla

SCHEDULE OF QUANTITY

JOB NO. 9
Estimate Cost :- Rs. 4,95,710/-
Earnest Money :- Rs. 10000/-
Time Limit :- One Months.

Name of work:- Repair & Maintenance on Kaloha Pragpur Dhaliara Dada siba Sansarpur Terrace road (SH:- Repair of Pot Holes in between Km. 31/200 to 33/200)

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing laying, spreading by manual/mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, stone aggregates of Grading-II, 53mm to 22.4mm (fifty three to twenty two point four millimeter) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (eighty to hundred) KN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two millimeter) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-II as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government	5.62 Cubic Metre			Per Cubic Metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimeter) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1. and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government	1495.00 Square meter			Per square meter	
TOTAL						


Executive Engineer
Kotla Behar Division
HPPWD Kotla Behar

SCHEDULE OF QUANTITY

JOB NO. 10
Estimate Cost :- Rs. 2,66,25/-
Earnest Money :-Rs. 5000/-
Time Limit :-One Months.

Name of work:- Repair & Maintenance on Saw Mill to Village Gurnawar Km. 0/0 to 3/0 (SH: Repair of Pot Holes in between Km. 2/0 to 3/0)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing laying, spreading by manual/mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, stone aggregates of Grading-III, 53mm to 22.4mm (fifty three to twenty two point four millimetre) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (eighty to hundred) kN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.76 Cubic Metre			Per Cubic Metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1, and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	799.00 Square meter			Per square meter	
TOTAL						


Executive Engineer
Kotla Behar Div
HPPWD Kotla E

SCHEDULE OF QUANTITY

JOB NO. 11
Estimate Cost :- Rs. 2,82,060/-
Earnest Money :-Rs. 6000/-
Time Limit :-One Months.

Name of work:- Repair & Maintenance on Swan Khad to Kahanpur Km. 0/0 to 2/160 (SH: Repair of Pot Holes in between Km. 0/0 to 2/600)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing laying, spreading by manual/mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, stone aggregates of Grading-III, 53mm to 22.4mm (fifty three to twenty two point four millimetre) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (eighty to hundred) kN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals.	3.32 Cubic Metre			Per Cubic Metre	
2	The rate is including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	850.00 Square meter			Per square meter	
TOTAL						


Executive Engineer
Kota Behar Division
RRWD Kota Behar

SCHEDULE OF QUANTITY

Name of work:- Repair & Maintenance on Karoo to Tiamal road Km. 0/0 to 3/500 (SH: Repair of Pot Holes in between Km. 2/0 to 3/0)

JOB NO. 12
Estimate Cost :- Rs. 2,26,445/-
Earnest Money :- Rs. 5000/-
Time Limit :- One Months.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Rate
			Figures	Words		
1	Providing laying, spreading by manual/mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, stone aggregates of Grading-III, 53mm to 22.4mm (fifty three to twenty two point four millimeter) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (eighty to hundred) kN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two millimeter) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government	4.04 Cubic Metre			Per Cubic Metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimeter) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government	675.00 Square meter			Per square meter	
TOTAL						

Executive Eng
Kotla Behar D
HPRWD Kotla

SCHEDULE OF QUANTITY

JOB NO. 13
Estimate Cost :- Rs. 3,15,050/-
Earnest Money :-Rs. 6000/-
Time Limit :-One Months.

Sr. No.	Description of item	Quantity	Rate in		Unit	Am
			Figures	Words		
1	Providing laying, spreading by manual/mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, stone aggregates of Grading-III, 53mm to 22.4mm (fifty three to twenty two point four millimetre) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (eighty to hundred) KN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals.	3.60 Cubic Metre			Per Cubic Metre	
2	The rate is including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	950.00 Square meter			Per square meter	
TOTAL						

Executive Engineer
Kotta Behar Division
HPPWD Kotta Behar

SCHEDULE OF QUANTITY

Name of work:- Repair & Maintenance on Kotla Bassi Malot Seul road Km. 2/0 to 6/825 (SH: Repair of Pot Holes in between Km. 2/0 to 4/0)

JOB NO. 14
Estimate Cost :- Rs. 2,98,800/-
Earnest Money :-Rs. 6000/-
Time Limit :-One Months.

Sr. No.	Description of Item	Quantity	Rate in		Unit	A
			Figures	Words		
1	Providing laying, spreading by manual/mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, stone aggregates of Grading-II, 53mm to 22.4mm (fifty three to twenty two point four millimeter) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (eighty to hundred) kN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two millimeter) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.60 Cubic Metre			Per Cubic Metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimeter) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	900.00 Square meter			Per square meter	
TOTAL						

Executive Eng
Kotla Behar D
HPPWD-Kotla

SCHEDULE OF QUANTITY

Name of work:- Repair & Maintenance on Kaloha Pragpur Dhaliara Dada siba Sansarpur Terrace road (Section Terrace) (SH: Repair of Pot Holes in between 33/200 to 60/920)

JOB NO. 15
Estimate Cost :- Rs. 3,33,210/-
Earnest Money :- Rs. 6000/-
Time Limit :- One Months.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing laying, spreading by manual/mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, stone aggregates of Grading-II, 53mm to 22.4mm (fifty three to twenty two point four millimeter) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (eighty to hundred) KN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two millimeter) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	5.62 Cubic Metre			Per Cubic Metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	995.00 Square meter			Per square meter	
TOTAL						

Executive Engg
Kotla Behar Di
HPPWBD-Kotla

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on various roads under the HP PWD Sub Division Pragpur (SH: Painting and writing of sign board, km. stones, c, Rain Shelters etc.).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Am
			Figures	Words		
1	Removing old paint from Steel and other metal surfaces & making the surface even With paint remover of approved brand and manufacture as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	80.00 Square metre			Per Square metre	
2	Painting one coat (excluding priming coat) on previously painted steel and other metal surfaces with white enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	80.00 Square metre			Per Square metre	
3	Extra over item number 2 (Two) for Painting every subsequent coat on previously painted steel and other metal surfaces with white enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	80.00 Square metre			Per Square metre	
4	Painting one coat (excluding priming coat) on previously painted concrete/masonry/plastered surface with white paint for use on floors to give an even shade including cleaning the surface of all dirt, dust and other foreign matter and sand papering as required as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	160.00 Square metre			Per Square metre	
5	Extra over item number 4 (Four) for Painting every subsequent coat previously painted concrete/masonry/plastered surface with white paint for use on floors to give an even shade including cleaning the surface of all dirt, dust and other foreign matter and sand papering as required as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	160.00 Square metre			Per Square metre	
6	Writing Indian letters or figures on any surface with black japan paint (stops, commas, hyphens and the like not to be measured and paid separately) as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	202193.00 per cm height			Per letter per centimetre height	
7	Painting index hands normal size or arrows on any surface with Black Japan as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	103.00 Figure			Per figure	
	TOTAL					