



Office of
EXECUTIVE ENGINEER (KULLU DIVISION)
H.P. PUBLIC WORKS DEPARTMENT, KULLU-175101
FAX: 01902-222571, E.mail. ee-kul2-hp@nic.in

No.PW/KD/TA/Tender/2023-2024-

7078-85

Dated:- 26-7-2023

To

The Executive Engineer, I.T. Cell,
Nigam Bihar Shimla-2.

Subject:- Publishing of Notice inviting tender.

Enclosed please find herewith copies of notice inviting tender for the up loading on department website 07.08.2023 as per notification issued by Secretary (PW) to the Govt. of HP Shimla vide letter No.PBW(S)A(3)1/2020 dated 16.07.2021. As per works mentioned in the Tender Notice is urgent nature of work in the public interest.


DA/As above.


**Executive Engineer,
Kullu Division,
HP. PWD, Kullu.**

Copy alongwith notice inviting tender is forwarded to the following for information and necessary action.

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, (MZ) HP.PWD, Mandi.
3. Superintending Engineer, 6th Circle HP.PWD, Kullu.
4. Supdt./DAO/HDM of this office.
5. Notice Board.

DA/Nil.


**Executive Engineer,
Kullu Division,
HP. PWD, Kullu.**

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

The Executive Engineer, Kullu Division HP.PWD, Kullu on behalf of the Government of Himachal Pradesh invites the **offline tender i.e. on percentage rates** for the following works from the eligible contractors/Firms registered with HP.PWD, department, so as to reach in the office as per time schedule given below:-

1	Date of receipt of application for tender form.	05.08.2023 upto 4:00 PM			
2	Date of issue/sale of tender form.	05.08.2023 upto 4:00 PM			
3	Date of receipt of tender.	07.08.2023 upto 10:30 PM			
4	Date of opening tender.	07.08.2023 upto 11:00 AM			
Sr. No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	2	3	4	5	6
1	A/R and M/O General pooled accommodation (SH:- Providing and fixing various sanitary accessories in various residential building under General pooled accommodation).	89,271/-	2,000/-	Two months	350/-
2	Restoration of rain damage Badah Pahnallan road to Shillihar Km. 0/0 to 19/700 (SH:-Removal of slips in various RDs).	4,97,373/-	10,000/-	One month	350/-
3	Restoration of rain damages on Shat Sub Division HP.PWD, (SH:- Hiring of Tipper for carriage of slips/muck/debries at various roads under (Jari Section) Job No.1.	1,39,800/-	3,000/-	Two months	350/-
4	Restoration of rain damages on Bhunter Manikaran road Km.1/610 to 35/110 (SH:- Removal of slips in various RDs (Jari Section) Job No.1.	4,95,046/-	10,000/-	One month	350/-
5	Restoration of rain damages on Bhunter Manikaran road Km.1/610 to 35/110 (SH:- Removal of slips in various RDs (Jari Section) Job No.2.	4,86,702/-	10,000/-	One month	350/-
6	Restoration of rain damages on Bhunter Manikaran road Km.1/610 to 35/110 (SH:- Removal of slips in various RDs (Jari Section) Job No.3.	4,86,702/-	10,000/-	One month	350/-
7	Restoration of rain damages on Shat Sub Division HP.PWD, (SH:- Hiring of Tipper of carriage of slips/muck/debries at various roads under (Manikaran Section) Job No.1.	1,39,800/-	3,000/-	One month	350/-
8	Restoration of rain damages on Shat Sub Division HP.PWD(SH:- Hiring of Tipper of carriage of slips/muck/debries at various roads under (Manikaran Section) Job No.2.	1,39,800/-	3,000/-	One month	350/-
9	Restoration of rain damages on Bhunter Manikaran road Km. 1/610 to 35/110 (SH:- Removal of slips in various RDs) (Manikaran Section) Jon No.3.	4,97,961/-	10,000/-	One month	350/-
10	Restoration of rain damages on Bhunter Manikaran road Km.1/610 to 35/110 (SH:- Removal of slips in various RDs (Manikaran Section) Job No.1.	4,97,348/-	10,000/-	One month	350/-
11	Restoration of rain damages on Bhunter Manikaran road Km.1/610 to 35/110 (SH:- Removal of slips in various RDs (Manikaran Section) Job No.2.	4,97,961/-	10,000/-	One month	350/-

4

12	Restoration of rain damages on Bhunter Manikaran road Km.1/610 to 35/110 (SH:- Removal of slips in various RDs (Hathithan Section) Job No.1.	4,81,673/-	10,000/-	One month	350/-
13	Restoration of rain damages on Bhunter Manikaran road Km.1/610 to 35/110 (SH:- Removal of slips in various RDs (Hathithan Section) Job No.2.	4,94,170/-	10,000/-	One month	350/-
14	Restoration of rain damages on Bhunter Manikaran road Km.1/610 to 35/110 (SH:- Removal of slips in various RDs (Hathithan Section) Job No.3.	4,97,348/-	10,000/-	One month	350/-
15	Restoration of rain damages on Shat Sub Division HP.PWD, (SH:- Hiring of Tipper for carriage of slips/Muck/debries at various roads under (Jari Section) Job No.2.	1,39,800/-	3,000/-	Two months	350/-
16	Restoration of rain damages on Shat Sub Division HP.PWD, (SH:- Hiring of Tipper for carriage of slips/Muck/debries at various roads under (Hathithan Section) Job No.1.	1,39,800/-	3,000/-	Two months	350/-
17	Restoration of rain damages on Shat Sub Division HP.PWD, (SH:- Hiring of Tipper for carriage of slips/Muck/debries at various roads under (Hathithan Section) Job No.2.	1,39,800/-	3,000/-	Two months	350/-
18	Restoration of rain damages on Buins Bai Bhulang road Km. 0/00 to 11/020 (SH:- Construction of Retaining wall at Km. 8/660 to 8/670).	3,38,358/-	6,800/-	Three months	350/-
19	Restoration of rain damages on Buins Bai Bhulang road Km. 0/00 to 11/020 (SH:- Construction of Retaining wall at Km. 9/720 to 9/732.5).	4,16,774/-	8,400/-	Three months	350/-
20	Restoration of rain damages on Buins Bai Bhulang road Km. 0/00 to 11/020 (SH:- Construction of Retaining wall at Km. 5/580 to 5/592.50).	4,24,986/-	8,500/-	Three months	350/-
21	Restoration of rain damages on Buins Bai Bhulang road Km. 0/00 to 11/020 (SH:- Construction of Retaining wall at Km. 9/775 to 9/787.50).	4,24,604/-	5,800/-	Three months	350/-
22	Restoration of rain damages on Darka Bhumteer road Km. 0/00 to 7/500 (SH:- Construction of Retaining wall at RD 1/585 to 1/598.75).	4,93,339/-	10,000/-	Three months	350/-
23	Restoration of rain damages on Bailey Bridge near Rambag Kullu (SH:- Construction of PCC Retaining wall for approach for Highwar side (Valley Side) Job No.1.	3,53,775/-	7,100/-	Three months	350/-
24	Restoration of rain damages on Bailey Bridge near Rambag Kullu (SH:- Construction of PCC Retaining wall for approach for Highwar side (Valley Side) Job No.2.	3,82,696/-	7,700/-	Three months	350/-

3

25	Restoration of rain damages on Bailey Bridge near Rambag Kullu (SH:- Construction of PCC Retaining wall for approach for Rambag Side (Hill Side) Job No.1.	3,55,877/-	7,200/-	Three months	350/-
26	Restoration of rain damages on Bailey Bridge near Rambag Kullu (SH:- Construction of PCC Retaining wall for approach for Rambag Side (Hill Side) Job No.2.	3,84,972/-	7,700/-	Three months	350/-
27	Restoration of rain damages on Darka Bhumteer road Km. 0/00 to 7/500 (SH:- Construction of Retaining wall at RD 1/598.75 to 1/612.50).	4,94,566/-	10,000/-	Three months	350/-
28	A/R and M/O Non Residential building at Kullu (SH:- Construction of additional office in replacement of store room at GF of Sub Division office at Kullu).	1,36,128/-	3,000/-	Two months	350/-
29	Restoration of rain damages on Dohranallah Kharihar road (SH:- C/O R/wall on Pushta at RD 2/070 to 2/084).	4,85,993/-	9,800/-	Two months	350/-
30	Restoration of flush flood damages to Duff Dumber Bridge at Bhunter (SH:- C/O wire crates for protection work).	4,78,502/-	9,600/-	Two months	350/-
31	Restoration of rain damages on Dohranallah Kharihar road Km. 0/0 to 10/120 (SH:-C/O R/wall on Pushta at RD 2/509 to 2/518).	4,91,283/-	9,900/-	Two months	350/-
32	RRD on Chharour Nallah to Kashawari road Km. 0/0 to 8/010 (SH:- C/O R/wall with PCC Toe wall at RD 0/280 to 0/290).	4,66,427/-	9,400/-	Two months	350/-
33	Restoration of rain damages on Dohranallah Kharihar road (SH:- C/O R/wall on Pushta wall at RD 2/084 to 2/098).	4,86,079/-	9,800/-	Two months	350/-
34	Restoration of rain damages on Dohranallah Kharihar road Km. 0/0 to 10/120 (SH:- C/O R/wall on Pushta wall at RD 2/518 to 2/527).	4,89,552/-	9,800/-	Two months	350/-
35	Restoration of rain damages on Badah Pahnallah road Km. 0/0 to 9/700 (SH:- C/O R/wall on Pushta wall at RD 6/760 to 6/780).	4,53,139/-	9,100/-	Two months	350/-
36	Restoration of rain damages on Dohranallah Barahar road Km. 0/0 to 10/120 (SH:- C/O R/wall at RD 4/560 to 4/580).	4,55,745/-	9,200/-	Two months	350/-
37	RRD on Kullu Karon road Km. 0/00 to 4/500 (SH:-C/O R/wall at RD 6/955 to 6/973).	4,99,563/-	10,000/-	Two months	350/-
38	Restoration of rain damages Bari Padhru Tharku Pechha road (SH:- C/O R/wall at RD 1/710 to 1/725).	4,67,749/-	9,400/-	Two months	350/-
39	Restoration of rain damages Bari Padhru Tharku Pechha road (SH:- C/O R/wall at RD 0/410 to 0/420 and 0/430 to 0/440).	4,54,971/-	9,100/-	Two months	350/-
40	A/R and M/O General Pooled accommodation (SH:- Painting, distempering & P/I tiles in Type-I qtr. No.5 in LIG colony near pooled accommodation Kullu).	3,02,982/-	6,100/-	Two months	350/-

2

The tender documents shall be issued only to those contractor/firm who fulfill the following documents with the application.

1	The valid enlistment/Registration of contractor in Appropriate Class.
2	Permanent account No. (PAN No.).
3	G.S.T. No.
4	Earnest Money in the shape of National Saving certificate/time deposit account in the any of the post office in HP F.D.R. from any Nationalized Bank duly pleaded in favour of the Executive Engineer, Kullu Division HP.PWD, Kullu.
5	The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
6	The offer of the tender shall remain valid upto 90 days after the opening of tender.
7	Ambiguous/telephonic conditional tenders of tender by fax/E-mail not be considered and will be summarily be rejected.
8	Executive Engineer, reserve the right to reject or cancel any or all tenders without assigning any reasons.
9	If the date given above happens to be holiday the same shall be processed on next working day.
0	The contractor/firm must quote their rates in words as well as in figures failing which XEN reserve the right to accept/reject any or all tenders.
11	The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12	One contractor shall not have more than two major works in hand at a time.
13	Work should be completed by the contractor within stipulated period.
14	The rates beyond over +5% will be rejected, besides this the Additional Performance security will have to borne @ 20% & 30% for unbalanced bid in case rates is lower than 10% but upto 20% & lower than 20% upto 30% respectively. The tender beyond the limit of -30% will also be excepted.

**Executive Engineer,
Kullu Division,
HP.PWD, Kullu.**

Dated:- 26-7-2023

No.PW/KD/TA/2023-2024-

Copy is forwarded to the following for information and necessary action:-

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, (MZ) HP.PWD, Mandi.
3. Superintending Engineer, 6th Circle HP.PWD, Kullu.
4. All the Executive Engineers, in HP.PWD,.
5. All the Assistant Engineers, working under this Division.
6. All the registered contractors, in HP.PWD.
7. Supdt./DA/HDM of this office.
8. Notice Board.

**Executive Engineer,
Kullu Division,
HP.PWD, Kullu.**

CERTIFICATE

It is certified that the above works are required to be carried out immediately being emergent nature of work in the public interest.


**Executive Engineer,
Kullu Division, 
HP.PWD,  Kullu.**

Estimated cost:-Rs. 89271.00
 Earnest money :- Rs. 2000.00
 Time :-Two months

DRAFT SCHEDULE OF QUANTITY

Name of work :-A/R & M/O General pooled accommodation. (SH:-Providing and fixing various sanitary accessories in various residential building under General pooled accommodation.

Sr. No.	Description of item	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing and fixing PTMT coloured/white high density polyethylene / poly propylene 10 litres capacity (full flush) European standard control low level flushing cistern with fittings with a pair of brackets with fittings such as lead valve, syphon, 15mm nominal size PVC ball valve with polythene float, with push button, couplings for connections with inlet, outlet and over flow pipe, 40mm (forty millimetre) dia C.P. flush bend including cutting holes in walls and making good the same and connecting the flush bend with cistern and closet (overflow pipe to be measured and paid for separately) within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge.	10.00	1010.80	Rupees thousand ten and paise eighty only	Each	10108.00
2	Providing and fixing solid plastic seat with lid for pedestal type W.C. pan complete within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge.	8.00	1105.10	Rupees thousand hundred five and paise ten only	Each	8841.00
3	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour 15 mm(fifteen millimetre) nominal bore with 45 cm length within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge.	20.00	147.00	Rupees one hundred forty seven and paise zero only	Each	2940.00

4	Providing and fixing 3 (three) layer PP-R (Poly propylene Random copolymer) pipes conforming to IS:15801, UV stabilized & anti - microbial fusion welded, having thermal stability for hot & cold water supply, including all PP - R plain & brass threaded polypropylene random fittings, i/c fixing the pipe with clamps at 1.00 m(one metre) spacing. This includes the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer-in-Charge) PN - 16 Pipe, 20mm (twenty millimetre)OD (SDR-7.4 within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge.	18.00	466.60	Rupees four hundred sixty six and paise sixty only	Running metre	8399.00
5	Providing and fixing PTMT jet spray of approved quality and colour with one metre tube pipe with necessary fitting etc. complete within all leads and lifts and other incidentals including carriage of materials in all respect and as per direction of Engineer-in-charge.	10.00	990.12	Rupees one hundred ninety and paise twelve only	Each	9901.00
6	Providing and fixing 100 mm(one hundred millimetre) dia chromium plated grating of superior quality for floor, gully or nahani trap within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge.	4.00	132.75	Rupees one hundred thirty two and paise seventy five only	Each	531.00
7	Providing and fixing CP brass angle valve 15mm (fifteen millimetre) without Nuts and pipe within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge.	15.00	900.25	Rupees nine hundred and paise twenty five only	Each	13504.00
8	Providing and fixing bright finished brass handles with screws etc. complete: 125 mm(one hundred twenty five millimetre) within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge.	5.00	172.70	Rupees one hundred seventy two and paise seventy only	Each	864.00
9	Providing and fixing bright finished brass tower bolts (barrel type) with necessary screws etc. complete : 150x10 mm(one hundred fifty millimetre x ten millimetre) within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge.	15.00	147.90	Rupees one hundred forty seven and paise ninety only	Each	2219.00
10	Providing and fixing brass bib tap (Superior or heavy type) 15mm dia long nose within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge.	15.00	937.15	Rupees one hundred thirty seven and paise fifteen only	Each	14057.00

11	Providing and fixing C.P. soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm (seventy five millimetre) with concealed fitting arrangements, weighing not less than 106 gms.within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge.	3.00	477.40	Rupees four hundred seventy seven and paise forty only	Each	1432.00
12	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg (thirty fivoe kilogramme)and door width upto 700 mm(seven hundred), with necessary accessories and screws etc. complete.within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge.	10.00	1647.45	Rupees one hundred six hundred forty seven and paise forty five only	Each	16475.00
					Total	89271


 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu

Estimated cost:-497373.00
 Earnest money :10000.00
 Time :-one month

DRAFT SCHEDULE OF QUANTITY

/Name of work:- Restoration of rain damages on Badha Pahnallah road to shillihar km. 0/0 to 19/700
 (SH:- Removal of slips in various Rds

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials upto any and any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3975.80	125.10	Rupees One hundred twenty five and paise ten only.	Per cubic metre	497373.00
					Total	497373.00


 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu.

Estimated cost:-139800.00
 Earnest money :-3000.00
 Time :- Two months.

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Shat Sub Division HPPWD
 (SH):- Hiring of Tipper for carriage of slips/Muck/debries at various roads under (Jari) section Job No-I

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Hiring of tipper in good condition of minimum 4.00 cubic metre carriage capacity on daily basis from 9.00 AM to 5.00 PM with hydraulic facility , jack facility for Carriage of slips and disposal of same at suitable dumping places including P.O.L. charges and wages of driver and other operational staff as per the direction and entire satisfaction of Engineer-in-charge.	60	2330.00	Rupees Two thousand three hundred thirty and paise zero only.	Per days	139800.00
	Conditions					
	1) The cost of P.O.L. will be borne by the contractor/ owner of the vehicle/ machine at his own cost.					
	2) The repair etc. will be got done by the contractor at his own cost.					
					Total:-	139800.00

Executive Engineer,
 Kullu Division,
 HP.PWD Kullu.

Estimated cost:-495046.00
Earnest money :10000.00
Time :-one month

DRAFT SCHEDULE OF QUANTITY

/Name of work:- Restoration of rain damages on Bhunter manikaran road km. 1/610 to 35/110
(SH:- Removal of slips in various Rds (Jari section) Job No.--I

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials upto any and any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3957.20	125.10	Rupees One hundred twenty five and paise ten only.	Per cubic metre	495046.00
					Total	495046.00


Executive Engineer,
Kullu Division
HP.PWD Kullu

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-486702.00

Earnest money :10000.00

Time :one month

/Name of work:- Restoration of rain damages on Bhunter manikaran road km.1/610 to 35/110

(SH:- Removal of slips in various Rd's (Jari section) Job No.--II

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials upto any and any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3890.50	125.10	Rupees One hundred twenty five and paise ten only.	Per cubic metre	486702.00
					Total	486702.00

Executive Engineer,
Kullu Division ,
HP.PWD Kullu.

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-486702.00
Earnest money :10000.00
Time :-one month

Name of work:- Restoration of rain damages on Bhunter manikaran road km. 1/610 to 35/110
(SH:- Removal of slips in various Rds (Jari section) Job No.-III

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials upto any and any lead as per technical specification 302.3.5 and 16-11 within all leads and lift of materials and as per direction of Engineer-in-charge.	3890.50	125.10	Rupees One hundred twenty five and paise ten only.	Per cubic metre	486702.00
					Total	486702.00

Executive Engineer,
Kullu Division ,
HP.PWD Kullu.

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-139800.00
Earnest money :-3000.00
Time :- Two months.

Name of work:- Restoration of rain damages on Shat Sub Division HPPWD
(SH):- Hiring of Tipper for carriage of slips/Muck/debris at various roads under (Manikaran) section Job No-I

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Hiring of tipper in good condition of minimum 4.00 cubic metre carriage capacity on daily basis from 9.00 AM to 5.00 PM with hydraulic facility , jack facility for Carriage of slips and disposal of same at suitable dumping places including P.O.L. charges and wages of driver and other operational staff as per the direction and entire satisfaction of Engineer-in-charge.	60	2330.00	Rupees Two thousand three hundred thirty and paise zero only.	Per days	139800.00
	Conditions					
	1) The cost of P.O.L. will be borne by the contractor/ owner of the vehicle/ machine at his own cost.					
	2) The repair etc. will be got done by the contractor at his own cost.					
					Total:-	139800.00


Executive Engineer,
Kullu Division ,
HP.PWD Kullu.

Estimated cost:-139800.00
 Earnest money :-3000.00
 Time :- Two months.

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Shat Sub Division HPPWD
 (SH:- Hiring of Tipper for carriage of slips/Muck/debris at various roads under (Manikaran) section Job No-II

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Hiring of tipper in good condition of minimum 4.00 cubic metre carriage capacity on daily basis from 9.00 AM to 5.00 PM with hydraulic facility , jack facility for Carriage of slips and disposal of same at suitable dumping places including P.O.L. charges and wages of driver and other operational staff as per the direction and entire satisfaction of Engineer-in-charge.	60	2330.00	Rupees Two thousand three hundred thirty and paise zero only.	Per days	139800.00
	Conditions					
	1) The cost of P.O.L. will be borne by the contractor/ owner of the vehicle/ machine at his own cost.					
	2) The repair etc. will be got done by the contractor at his own cost.					
					Total:-	139800.00


 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu.

9

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-497961.00
Earnest money :10000.00
Time :-one month

Name of work:- Restoration of rain damages on Bhunter manikaran road km.1/610 to 35/110
(SH:- Removal of slips in various Rds (Manikaran section) Job No.--III

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials upto any and any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3980.50	125.10	Rupees One hundred twenty five and paise ten only.	Per cubic metre	497961.00
					Total	497961.00


Executive Engineer,
Kullu Division
HP.PWD Kullu.

Estimated cost:-497348.00
Earnest money :10000.00
Time :one month

DRAFT SCHEDULE OF QUANTITY

/Name of work:- Restoration of rain damages on Bhunter manikaran road km.1/610 to 35/110
(SH:- Removal of slips in various Rds (Manikaran section) Job No.--1

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials upto any and any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3975.60	125.10	Rupees One hundred twenty five and paise ten only.	Per cubic metre	497348.00
					Total	497348.00


Executive Engineer,
Kullu Division
HP.PWD Kullu.

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-497961.00
Earnest money :10000.00
Time :-one month

/Name of work:- Restoration of rain damages on Bhunter manikaran road km.1/610 to 35/110
(SH:- Removal of slips in various Rds (Manikaran section) Job No.--II

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials upto any and any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3980.50	125.10	Rupees One hundred twenty five and paise ten only.	Per cubic metre	497961.00
					Total	497961.00


Executive Engineer,
Kullu Division ,
HP.PWD Kullu.

12

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-481673.00

Earnest money :10000.00

Time :-one month

/Name of work:- Restoration of rain damages on Bhunter manikaran road km. 1/610 to 35/110

(SH:- Removal of slips in various Rds (Hathithan section) Job No.- I

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials upto any and any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3850.30	125.10	Rupees One hundred twenty five and paise ten only.	Per cubic metre	481673.00
					Total	481673.00


 Executive Engineer,
 Kullu Division
 HP, PWD Kullu

13

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-494170.00
Earnest money :10000.00
Time :-one month

/Name of work:- Restoration of rain damages on Bhunter manikaran road km.1/610 to 35/110
(SH:- Removal of slips in various Rds (Hathithan section) Job No.- II

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials upto any and any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3950.20	125.10	Rupees One hundred twenty five and paise ten only.	Per cubic metre	494170.00
					Total	494170.00

Executive Engineer,
Kullu Division
HP.PWD Kullu

Estimated cost:-497348.00
Earnest money :10000.00
Time :one month

DRAFT SCHEDULE OF QUANTITY

/Name of work:- Restoration of rain damages on Bhunter manikaran road km.1/610 to 35/110
(SH:- Removal of slips in various Rds (Hathithan section) Job No. - III

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials upto any and any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3975.60	125.10	Rupees One hundred twenty five and paise ten only.	Per cubic metre	497348.00
					Total	497348.00


Executive Engineer,
Kullu Division
HP.PWD Kullu.

DRAFT SCHEDULE OF QUANTITY

Estimated cost-139800.00
Earnest money :-3000.00
Time :- Two months.

Name of work:- Restoration of rain damages on Shat Sub Division HPPWD
(SH):- Hiring of Tipper for carriage of slips/Muck/debries at various roads under (Jari) section Job No-II

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Hiring of tipper in good condition of minimum 4.00 cubic metre carriage capacity on daily basis from 9.00 AM to 5.00 PM with hydraulic facility , jack facility for Carriage of slips and disposal of same at suitable dumping places including P.O.L. charges and wages of driver and other operational staff as per the direction and entire satisfaction of Engineer-in-charge.	60	2330.00	Rupees Two thousand three hundred thirty and paise zero only.	Per days	139800.00
	Conditions					
	1) The cost of P.O.L. will be borne by the contractor/ owner of the vehicle/ machine at his own cost.					
	2) The repair etc. will be got done by the contractor at his own cost.					
					Total:-	139800.00

Executive Engineer,
Kullu Division ,
HP.PWD Kullu

Estimated cost:-139800.00
Earnest money :-3000.00
Time :- Two months.

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Shat Sub Division HPPWD
(SH:- Hiring of Tipper for carriage of slips/Muck/debries at various roads under (Hathithan) section Job No-I

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of tipper in good condition of minimum 4.00 cubic metre carriage capacity on daily basis from 9.00 AM to 5.00 PM with hydraulic facility , jack facility for Carriage of slips and disposal of same at suitable dumping places including P.O.L. charges and wages of driver and other operational staff as per the direction and entire satisfaction of Engineer-in-charge.	60	2330.00	Rupees Two thousand three hundred thirty and paise zero only.	Per days	139800.00
	Conditions					
	1) The cost of P.O.L. will be borne by the contractor/ owner of the vehicle/ machine at his own cost.					
	2) The repair etc. will be got done by the contractor at his own cost.					
					Total:-	139800.00

Executive Engineer,
Kullu Division ,
HP.PWD Kullu

Estimated cost:-139800.00
Earnest money :-3000.00
Time :- Two months.

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Shat Sub Division HPPWD
(SH:- Hiring of Tipper for carriage of slips/Muck/debries at various roads under (Hathithan) section Job No-II

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Hiring of tipper in good condition of minimum 4.00 cubic metre carriage capacity on daily basis from 9.00 AM to 5.00 PM with hydraulic facility , jack facility for Carriage of slips and disposal of same at suitable dumping places including P.O.L. charges and wages of driver and other operational staff as per the direction and entire satisfaction of Engineer-in-charge.	60	2330.00	Rupees Two thousand three hundred thirty and paise zero only.	Per days	139800.00
	Conditions					
	1) The cost of P.O.L. will be borne by the contractor/ owner of the vehicle/ machine at his own cost.					
	2) The repair etc. will be got done by the contractor at his own cost.					
					Total:-	139800.00

Executive Engineer,
Kullu Division ,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Buins Bai Bhulang road Km 0/00 to 11/020.
(SH:- Construction of Retaining Wall at Km8/660 to 8/670).

Estimated cost:-Rs. 338358/-only.
Earnest money :- Rs.8800/-only.
Time :- Three months

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material upto a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	27.40	355.35	Rupees Three hundred sixty five and paise thirty five only	Per Cubic metre	10011.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	7.20	4509.15	Rupees four thousand five hundred nine and paise fifteen only	Per cubic metre	32466.00
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	4.30	4957.40	Rupees four thousand nine hundred fifty seven and paise forty only	Per cubic metre	21317.00
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	28.64	5252.45	Rupees five thousand two hundred fifty two and paise forty five only.	Per Cubic metre	150430.00
5	Construction of dry rubble stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportation within all leads and lift of materials and as per direction of Engineer-in-charge.	33.59	2735.20	Rupees two thousand seven hundred thirty five and paise twenty only	Per cubic metre	91875.00
6	Back filling behind wing walls and return walls complete as per drawing and technical specification of Ministry of Rural Development for rural road as per drawing and technical specifications under clause 1204.3.8 including hauling/carriage of all labour equipment and material to various location through with in all leads and lift of materials and as pr direction of engineer in charge.	20.10	1604.95	Rupees one Thousand six hundred four and paise ninty five only	Per Cubic metre	32259.00
					Total:-	338358.00

Executive Engineer,
Kullu Division
HP,PWD Kullu.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Buins Bai Bhulang road Km 0/00 to 11/020.
(SH:- Construction of Retaining Wall at Km 9/720 to 9/732.50).

Estimated cost:-Rs. 416774/-only.
Earnest money :- Rs.8400/-only.
Time :- Three months

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material upto a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	32.75	365.35	Rupees Three hundred sixty five and paise thirty five only	Per Cubic metre	11965.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.00	4509.15	Rupees four thousand five hundred nine and paise fifteen only	Per cubic metre	40582.00
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	5.38	4957.40	Rupees four thousand nine hundred fifty seven and paise forty only	Per cubic metre	26671.00
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	35.80	5252.45	Rupees five thousand two hundred fifty two and paise forty five only.	Per Cubic metre	188038.00
5	Construction of dry rubble stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportation within all leads and lift of materials and as per direction of Engineer-in-charge.	41.99	2735.20	Rupees two thousand seven hundred thirty five and paise twenty only	Per cubic metre	114851.00
6	Back filling behind wing walls and return walls complete as per drawing and technical specification of Ministry of Rural Development for rural road as per drawing and technical specifications under clause 1204.3.8 including hauling/carriage of all labour equipment and material to various location through with in all leads and lift of materials and as per direction of engineer in charge.	21.60	1604.95	Rupees one Thousand six hundred four and paise ninety five only	Per Cubic metre	34667.00
					Total:-	416774.00

Executive Engineer,
Kullu Division
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Buins Bai Bhulang road Km 0/00 to 11/020.
(SH:- Construction of Retaining Wall at Km 5/580 to 5/592.50).

Estimated cost :-Rs. 424986/-only.
Earnest money :- Rs. 8500/-only.
Time :-Three months

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material upto a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	33.13	365.35	Rupees Three hundred sixty five and paise thirty five only	Per Cubic metre	12104.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.00	4509.15	Rupees four thousand five hundred nine and paise fifteen only	Per cubic metre	40582.00
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	5.38	4957.40	Rupees four thousand nine hundred fifty seven and paise forty only	Per cubic metre	26671.00
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	35.80	5252.45	Rupees five thousand two hundred fifty two and paise forty five only.	Per Cubic metre	188038.00
5	Construction of dry rubble stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportation within all leads and lift of materials and as per direction of Engineer-in-charge.	41.99	2735.20	Rupees two thousand seven hundred thirty five and paise twenty only	Per cubic metre	114851.00
6	Back filling behind wing walls and return walls complete as per drawing and technical specification of Ministry of Rural Development for rural road as per drawing and technical specifications under clause 1204.3.8 including hauling/carriage of all labour equipment and material to various location through with in all leads and lift of materials and as per direction of engineer in charge.	26.63	1604.95	Rupees one Thousand six hundred four and paise ninety five only	Per Cubic metre	42740.00
					Total:-	424986.00


 Executive Engineer,
 Kullu Division
 HP. PWD Kullu.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Buins Bai Bhulang road Km 0/00 to 11/020.
(SH:- Construction of Retaining Wall at Km 9/775 to 9/787.50).

Estimated cost-Rs. 424604/-only.
Earnest money :- Rs. 8500/-only.
Time :- Three months

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material upto a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	35.38	365.35	Rupees Three hundred sixty five and paise thirty five only	Per Cubic metre	12926.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.00	4509.15	Rupees four thousand five hundred nine and paise fifteen only	Per cubic metre	40582.00
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within-all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	5.38	4957.40	Rupees four thousand nine hundred fifty seven and paise forty only	Per cubic metre	26671.00
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	35.80	5252.45	Rupees five thousand two hundred fifty two and paise forty five only	Per Cubic metre	188038.00
5	Construction of dry rubble stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportation within all leads and lift of materials and as per direction of Engineer-in-charge.	41.99	2735.20	Rupees two thousand seven hundred thirty five and paise twenty only	Per cubic metre	114851.00
6	Back filling behind wing walls and return walls complete as per drawing and technical specification of Ministry of Rural Development for rural road as per drawing and technical specifications under clause 1204.3.8 including hauling/carriage of all labour equipment and material to various location through with in all leads and lift of materials and as pr direction of engineer in charge.	25.88	1604.95	Rupees one Thousand six hundred four and paise ninety five only	Per Cubic metre	41536.00
					Total:-	424604.00

Executive Engineer,
Kullu Division
HP.PWD Kullu.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Darka Bhumteer road Km 0/00 to 7/500.
(SH:- Construction of Retaining Wall at RD 1/585 to 1/598.75).

Estimated cost:-Rs. 493339/-only.
Earnest money :- Rs. 10000/-only.
Time :- Three months

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material upto a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	39.53	365.35	Rupees Three hundred sixty five and paise thirty five only	Per Cubic metre	14442.00
2	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	30.93	4957.40	Rupees four thousand nine hundred fifty seven and paise forty only	Per cubic metre	153332.00
3	Providing and laying boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS : 280 and IS : 4826 in 150mm x 150mm (one hundred fifty into one hundred fifty millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighting not less than 25kg. (twenty five kilogram) each as per drawing and technical specifications under clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge.	109.32	2784.30	Rupees two thousand seven hundred eighty four and paise thirty only	Per cubic metre	304380.00
4	Back filling behind wing walls and return walls complete as per drawing and technical specification of Ministry of Rural Development for rural road as per drawing and technical specifications under clause 1204.3.8 including hauling/carriage of all labour equipment and material to various location through with in all leads and lift of materials and as per direction of engineer in charge.	13.20	1604.95	Rupees one Thousand six hundred four and paise ninety five only	Per Cubic metre	21185.00
					Total:-	493339.00

Executive Engineer,
Kullu Division
HP.PWD Kullu

155

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Bailey Bridge near Rambag Kullu.

{SH:- Construction of PCC Retaining Wall for approach for Highway side (Valley Side)}. Job No. 1

Estimated cost:-Rs. 353775/-only.

Earnest money :- Rs. 7100/-only.

Time :- Three months

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material upto a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	24.12	365.35	Rupees Three hundred sixty five and paise thirty five only	Per Cubic metre	8812.00
2	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	3.18	4957.40	Rupees four thousand nine hundred fifty seven and paise forty only	Per cubic metre	15765.00
3	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 P.C.C. Grade M 10 (M-Ten) Nominal mix 1:3:6 (One cement : Six sand : Twelve graded stone aggregate) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	56.10	5212.70	Rupees five thousand two hundred twelve and paise seventy only	Per cubic metre	292432.00
4	Back filling behind wing walls and return walls complete as per drawing and technical specification of Ministry of Rural Development for rural road as per drawing and technical specifications under clause 1204.3.8 including hauling/carriage of all labour equipment and material to various location through with in all leads and lift of materials and as per direction of engineer in charge.	15.60	1604.95	Rupees one Thousand six hundred four and paise ninety five only	Per Cubic metre	25037.00
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia PVC pipe extending through the full with of the structure with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clause 614 , 709 , 1204.3.7 including carriage of materials and as per direction of Engineer-in-charge.	30	390.95	Rupees three hundred ninety and paise ninety five only	Each	11729.00
					Total:-	353775.00

Executive Engineer,
Kullu Division
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Bailey Bridge near Rambag Kullu.

{SH:- Construction of PCC Retaining Wall for approach for Highway side (Valley Side)}. Job No. 2

Estimated cost:-Rs. 382696/-only.

Earnest money :- Rs. 7700/-only.

Time :- Three months

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material upto a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	26.13	365.35	Rupees Three hundred sixty five and paise thirty five only	Per Cubic metre	9547.00
2	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	3.45	4957.40	Rupees four thousand nine hundred fifty seven and paise forty only	Per cubic metre	17103.00
3	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 P.C.C. Grade M 10 (M-Ten) Nominal mix 1:3:6 (One cement : Six sand : Twelve graded stone aggregate) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	60.85	5212.70	Rupees five thousand two hundred twelve and paise seventy only	Per cubic metre	317193.00
4	Back filling behind wing walls and return walls complete as per drawing and technical specification of Ministry of Rural Development for rural road as per drawing and technical specifications under clause 1204.3.8 including hauling/carriage of all labour equipment and material to various location through with in all leads and lift of materials and as pr direction of engineer in charge.	16.90	1604.95	Rupees one Thousand six hundred four and paise ninety five only	Per Cubic metre	27124.00
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia PVC pipe extending through the full with of the structure with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clause 614 , 709 , 1204.3.7 Including carriage of materials and as per direction of Engineer-in-charge.	30	390.95	Rupees three hundred ninety and paise ninety five only	Each	11729.00
					Total:-	382696.00

Executive Engineer,
Kullu Division
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work :- Restoration on Bailey Bridge near Rambag Kullu.

{SH:- Construction of PCC R/Wall for approach Rambag side (Hill Side)}. Job No. 1

Estimated cost:-Rs.355877/-only.

Earnest money :- Rs. 7200/-only.

Time :-Three months

Sr. No.	Description	Qty	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material upto a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	39.36	365.35	Rupees Three hundred sixty five and paise thirty five only	Per Cubic metre	14380.00
2	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	3.18	4957.40	Rupees four thousand nine hundred fifty seven and paise forty only	Per cubic metre	15765.00
3	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 P.C.C. Grade M 10 (M-Ten) Nominal mix 1:3:6 (One cement : Six sand : Twelve graded stone aggregate) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	56.10	5212.70	Rupees five thousand two hundred twelve and paise seventy only	Per cubic metre	292432.00
4	Back filling behind wing walls and return walls complete as per drawing and technical specification of Ministry of Rural Development for rural road as per drawing and technical specifications under clause 1204.3.8 including hauling/carriage of all labour equipment and material to various location through with in all leads and lift of materials and as pr direction of engineer in charge.	13.44	1604.95	Rupees one Thousand six hundred four and paise ninety five only	Per Cubic metre	21571.00
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia PVC pipe extending through the full with of the structure with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clause 614 , 709 , 1204.3.7 including carriage of materials and as per direction of Engineer-in-charge.	30	390.95	Rupees three hundred ninety and paise ninety five only	Each	11729.00
					Total:-	355877.00

Executive Engineer,
Kullu Division
HP.PWD Kullu.

26 154 SCHEDULE OF QUANTITY

Name of work :- Restoration on Bailey Bridge near Rambag Kullu.

{SH:- Construction of PCC R/Wall for approach Rambag side (Hill Side)}; Job No. 2

Estimated cost:-Rs.384972/-only.

Earnest money :- Rs. 7700/-only.

Time :- Three months

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material upto a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	42.64	365.35	Rupees Three hundred sixty five and paise thirty five only	Per Cubic metre	15579.00
2	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :four sand : eight graded stone aggregate 40mm. (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	3.45	4957.40	Rupees four thousand nine hundred fifty seven and paise forty only	Per cubic metre	17103.00
3	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 P.C.C. Grade M 10 (M-Ten) Nominal mix 1:3:6 (One cement : Six sand : Twelve graded stone aggregate) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	60.85	5212.70	Rupees five thousand two hundred twelve and paise seventy only	Per cubic metre	317193.00
4	Back filling behind wing walls and return walls complete as per drawing and technical specification of Ministry of Rural Development for rural road as per drawing and technical specifications under clause 1204.3.8 including hauling/carriage of all labour equipment and material to various location through with in all leads and lift of materials and as pr direction of engineer in charge.	14.56	1604.95	Rupees one Thousand six hundred four and paise ninety five only	Per Cubic metre	23368.00
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia PVC pipe extending through the full with of the structure with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clause 614 , 709 , 1204.3.7 including carriage of materials and as per direction of Engineer-in-charge.	30	390.95	Rupees three hundred ninety and paise ninety five only	Each	11729.00
					Total:-	384972.00


Executive Engineer,
Kullu Division
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Darka Bhumteer road Km 0/00 to 7/500.
(SH:- Construction of Retaining Wall at RD 1/598.75 to 1/612.50).

Estimated cost-Rs. 494566/-only.
 Earnest money :- Rs.10000/-only.
 Time :- Three months

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material upto a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	44.69	365.35	Rupees Three hundred sixty five and paise thirty five only	Per Cubic metre	16327.00
2	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	30.93	4957.40	Rupees four thousand nine hundred fifty seven and paise forty only	Per cubic metre	153332.00
3	Providing and laying boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS : 280 and IS : 4826 in 150mm x 150mm (one hundred fifty into one hundred fifty millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighting not less than 25kg. (twenty five kilogram) each as per draw/g and technical specifications under clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge.	109.32	2784.30	Rupees two thousand seven hundred eighty four and paise thirty only	Per cubic metre	304380.00
4	Back filling behind wing walls and return walls complete as per drawing and technical specification of Ministry of Rural Development for rural road as per draw/g and technical specifications under clause 1204.3.8 including hauling/carriage of all labour equipment and material to various location through with in all leads and lift of materials and as pr direction of engineer in charge.	12.79	1604.95	Rupees one Thousand six hundred four and paise ninty five only	Per Cubic metre	20527.00
					Total:-	494566.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

103

28

Estimated cost:-Rs. 1,36,128.00
 Earnest money :- Rs. 3,000.00
 Time :-Two months

DRAFT SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Non Residential building at kullu. (SH :- Construction of additional office in replacement of store room at GF of Sub division office at kullu.)

Sr. No.	Description of item	Qty	Figure	Rate in Words	Unit	Amount
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres (fifty metre) lead as per direction of Engineer-in-charge n cement mortar within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge	0.61	1227	Rupees thousand hundred seven and paise zero only	Per Cube two metre	748.00
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge	163.62	15.60	Rupees fifteen and paise sixty only	Per Square metre	2552.00
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :Cement mortar 1:4 (one cement : four coarsesand) within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge	2.23	10718.00	Rupees thousand hundred and paise zero only	Per Cube ten seven metre	23901.00
4	15 mm (fifteen millimetre) cement plaster on rough side of single or half brick wall of mix:1:6 (one cement : six coarse sand) within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge	26.76	277.40	Rupees hundred seventy seven and paise forty only	Per Square metre	7423.00
5	Distemping with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre (fifty grams per litre), of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. 13.42.1 Two or more coats on new work Walls within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge	163.62	120.55	Rupees hundred and paise fifty five only	Per Square metre	19724.00

6	Providing and applying white cement based putty of average thickness 1 mm (one millimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge	155.44	103.40	Rupees hundred three and paise forty only	Per one Square metre	16072.00
7	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two or more coat applied @ 1.67 ltr/10 sqm (one point sixty seven litre per ten square metre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two point twenty litre per ten square metre) within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge	12.00	123.05	Rupees hundred three and paise zero five only	Per one Square metre	1477.00
8	Providing and fixing 2mm (two millimetre) thick PVC antistatic vinyl Flooring plain or coloured, carbed or mosaic/metalled finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for separately within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge	27.82	1588.9	Rupees thousand hundred eight and paise ninety only	Per one five Square metre	44203.00
9	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Deodar wood within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge	0.046	129393.44	Rupees one lakh nine thousand three hundred ninety three and paise forty four only	Per Cube metre	5952.00
10	Providing and fixing 40mm (forty millimetre) thick panelled shutter for door with deodar wood style rail beading and infill panele of 12mm (twelve millimetre) thick phenol bonded prelaminated board both side particle board panel ISI marked 12823 including ISI marked within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge	1.85	4167.31	Rupees thousand four one hundred sixty seven and paise thirty one only	Per one Square metre	7710.00
11	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (zero point ninety litre per ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm (zero point seventy five litre per ten square metre) of approved brand and manufacture within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge	20.26	106.20	Rupees hundred six and paise twenty only	Per one Square metre	2152.00

12	Providing and fixing bright finished brass handles with screws etc. complete: 125 mm (one hundred twenty five millimetre) within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge	2.00	172.7	Rupees hundred two and seventy only	one seventy paise EACH	345.00
13	Providing and fixing bright finished brass tower bolts (barrel type) with necessary screws etc. complete : 150x10 mm (one hundred fifty into ten millimetre) within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge	2.00	147.90	Rupees hundred seven and ninety only	one forty paise EACH	296.00
14	Renewing glass panes and refixing existing wooden fillets: Float glass panes of nominal thickness 4 mm (four millimetre) (weight not less than 10kg/sqm (ten kilogram per square metre) within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge	3.08	1160.10	Rupees thousand hundred sixty and paise ten only	Per one square metre	3573.00
					Total	136128


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,85,993.00
Earnest money :- Rs. 9,800.00
Time :- Two months

Name of work:- Restoration of rain damages on Dohranallah Kharihar road (SH:- C/O R/wall on Pushta at RD. 2/070 to 2/084).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	64.40	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	23529
2	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :Four sand : eight graded stone) nominal mix 25 mm (Twenty five millimetre) aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203, within all leads and lift of materials and as per direction of Engineer-in-charge.	38.64	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	191554
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	26.12	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	137194
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	43.26	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	118325
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.59	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	15391
					Total	485993

Executive Engineer,
Kullu Division
HP.PWD Kullu

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,78,502.00
Earnest money :- Rs. 9,600.00
Time :- Two months

Name of work:- Restoration of flush flood damages to Duff Dumber Bridge at Bhunter (SH:- C/O Wire crates for protection work).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in-charge.	38.48	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	14059
2	Providing and laying boulder apron laid in wire crate with 4 mm (Four millimetre) dia wire conforming to IS 280 and 4826 in 150 x 150 mm (One hundred fifty x One hundred fifty millimetre) mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge.	140.63	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	391556
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	33.75	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	54167
4	Construction of Embankment with approved material obtained from barrow pits with all lifts and leads, transporting to site, spreading grading to required slope and compacting to meet requirement of table 300-2 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	106.73	175.40	Rupees One hundred seventy five and paise forty only	Per cubic metre	18720
					Total	478502


Executive Engineer,
Kullu Division ,
HP.PWD Kullu

Estimated cost:- Rs. 4,91,283.00
Earnest money :- Rs. 9,900.00
Time :- Two months

31

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Dohranallah Kharihar road Km 0/0 to 10/120 (SH:- C/O R/wall on Pushta at RD. 2/518).

Sr. No.	Description	Qty	Figure	Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	57.10	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	20861
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:4:8 (One cement :Four sand : eight graded stone) aggregate nominal mix 25 mm (Twenty five millimetre) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in-charge.	46.80	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	232006
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	26.84	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	140976
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	29.17	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	79786
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	11.00	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	17654
					Total	491283


Executive Engineer,
Kullu Division,
HP.PWD Kullu

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,66,427.00
 Earnest money :- Rs. 9,400.00
 Time :- Two months

Name of work:- R.R.D on Chharour Nallah to Kashawari road Km 0/0 to 8/010 (SH:- C/O R/wall with PCC toe wall at RD 0/280 to 0/290).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	33.50	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	12239
2	Providing and laying concrete for plain/ reinforced concrete 1:3:6 (One cement : Three sand : Six graded stone) aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in- charge.	30.00	5212.70	Rupees Five thousand two hundred twelve and paise seventy only	Per cubic metre	156381
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :Four sand : eight graded stone) aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in- charge.	4.30	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	21317
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	28.64	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	150430
5	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in- charge.	33.59	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	91875
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	21.30	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	34185
					Total	466427


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,86,079.00

Earnest money :- Rs. 9,800.00

Time :- Two months

Name of work:- Restoration of rain damages on Dohranallah Kharihar road (SH:- C/O R/wall on Pushta at RD. 2/084 to 2/098).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer in- charge.	62.79	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	22940
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:4:8 (One cement :Four sand : eight graded stone) aggregate nominal mix 25 mm (Twenty five millimetre) in open foundations complete as per drawing and technical specification clause 802.803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in- charge.	38.64	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	191554
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	26.12	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	137194
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in- charge.	43.26	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	118325
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	10.01	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	16066
					Total	486079


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,89,552.00
Earnest money :- Rs. 9,800.00
Time :- Two months

Name of work:- Restoration of rain damages on Dohranallah Kharthar road Km 0/0 to 10/120 (SH:- C/O R/wall on Pushta at RD. 2/518 to 2/527).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	60.75	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	22195
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:4:8 (One cement :Four sand : eight graded stone) aggregate nominal mix 25 mm (Twenty five millimetre) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in-charge.	46.80	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	232006
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	26.84	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	140976
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	29.17	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	79786
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.09	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	14589
					Total	489552

Executive Engineer,
Kullu Division
HP.PWD Kullu

Estimated cost:- Rs. 4,53,139.00
Earnest money :- Rs. 9,100.00
Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Badah Pahnallah road Km 0/0 to 9/700 (SH:- C/O Rwall on Pushta at RD. 6/760 to 6/780).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	55.40	365.35	Rupees Three hundred sixty five and paissa thirty five only	Per cubic metre	20240
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:6:12 (One cement :Six sand : Twelve graded stone) for nominal mix 25 mm (Twenty five millimetre) aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.80	4509.15	Rupees Four thousand five hundred nine and paissa fifteen only	Per cubic metre	44190
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	37.32	5252.45	Rupees Five thousand two hundred fifty two and paissa forty five only	Per cubic metre	196021
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	63.23	2735.20	Rupees Two thousand seven hundred thirty five and paissa twenty only	Per cubic metre	172947
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	12.30	1604.95	Rupees One thousand four and paissa ninety five only	Per cubic metre	19741
					Total	453139


Executive Engineer,
Kullu Division,
HP.PWD Kullu

36

Estimated cost:- Rs. 4,55,745.00
Earnest money :- Rs. 9,200.00
Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Dohranallah Barahar road Km 0/0 to 10/120 (SH:- C/O R/wall at RD. 4/560 to 4/580).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	57.70	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	21081
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:6:12 (One cement :Six sand : Twelve graded stone) for nominal mix 25 mm (Twenty five millimetre) aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.80	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	44190
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	37.32	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	196021
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	63.23	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	172947
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	13.40	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	21506
					Total	455745


Executive Engineer,
Kullu Division ,
HP.PWD Kullu

Estimated cost:- Rs. 4,99,563.00
Earnest money :- Rs. 10,000.00
Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- R.R.D on Kullu Karon road Km 0/00 to 4/500 (SH:- C/O R/wall at RD. 6/955 to 6/973).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	36.00	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	13153
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone) aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	8.82	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	39771
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :Four sand : eight graded stone aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in-charge.	16.28	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	80706
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	33.09	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	173804
5	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	57.40	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	157000
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	14.58	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	23400
7	P/L PVC Weep hole 100 mm (One hundred millimeter) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	30.00	390.95	Rupees Three hundred ninety and paise ninety five only	Each	11729
					Total	499563


Executive Engineer,
Kullu Division
HP.PWD Kullu

38

Estimated cost:- Rs. 4,67,749.00
 Earnest money :- Rs. 9,400.00
 Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Tharku Pechha road (SH:- C/O R/wall at RD 17/10 to 1/725).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	41.40	365.35	Rupees Three hundred sixty five and paisa thirty five only	Per cubic metre	15125
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:6:12 (One cement :Six sand : Twelve graded stone) for nominal mix 25 mm (Twenty five millimetre) aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	5.70	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	25702
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :Four sand : eight graded stone aggregate 25 mm Twenty five millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in-charge.	77.55	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	384446
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	11.85	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	19019
5	Providing waephholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100 mm (One hundred millimetre) dia PVC pipe extending through the full width of the structure with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 719, 1204.3.7	60.00	390.95	Rupees Three hundred ninety and paise ninety five only	Each	23457
					Total	467749

Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,54,971.00
Earnest money :- Rs. 9,100.00
Time :- Two months

Name of work:- Restoration of rain damages on Tharku Pechha road (SH:- C/O R/wall at RD. 0/410 to 0/420 and 0/430 to 0/440).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	55.80	365.35	Rupees Three hundred sixty five and paisa thirty five only	Per cubic metre	20387
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:6:12 (One cement :Six sand : Twelve graded stone) for nominal mix foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.80	4509.15	Rupees Four thousand five hundred nine and paisa fifteen only	Per cubic metre	44190
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	37.32	5252.45	Rupees Five thousand two hundred fifty two and paisa forty five only	Per cubic metre	196021
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	63.23	2735.20	Rupees Two thousand seven hundred thirty five and paisa twenty only	Per cubic metre	172947
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	13.35	1604.95	Rupees One thousand four and paisa ninety five only	Per cubic metre	21426
					Total	454971

Executive Engineer,
Kullu Division,
HP.PWD Kullu

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 3,02,982
 Earnest money :- Rs. 6,100
 Time :- Two months

Name of work:- A/R and M/O General Pooled accomodation.						
(SH):- Painting,distempering & p/l tiles in Type-I qtr no-5 in LIG colony near pooled accommodation Kullu.						
Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Demolishing cement concrete manually/ bymechanical means including disposal of material within 50 metres (Fifty metre) lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/equivalent design mix) with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.42	1004.45	Rupees One thousand four and paise forty five only.	Per Cubic metre	1426
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	135.42	11.85	Rupees Eleven and paise eighty five only.	Per Square metre	1605
3	Providing and applying white cement based putty of average thickness 1 mm (One millimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	115.11	103.40	Rupees One hundred three and paise forty only.	Per Square metre	11902
4	Repairs to plaster of thickness 12 mm (Twelve millimetre) to 20 mm (Twenty millimetre) in patches of area 2.5 sq.meters (Two point five square metre) and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-charge. With cement mortar 1:4 (1 cement : 4 fine sand) with in all leads and lift of materials and as per direction of Engineer-in-charge.	32.40	384.46	Rupees Three hundred eighty four and paise forty six only.	Per Square metre	12457
5	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content: less than 50 gms/litre (Fifty grams/litre), of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. 13.42.1 Two or more coats on new work Walls with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.42	128.50	Rupees One hundred twenty eight and paise fifty only.	Per Square metre	182
6	Providing and fixing wire gauge shutter using galvanised MS wire gauge of aperture 1.4 mm (One point four millimetre) both direction with wire of dia 0.63 mm (Zero point sixty three millimetre) for door window and cleftory window with hinges and necessary screw 35 mm (Thirty five millimetre) klin seasoned wood with in all leads and lift of materials and as per direction of Engineer-in-charge.	7.77	3086.00	Rupees Three thousand eighty six only.	Per Square metre	23978

7	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm (Twelve millimetre) thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm (Three point three kilogram per square metre), including pointing in white cement mixed with pigment of matching shade complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	21.22	1833.60	Rupees One thousand eight hundred thirty three and paise sixty only.	Per Square metre	38918
8	Providing and laying Vitrified tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm (Six millimetre) thickness, including grouting of joints (Payment for grouting of joints to be made separately) Size of Tile 600x600 mm (Six hundred x Six hundred millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	38.76	1935.50	Rupees One thousand nine hundred thirty five and paise fifty only.	Per Square metre	75020
9	Renewing glass panes and refixing existing wooden fillets: Float glass panes of nominal thickness 4 mm (Four millimetre) (weight not less than 10kg/sqm (Ten kilogram/ square metre)) with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.43	1160.10	Rupees One thousand one hundred sixty and paise ten only.	Per Square metre	2819
10	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (Zero point ninety litre/ Ten square metre) over an under coat of primer applied @ 0.75 ltr/10 sqm (Zero point seventy five litre/ Ten square metre) of approved brand and manufacture with in all leads and lift of materials and as per direction of Engineer-in-charge.	200.14	106.20	Rupees One hundred six and paise twenty only.	Per Square metre	21254
11	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (Zero point ninety litre/ Ten square metre) over an under coat of primer applied @ 0.80 ltr/10 sqm (Zero point eighty litre/ Ten square metre) of approved brand and manufacture with in all leads and lift of materials and as per direction of Engineer-in-charge.	6.19	111.60	Rupees One hundred eleven and paise sixty only	Per Square metre	691
12	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 110 mm (One hundred ten millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	22.00	981.21	Rupees Nine hundred eighty one and paise twenty one only	Per running metre	21587

13	Providing and fixing 3 layer PP-R (Poly propylene Random copolymer) pipes conforming to IS: 15801, UV stabilized & anti-microbial fusion welded, having thermal stability for hot & cold water supply, including all PP-R plain & brass threaded polypropylene random fitting, i/c fixing the pipe with clamps at 1.00 m (One point zero metre) spacing. This includes the cost of cutting chases and making good the same including testing of joints complete PN - 16 pipe, 20 mm (Twenty millimetre) OD (SDR-7.4) with in all leads and lift of materials and as per direction of Engineer-in-charge.	24.00	466.60	Rupees Four hundred sixty six and paise sixty only.	Per running metre	11198
14	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre (Ten litre) low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm (Forty millimetre) flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	9379.30	Rupees Nine thousand three hundred seventy nine and paise thirty only.	Each	9379
15	Providing and fixing wash basin with C.I. brackets, 15mm (Fifteen millimetre) dia CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required White Vitreous China Wash basin size 550x400 mm (Five hundred fifty x Four hundred millimetre) with a 15 mm (Fifteen millimetre) CP Brass single hole basin mixer with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	4685.97	Rupees Four thousand six hundred eighty five and paise ninety seven only.	Each	4686
16	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	2038.15	Rupees Two thousand thirty eight and paise fifteen only.	Each	2038
17	Providing and fixing PTMT jet spray of approved quality and colour with one metre tube pipe with necessary fitting etc. complete within all leads and lifts and other incidentals including carriage of materials in all respect with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	990.12	Rupees Nine hundred ninety and paise twelve only	Each	990
18	Providing and fixing CP soap Dish Holder having length of 138mm (One hundred thirty eight millimetre), breadth 102mm (One hundred two millimetre), height of 75mm (Seventy five millimetre) with concealed fitting arrangements, weighing not less than 106 gms (One hundred six grams) with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	477.39	Rupees Four hundred seventy seven and paise thirty nine only	Each	955
19	Providing and fixing brass bib cock of approved quality : 15mm (Fifteen millimeter) diabore with in all leads and lift of materials and as per direction of Engineer-in-charge.	6.00	937.14	Rupees Nine hundred thirty seven and paise fourteen only	Each	5623

20	Providing and fixing uplasticised PVC connection pipe with brass unions :45 cm (Forty five centimetre) length 15 mm (Fifteen millimetre) nominal bore with in all leads and lift of , materials and as per direction of Engineer-in-charge.	7.00	183.15	Rupees One hundred eighty three and paise fifteen only	Each	1282
21	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors with in all leads and lift of materials and as per direction of Engineer-in-charge.	3.00	1002.99	Rupees One thousand two and paise ninety nine only	Each	3009
22	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 with in all leads and lift of materials and as per direction of Engineer-in-charge.	7.00	900.24	Rupees Nine hundred and paise twenty four only	Each	6302
23	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete :300x16mm (Three hundred x Sixteen millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	172.70	Rupees One hundred seventy two and paise seventy only	Each	345
24	Providing and fixing oxidised M.S. tower bolts (barrel type) with necessary screws etc. complete.150x10mm (One hundred fifty x Ten millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	6.00	147.90	Rupees One hundred forty seven and paise ninety only	Each	887
25	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm (Forty millimetre), including painting of fittings and brackets, cutting and making good the walls wherever required 610x460 mm (Six hundred ten x Four hundred sixty millimetre) bowl depth 200 with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	4278.90	Rupees Four thousand two hundred seventy eight and paise ninety only.	Each	8558
26	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :Cement mortar 1:4 (1 cement : 4 coarsesand) with in all leads and lift of materials and as per direction of Engineer-in-charge.	0.86	10718.00	Ten thousand seven hundred eighteen only	Per Cubic metre	9223
27	Providing and laying in position cement concrete of specified grade excluding the cost of centering andshuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand): 6 gradedstone aggregate 40 mm (Forty millimetre) nominal size) with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.54	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only.	Per Cubic metre	12603
28	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position with necessary stainless steel screws etc. Sal wood/ hard wood with in all leads and lift of materials and as per direction of Engineer-in-charge.	0.12	122082.60	Rupees One lac twenty two thousand eighty two and paise sixty only.	Per Cubic metre	14064
	Total	Total				302982


 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu