



Office of
EXECUTIVE ENGINEER (KULLU DIVISION)
H.P. PUBLIC WORKS DEPARTMENT, KULLU-175101
FAX: 01902-222571, E.mail. ee-kul2-hp@ntc.in

No.PW/KD/TA/Tender/2023-2024-

7472-7479

Dated:- 28-7-2023

To

The Executive Engineer, I.T. Cell,
Nigam Bihar Shimla-2.

Subject:- Publishing of Notice inviting tender.

Enclosed please find herewith copies of notice inviting tender for the up loading on department website 09.08.2023 as per notification issued by Secretary (PW) to the Govt. of HP Shimla vide letter No.PBW(S)A(3)1/2020 dated 16.07.2021. As per works mentioned in the Tender Notice is urgent nature of work in the public interest.

DA/As above.


Executive Engineer,
Kullu Division,
HP. PWD, Kullu.

Copy alongwith notice inviting tender is forwarded to the following for information and necessary action.

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, (MZ) HP.PWD, Mandi.
3. Superintending Engineer, 6th Circle HP.PWD, Kullu.
4. Supdt./DAO/HDM of this office.
5. Notice Board.

DA/Nil.


Executive Engineer,
Kullu Division,
HP. PWD, Kullu.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

The Executive Engineer, Kullu Division HP.PWD, Kullu on behalf of the Government of Himachal Pradesh invites the **offline tender i.e. on percentage rates** for the following works from the eligible contractors/Firms registered with HP.PWD, department, so as to reach in the office as per time schedule given below:-

1	Date of receipt of application for tender form.		08.08.2023 upto 4:00 PM		
2	Date of issue/sale of tender form.		08.08.2023 upto 4:00 PM		
3	Date of receipt of tender.		09.08.2023 upto 10:30 PM		
4	Date of opening tender.		09.08.2023 upto 11:00 AM		
Sr. No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	2	3	4	5	6
1	Restoration of rain damages on Buins Bai Bhulang road Km. 0/00 to 11/020 (SH;- Construction of Retaining wall at Km. 5/160 to 5/172.5).	4,26,897/-	8,600/-	Three months	350/-
2	Restoration of rain damages on Buins Bai Bhulang road Km. 0/00 to 11/020 (SH;- Construction of Retaining wall at Km. 7/100 to 7/112.5).	4,22,926/-	8,500/-	Three months	350/-
3	Restoration of rain damages on Buins Bai Bhulang road Km. 0/00 to 11/020 (SH;- Construction of Retaining wall at Km. 8/700 to 8/712.50).	4,22,926/-	8,500/-	Three months	350/-
4	Restoration of rain damages on Buins Bai Bhulang road Km. 0/00 to 11/020 (SH;- Construction of Retaining wall at Km. 8/815 to 8/827.50).	4,27,335/-	8,600/-	Three months	350/-
5	Restoration of rain damages on Dohranallah Barahar road Km. 0/0 to 10/120 (SH:- C/O R/wall at RD 4/580 to 4/600).	4,54,186/-	9,100/-	Two months	350/-
6	Restoration of rain damages on Badah Pahnallah road Km. 0/0 to 9/700 (SH:- C/O R/wall on Pushta at RD 4/210 to 4/230).	4,55,202/-	9,200/-	Two months	350/-
7	Restoration of rain damages on Kolibehar Barahar road Km. 0/0 to 6/0 (SH:- C/O R/wall at RD 2/400 to 2/415).	4,84,737/-	9,700/-	Two months	350/-
8	Restoration of rain damages on Kolibehar Barahar road Km. 0/0 to 6/0 (SH:- C/O R/wall at RD 2/415 to 2/430).	4,84,209/-	9,700/-	Two months	350/-
9	Restoration of rain damages on Dohranallah Kharihar road Km. 0/0 to 10/120 (SH:- C/O R/O R/wall on Pushta at RD 2/500 to 2/509).	4,89,807/-	9,800/-	Two months	350/-
10	Restoration of rain damages Bari Padhru Tharku Pechha road (SH:- C/O B/wall at RD 2/180 to 2/205).	4,45,489/-	9,000/-	Two months	350/-
11	Restoration of rain damages Bari Padhru Tharku Pechha road (SH:- C/O PCC R/wall at RD 1/950 to 1/966).	4,99,231/-	10,000/-	Two months	350/-
12	Restoration of rain damages Bari Padhru Tharku Pechha road (SH:- C/O R/wall at RD 0/080 to 0/100).	4,54,931/-	9,100/-	Two months	350/-
13	Restoration of rain damages Bari Padhru Tharku Pechha road (SH:- C/O R/wall on Pushta at RD 0/830 to 0/845).	4,84,338/-	9,700/-	Two months	350/-

b

14	RRD on Bhutti Bhalyani road 0/00 to 4/500 (SH:- C/O R/wall at RD 2/530 to 2/551).	4,82,856/-	9,700/-	Two months	350/-
15	RRD on Kullu Karon road Km. 0/00 to 15/00 (SH:- C/O B/wall at RD 7/090 to 7/115).	3,63,082/-	7,300/-	Two months	350/-
16	RRD on Kullu Karon road Km. 0/00 to 15/00 (SH:- C/O B/wall at RD 6/980 to 7/999).	4,99,708/-	10,000/-	Two months	350/-
17	RRD on Bhutti Bhalyani road 0/00 to 4/500 (SH:- C/O R/wall at RD 1/145 to 1/160).	3,43,030/-	6,900/-	Two months	350/-
18	RRD on Bhutti Bhalyani road 0/00 to 4/500 (SH:- C/O R/wall at RD 0/20 to 0/830 and 3/210 to 3/223).	4,64,350/-	9,300/-	Two months	350/-
19	RRD on Chharour Nallah to Kashwari road Km. 0/0 to 8/010 (SH:- C/O R/wall with PCC toe wall at RD 3/225 to 3/245).	3,79,116/-	7,600/-	Two months	350/-
20	RRD on Chharour Nallah to Kashwari road Km. 0/0 to 4/070 (SH:- Removal of slips at various RD's).	2,35,551/-	4,800/-	Two months	350/-
21	RRD on Chharour Nallah to Kashwari road Km. 0/0 to 4/070 (SH:- Removal of slips at various RD's).	1,48,556/-	3,000/-	Two months	350/-
22	RRD on Chharour Nallah to Kashwari road Km. 0/0 to 8/010 (SH:- C/O R/wall with PCC toe wall at RD 0/635 to 0/645).	4,71,193/-	9,500/-	Two months	350/-
23	RRD on Chharour Nallah to Kashwari road Km. 0/0 to 8/010 (SH:- C/O R/wall with PCC toe wall at RD 0/625 to 0/635).	4,71,113/-	9,500/-	Two months	350/-
24	RRD on Chharour Nallah to Kashwari road Km. 0/0 to 8/010 (SH:- C/O R/wall with PCC toe wall at RD 0/300 to 0/310).	4,66,184/-	9,400/-	Two months	350/-
25	RRD on Chharour Nallah to Kashwari road Km. 0/0 to 8/010 (SH:- C/O R/wall with PCC toe wall at RD 0/0/290 to 0/300).	4,65,921/-	9,400/-	Two months	350/-
26	Restoration of rain damages on Sharni Pini road Km. 0/0 to 15/180 (SH:- Removal of slips in Km. 0/0 to 13/700) Job No.1.	4,06,638/-	10,000/-	One month	350/-
27	Restoration of rain damages on Sharni Pini road Km. 0/0 to 15/180 (SH:- Removal of slips in Km. 0/0 to 13/700) Job No.2.	4,06,638/-	10,000/-	One month	350/-
28	Restoration of rain damages on Kabristan Muth road (SH:- Construction of boulder Apron at RD 0/280 to 0/295) Job No.1.	4,71,715/-	9,500/-	Two months	350/-
29	Restoration of rain damages on Kabristan Muth road (SH:- Construction of boulder Apron at RD 0/280 to 0/295) Job No.2.	4,72,983/-	9,500/-	Two months	350/-

The tender documents shall be issued only to those contractor/firm who fulfill the following documents with the application.

1	The valid enlistment/Registration of contractor in Appropriate Class.
2	Permanent account No. (PAN No.).
3	G.S.T. No.
4	Earnest Money in the shape of National Saving certificate/time deposit account in the any of the post office in HP F.D.R. from any Nationalized Bank duly pleaded in favour of the Executive Engineer, Kullu Division HP.PWD, Kullu.

e

5	The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
6	The offer of the tender shall remain valid upto 90 days after the opening of tender.
7	Ambiguous/telephonic conditional tenders of tender by fax/E-mail not be considered and will be summarily be rejected.
8	Executive Engineer, reserve the right to reject or cancel any or all tenders without assigning any reasons.
9	If the date given above happens to be holiday the same shall be processed on next working day.
10	The contractor/firm must quote their rates in words as well as in figures failing which XEN reserve the right to accept/reject any or all tenders.
11	The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12	One contractor shall not have more than two major works in hand at a time.
13	Work should be completed by the contractor within stipulated period.
14	The rates beyond over +5% will be rejected, besides this the Additional Performance security will have to borne @ 20% & 30% for unbalanced bid in case rates is lower than 10% but upto 20% & lower than 20% upto 30% respectively. The tender beyond the limit of -30% will also be excepted.

No.PW/KD/TA/2023-2024-

Copy is forwarded to the following for information and necessary action:-

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, (MZ) HP.PWD, Mandi.
3. Superintending Engineer, 6th Circle HP.PWD, Kullu.
4. All the Executive Engineers, in HP.PWD,.
5. All the Assistant Engineers, working under this Division.
6. All the registered contractors, in HP.PWD.
7. Supdt./DA/HDM of this office.
8. Notice Board.

Executive Engineer,
Kullu Division,
HP.PWD, Kullu.

Dated:- 28-7-2023

Executive Engineer,
Kullu Division,
HP.PWD, Kullu.

CERTIFICATE

It is certified that the above works are required to be carried out immediately being emergent nature of work in the public interest.


**Executive Engineer,
Kullu Division, 
HP.PWD, Kullu.**

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Buins Bai Bhulang road Km 0/00 to 11/020.


(SH):- Construction of Retaining Wall at Km 5/160 to 5/172.50).

Estimated cost:-Rs. 426897/-only.

Earnest money :- Rs.8600/-only.

Time :- Three months

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material upto a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	27.38	365.35	Rupees Three hundred sixty five and paise thirty five only	Per Cubic metre	10003.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.00	4509.15	Rupees four thousand five hundred nine and paise fifteen only	Per cubic metre	40582.00
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	5.38	4957.40	Rupees four thousand nine hundred fifty seven and paise forty only	Per cubic metre	26671.00
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	35.80	5252.45	Rupees five thousand two hundred fifty two and paise forty five only.	Per Cubic metre	188038.00
5	Construction of dry rubble stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportation within all leads and lift of materials and as per direction of Engineer-in-charge.	41.99	2735.20	Rupees two thousand seven hundred thirty five and paise twenty only	Per cubic metre	114851.00
6	Back filling behind wing walls and return walls complete as per drawing and technical specification of Ministry of Rural Development for rural road as per drawing and technical specifications under clause 1204.3.8 including hauling/carriage of all labour equipment and material to various location through with in all leads and lift of materials and as per direction of engineer in charge.	29.13	1604.95	Rupees one Thousand six hundred four and paise ninty five only	Per Cubic metre	46752.00
					Total:-	426897.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

2

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Buins Bai Bhulang road Km 0/00 to 11/020.
(SH:- Construction of Retaining Wall at Km 7/100 to 7/112.50).

Estimated cost:-Rs. 422926/-only.
Earnest money :- Rs. 8500/-only.
Tinge :- Three months

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material upto a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	35.75	365.35	Rupees Three hundred sixty five and paise thirty five only	Per Cubic metre	13061.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.00	4509.15	Rupees four thousand five hundred nine and paise fifteen only	Per cubic metre	40582.00
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	5.38	4957.40	Rupees four thousand nine hundred fifty seven and paise forty only	Per cubic metre	26671.00
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	35.80	5252.45	Rupees five thousand two hundred fifty two and paise forty five only.	Per Cubic metre	188038.00
5	Construction of dry rubble stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportation within all leads and lift of materials and as per direction of Engineer-in-charge.	41.99	2735.20	Rupees two thousand seven hundred thirty five and paise twenty only	Per cubic metre	114851.00
6	Back filling behind wing walls and return walls complete as per drawing and technical specification of Ministry of Rural Development for rural road as per drawing and technical specifications under clause 1204.3.8 including hauling/carriage of all labour equipment and material to various location through with in all leads and lift of materials and as pr direction of engineer in charge.	24.75	1604.95	Rupees one Thousand six hundred four and paise ninty five only	Per Cubic metre	39723.00
					Total:-	422926.00

Executive Engineer,
Kullu Division
HP.PWD Kullu.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Buins Bai Bhulang road Km 0/00 to 11/020.
(SH)- Construction of Retaining Wall at Km 8/700 to 8/712.50).

Estimated cost:-Rs. 422926/-only.
Earnest money :- Rs. 8500/-only.
Time :-Three months

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material upto a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	35.75	365.35	Rupees Three hundred sixty five and paise thirty five only	Per Cubic metre	13061.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.00	4509.15	Rupees four thousand five hundred nine and paise fifteen only	Per cubic metre	40582.00
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	5.38	4957.40	Rupees four thousand nine hundred fifty seven and paise forty only	Per cubic metre	26671.00
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	35.80	5252.45	Rupees five thousand two hundred fifty two and paise forty five only.	Per Cubic metre	188038.00
5	Construction of dry rubble stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportation within all leads and lift of materials and as per direction of Engineer-in-charge.	41.99	2735.20	Rupees two thousand seven hundred thirty five and paise twenty only	Per cubic metre	114851.00
6	Back filling behind wing walls and return walls complete as per drawing and technical specification of Ministry of Rural Development for rural road as per drawing and technical specifications under clause 1204.3.8 including hauling/carriage of all labour equipment and material to various location through with in all leads and lift of materials and as pr direction of engineer in charge.	24.75	1604.95	Rupees one Thousand six hundred four and paise ninty five only	Per Cubic metre	39723.00
					Total:-	422926.00

Executive Engineer,
Kullu Division
HP.PWD Kullu.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Buins Bai Bhulang road Km 0/00 to 11/020.
(SH:- Construction of Retaining Wall at Km 81815 to 8/827.50).

Estimated cost:-Rs. 427335/-only.
Earnest money :- Rs. 8600/-only.
Time :- Three months

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material upto a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	26.38	365.35	Rupees Three hundred sixty five and paise thirty five only	Per Cubic metre	9638.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.00	4509.15	Rupees four thousand five hundred nine and paise fifteen only	Per cubic metre	40582.00
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	5.38	4957.40	Rupees four thousand nine hundred fifty seven and paise forty only	Per cubic metre	26671.00
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	35.80	5252.45	Rupees five thousand two hundred fifty two and paise forty five only.	Per Cubic metre	188038.00
5	Construction of dry rubble stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportation within all leads and lift of materials and as per direction of Engineer-in-charge.	41.99	2735.20	Rupees two thousand seven hundred thirty five and paise twenty only	Per cubic metre	114851.00
6	Back filling behind wing walls and return walls complete as per drawing and technical specification of Ministry of Rural Development for rural road as per drawing and technical specifications under clause 1204.3.8 including hauling/carriage of all labour equipment and material to various location through with in all leads and lift of materials and as pr direction of engineer in charge.	29.63	1604.95	Rupees one Thousand six hundred four and paise ninty five only	Per Cubic metre	47555.00
					Total:-	427335.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

5

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,54,186.00
 Earnest money :- Rs. 9,100.00
 Time :- Two months

Name of work:- Restoration of rain damages on Dohranallah Barahar road Km 0/0 to 10/120 (SH:- C/O R/wall at RD. 4/580 to 4/600).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	60.90	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	22250
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:6:12 (One cement :Six sand : Twelve graded stone) for nominal mix 25 mm (Twenty five millimetre) aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.80	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	44190
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	37.32	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	196021
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	63.23	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	172947
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	11.70	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	18778
					Total	454186

Executive Engineer,
 Kullu Division
 HP.PWD Kullu

Estimated cost:- Rs. 4,55,202.00
Earnest money :- Rs. 9,200.00
Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Badah Pahnallah road Km 0/0 to 9/700 (SH:- C/O R/wall on Pushta at RD. 4/210 to 4/230).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	65.00	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	23748
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:6:12 (One cement :Six sand : Twelve graded stone) for nominal mix 25 mm (Twenty five millimetre) aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.80	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	44190
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	37.32	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	196021
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	63.23	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	172947
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	11.40	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	18296
					Total	455202

Executive Engineer,
Kullu Division ,
HP.PWD Kullu

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,84,737.00
Earnest money :- Rs. 9,700.00
Time :- Two months

Name of work:- Restoration of rain damages on Kolibeher Barahar road Km 0/0 to 5/0 (SH:- C/O R/wall at RD. 2/400 to 2/415).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	63.00	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	23017
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone) aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	10.80	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	48699
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :Four sand : eight graded stone aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in- charge.	6.45	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	31975
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	42.96	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	225645
5	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in- charge.	50.39	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	137827
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	10.95	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	17574
					Total	484737

Executive-Engineer,
Kullu Division
HP.PWD Kullu

8

Estimated cost:- Rs. 4,84,209.00
 Earnest money :- Rs. 9,700.00
 Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Kolibeher Barahar road Km 0/0 to 6/0 (SH:- C/O R/wall at RD. 2/415 to 2/430).

Sr. No.	Description	Qty	Figure	Words	Rate in	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	57.60	385.35	Rupees Three hundred sixty five and paise thirty five only		Per cubic metre	21044
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone) aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	10.80	4509.15	Rupees Four thousand five hundred nine and paise fifteen only		Per cubic metre	48699
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :Four sand : eight graded stone aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in-charge.	6.45	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only		Per cubic metre	31975
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	42.96	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only		Per cubic metre	225645
5	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704,6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	50.39	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only		Per cubic metre	137827
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	11.85	1604.95	Rupees One thousand six hundred four and paise ninety five only		Per cubic metre	19019
						Total	484209

Executive Engineer,
 Kullu Division,
 HP.PWD Kullu.

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,89,807.00
Earnest money :- Rs. 9,800.00
Time :- Two months

Name of work:- Restoration of rain damages on Dohranallah Kharihar road Km 0/0 to 10/120 (SH:- C/O R/wall on Pushta at RD. 2/500 to 2/509).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	57.10	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	20861
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:4:8 (One cement :Four sand : eight graded stone) aggregate nominal mix 25 mm (Twenty five millimetre) in open foundations complete as per drawing and technical specification clause 802.803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in-charge.	46.80	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	232006
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	26.84	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	140976
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	29.17	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	79786
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	10.08	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	16178
					Total	489807


Executive Engineer,
Kullu Division
HP.PWD Kullu

Estimated cost:- Rs. 4,45,489.00
Earnest money :- Rs. 9,000.00
Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bari Padhru Tharku Pechha road (SH:- C/O B/wall at RD. 2/180 to 2/205).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area manual means including cutting and trimming of slopes and disposal of cut material with a lift upto 1.5 m (One point five metre) and lead upto 20 m (Twenty metre) as per drawing and technical specification as per Clause 1603.1.1 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	189.80	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	43341
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	20.20	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	7380
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	48.96	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	257160
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	50.31	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	137608
					Total	445489


Executive Engineer,
Kullu Division
HP.PWD Kullu

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,99,231.00
Earnest money :- Rs. 10,000.00
Time :- Two months

Name of work:- Restoration of rain damages on Tharku Pechha road (SH:- C/O PCC R/wall at RD 1/950 to 1/966).

Sr. No.	Description	Qty	Figure	Words	Rate in	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	45.76	365.35	Rupees Three hundred sixty five and paise thirty five only		Per cubic metre	16718
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:8:12 (One cement :Six sand : Twelve graded stone) for nominal mix 25 mm (Twenty five millimetre) aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	6.08	4509.15	Rupees Four thousand five hundred nine and paise fifteen only		Per cubic metre	27416
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :Four sand : eight graded stone aggregate 25 mm Twenty five millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203, within all leads and lift of materials and as per direction of Engineer-in-charge.	82.66	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only		Per cubic metre	409779
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	12.16	1604.95	Rupees One thousand six hundred four and paise ninety five only		Per cubic metre	19516
5	Providing waepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100 mm (One hundred millimetre) dia PVC pipe extending through the full width of the structure with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 719, 1204.3.7	66.00	390.95	Rupees Three hundred ninety and paise ninety five only		Each	25802
						Total	499231


Executive Engineer,
Kullu Division ,
HP.PWD Kullu

12

Estimated cost:- Rs. 4,54,931.00
Earnest money :- Rs. 9,100.00
Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Tharku Pechha road (SH:- C/O R/wall at RD. 0/080 to 0/100).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	50.20	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	18341
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:6:12 (One cement :Six sand : Twelve graded stone) for nominal mix foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.80	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	44190
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	37.32	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	196021
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	63.23	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	172947
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	14.60	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	23432
					Total	454931

Executive Engineer,
Kullu Division,
HP.PWD Kullu

13

Estimated cost:- Rs. 4,84,338.00
 Earnest money :- Rs. 9,700.00
 Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Tharku Pechha road (SH:- C/O R/wall on Pushta at RD. 0/830 to 0/845).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	54.00	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	19729
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:6:12 (One cement :Six sand : Twelve graded stone) for nominal mix 25 mm (Twenty five millimetre) aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	10.80	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	48699
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :Four sand : eight graded stone aggregate 25 mm Twenty five millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in- charge.	6.45	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	31975
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	42.96	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	225645
5	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in- charge.	50.39	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	137827
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	12.75	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	20463
					Total	484338

Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

Estimated cost:- Rs. 4,82,856.00
Earnest money :- Rs. 9,700.00
Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- R.R.D on Bhuthi Bhaliyani road 0/00 to 4/500 (SH:- C/O R/wall at RD. 2/530 to 2/551).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	46.83	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	17109
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone) aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	10.29	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	46399
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	35.70	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	187512
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	69.88	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	191136
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	16.59	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	26626
6	P/L PVC Weep hole 100 mm (One hundred millimeter) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	36.00	390.95	Rupees Three hundred ninety and paise ninety five only	Per cubic metre	14074
					Total	482856

Executive Engineer,
Kullu Division
HP.PWD Kullu

15

Estimated cost:- Rs. 3,63,082.00
Earnest money :- Rs. 7,300.00
Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- R.R.D on Kullu Karon road Km 0/00 to 15/000 (SH:- C/O B/wall at RD. 7/090 to 7/115).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with a lift upto 1.5 m (One point five metre) and lead upto 20 m (Twenty metre) as per drawing and technical specification as per Clause 1603.1.1 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	37.00	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	13518
2	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	60.50	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	317773
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	12.50	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	20062
4	Weep holes 100 mm (One hundred millimeter) dia within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	30.00	390.95	Rupees Three hundred ninety and paise ninety five only	Each	11729
					Total	363082

Executive Engineer,
Kullu Division,
HP.PWD Kullu

Estimated cost:- Rs. 4,99,708.00
Earnest money :- Rs. 10,000.00
Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- R.R.D on Kullu Karon road Km 0/00 to 15/000 (SH:- C/O B/wall at RD. 6/980 to 7/999).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	83.03	228.35	Rupees Two hundred twenty eight and paisa thirty five only	Per cubic metre	18960
2	Excavation in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with a lift upto 1.5 m (One point five metre) and lead upto 20 m (Twenty metre) as per drawing and technical specification as per Clause 1603.1.1 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	15.05	365.35	Rupees Three hundred sixty five and paisa thirty five only	Per cubic metre	5499
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702.704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	55.87	5252.45	Rupees Five thousand two hundred fifty two and paisa forty five only	Per cubic metre	293454
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in- charge.	64.75	2735.20	Rupees Two thousand seven hundred thirty five and paisa twenty only	Per cubic metre	177104
5	Weep holes 100 mm (One hundred millimeter) dia within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	12.00	390.95	Rupees Three hundred ninety and paisa ninety five only	Each	4691
					Total	499708

Executive Engineer,
Kullu Division
HP.PWD Kullu

Estimated cost- Rs. 3,43,030.00
Earnest money :- Rs. 6,900.00
Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- R.R.D on Bhuthi Bhaliyani road 0/00 to 4/500 (SH:- C/O R/wall at RD.1/145 to 1/160).

Sr. No.	Description	Qty	Figure	Words	Rate in	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	36.60	365.35	Rupees Three hundred sixty five and paise thirty five only		Per cubic metre	13372
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone) aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	7.84	4509.15	Rupees Four thousand five hundred nine and paise fifteen only		Per cubic metre	35352
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	25.50	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only		Per cubic metre	133937
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	49.92	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only		Per cubic metre	136541
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.00	1604.95	Rupees One thousand four and paise ninety five only		Per cubic metre	14445
6	P/L PVC Weep hole 100 mm (One hundred millimeter) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	24.00	390.95	Rupees Three hundred ninety and paise ninety five only		Per cubic metre	9383
						Total	343030

Executive Engineer,
Kullu Division
HP.PWD Kullu

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,64,350.00
 Earnest money :- Rs. 9,300.00
 Time :- Two months

Name of work:- R.R.D on Bhuthi Bhaliyani road 0/00 to 4/500 (SH:- C/O R/wall at RD.0/820 to 0/830 & 3/210 to 3/223).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	50.18	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	18333
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone) aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	10.49	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	47301
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	35.44	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	186147
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	64.11	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	175354
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	15.88	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	25487
6	P/L PVC Weep hole 100 mm (One hundred millimeter) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	30.00	390.95	Rupees Three hundred ninety and paise ninety five only	Per cubic metre	11728
					Total	464350

Executive Engineer,
 Kullu Division
 HP.PWD Kullu

19

Estimated cost:- Rs. 3,79,116.00
 Earnest money :- Rs. 7,600.00
 Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- R.R.D on Chharour Nallah to Kashawari road Km 0/0 to 8/010 (SH:- C/O R/wall with PCC toe wall at RD 3/225 to 3/245).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) , dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	32.10	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	11728
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	8.60	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	38779
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	30.20	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	158624
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in- charge.	45.60	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	124725
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	28.20	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	45260
					Total	379116


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

DRAFT SCHEDULE OF QUANTITY

Name of work:- R.R.D on Chharour Nallah to Kashawari road Km 0/0 to 4/070 (SH:- Removal of slips at various RD's).

Estimated cost:- Rs. 2,35,551.00
Earnest money :- Rs. 4,800.00
Time :- Two months

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.50 m (One point fifty metre) and lead upto 1000 m (One thousand metre) a sper technical specification 302.5 and 1611 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	1882.90	125.10	Rupees One hundred twenty five and paissa ten only	Per cubic metre	235551
					Total	235551

Executive Engineer,
Kullu Division ,
HP.PWD Kullu


21

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 1,48,556.00
Earnest money :- Rs. 3,000.00
Time :- Two months

Name of work:- R.R.D on Chharour Nallah to Kashawari road Km 0/0 to 4/070 (SH:- Removal of slips at various RD).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.50 m (One point fifty metre) and lead upto 1000 m (One thousand metre) a sper technical specification 302.5 and 1611 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	1187.50	125.10	Rupees One hundred twenty five and paisa ten only	Per cubic metre	148556
					Total	148556


Executive Engineer,
Kullu Division
HP.PWD Kullu

22

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,71,193.00
 Earnest money :- Rs. 9,500.00
 Time :- Two months

Name of work:- R.R.D on Chharour Nallah to Kashawari road Km 0/0 to 8/010 (SH:- C/O R/wall with PCC toe wall at RD 0/635 to 0/645).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	36.00	365.35	Rupees Three hundred sixty five and paisa thirty five only	Per cubic metre	13153
2	Providing and laying concrete for plain/ reinforced concrete 1:3:6 (One cement : Three sand : Six graded stone) aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in-charge.	30.00	5212.70	Rupees Five thousand two hundred twelve and paise seventy only	Per cubic metre	156381
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement : Four sand : eight graded stone) aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in-charge.	4.30	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	21317
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	28.64	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	150430
5	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	33.59	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	91875
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	23.70	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	38037
					Total	471193

 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,71,113.00
Earnest money :- Rs. 9,500.00
Time :- Two months

Name of work:- R.R.D on Chharour Nallah to Kashawari road Km 0/0 to 8/010 (SH:- C/O R/wall with PCC toe wall at RD 0/625 to 0/635).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer in- charge.	37.10	365.35	Rupees Three hundred sixty five and paisa thirty five only	Per cubic metre	13554
2	Providing and laying concrete for plain/ reinforced concrete 1:3:6 (One cement : Three sand : Six graded stone) aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in- charge.	30.00	5212.70	Rupees Five thousand two hundred twelve and paise seventy only	Per cubic metre	156381
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :Four sand : eight graded stone) aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in- charge.	4.30	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	21317
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	28.64	5252.45	Rupees Five thousand two hundred fifty two and paisa forty five only	Per cubic metre	150430
5	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in- charge.	33.59	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	91875
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	23.40	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	37556
					Total	471113

Executive Engineer,
Kufu Division,
HP.PWD Kullu

24

Estimated cost:- Rs. 4,66,184.00
 Earnest money :- Rs. 9,400.00
 Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- R.R.D on Chharour Nallah to Kashawari road Km 0/0 to 8/010 (SH:- C/O R/wall with PCC toe wall at RD 0/300 to 0/310).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	34.15	365.35	Rupees Three hundred sixty five and paisa thirty five only	Per cubic metre	12477
2	Providing and laying concrete for plain/ reinforced concrete 1:3:6 (One cement : Three sand : Six graded stone) aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in- charge.	30.00	5212.70	Rupees Five thousand two hundred twelve and paise seventy only	Per cubic metre	156381
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :Four sand : eight graded stone) aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in- charge.	4.30	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	21317
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	28.64	5252.45	Rupees Five thousand two hundred fifty two and paisa forty five only	Per cubic metre	150430
5	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in- charge.	33.59	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	91875
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	21.00	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	33704
					Total	466184


 Executive Engineer,
 Kullu Division ,
 HP.PWS Kullu

25

Estimated cost:- Rs. 4,65,921.00
 Earnest money :- Rs. 9,400.00
 Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- R.R.D on Chharour Nallah to Kashawari road Km 0/0 to 8/010 (SH:- C/O R/wall with PCC toe wall at RD 0/290 to 0/300).

Sr. No.	Description	Qty	Rate In		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	34.75	365.35	Rupees Three hundred sixty five and paisa thirty five only	Per cubic metre	12696
2	Providing and laying concrete for plain/ reinforced concrete 1:3:6 (One cement : Three sand : Six graded stone) aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in-charge.	30.00	5212.70	Rupees Five thousand two hundred twelve and paise seventy only	Per cubic metre	156381
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :Four sand : eight graded stone) aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in-charge.	4.30	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	21317
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	28.64	5252.45	Rupees Five thousand two hundred fifty two and paisa forty five only	Per cubic metre	150430
5	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	33.59	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only	Per cubic metre	91875
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	20.70	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	33222
					Total	465921

 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu

26

Estimated cost:-406638.00
 Earnest money :10000.00
 Time :-one month

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Sharni pini road km. 0/0 to 15/ 180
 (SH:- Removal of slips in km 0/0 to 13/700 (Job No.-I)

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials upto any and any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3250.50	125.10	Rupees One hundred twenty five and paise ten only.	Per cubic metre	406638.00
					Total	406638.00


 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu.

27

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-406638.00
Earnest money :10000.00
Time :one month

Name of work:- Restoration of rain damages on Sharni pini road km. 0/0 to 15/ 180
(SH:- Removal of slips in km 0/0 to 13/700 (Job No.-II)

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials upto any and any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3250.50	125.10	Rupees One hundred twenty five and paise ten only.	Per cubic metre	406638.00
					Total	406638.00


Executive Engineer,
Kullu Division ,
HP.PWD,Kullu.

28

Estimated cost:- Rs. 471715.00
 Earnest money :- Rs. 10000.00
 Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- Resto ration of rain damages on Kabristan muth road SH:- C/O Boulder apron at RD 0/280 to 0/295). Job No.-I

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	112.50	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	25689
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	22.50	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	8220
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :Four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in-charge.	22.50	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	111542
4	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 150mm x 150mm (One hundred fifty millimetre x One hundred fifty millimetre) mesh (woven diagonally) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg. (Twenty five kilogram) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge.	117.18	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only.	Per cubic metre	326264
					Total	471715

Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu

29

Estimated cost:- Rs. 472983.00
 Earnest money :- Rs. 10000.00
 Time :- Two months

DRAFT SCHEDULE OF QUANTITY

Name of work:- Resto ration of rain damages on Kabristan muth road SH:- C/O Boulder apron at RD 0/295 to 0/310). Job No.-II

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	118.05	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	26957
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	22.50	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	8220
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement :Four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in-charge.	22.50	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	111542
4	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) diameter wire conforming to IS: 280 and IS: 4826 in 150mm x 150mm (One hundred fifty millimetre x One hundred fifty millimetre) mesh (woven diagonally) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg. (Twenty five kilogram) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge.	117.18	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only.	Per cubic metre	326264
					Total	472983

 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu