



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140

Fax No. 01904-255740

No.-PW/OSDN/ Tender-NIT/2023-24 **6478-88**

Dated **07-08-2023**

To

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.

Subject:-

Publication of Tender Notice.

Jai Hind

Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

**DA/ Notice inviting tender/Schedule of Quantity
And "A" Certificate**

**Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.**

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.

**Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.**



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD, Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140

Fax No. 01904-255740



NOTICE INVITING TENDER


Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD, for the following works, so as to reach this office on **16.08.2023** up to 10.30 A.M. and same will be opened on the same day at 11.00 a.m. in presence of the interested contractors or their authorized representative. The tender form can be had from the office of Executive Engineer Outer Seraj Division HP.PWD, Nirmand on cash payment (Non- refundable) on or before **14.08.2023** during office hours till 1.00 p.m. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued . The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected .The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF** failing which no tender form will be issued to him.

1	A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O P.C.C. R/Walls at RD. 24/150 to 24/156.50)	494878.00	10000.00	One month
2	A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O P.C.C. R/Walls at RD. 24/156.50 to 24/160)	266613.00	6000.00	One month
3	A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O R/Walls at RD. 25/284.80 to 25/296)	496091.00	10000.00	One month
4	A/R & M/O link road to villge Sarapara km. 0/00 to 1/420 (SH:- Earth filling behind abutments of RCC Slab Culvert at RD 0/450)	191349.00	4000.00	One month
5	Restoration of rain damages on Nore to Wazir Bowali road km. 0/00 to 37/00 (Sub Head:- Construction of R/Wall at RD. 18/780 to 18/813)	470820.00	10000.00	Two months

	Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH:-C/O retaining wall at RD. 3/762 to 3/782.80. UNDER BASP	432165.00	10000.00	Two months
7	Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH:-C/O retaining wall at RD. 4/545 to 4/559. UNDER BASP	432165.00	10000.00	Two months
8	Construction of Link road from Moin to Gothna km 0/00 to 2/600 (SH:-Balance work of F/C 5/7 mtrs wide in km 2/240 to 2/375)	464794.00	10000.00	One month
9	Construction of Link road from Moin to Gothna km 0/00 to 2/600 (SH:-Balance work of F/C 5/7 mtrs wide in km 2/375 to 2/465)	493696.00	10000.00	One month
10	Construction of link road from Deorikhad to Burjikhad km. 0/00 to 2/500 under MNP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 1/975 to 2/090)	450421.00	10000.00	Three months
11	Construction of link road from Deorikhad to Burjikhad km. 0/00 to 2/500 under MNP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 2/090 to 2/170)	494934.00	10000.00	Three months
12	Restoration of rain damages on Bakhan to Kharga road Km. 0/00 to 9/840. (SH:- Hiring of L&T PC 210 crawler mounted hydaurlic excavator for removal of slips, dressing of road surface and construction of road side kutchra drain in Km. 0/00 to 9/840).	495000.00	10000.00	Three months
13	Restoration of rain damages on Shroo to Kapti road Km. 0/00 to 7/700. (SH:- Hiring of L&T PC 210 crawler mounted hydaurlic excavator for removal of slips, dressing of road surface and construction of road side kutchra drain in Km. 0/00 to 7/700).	405000.00	10000.00	Three months
14	Restoration of rain damages on Wazir Bowali to Mohali road Km. 0/00 to 26/00. (SH:- Hiring of L&T PC 210 crawler mounted hydaurlic excavator for removal of slips, dressing of road surface and construction of road side kutchra drain in Km. 0/00 to 26/00).	495000.00	10000.00	Three months
15	Restoration of rain damages on Koil to Neethar road Km. 0/00 to 18/360. (SH:- Hiring of L&T PC 210 crawler mounted hydaurlic excavator for removal of slips, dressing of road surface and construction of road side kutchra drain in Km. 0/00 to 18/360).	360000.00	8000.00	Three months
16	Restoration of rain damages on Bakhan to Kharga road Km. 0/00 to 9/840. (SH:- Hiring of Tpiier for carriage of excavated earth for removal upto dumping sites and shifting of other material in Km. 0/00 to 9/840).	112860.00	4000.00	One month
17	Restoration of rain damages on Nore to Neethar road Km. 0/00 tom 65/765. (SH:- Hiring of Tpiier for carriage of excavated earth for removal upto dumping sites and shifting of other material in Km. 0/00 to 23/00).	189810.00	4000.00	One month

8	Restoration of rain damages on Punan to Gad Deem road Km. 0/00 to 10/345. (SH:- Construction of wire crate Breast Wall at Rd 3/360 to 3/392 and 0/720 to 0/754, 7/960 to 7/984).	475415.00	10000.00	One month
19	Restoration of rain damages on Punan to Gad Deem road Km. 0/00 to 10/345. (SH:- Construction of wire crate Breast Wall at Rd 6/720 to 6/758 and 7/750 to 7/786).	489543.00	10000.00	One month
20	Restoration of rain damages on Farbog to Thach road Km. 0/00 to 3/075. (SH:- Construction of wire crate R/Wall at Rd 1/985 to 2/00 and 2/330 to 2/345).	435643.00	10000.00	One month
21	Restoration of rain damages on Ranabag to Karshaigad road Km. 0/00 to 14/510. (SH:- Construction of wire crate R/Wall at Rd 10/230 to 10/250).	386999.00	8000.00	One month
22	Restoration of rain damages on Nore to Luhri road (MDR-120) Km. 0/00 to 65/765. (SH:- Construction of R/Wall at Rd 41/570 to 41/585).	447386.00	10000.00	Two months
23	Restoration of rain damages on Nore to Luhri road (MDR-120) Km. 0/00 to 65/765. (SH:- Construction of R/Wall at Rd 36/790 to 36/802).	366069.00	8000.00	Two months
24	Restoration of rain damages on Pipal Hatti to Bhatkiol road Km. 0/00 to 1/00. (SH:- Construction of wire crated B/Wall at Rd 0/800 to 0/880).	367339.00	8000.00	one month

HIM SUCHANA AVAM JAN SAMPARK


Executive Engineer
Outer Seraj Division
H.P PWD, Nirmand
on behalf of Governor of Himachal Pradesh



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand

Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in


Phone No.-01904-255140

Fax No. 01904-255740



Certificate

Certified that the tenders called vide this Office letter No.-PW/OSDN/TA/Tender-NIT/2023-24- 6478-88 dated 07.08.2023 is very urgent nature. So may be uploaded on Departmental website in public interest please.


Executive Engineer
Outer Seraj Division
H.P PWD, Nirmand

on behalf of Governor of Himachal Pradesh

Schedule of quantity

Executive Engineer
Outer Garaj Division
UppwD, Khammam

Executive Engineer
Outer Garaj Division
UppwD, Khammam

Schedule of quantity

Schedule of quantity									
Name of Work:- A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O P.C.C. R/Walls at RD. 24/156.50 to 24/160)				Estimated cost:-		266613.00			
				Earnest Money		6000			
				Time		One month			
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Words	AMOUNT	
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	10.68	Cubic Metre	327.60	Rupees Three Hundred & Twenty Seven - Paise Sixty Only			3499.00	
	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	11.83	Cubic Metre	524.10	Rupees Five Hundred & Twenty Four - Paise Ten Only			6200.00	
2	Providing and Laying plain cement concrete 1:3:6 (one cement : three sand : six graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	40.29	Cubic Metre	6185.60	Rupees Six Thousand One Hundred & Eighty Five - Paise Sixty Only			249218.00	
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.25	Cubic Metre	1322.29	Rupees One Thousand Three Hundred & Twenty			6942.00	
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	2.00	Each	377.00	Rupees Three Hundred & Seventy Seven Only			754.00	
Total in Figures								266613.00	
Rate quoted by contractor +/-						Percent			
quoted rate in figure									
Quoted rate in workds									

Executive Engineer
Outer Soral Division
UPPWD, Mirzapur

Schedule of quantity

Name of Work:- A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O R/Walls at RD. 25/284.80 to 25/296)									
Estimated cost:-									
Earnest Money									
Time									
One month									
AMOUNT									
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Words	Amount	One month
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	16.80	Cubic Metre	327.60	Rupees Three Hundred & Twenty Seven - Paise Sixty Only	5504.00			
	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	19.71	Cubic Metre	524.10	Rupees Five Hundred & Twenty Four - Paise Ten Only	10330.00			
2	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.05	Cubic Metre	5313.47	Rupees Five Thousand Three Hundred & Thirteen - Paise Forty Seven Only	32146.00			
	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	71.46	Cubic Metre	6070.70	Rupees Six Thousand & Seventy - Paise Seventy Only	433812.00			
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.61	Cubic Metre	1364.83	Rupees One Thousand Three Hundred & Sixty Four - Paise Eighty Three	9022.00			
4	Providing weapholes in brick masonry / stone masonry (plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):2(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	14.00	Each	376.90	Rupees Three Hundred & Seventy Six - Paise Ninety Only	5277.00			
Total in Figures								496091.00	
Rate quoted by contractor +/-						Percent			
Quoted rate in figure									
Quoted rate in words									


 Engineer
 Outer Saraj Division
 Supply & Nirmand

(9)

Schedule of quantity

Name of Work:- A/R & M/O link road to village Sarapara km. 0/00 to 1/420 (SH:- Earth filling behind abutments of RCC Slab Culvert at RD 0/450)						
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	540.00	Cubic Metre	354.35	Rupees Three Hundred & Fifty Four - Paise Thirty Five Only	191349.00
						191349.00

Executive Engineer
Outer Seral Division
HPPWD, Jharkhand

5

Schedule of quantity									
Name of Work: Restoration of rain damages on Nore to Wazir Bowali road km. 0/00 to 37/00 (Sub Head:- Construction of R/Wall at RD. 18/780 to 18/813)				Estimated cost:-		470820.00			
				Earnest Money		10000.00			
				Time		Two months			
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Words	AMOUNT	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	21.78	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only			3886.00	
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	33.66	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only			13402.00	
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	11.21	Cubic Metre	4278.50	Rupees Four Thousand Two Hundred & Seventy Eight - Paise Fifty Only			47962.00	
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	48.77	Cubic Metre	4359.90	Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only			212632.00	
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	61.78	Cubic Metre	3025.00	Rupees Three Thousand & Twenty Three Only			186761.00	
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.80	Cubic Metre	1065.00	Rupees One Thousand & Sixty Five Only			6177.00	
Total in Figures								470820.00	
Rate quoted by contractor +/-						Percent			
Quoted rate in figure									
Quoted rate in words									

Executive Engineer
Outer Seral Division
HPPWD, Bhand

6

Schedule of quantity

Name of Work: Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH-C/O retaining wall at RD. 3/762 to 3/782.80). UNDER BASP									
Sl. No.	Description of work	Qty.	Unit	RATE		Estimated cost:-			
				Figures	Words				
							Time		
						Amount			
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	14.56	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Forty Only	2598.00			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	68.43	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	27245.00			
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	4.78	Cubic Metre	4254.50	Rupees Four Thousand Two Hundred & Fifty Four - Paise Fifty Only	20337.00			
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	87.36	Cubic Metre	4359.90	Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only	380881.00			
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20.00	Each	311.70	Rupees Three Hundred & Eleven - Paise Seventy Only	6234.00			
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	0.60	Cubic Metre	1265.00	Rupees One Thousand Two Hundred & Sixty Five Only	759.00			
Total in Figures						438054.00			
Rate quoted by contractor +/-						Percent			
Quoted rate in figure									
Quoted rate in words									


 Executive Engineer
 Outer Seraj Division
 HPPWD, Bikaner

(7)

Schedule of quantity

Name of Work: Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH-C/O retaining wall at RD. 4/545 to 4/559, UNDER BASP									
Sl. No.	Description of work	Qty.	Unit	RATE		Estimated cost:-	AMOUNT		
				Figures	Words		Earnest Money	Time	Two months
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	30.38	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only				5420.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 395.1 including setting out, construction of shoring and bracing, removal of stutrips and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	56.28	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only				22408.00
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	3.22	Cubic Metre	4254.50	Rupees Four Thousand Two Hundred & Fifty Four - Paise Fifty Only				13699.00
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications (Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	87.80	Cubic Metre	4359.90	Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only				382799.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	15.00	Each	311.70	Rupees Three Hundred & Eleven - Paise Seventy Only				4676.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	2.50	Cubic Metre	1265.00	Rupees One Thousand Two Hundred & Sixty Five Only				3163.00
Total in Figures									432165.00
Rate quoted by contractor +/-					Percent				
Quoted rate in figure									
Quoted rate in words									

Executive Engineer
Outer Saraj Division
HPPWD, Baramulla

20

Schedule of quantity

Schedule of quantity										
Name of Work: Construction of Link road from Moin to Gothna km 0/00 to 2/600 (SH:-Balance work of F/C 5/7 mtrs wide in km 2/240 to 2/575)										
				Estimated cost:-		464794.00				
				Earnest Money		10000				
				Time		One month				
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT			
					Words					
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 315.51 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2201.25	Cubic Metre	211.15	Rupees Two Hundred & Eleven - Paise Fifteen Only	464794.00				
Total in Figures							464794.00			
Rate quoted by contractor +/-							Percent			
quoted rate in figure										
Quoted rate in workds										

Executive Engineer
Outer Seraj District
UPPWD, Alimnand

9

Schedule of quantity									
Name of Work: Construction of Link road from Moin to Gothna km 0/00 to 2/600 (SH:-Balance work of F/C 5/7 mtrs wide in km 2/375 to 2/465)					Estimated cost:-		493696.00		
					Earnest Money		10000		
					Time		One month		
SL No.	Description of work	Qty.	Unit	Figures	RATE		Words	AMOUNT	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road. August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 335.13 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on pro rata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2338.13	Cubic Metre	211.15	Rupees Two Hundred & Eleven - Paise Fifteen Only			493696.00	
Total in Figures								493696.00	
Rate quoted by contractor +/-							Percent		
quoted rate in figure									
Quoted rate in words									

Executive Engineer
Outer Sarai Division
HPPWB, Nirmal

Schedule of quantity

Name of Work: Construction of link road from Deorikhad to Burjikhad km. 0/00 to 2/500 under MNP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 2/090 to 2/170)					Estimated cost:- Earnest Money Time Three months	494934.00 10000
SL No.	Description of work	Qty.	Unit	Figures	RATE	
					Words	AMOUNT
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 329.29cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on porta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1550.40	Cubic Metre	319.23	Rupees Three Hundred & Nineteen - Paise Twenty Three Only	494934.00
Total in Figures						494934.00
Rate quoted by contractor +/-					Percent	
Quoted rate in figure						
Quoted rate in words						


 Executive Engineer
 Outer Seraj Division
 UPPWD, Mirzapur

11

Schedule of quantity						
Name of Work: Construction of link road from Deorikhad to Burjikhad km. 0/00 to 2/500 under MNP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 1/975 to 2/090)				Estimated cost:- Earnest Money Time		450421.00 10000 Three months
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 282.35cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on pro rata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1689.12	Cubic Metre	266.66	Rupees Two Hundred & Sixty Six - Paise Sixty Six Only	450421.00
Total in Figures						450421.00
Rate quoted by contractor +/-				Percent		
Quoted rate in figure						
Quoted rate in words						


Executive Engineer
Outer Seral Division
HPPWD, Narmada

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Bakhan Kharga road km 0/00 to 9/840 (SH:- Hiring of L&T PC 210 crawler mounted hydraulic excavator for removal of slips, dressing of road surface and construction of road side kutcha drain in km. 0/00 to 9/840).

Estimated Cost Rs. 495000.00
Earnest Money Rs. 10000.00
Time :- Three months.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of L&T PC 210 crawler mounted hydraulic excavator with breaker for cutting, excavation, filling, dressing of road surface, construction of road side kutcha drain and removal of slips from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Shifting of the machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hour will be accounted for the payment. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel and machine operator and stays for machine operator will be provided by the owner of the machine. The repair and spare including watch and ward of machine and all admissible taxes also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. The scroll hour of the machine up to site of work will fully be born by the	110.00	4500.00	Rupees two thousand five hundred only	Per Hour	495,000.00
		Total in Figures				495000.00
		Rate quoted by contractor +/-				
		Quoted rate in figure				
		Quoted rate in words				
		Percent				


Executive Engineer,
Outer Seraj Division,
HPPWD, Demand.

1318

Estimated Cost Rs. 405000.00
Earnest Money Rs. 10000.00
Time :- Three months.

Executive Engineer,
Outer Seraj Division,
HPPWD Mirmand.

Executive Engineer,
Outer Seraj Division,
HPPWD Mirmand.

14

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Wazir Bowali to Mohali road km 0/00 to 26/00 (SH:- Hiring of L&T PC 210 crawler mounted hydraulic excavator for removal of slips, dressing of road surface and construction of road side kutchha drain in km. 0/00 to 26/00). Estimated Cost Rs. 495000.00
 Earnest Money Rs. 10000.00
 Time :- Three months.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of L&T PC 210 crawler mounted hydraulic excavator with breaker for cutting, excavation, filling, dressing of road surface, construction of road side kutch drain and removal of slips from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Shifting of the machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. only actual working hour will be accounted for the payment. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel and machine operator and stays for machine operator will be provided by the owner of the machine. The repair and spare including watch and ward of machine and all admissible taxes also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. The scroll hours of the machine up to site of work will fully be born by the	110.00	4500.00	Rupees two thousand five hundred only	Per Hour	495,000.00
		Total in Figures				495000.00
		Rate quoted by contractor +/-			Percent	
		quoted rate in figure				
		Quoted rate in words				


 Executive Engineer,
 Outer Serai Division,
 HPPWD, Noida.

SCHEDULE OF QUANTITY


Name of work :- Restoration of rain damages on Koll to Neether road km 0/00 to 18/360 (SH:- Hiring of L&T PC 210 crawler mounted hydraulic excavator for removal of slips, dressing of road surface and construction of road side kutch drain in km. 0/00 to 18/360).

Estimated Cost Rs. 360000.00

Earnest Money Rs. 8000.00

Time :- Three months.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of L&T PC 210 crawler mounted hydraulic excavator with breaker for cutting, excavation, filling, dressing of road surface, construction of road side kutch drain and removal of slips from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Shifting of the machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. only actual working hour will be accounted for the payment. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel and machine operator and stays for machine operator will be provided by the owner of the machine. The repair and spare including watch and ward of machine and all admissible taxes also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. The scroll hour of the machine up to site of work will fully be born by the	80.00	4500.00	Rupees two thousand five hundred only	Per Hour	360,000.00
		Total in Figures				360000.00
		Rate quoted by contractor +/-			Percent	
		quoted rate in figure				
		Quoted rate in words				


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Narmad.


SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Bakhan to Kharga road km 0/00 to 9/840 (SH:- Hiring of tipper for carriage of Estimated Cost Rs. 112860.00 excavated earth for removal up to dumping sites and shifting of other materials in km. 0/00 to 9/840 .)

Earnest Money Rs.4000/-

Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different site of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 8.00 hours (Eight hours) from 9.00 A.M. to 5.00 P.M. daily. Any loss to the public/ private property of any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him all cases. The fuel of the tipper driver, repair work shall have to be born by the contractor/ owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in-charge.	220.00	513.00	Rupees five hundred thirteen only	Per Hour	112,860.00
Total in Figures						112860.00
Rate quoted by contractor +/-				Percent		
quoted rate in figure						
Quoted rate in words						


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Narmad.

(17)

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Nore to Luhri road km 0/00 to 65/765 (SH:- Hiring of tipper for carriage of excavated earth for removal up to dumping sites and shifting of other materials in km. 0/00 to 23/00 .)

Estimated Cost Rs. 189810.00

Earnest Money Rs.4000/-

Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different site of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 8.00 hours (Eight hours) from 9.00 A.M. to 5.00 P.M. daily. Any loss to the public/ private property of any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him all cases. The fuel of the tipper driver, repair work shall have to be born by the contractor/ owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in-charge.	370.00	513.00	Rupees five hundred thirteen only	Per Hour	189,810.00
Total in Figures						189810.00
	Rate quoted by contractor +/-			Percent		
	quoted rate in figure					
	Quoted rate in words					

K. S. Choudhary
Executive Engineer,
Outer Seraj Division,
HPPWD, Noida.

Schedule of quantity

Schedule of quantity							
Name of Work: Restoration of rain damages on Punan to Gad deem road km 0/00 to 10/345 (SH: Construction of wire crate Breast wall at RD 3/360 to 3/392 and 0/720-0/754 , 7/960- 7/984)							
Sl. No.	Description of work	Qty.	Unit	Figures	Estimated cost:-		One month
					RATE		
					Words	AMOUNT	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	33.30	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only		5941.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	22.96	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only		9142.00
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the department free of cost)	255.74	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only		460332.00
Total in Figures							475415.00
Rate quoted by contractor +/-					Percent		
quoted rate in figure							
Quoted rate in words							


 Executive Engineer,
 Outer Seeraj Division,
 HPPWD Himnand.

Schedule of quantity

Name of Work: Restoration of rain damages on Punan to Gad deem road km 0.00 to 10.345 (SH: Construction of wire crate Breast wall at RD 6/720 - 6/758.40 and 7/750-7/786)							Estimated cost:- Earnest Money	489543.00
							Time	One month
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		Amount	
					Words	Amount		
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	17.02	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Forty Only	3036.00		
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	18.86	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	7509.00		
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the department free of cost)	266.11	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only	478998.00		
Total in Figures								489543.00
Rate quoted by contractor +/-							Percent	
quoted rate in figure								
Quoted rate in words								


 Executive Engineer,
 Outer Seraj Division,
 HPPWD D. D. Mand.

Schedule of quantity

Name of Work:- Restoration of rain damages on Farbog to Thach road km. 0/00 to 3/075 (SH:-C/O wire crated R/Wall at RD. 1/985 to 2/00 and 2/330 to 2/345)						
Sl. No.	Description of work	Qty.	Unit	RATE i.e GST & all taxes		AMOUNT
				Figures	Words	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	13.05	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Forty Only	2328.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	9.15	Cubic Metre	398.20	Rupees Three Hundred & Ninety Eight - Paise Twenty Only	3644.00
3	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS:280 and I.S.4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stones boulders of approved quality weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 complete including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge complete. (wire crates will be supplied by the department free of cost)	221.40	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only	398520.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	29.25	Cubic Metre	1065.00	Rupees One Thousand & Sixty Five Only	31151.00
Total in Figures						435643.00
Rate quoted by contractor +/-				Percent		
quoted rate in figure						
Quoted rate in words						


 Executive Engineer,
 Outer Seraj Division,
 HP PWD, Shimla.

(21)

Schedule of quantity

Name of Work:- Restoration of rain damages on Ranabag Karshaigad road km. 0/00 to 14/510 (SH:-C/O wire crated R/Wall at RD, 10/230 to 10/250)							Estimated cost:-	386999.00
							Earnest Money	8000
							Time	One month
Sl. No.	Description of work	Qty.	Unit	Figures	Words	RATE i.e GST & all taxes	AMOUNT	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	4.40	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only		785.00	
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	5.60	Cubic Metre	398.20	Rupees Three Hundred & Ninety Eight - Paise Twenty Only		2230.00	
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	43.20	Cubic Metre	4563.00	Rupees Four Thousand Five Hundred & Sixty Three Only		197122.00	
3	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS:280 and I.S.4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stones boulders of approved quality weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 complete including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge complete	64.80	Cubic Metre	2522.10	Rupees Two Thousand Five Hundred & Twenty Two - Paise Ten Only		163432.00	
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	22.00	Cubic Metre	1065.00	Rupees One Thousand & Sixty Five Only		23430.00	
Total in Figures							386999.00	
Rate quoted by contractor +/-							Percent	
quoted rate in figure								
Quoted rate in works								

Executive Engineer,
Outer Seta Division,
HP PWD
Jalandhar

Schedule of quantity

Name of Work: Restoration of rain damages on Nore to Lahri road (MDR-120) km. 0/00 to 65/765. (Sub Head:- Construction of R/Wall at RD.41/570 to 41/585)									
Sl. No.	Description of work	Qty.	Unit	RATE i.e GST & all taxes		Estimated cost:-	Earnest Money	Time	AMOUNT
				Figures	Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	20.00	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only	3568.00		Two months	10000.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	31.00	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	12343.00			
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.00	Cubic Metre	4278.50	Rupees Four Thousand Two Hundred & Seventy Eight - Paise Fifty Only	25671.00			
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	51.00	Cubic Metre	4359.90	Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only	222355.00			
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	64.00	Cubic Metre	2766.54	Rupees Two Thousand Seven Hundred & Sixty Six - Paise Fifty Four Only	177059.00			
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.00	Cubic Metre	1065.00	Rupees One Thousand & Sixty Five Only	6390.00			
Total in Figures									447386.00
Rate quoted by contractor +/-									
Quoted rate in figure									
Quoted rate in words									


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Narmad.

Schedule of quantity

Name of Work: Restoration of rain damages on Nore to Luhri road (MDR-120) km. 0/00 to 65/765. (Sub Head:- Construction of R Wall at RD.36/790 to 36/802)									
Sl. No.	Description of work	Qty.	Unit	RATE i.e GST & all taxes		Time	Estimated cost:-		Two months
				Figures	Words		Earnest Money	AMOUNT	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	32.00	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only			5709.00	
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	33.00	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only			13139.00	
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	10.00	Cubic Metre	4278.50	Rupees Four Thousand Two Hundred & Seventy Eight - Paise Fifty Only			42785.00	
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	37.00	Cubic Metre	4359.90	Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only			161316.00	
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	50.00	Cubic Metre	2766.54	Rupees Two Thousand Seven Hundred & Sixty Six - Paise Fifty Four Only			138327.00	
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	4.50	Cubic Metre	1065.00	Rupees One Thousand & Sixty Five Only			4793.00	
Total in Figures								366069.00	
Rate quoted by contractor +/-									
Quoted rate in figure									
Quoted rate in words									


 Executive Engineer,
 Outer Seroj Division,
 HPPWD, Noida.

24

Schedule of quantity

Name of Work: Restoration of rain damages on Pipal Hatti to Bhatkiol road km. 0/00 to 1/00 (SH-C/O wire crated B/Wall at RD. 0/800 to 0/380)									
				Estimated cost:-		367339.00			
				Earnest Money		8000			
				Time		One month			
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT			
				Figures	Words				
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	54.60	Cubic Metre	398 15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	21739.00			
2	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the depotment free of cost)	192.00	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only	345600.00			
				Total in Figures		367339.00			
				Rate quoted by contractor +/-					
				Percent					
				Quoted rate in figure					
				Quoted rate in workds					

Executive Engineer,
Outer Serai Division,
HPPWDD, Himmatnagar.