



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140
Fax No. 01904-255740

No.-PW/OSDN/ Tender-NIT/2023-24

6657-67

Dated 09-08-2023

To

Executive Engineer IT Cell,
Nigam Bihar, H.P. Shimla-2.

Subject:-

Publication of Tender Notice on Departmental site.

Jai Hind

Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

**DA/ Notice inviting tender/Schedule of Quantity
And "A" Certificate**

[Signature]
Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Notice Board.

[Signature]
Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140
Fax No. 01904-255740



NOTICE INVITING TENDER

Sealed item rate tender on form 6 & 8 are hereby invited by Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the eligible contractors enlisted in HP.PWD, for the following works, so as to reach this office on **17.08.2023** at 10.30 A.M. and same will be opened on the same day at 11.00 a.m. in presence of the interested contractor or their authorized representative. The tender form can be had from the office of Executive Engineer Outer Seraj Division HP.PWD, Nirmand on cash payment (Non- refundable) on or before **16.08.2023** during of hours till 1.00 p.m. The application must be accompanied with earnest money in shape of NSD/FDR/Ti deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall kept open for 90 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, Etc.** failing which no tender form will be issued to him.

1	Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH:-C/O retaining wall at RD.4/597 to 4/614). UNDER BASP	413110.00	10000.00	One month
2	Restoration of rain damages on Ranabag to Kandibad road Km. 0/00 to 10/800. (SH:- C/o wire crated R/wall at RD. 8/275 to 8/304).	415679.00	10000.00	One month
3	Restoration of rain damages on Ranabag to Kandibad road Km. 0/00 to 10/800. (SH:- C/o PCC R/wall at RD. 9/120 to 9/145).	479370.00	10000.00	One month
4	Restoration of rain damages on Panetanal to Bishal road Km. 0/00 to 3/470. (Sub Head:- Construction of wire crated R/wall at Rd. 0/450 to 0/522).	190031.00	4000.00	One month
5	Extention of Raja Raghuvir Stadium at Anni District kullu H.P. (SH:-C/o 10.20 meter long R/wall in ground) under deposit work	413142.00	10000.00	One month

6	Restoration of rain damages on Chouradhar to Paneo road Km. 0/00 to 8/015. (SH:-C/o R/wall at Rd. 2/465 to 2/479).	389911.00	8000.00	Two months
7	Restoration of rain damages on Soidhar to Beungal road Km. 0/00 to 9/855. (SH:- C/o PPC R/wall at RD. 3/555.50 to 3/561).	225845.00	5000.00	Two months
8	Restoration of rain damages on Jaon to Buchhair road Km. 0/00 to 5/00. (SH:- C/o wire crate B/wall at Rd. 2/435 to 2/483).	259836.00	5000.00	One month
9	Restoration of rain damages on Gugra to Kutwa road Km. 0/00 to 10/400. (SH:- C/o wire crate B/wall at Rd. 5/675 to 5/695).	104125.00	2000.00	One month
10	Restoration of rain damages on Punan to Gad Deem road Km. 0/00 to 10/345. (SH:- Construction of wire crate Breast Wall at Rd 3/720 to 3/734).	488511.00	10000.00	two months
11	Restoration of rain damages on Behna to Dalash road upto Kandagai road Km. 0/00 to 17/345. (SH:- Construction of wire crate R/ Wall at Rd 9/210 to 9/235).	378023.00	7500.00	One month
12	Restoration of rain damages on Behna to Dalash road upto Kandagai road Km. 0/00 to 17/345. (SH:- Construction of wire crate B/ Wall at Rd 7/420 to 7/435 and 8/885 to 8/900).	188763.00	4000.00	One month
13	Restoration of rain damages on Behna to Dalash road upto Kandagai road Km. 0/00 to 17/345. (SH:- Construction of wire crate B/ Walls at Rd 16/930 to 16/960 and 17/015 to 17/030).	283146.00	6000.00	One month
14	Restoration of rain damages on Behna to Dalash road upto Kandagai road Km. 0/00 to 17/345. (SH:- Construction of wire crate R/ Walls at Rd 16/410 to 16/430 and 16/840 to 16/865).	361319.00	7500.00	One month
15	Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH:-C/O retaining wall at RD.5/420 to 5/432). UNDER BASP	432619.00	10000.00	One month
16	Restoration of rain damages on Anni Basta road Km. 0/00 to 20/210. (SH:- Construction of wire crate R/ Walls at Rd 12/945 to 12/965 and 10/255 to 10/270).	366549.00	7500.00	One month
17	Restoration of rain damages on Anni Basta road Km. 0/00 to 20/210. (SH:- Construction of wire crate R/ Walls at Rd 8/945 to 8/965, 13/594 to 13/610 and B/wall at RD 12/395 to 12/415).	439467.00	9000.00	One month
18	Restoration of rain damages on Anni Basta road Km. 0/00 to 20/210. (SH:- Construction of wire crate B/walls and R/ Walls at Rd 8/540 to 8/560, 8/580 to 8/600 and 8/870 to 8/885).	487162.00	10000.00	One month
19	Restoration of rain damages on Anni Basta road Km. 0/00 to 20/210. (SH:- Construction of wire crate R/ Wall at Rd 11/970 to 11/995).	378023.00	8000.00	One month

20	Restoration of rain damages on LDCK road Km. 11/00 to 37/00. (SH:- Construction of wire crate R/wall at RD. 34/555 to 34/575).	302417.00	6500.00	One month
21	Restoration of rain damages on Runa to Jundwa road Km. 0/00 to 5/575. (SH:- Construction of wire crate R/ Wall at Rd 2/170 to 2/185).	226813.00	5000.00	One month
22	Restoration of rain damages on Runa to Jundwa road Km. 0/00 to 5/575. (SH:- Construction of wire crate R/ Walls at Rd 1/635 to 1/645, 3/135 to 3/145, 3/170 to 3/180 and 4/112 to 4/122).	412936.00	8500.00	One month
23	Restoration of rain damages on GP Headquarter Namhog to Tikridal road Km. 0/00 to 3/810. (SH:- Construction of wire crated R/ Wall at Rd 0/675 to 0/685 and 1/800 to 1/815).	367885.00	8000.00	One month
24	Restoration of rain damages on Behna to Dalash road upto Kandagai road Km. 0/00 to 17/345. (SH:- Construction of wire crate R/ Walls at Rd 7/420 to 7/435, 9/800 to 9/810, 9/970 to 9/985 and 10/845 to 10/855).	488799.00	10000.00	One month
25	Restoration of rain damages on Behna to Dalash road upto Kandagai road Km. 0/00 to 17/345. (SH:- Construction of wire crate R/ Walls at Rd 10/480 to 10/500 and 14/285 to 14/305).	423396.00	8500.00	One month
26	Restoration of rain damages on Dalash to Gungi road Km. 0/00 to 3/210. (SH:- Construction of R/ Wall at Rd 0/740 to 0/755).	278760.00	6000.00	One month
27	Restoration of rain damages on Behna to Dalash road upto Kandagai road Km. 0/00 to 17/345. (SH:- Construction of R/ Wall at Rd 2/345 to 2/360).	357300.00	7500.00	Two months
28	Restoration of rain damages on Soidhar to Beungal road Km. 0/00 to 9/855. (SH:- C/o wire crated R/wall at RD. 6/240 to 6/255 and 9/090 to 9/105).	309684.00	6500.00	one month
29	Restoration of rain damages on Soidhar to Beungal road Km. 0/00 to 9/855. (SH:- C/o wire crated R/wall at RD. 9/555 to 9/575).	302417.00	6500.00	one month
30	Restoration of rain damages on Togi to Dhair road Km. 0/00 to 1/975. (SH:- C/o wire crated R/wall at RD. 1/305 to 1/320).	94355.00	2000.00	one month

HIM SUCHANA AVAM JAN SAMPARK


Executive Engineer
Outer Seraj Division
H.P PWD, Nirmand
on behalf of Governor of Himachal Pradesh



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**


Office of the Executive Engineer, Outer Seraj Division, HP.PWD, Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140
Fax No. 01904-255740



Certificate

Certified that the tenders called vide this
Office letter No.-PW/OSDN/TA/Tender-NIT/2023-24- 6657-67 dated
09.08.2023 is very urgent nature. So may be uploaded on Departmental
website in public interest please.


**Executive Engineer
Outer Seraj Division
H.P PWD, Nirmand**
on behalf of Governor of Himachal Pradesh

10

Schedule of quantity

Schedule of quantity									
Name of Work: Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH:-C/O retaining wall at RD.4/495 to 4/505).									
UNDER BASP									
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		Two months		
					Words	AMOUNT			
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	6.00	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only	1070.00			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	15.30	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	6092.00			
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	2.30	Cubic Metre	4254.50	Rupees Four Thousand Two Hundred & Fifty Four - Paise Fifty Only	9785.00			
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	31.40	Cubic Metre	4359.90	Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only	136901.00			
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	10.00	Each	311.70	Rupees Three Hundred & Eleven - Paise Seventy Only	3117.00			
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	0.75	Cubic Metre	1265.00	Rupees One Thousand Two Hundred & Sixty Five Only	949.00			
Total in Figures						157914.00			
Rate quoted by contractor +/-				Percent					
Quoted rate in figure									
Quoted rate in words									

Executive Engineer
Outer Seraj Division
P.W.D. Mirmand

(11)

Schedule of quantity

Name of Work: Construction of link road from Rumali to Deem km. 0/00 to 6/210 (SH:-C/O retaining wall at RD.4/97 to 4/614). UNDER BASP									
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Words	Estimated cost:-	
								Time	AMOUNT
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	11.90	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only				413110.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	55.93	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only				22269.00
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	7.31	Cubic Metre	4254.50	Rupees Four Thousand Two Hundred & Fifty Four - Paise Fifty Only				31100.00
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	80.40	Cubic Metre	4359.90	Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only				350536.00
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20.00	Each	311.70	Rupees Three Hundred & Eleven - Paise Seventy Only				6234.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	0.67	Cubic Metre	1265.00	Rupees One Thousand Two Hundred & Sixty Five Only				848.00
Total in Figures									413110.00
Rate quoted by contractor +/-									
Quoted rate in figure									
Quoted rate in words									

Schedule of quantity

Name of Work:- Restoration of rain damages on Ranabag Kandibag road km. 0/00 to 10/800 (SHI:-C/O wire crated R/Wall at RD. 8/275 to 8/304)									
Sl. No.	Description of work	Qty.	Unit	RATE i.e GST & all taxes		Estimated cost:- Earnest Money	Time	One month	AMOUNT
				Figures	Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	13.05	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only				2328.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	9.57	Cubic Metre	398.20	Rupees Three Hundred & Ninety Eight - Paise Twenty Only				3811.00
3	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS:280 and I.S.4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stones boulders of approved quality weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 complete including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge complete	153.99	Cubic Metre	2522.10	Rupees Two Thousand Five Hundred & Twenty Two - Paise Ten Only				388378.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	19.87	Cubic Metre	1065.00	Rupees One Thousand & Sixty Five Only				21162.00
Total in Figures									415679.00
Rate quoted by contractor +/-					Percent				
quoted rate in figure									
Quoted rate in words									


 Executive Engineer,
 Outer Sert Division,
 HP PWD, Sirmour.

Schedule of quantity

Schedule of quantity									
Name of Work: Restoration of rain damages on Ranabag to kandibag road km. 0/00 to 10/800. (Sub Head:- Construction of PCC R/Wall at RD.9/120 to9/145)									
Sl. No.	Description of work	Qty.	Unit	RATE i/c GST and all taxes		AMOUNT			
				Figures	Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge	29.25	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Forty Only	5218.00			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	21.25	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	8461.00			
3	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	100.02	Cubic Metre	4563.00	Rupees Four Thousand Five Hundred & Sixty Three Only	456391.00			
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	50	Each	311.70	Rupees Three Hundred & Eleven - Paise Seventy Only	15585.00			
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	11.00	Cubic Metre	1065.00	Rupees One Thousand & Sixty Five Only	11715.00			
Total in Figures						497370.00			
Rate quoted by contractor +/-				Percent					
quoted rate in figure									
Quoted rate in words									



 Executive Engineer,
 Outer Serai Division,
 HPPWD Mirmand.

Schedule of quantity

Name of Work:- Restoration of rain damages on Panetanal to Bishal road km. 0/00 to 3/470 (SH:-C/O wire crated R/Wall at RD. 0/540 to 0/552)							Estimated cost:-	190031.00
							Earnest Money	4000
							Time	One month
Sl. No.	Description of work	Qty.	Unit	RATE i.e GST & all taxes		AMOUNT		
				Figures	Words			
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	5.40	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only	963.00		
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	3.96	Cubic Metre	398.20	Rupees Three Hundred & Ninety Eight - Paise Twenty Only	1577.00		
3	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS:280 and I.S.4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stones boulders of approved quality weighing not less than 25 kg each as per drawing and technical specifications Clause1301complete including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge complete	69.12	Cubic Metre	2522.10	Rupees Two Thousand Five Hundred & Twenty Two - Paise Ten Only	174328.00		
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	12.36	Cubic Metre	1065.00	Rupees One Thousand &Sixty Five Only	13163.00		
Total in Figures						190031.00		
Rate quoted by contractor +/-				Percent				
quoted rate in figure								
Quoted rate in workds								


 Executive Engineer,
 Outer Survey Division,
 HP.P.W.D., Narnaul.

Schedule of quantity									
Name of Work: Construction of Raja Raghuvir Singh Stadium at Anni (Sub Head:- Construction of 10.20 metre long R/Wall in ground)				Estimated cost:-		413142.00			
				Earnest Money		10000			
				Time		One month			
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT			
				Figures	Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	24.48	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Forty Only	4367.00			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	12.84	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	5112.00			
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.73	Cubic Metre	4278.90	Rupees Four Thousand Two Hundred & Seventy Eight - Paise Ninety Only	28797.00			
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	84.05	Cubic Metre	4359.90	Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only	366450.00			
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	16.00	Each	311.70	Rupees Three Hundred & Eleven - Paise Seventy Only	4987.00			
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	3.22	Cubic Metre	1065.00	Rupees One Thousand & Sixty Five Only	3429.00			
Total in Figures						413142.00			
Rate quoted by contractor +/-					Percent				
quoted rate in figure									
Quoted rate in words									



 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Noida.

Schedule of quantity

Name of Work: Restoration of rain damages on Chouradhar to Pancoo road km. 0/00 to 8/015. (Sub Head:- Construction of R/W all at RD.2/465 to 2/479)									
Sl. No.	Description of work	Qty.	Unit	RATE i/c GST and all taxes		AMOUNT	Estimated cost:-		
				Figures	Words		Earliest Money	Time	Two months
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge	13.44	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only	2398.00			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	23.10	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	9197.00			
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.16	Cubic Metre	4200.00	Rupees Four Thousand Two Hundred Only	25872.00			
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	74.62	Cubic Metre	4563.00	Rupees Four Thousand Five Hundred & Sixty Three Only	340491.00			
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20	Each	311.70	Rupees Three Hundred & Eleven - Paise Seventy Only	6234.00			
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.37	Cubic Metre	1065.00	Rupees One Thousand & Sixty Five Only	5719.00			
Total in Figures				5.37		389911.00			
Rate quoted by contractor +/-					Percent				
quoted rate in figure									
Quoted rate in works									



 Executive Engineer,
 Outer Sesaj Division,
 HPPWD, Mirmand.

Schedule of quantity						
Name of Work: Restoration of rain damages on Soidhar Beungal road km. 0/00 to 9/855 (SH-C/O PCC retaining Wall at RD. 3/555.50 to 3/561)				Estimated cost:- Earnest Money Time		225845.00 5000 Two months
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	11.94	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Forty Only	2130.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	22.11	Cubic Metre	398.20	Rupees Three Hundred & Ninety Eight - Paise Twenty Only	8804.00
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	2.75	Cubic Metre	4366.50	Rupees Four Thousand Three Hundred & Sixty Six - Paise Fifty Only	12008.00
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) curing complete in retaining and breast walls as per drawing and technical specification including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	43.78	Cubic Metre	4563.40	Rupees Four Thousand Five Hundred & Sixty Three - Paise Forty Only	199786.00
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	10.00	Each	311.70	Rupees Three Hundred & Eleven - Paise Seventy Only	3117.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	2.48	Cubic Metre	1065.00	Rupees One Thousand & Sixty Five Only	2641.00
Total in Figures						225845.00
Rate quoted by contractor +/-				Percent		
Quoted rate in figure						
Quoted rate in words						


 Executive Engineer,
 Outer Seraj Division,
 HPPW/D, Noida.

Schedule of quantity

Name of Work: Restoration of rain damages on jaon to Buchhair road km 0/00 to 5/00 (SH: Construction of wire crate Breast wall at RD 2/435 to 2/483)									
Sl. No.	Description of work	Qty.	Unit	RATE		Estimated cost:- Earnest Money	259836.00	One month 5000	Time
				Figures	Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	17.76	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only			3168.00	
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	19.68	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only			7836.00	
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the depoartment free of cost)	138.24	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only			248832.00	
Total in Figures								259836.00	
Rate quoted by contractor +/-						Percent			
quoted rate in figure									
Quoted rate in workds									


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Nirmand.


Schedule of quantity

Schedule of quantity									
Name of Work: Restoration of rain damages on Gugra to Kutwa road km 0/00 to 10/400 (SH: Construction of wire crate breast wall at RD 5/675 to 5/695)									
Sl. No.	Description of work	Qty.	Unit	RATE		One month	AMOUNT		
				Figures	Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	7.40	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Forty Only	2000	104125.00		
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	8.20	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only		3265.00		
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the depaortment free of cost)	55.30	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only		99540.00		
Total in Figures							104125.00		
Rate quoted by contractor +/-					Percent				
quoted rate in figure									
Quoted rate in workds									


K. J.
Executive Engineer,
Outer Seraj Division,
HPPWD Demand.

Schedule of quantity

Name of Work: Restoration of rain damages on Punan to Gad deem road Km 0/00 to 10/345 (SH. :- C/o RR masonry R/Wall at RD 3/720-3/734) 3/734									
Sl. No.	Description of work	Qty.	Unit	RATE i.e GST & all taxes		R/Wall at RD	Estimated cost:-		AMOUNT
				Figures	Words		Earnest Money	Time	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	9.80	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only			Two months	1748.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	46.06	Cubic Metre	398.20	Rupees Three Hundred & Ninety Eight - Paise Twenty Only				18341.00
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.02	Cubic Metre	4510.70	Rupees Four Thousand Five Hundred & Ten - Paise Seventy Only				27154.00
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	74.06	Cubic Metre	5876.50	Rupees Five Thousand Eight Hundred & Seventy Six - Paise Fifty Only				435214.00
5	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimeter) diameters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	17.50	Cubic Metre	292.40	Rupees Two Hundred & Ninety Two - Paise Fourty Only				5117.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	0.88	Cubic Metre	1065.00	Rupees One Thousand & Sixty Five Only				937.00
Total in Figures									488511.00
Rate quoted by contractor +/-									
Quoted rate in figure									
Quoted rate in words									
					Percent				


 Executive Engineer,
 Outer Seraj Division,
 HPPWFD, Mirmand.


Schedule of quantity									
Name of Work: Restoration of rain damages on Behna to Dalash road upto Kandagai road KM 0/00 to 17/345 (SH:-C/O wire created R/wall at RD 9/210 to 9/235)					Estimated cost:-		378023.00		
					Earnest Money		7500		
					Time		One month		
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT		
					Words	Words			
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	61.50	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only		10972.00		
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	26.75	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only		10651.00		
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the depoartment free of cost)	198.00	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only		356400.00		
Total in Figures							378023.00		
Rate quoted by contractor +/-					Percent				
quoted rate in figure									
Quoted rate in workds									


 Executive Engineer,
 Outer Seraj Division,
 HPPWD Nirmand.

Schedule of quantity

Name of Work: Restoration of rain damages on Behna to Dalash road upto Kandagal road KM 0/00 to 17/345 (SH-C/O wire created B/walls at RD 7/420 to 7/435 and 8/885 to 8/900)


Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
						One month
						188763.00
						4000
						One month
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	28.50	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only	5084.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	21.90	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	8719.00
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the deparatment free of cost)	97.20	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only	174960.00
Total in Figures						188763.00
Rate quoted by contractor +/-%				Percent		
quoted rate in figure						
Quoted rate in words						


 Executive Engineer,
 Outer Scraj Division,
 HPPW/D, Dindimand.

Schedule of quantity

ne of Work: Restoration of rain damages on Behna to Dalash road upto Kandagai road KM 0/00 to 17/345 (SH:-C/O wire
ted B/walls at RD 16/930 to 16/960 and 17/015 to 17/030)


Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT
					Words	Time	
					Estimated cost:- Earnest Money	One month	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	42.75	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only		7627.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	32.85	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only		13079.00
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete. (Wire crate will be supplied by the depoartment free of cost)	145.80	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only		262440.00
Total in Figures							283146.00
Rate quoted by contractor +/-					Percent		
quoted rate in figure							
Quoted rate in workds							


Executive Engineer,
Outer Seraj Division,
HPPWD, Nirmand.

Signature of Tenderer with seal

Schedule of quantity


Name of Work: Restoration of rain damages on Behna to Dalash road upto Kandagai road road KM 0/00 to 17/345 (SH:-C/O wire ated R/walls at RD 16/410 to 16/430 and 16/840 to 16/865)									
				Estimated cost:-		361319.00			
				Earnest Money		7500			
				Time		One month			
Description of work				Qty.	Unit	RATE		AMOUNT	
						Figures	Words		
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.			63.70	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only	11364.00	
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.			24.50	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	9755.00	
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the depoartment free of cost)			189.00	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only	340200.00	
				Total in Figures				361319.00	
				Rate quoted by contractor +/-		Percent			
quoted rate in figure									
Quoted rate in workds									


 Executive Engineer,
 Outer Serai Division,
 HPPWD, Nirmand.

Schedule of quantity

Name of Work: Restoration of rain damages on Ani to Basta road KM 11/00 to 37/000 (SH:-C/O wire crated R/walls at RD 12/945 to 12/963 and 10/255 to 10/270)

					Estimated cost:-	366549.00
					Earnest Money	7500
					Time	One month
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	76.50	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only	13648.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	31.90	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	12701.00
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the depoartment free of cost)	189.00	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only	340200.00
				Total in Figures		366549.00
				Rate quoted by contractor +/-		
				Percent		
				quoted rate in figure		
				Quoted rate in workds		


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Nirmand.


Schedule of quantity

Name of Work: Restoration of rain damages on Ani to Basta road road KM 11/00 to 37/000 (SH:-C/O wire crated R/walls at RD 8/945 to 8/960, 13/594 to 13/610 and B/wall at RD 12/395 to 12/415)									
Sl. No.	Description of work	Qty.	Unit	RATE		Estimated cost:- Earnest Money Time One month			
				Figures	Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	83.20	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only	14843.00			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	41.15	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	16384.00			
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the depoartment free of cost)	226.80	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only	408240.00			
		Total in Figures				439467.00			
		Rate quoted by contractor +/-			Percent				
quoted rate in figure									
Quoted rate in workds									


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Nirmand.

Schedule of quantity

Name of Work: Restoration of rain damages on Ani to Basta road road KM 11/00 to 37/000 (SH:-C/O wire crated B/wall and R/walls at RD 8/540 to 8/560, 8/580 to 8/600 and 8/870 to 8/885)									
Sl. No.	Description of work	Qty.	Unit	RATE		Estimated cost:- Earnest Money Time	One month AMOUNT		
				Figures	Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	82.70	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only		14754.00		
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	39.10	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only		15568.00		
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the depoartment free of cost)	253.80	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only		456840.00		
				Total in Figures			487162.00		
				Rate quoted by contractor +/-					
quoted rate in figure									
Quoted rate in words									


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Nirmand.

Schedule of quantity

Subject of Work: Restoration of rain damages on Ani to Basta road KM 11/00 to 37/000 (SH-C/O wire crated R/walls at RD 970 to 11/995)

Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	61.50	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Forty Only	10972.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	26.75	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	10651.00
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete. (Wire crate will be supplied by the deopartment free of cost)	198.00	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only	356400.00
Total in Figures						378023.00
Rate quoted by contractor +/-				Percent		
quoted rate in figure						
Quoted rate in words						


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Mirmand.

Schedule of quantity

Name of Work: Restoration of rain damages on L.DCK road KM 11/00 to 37/000 (SH:-C/O wire crated R/walls at RD 34/555 TO 4/575)

SL. No.	Description of work	Qty.	Unit	RATE		Estimated cost:- Earnest Money Time One month	AMOUNT
				Figures	Words		
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	49.20	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only		8777.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	21.40	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only		8520.00
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the depoartment free of cost)	158.40	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only		285120.00
Total in Figures							302417.00
Rate quoted by contractor +/-				Percent			
quoted rate in figure							
Quoted rate in workds							


Executive Engineer,
Outer Seraj Division,
HPPWD, Mirmand.

Schedule of quantity


Estimated cost:-

5000

Executive Engineer,
Outer Seraj Division,
HPPWD, Mirmand.


Schedule of quantity

Name of Work: Restoration of rain damages on Runa to Jundwa road KM 0/00 to 5/575 (SH:-C/O wire crated R/walls at RD 1/635 to 1/645, 3/135 to 3/145, 3/170 to 3/180 and 4/112 to 4/122)									
				Estimated cost:-		412936.00			
				Earnest Money		8500			
				Time		One month			
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	Words	AMOUNT	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	72.80	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only			12988.00	
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	28.00	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only			11148.00	
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the depoartment free of cost)	216.00	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only			388800.00	
				Total in Figures				412936.00	
				Rate quoted by contractor +/-		Percent			
				quoted rate in figure					
				Quoted rate in workds					


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Mirmand.


Schedule of quantity

Name of Work: Restoration of rain damages on GP Headquarter Namhong to Tikridal road KM 0/00 to 3/810 (SH:-C/O wire crated R/wall at RD 0/675 to 0/685 and 1/800 to 1/815)						Estimated cost:-	
						Earnest Money	2000
						Time	One month
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT	
				Figures	Words		
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	23.65	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only	4219.00	
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	18.25	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	7266.00	
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the depopartment free of cost)	198.00	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only	356400.00	
Total in Figures						367885.00	
Rate quoted by contractor +/-							
quoted rate in figure							
Quoted rate in workds							


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Nirmand.

Schedule of quantity

Name of Work: Restoration of rain damages on Behna to Dalash up to Kandagai road KM 0/00 to 17/345 (SH:-C/O wire crated R/walls RD 7/420 to 7/435, 9/800 to 9/810, 9/970 to 9/985 and 10/845 to 10/855)									
Sl. No.	Description of work	Qty.	Unit	RATE		Estimated cost:-	One month	AMOUNT	
				Figures	Words				
									Time
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	82.20	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only	14664.00		10000	
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	35.30	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	14055.00			
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer – in ~ Charge complete. (Wire crate will be supplied by the depoartment free of cost)	255.60	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only	460080.00			
Total in Figures								488799.00	
Rate quoted by contractor +/-					Percent				
quoted rate in figure									
Quoted rate in words									


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Mirmand.

Schedule of quantity

name of Work: Restoration of rain damages on Behna to Dalash up to Kandagai road KM 0/00 to 17/345 (SH:-C/O wire crated R/walls at RD 10/480 to 10/500 and 14/285 to 14/305)

					Estimated cost:-	423396.00
					Earnest Money	8500
					Time	One month
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	98.40	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only	17555.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	42.80	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	17041.00
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the depoartment free of cost)	216.00	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only	388800.00
				Total in Figures		423396.00
				Rate quoted by contractor +/-		
				Percent		
				quoted rate in figure		
				Quoted rate in workds		



 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Nirmand.

Signature of Tenderer with seal

Schedule of quantity

Name of Work: Restoration of rain damages on Dalash to Giungi road km. 0/00 to 3/210. (Sub Head:- Construction of R/Wall at RD.0/740 to 0/755)

Sl. No.		Description of work	Qty.	Unit	RATE i.e GST & all taxes		Estimated cost:-	
					Figures	Words	Earnest Money	Two months
1		Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	13.05	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only		278760.00
2		Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	26.25	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only		2328.00
3		Providing and Laying plain cement concrete 1:6:12 (one cement : six sand ; twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.75	Cubic Metre	4278.50	Rupees Four Thousand Two Hundred & Seventy Eight - Paise Fifty Only		28880.00
4		Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	50.85	Cubic Metre	4359.90	Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only		221701.00
5		Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	22.00	Each	311.70	Rupees Three Hundred & Eleven - Paise Seventy Only		6857.00
6		Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.75	Cubic Metre	1265.60	Rupees One Thousand Two Hundred & Sixty Five - Paise Sixty		8543.00
					Total in Figures			278760.00
					Rate quoted by contractor +/-			
					Percent			
					Quoted rate in figure			
					Quoted rate in workds			


 Executive Engineer,
 Outer Seraj Division,
 HPPWD Mirmand.

Schedule of quantity

Name of Work: Restoration of rain damages on Dalash to Gungi road km. 0/00 to 3/210. (Sub Head:- Construction of R/Wall at RD.2/345 to 2/360)

Sl. No.	Description of work	Qty.	Unit	RATE i.e GST & all taxes		Estimated cost:- Earnest Money Time	AMOUNT
				Figures	Words		
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	16.80	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only		2997.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	34.95	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only		13915.00
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	7.80	Cubic Metre	4278.50	Rupees Four Thousand Two Hundred & Seventy Eight - Paise Fifty Only		33372.00
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	66.60	Cubic Metre	4359.90	Rupees Four Thousand Three Hundred & Fifty Nine - Paise Ninety Only		290369.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	26.00	Each	311.70	Rupees Three Hundred & Eleven - Paise Seventy Only		8104.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.75	Cubic Metre	1265.60	Rupees One Thousand Two Hundred & Sixty Five - Paise Sixty		8543.00
Total in Figures							357300.00
Rate quoted by contractor +/-					Percent		
Quoted rate in figure							
Quoted rate in words							


 Executive Engineer,
 Outer Serai Division,
 HPPWD, Naraund.

Schedule of quantity

Name of Work: Restoration of rain damages on Soidhar to Beungal road km. 0/00 to 9/855 (SH:-C/O wire crated R/Wall at RD. 6/240 to 6/255 and 9/090 to 9/105)									
Sl. No.	Description of work	Qty.	Unit	RATE		Estimated cost:-	One month	AMOUNT	
				Figures	Words				
					Time				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	54.50	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Forty Only			9723.00	
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	21.00	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only			8361.00	
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the depoartment free of cost)	162.00	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only			291600.00	
				Total in Figures				309684.00	
				Rate quoted by contractor +/-		Percent			
				quoted rate in figure					
				Quoted rate in workds					


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Nirmal.

Schedule of quantity

Name of Work: Restoration of rain damages on Soidhar to Beungal road km. 0/00 to 9/855 (SH:-C/O wire crated R/Wall at RD. 9/555
o 9/575)

Estimated cost:-	302417.00
Earnest Money	6500
Time	One month

Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	49.20	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only	8777.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	21.40	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only	8520.00
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the depoartment free of cost)	158.40	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only	285120.00
Total in Figures						302417.00
Rate quoted by contractor +/-				Percent		
quoted rate in figure						
Quoted rate in workds						


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Nirmand.

Signature of Tenderer with seal

Schedule of quantity

Name of Work: Restoration of rain damages on Togi to Dhair road KM 0/00 to 1/975 (SH:-C/O wire crated R/wall at RD 1/305 to 1/320)										
Sl. No.		Description of work	Qty.	Unit	Estimated cost:-		Earnest Money		One month	
					Figures	Words	Time	Amount		
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	14.10	Cubic Metre	178.40	Rupees One Hundred & Seventy Eight - Paise Fourty Only				2515.00	
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	10.95	Cubic Metre	398.15	Rupees Three Hundred & Ninety Eight - Paise Fifteen Only				4360.00	
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Wire crate will be supplied by the depoartment free of cost)	48.60	Cubic Metre	1800.00	Rupees One Thousand Eight Hundred Only				87480.00	
		Total in Figures								94355.00
		Rate quoted by contractor +/-				Percent				
		quoted rate in figure								
		Quoted rate in workds								


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Nirmand.