

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No.PW-MDI(Padhar)E-Tender-NIT/2023-24- 5732-34 Dated:- 10/08/2023

To


✓ The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.

✓
Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 21.08.2023 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 19.08.2023 upto 1:00 P.M.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Construction of Link road Bikaner Janahan Nihon. (SH:- Construction of R.C.C. Hume pipe culvert along with wing walls at R.D. 0/060).	3,10,874.26	6,200/-	350/-	Three months
2	Construction of Link road Bikaner Janahan Nihon. (SH:- Construction of R.C.C. Hume pipe culvert along with wing walls at R.D. 0/600).	3,10,874.84	6,200/-	350/-	Three months
3	Restoration of rain damages on Drang Basahi road Km 0/0 to 22/0. (SH:- Construction of P.C.C. retaining wall at R.D. 12/345 to 12/355)	1,38,918.75	2,800/-	350/-	One month
4	Restoration of rain damages on Drang Basahi road Km 0/0 to 22/0. (SH:- Construction of P.C.C. retaining wall at R.D. 11/744 to 11/756 and providing and laying 900mm dia R.C.C. Hume pipe at R.D. 11/750)	4,56,902.51	9,100/-	350/-	One month
5	Restoration of rain damages on Drang Basahi road Km 0/0 to 22/0. (SH:- Construction of P.C.C. retaining wall at R.D. 13/210 to 13/220)	2,05,624.80	4,100/-	350/-	One month
6	Restoration of rain damages on Drang Basahi road Km 0/0 to 22/0. (SH:- Construction of P.C.C. retaining wall at R.D. 15/405 to 15/415)	2,05,256.00	4,100/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.

5. The intending Contractors are requested to see the site of the work before submitting the tender.
6. The offer of the tender shall remain valid upto 75 days after the opening of tender.
7. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)
on behalf of Governor of Himachal Pradesh 

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 310874.26

Earnest Money Rs:- 6200.00

Time :- Three months

Tender Inviting Authority: Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work:- Construction of Link road Bikaner Janahan Nihon. (Sub Head:- Construction of R.C.C. Hume Pipe culvert along with wing walls at R.D. 0/060).

Contract No.:

Name of Bidder/Bidding Firm/ Company:

SCHEDULE OF WORKS

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Excavation in soil in hilly area by manual means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	4.07	Per cubic metre	218.30	888.48	Rupees Eight Hundred Eighty Eight and Paise Forty Eight Only
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	43.71	Per cubic metre	485.30	21212.46	Rupees Twenty One Thousand Two Hundred Twelve and Paise Forty Six Only
3	Providing and laying concrete Mechanically mixed and vibrated mix 1:6:12 (one cement: six sand: twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1.98	Per cubic metre	5127.00	10151.46	Rupees Ten Thousand One Hundred Fifty One and Paise Forty Six Only
4	Providing and laying concrete mechanically mixed and vibrated mix 1:4:8 (one cement: four sand: eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.	28.26	Per cubic metre	5629.30	159084.02	Rupees One Lakh Fifty Nine Thousand Eighty Four and Paise Two Only
5	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded,crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	12.78	Per cubic metre	5731.00	73242.18	Rupees Seventy Three Thousand Two Hundred Forty Two and Paise Eighteen Only
6	Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2 as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.00	Per running metre	3638.40	25468.80	Rupees Twenty Five Thousand Hundred Sixty Eight and Paise Eighty Only

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
7	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303. Rubble stone laid in cement mortar 1:3 (one cement : three sand) (Excavation for preparation of bed and cement concrete bedding to be measured and paid for separately) including curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	0.49	Per cubic metre	5987.20	2933.73	Rupees Two Thousand Nine Hundred Thirty Three and Paise Seventy Three Only
8	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	12.00	Each	299.30	3591.60	Rupees Three Thousand Five Hundred Ninety One and Paise Sixty Only
9	Back filling behind abutment wing wall and return wall complete as per drawing and technical specifications clause 1206.3 with Granular material complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	9.48	Per cubic metre	1508.60	14301.53	Rupees Fourteen Thousand Three Hundred One and Paise Fifty Three Only
Total in Figure					310874.26	Rupees Three Lakh Ten Thousand Eight Hundred Four and Paise Twenty Six Only
Quoted Rate in Words		Rupees Three Lakh Ten Thousand Eight Hundred Seventy Four and Paise Twenty Six Only				


 Executive Engineer,
 Mandi Division No. I,
 H.P. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 310874.84
Earnest Money Rs:- 6200.00

Time :- Three months

Tender Inviting Authority: Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.

Name of work:- Construction of Link road Bikaner Janahan Nihon. (Sub Head:- Construction of R.C.C. Hume Pipe culvert along with wing walls at R.D. 0/600).

Contract No.:

Name of Bidder/Bidding Firm/ Company:

SCHEDULE OF WORKS						
Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Excavation in soil in hilly area by manual means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	3.05	Per cubic metre	218.30	665.82	Rupees Six Hundred Sixty Five and Paise Eighty Two Only
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	44.17	Per cubic metre	485.30	21435.70	Rupees Twenty One Thousand Hundred Thirty Five and Paise Seventy Only
3	Providing and laying concrete Mechanically mixed and vibrated mix 1:6:12 (one cement: six sand: twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1.98	Per cubic metre	5127.00	10151.46	Rupees Ten Thousand One Hundred Fifty One and Paise Forty Six Only
4	Providing and laying concrete mechanically mixed and vibrated mix 1:4:8 (one cement: four sand: eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.	28.26	Per cubic metre	5629.30	159084.02	Rupees One Lakh Fifty Nine Thousand Eighty Four and Paise Two Only
5	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded,crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	12.78	Per cubic metre	5731.00	73242.18	Rupees Seventy Three Thousand Two Hundred Forty Two and Paise Eighteen Only
6	Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2 as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.00	Per running metre	3638.40	25468.80	Rupees Twenty Four Hundred Sixty Eight and Paise Eighty Only

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
7	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303. Rubble stone laid in cement mortar 1:3 (one cement : three sand) (Excavation for preparation of bed and cement concrete bedding to be measured and paid for seperately) including curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	0.49	Per cubic metre	5987.20	2933.73	Rupees Two Thousand Nine Hundred Thirty Three and Paise Seventy Three Only
8	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	12.00	Each	299.30	3591.60	Rupees Three Thousand Five Hundred Ninety One and Paise Sixty Only
9	Back filling behind abutment wing wall and return wall complete as per drawing and technical specifications clause 1206.3 with Granular material complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	9.48	Per cubic metre	1508.60	14301.53	Rupees Fourteen Thousand Hundred One and Paise Fifty Three Only
Total in Figure					310874.84	Rupees Three Lakh Ten Thousand Eight Hundred Four and Paise Eighty Four Only
Quoted Rate in Words		Rupees Three Lakh Ten Thousand Eight Hundred Seventy Four and Paise Eighty Four Only				


 Executive Engineer,
 Mandi Division No. I,
 HP.PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 138918.75

Earnest Money Rs:- 2800.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Drang Basahi road Km. 0/0 to 22/0. (Sub Head:- Construction of P.C.C. retaining wall at R.D. 12/345 to 12/355.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	11.90	Per cubic metre	461.00	5485.90	Rupees Five Thousand Four Hundred Eighty Five and Paise Ninety Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	24.09	Per cubic metre	5077.45	122315.77	Rupees One Lakh Twenty Two Thousand Three Hundred Fifteen and Paise Seventy Seven Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.80	Per cubic metre	1508.60	8749.88	Rupees Eight Thousand Seven Hundred Forty Nine and Paise Eighty Eight Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	8.00	Each	295.90	2367.20	Rupees Two Thousand Three Hundred Sixty Seven and Paise Twenty Only
Total in figure :					138918.75	Rupees One Lakh Thirty Eight Thousand Nine Hundred and Paise Seventy
Total in Words :		Rupees One Lakh Thirty Eight Thousand Nine Hundred Five Only			Eighteen and Paise Seventy	


 Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 456902.51

Earnest Money Rs:- 9100.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- Restoration of rain damages on Drang Basahi road Km. 0/0 to 22/0. (Sub Head:- Construction of P.C.C. retaining wall at R.D. 11/744 to 11/756 & providing and laying 900mm dia, R.C.C. Hume Pipe at R.D. 11/750.)

Contract No. :

Bidder Name :

SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	58.04	Per cubic metre	461.00	26756.44	Rupees Twenty Six Thousand Seven Hundred Fifty Six and Paise Forty Four Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	78.21	Per cubic metre	5077.45	397107.36	Rupees Three Lakh Ninety Seven Thousand One Hundred Seven and Paise Thirty Six Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.96	Per cubic metre	1508.60	19551.46	Rupees Nineteen Thousand Five Hundred Fifty One and Paise Forty Six Only
4	Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2 as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	2.50	Per running metre	3619.50	9048.75	Rupees Nine Thousand Forty Eight and Paise Seventy Five Only

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	15.00	Each	295.90	4438.50	Rupees Four Thousand Four Hundred Thirty Eight and Paise Fifty Only
Total in figure :					456902.51	Rupees Four Lakh Fifty Six Thousand Nine Hundred Fifty One Only
Total in Words :		Rupees Four Lakh Fifty Six Thousand Nine Hundred Two and Paise Fifty One Only				


 Executive Engineer,
 Mandi Division No.I,
 S.P. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 205624.80
Earnest Money Rs:- 4100.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Drang Basahi road Km. 0/0 to 22/0. (Sub Head:- Construction of P.C.C. retaining wall at R.D. 13/210 to 13/220.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.20	Per cubic metre	461.00	Rupees Ten Thousand Two Hundred Thirty Four and Paise Twenty Only	10234.20
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	36.00	Per cubic metre	5077.45	Rupees One Lakh Eighty Two Thousand Seven Hundred Eighty Eight and Paise Twenty Only	182788.20
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	6.00	Per cubic metre	1508.60	Rupees Nine Thousand Fifty One and Paise Sixty Only	9051.60
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	295.90	Rupees Three Thousand Five Hundred Fifty and Paise Eighty Only	3550.80
Total in figure :						205624.80
Total in Words :		Rupees Two Lakh Five Thousand Six Hundred Twenty Four and Paise Eighty Only				


 Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 205256.00
Earnest Money Rs:- 4100.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Drang Basahi road Km. 0/0 to 22/0. (Sub Head:- Construction of P.C.C. retaining wall at R.D. 15/405 to 15/415.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	21.40	Per cubic metre	461.00	9865.40	Rupees Nine Thousand Eight Hundred Sixty Five and Paise Forty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	36.00	Per cubic metre	5077.45	182788.20	Rupees One Lakh Eighty Two Thousand Seven Hundred Eighty Eight and Paise Twenty Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	6.00	Per cubic metre	1508.60	9051.60	Rupees Nine Thousand Fifty One and Paise Sixty Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	295.90	3550.80	Rupees Three Thousand Five Hundred Fifty and Paise Eighty Only
Total in figure :					205256.00	Rupees Two Lakh Five Thousand Two Hundred Fifty Six Only
Total in Words :		Rupees Two Lakh Five Thousand Two Hundred Fifty Six Only				


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar.