

Telephone No: 01782-233214

E-mail: eenh-ram-hp@nic.in

No. PW/EE/NH/RMP-CB-Tender /2023-24-
To

3591

Dated:- 27/07/2023

The Executive Engineer, (IT)
Nigam Vihar Shimla-2.

Subject: - Publication of tender notice

Enclosed, please find herewith copy of NIT No.
PW/EE/NH/RMP/CB-Tender Notice/ 2023-24- 3580-90 dated 27.07.2023 for
uploading the same on department website for wide publicity.

DA:- Copy of NIT


Executive Engineer,
NH Division HPPWD,
Rampur Bushahr

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed item rate tender(s) on PWD form No.6 & 8 are hereby invited by the Executive Engineer, NH- Division, HP.PWD, Rampur Distt. Shimla (H.P) on behalf of the Governor of H.P for the following works from the registered contractors/consultants in HP.PWD in appropriate class to reach in this office on **05.08.2023** up to 10.30 A.M. and will be opened on the same day at 11.00A.M. in the presence of Contractors/ consultants or their authorized representative who wish to be present at that time. The application for obtaining the tender form will be received on **04.08.2023** i.e. 11.00 AM to 1.00 PM and the tender form can be had from this office against this cash payment (Non- refundable) on the same day from 2.00P.M. to 5.00 P.M. No application shall be entertained without **earnest money** or through FAX.

Earnest money shall be in shape of NSC/FDR duly pledged in favour of Executive Engineer NH-Division HP.PWD Rampur Bushahr Distt. Shimla H.P. Ambiguous /Telegraphically/conditional tenders or tender through FAX shall not be entertained/ considered in any case.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time	Form No.	Cost of form
1	R/R damages on NH-305 Km 0/00 to 53/00 (SH:- Hiring of hydraulic excavator with breaker for removal of slips/massive rock slides in Km 28/00 to 28/150 & 32/400 to 32/640 at various Rds).	492694/-	9900/-	One month	6&8	350/-
2	R/R damages on NH-305 Km 0/00 to 53/00 (SH:- Hiring of hydraulic excavator with breaker for removal of slips/massive rock slides in between Km 33/450 to 33/650).	492694/-	9900/-	One month	6&8	350/-
3	A/R & M/O on NH-05 Km 236/00 to 368/00 (SH:- Hiring of hydraulic excavator with breaker for removal of slips/massive rock slides in between Km 280/00 to 288/00 at various RDs).	492694/-	9900/-	One month	6&8	350/-
4	A/R & M/O on NH-05 Km 236/00 to 368/00 (SH:- Hiring of hydraulic excavator with breaker for removal of slips/massive rock slides in between Km 302/00 to 307/00 at various RDs).	492694/-	9900/-	One month	6&8	350/-
5	A/R & M/O on NH-05 Km 236/00 to 368/00 (SH:- Hiring of hydraulic excavator with breaker for removal of slips/massive rock slides in between Km 335/00 to 340/00).	452872/-	9100/-	One month	6&8	350/-
6	A/R & M/O on NH-05 Km 236/00 to 368/00 (SH:- C/O PCC B/wall above the existing B/wall at RD 272/140 to 272/155).	353258/-	7100/-	One month	6&8	350/-
7	A/R & M/O on NH-05 Km 236/00 to 368/00 (SH:- C/O PCC B/wall at RD 279/620 to 279/636).	492365/-	9900/-	One month	6&8	350/-

SPECIAL CONDITIONS

- The material shall be arranged by the contractor/ consultants himself.
- The detail of documents to be attached with the application is given below.
 - Latest copy of renewal enlistment/empanelment.
 - Copy of Pan Card.
 - Copy of GST No.
- The offer of the tender shall be kept open for 90 days
- Tender received after the specified time/date shall not be opened.
- Executive Engineer NH-division HP.PWD Rampur Distt. Shimla H.P. reserves the right to reject any or all tender/s without assigning any reasons.
- If due to any unforeseen reasons the office of the Executive Engineer NH-Division HP.PWD Rampur remain closed on the notified date of sale and receipt of tender, tender will be sold and received/opened the next working day of same specified time.
- Tenderers may contact the Executive Engineer for any further information they may require during the working day/ office hours.
- The contractor/ consultants are requested to insert the rate of each in words as well as in figures failing which Executive Engineer reserves the right to reject any or all tenders.
- The labourcess shall allow/ deduction @ 2% TDS amount of GST (1% CGST and 1% SGST).
- The labour cess @ 1% will be deducted from the gross amount of the bill
- A contractor enlisted in a particular class shall be eligible to tender for his own class and one step below as per Govt. notification No.PBW (B) 22-1/2002 dated 26-05-2015.
- The Contractor/consultants will have to submit the proof of registration under Employees Provident Funds & Miscellaneous Provision Act. 1952 before award of work.
- Cement should be purchased from H.P. State Civil Supply Corporation
- GST will be deducted from each bill as per latest instruction of the Government.

No.PW/EE/NH/RMP/CB-Tender Notice/2023-24-
Copy forwarded for information to the:-

- Engineer-in-Chief, HP.PWD, Shimla
- Chief Engineer (NH) HP.PWD, Shimla-1
- Superintending Engineer, NH-Circle, HP.PWD, Shimla
- All the Assistant Engineer working under this division
- A/B & D/B in this office.
- Notice board of this office.

3580-90


Dated:- **27.07.2023**

[Signature]
Executive Engineer,
NH Division, H.P.PWD,
Rampur Bushahr

[Signature]
Executive Engineer,
NH Division, H.P.PWD,
Rampur Bushahr

Certificate


Certified that the tenders of the works invited vide this office NIT No. PW/ EE/ NH/ RMP/ CB-tender/ 2023-24-3580-90 dated 27.07.2023 is of urgent nature in exigency of public interest.


Executive Engineer
NH Division HPPWD,
Rampur Bushahr.

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
Name of work:- R/R damages NH-305 Saini Luhri Aut Km 0/0 to 53/0 (SH:- Hiring of hydraulic /excucuator with breaker for removal of slips/ Massive rock slides in between Km 28/000 to 28/150 & 32/400 to 32/460 at various RDS)				Estimated cost:- 492694.00		
				Earnest money:- 9900.00		
				Time:- One Month		
Sr No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Hiring of (L & T comatsu / Bolvo/Hyundai /doosan and other) PC 210 crawler mounted hydraulic excavator with breaker for cutting / excavation/ filling /slips i/c cost of feul oil lubrificant and wages opprating any repair/breakage during operation will be carried out by the contractor /owner at his own risk. Shifting of machinery from one place to other place within site will be absolute responsibility of the contractor and no payment will be made for the same . Only actual working hours will be accounted for the payment. Any loss to the public/ private property during the course of execution of work shall be the sole responsibility of the contractor and will compensated by him at his on risk and cost , cutting in earth / removal of slips in all kinds of soil including loading in Tippers/ Trucks, removal / disposal of the same in all leads and lifts to the entire satisfaction of Engineer-in-charge. No payment will be made for machine lying ideal at site due to no work or non availbility of working hours due to unfavourable climatic conditions.	95.00			Per Hour	
					Total:-	

Note:- Any damage to machinery during the working hours will be responsibility of the contractor and repair charge will be born by him at his own risk and cost.



 Executive Engineer,
 NH Division HPPWD,
 Rampur Bsr.

SCHEDULE OF QUANTITY

Name of work:- R/R damages NH-305 Saini Luhri Aut Km 0/0 to 53/0 (SH:- Hiring of hydraulic /excavator with breaker for removal of slips/ Massive rock slides in between Km 33/450 to 33/650)

Estimated cost:- 492694.00
Earnest money:- 9900.00

Sr No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Time:- One Month	
					Unit	Amount
1	Hiring of (L & T comatsu / Bolvo/Hyundai /doosan and other) PC 210 crawler mounted hydraulic excavator with breaker for cutting / excavation/ filling /slips i/c cost of fuel oil lubricant and wages opprating any repair/breakage during operation will be carried out by the contractor /owner at his own risk. Shifting of machinery from one place to other place within site will be absolute responsibility of the contractor and no payment will be made for the same . Only actual working hours will be accounted for the payment. Any loss to the public/ private property during the course of execution of work shall be the sole responsibility of the contractor and will compensated by him at his on risk and cost , cutting in earth / removal of slips in all kinds of soil including loading in Tippers/ Trucks, removal / disposal of the same in all leads and lifts to the entire satisfaction of Engineer-in-charge. No payment will be made for machine lying ideal at site due to no work or non availibility of working hours due to unfavourable climatic conditions.	95.00	4	5	Per Hour	7
Note:- Any damage to machinery during the working hours will be responsibility of the contractor and repair charge will be born by him at his own risk and cost.					Total:-	


Executive Engineer,
NH Division HPPWD,
Rampur Bsr.

SCHEDULE OF QUANTITY

Name of work:- R/R damages NH-05 Km 236/0 to 368/0 (SH:- Hiring of hydrolic /excuvator with breaker for removal of slips/ Massive rock slides in between Km 280/000 to 288/000 at various RDs)

Estimated cost:- 492694.00
Earnest money:- 9900.00

Time:- One Month

Sr No.	Sub head/Item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Hiring of (L & T comatsu / Bolvo/Hyundai /doosan and other) PC 210 crawler mounted hydraulic excavator with breaker for cutting / excavation/ filling /slips i/c cost of feul oil lubricant and wages opprating any repair/breakage during operation will be carried out by the contractor /owner at his own risk. Shifting of machinery from one place to other place within site will be absolute responsibility of the contractor and no payment will be made for the same . Only actual working hours will be accounted for the payment. Any loss to the public/ private property during the course of execution of work shall be the sole responsibility of the contractor and will compensated by him at his on risk and cost , cutting in earth / removal of slips in all kinds of soil including loading in Tippers/ Trucks, removal / disposal of the same in all leads and lifts to the entire satisfaction of Engineer-in-charge. No payment will be made for machine lying ideal at site due to no work or non availbility of working hours due to unfavourable climatic conditions.	95.00			Per Hour	
Total:-						

Note:- Any damage to machinery during the working hours will be responsibility of the contractor and repair charge will be born by him at his own risk and cost.


AE(3)


Executive Engineer,
NH Division HPPWD,
Rampur Bsr.

Name of work:- R/R damages NH-05 Km 236/0 to 368/0 (SH:- Hiring of hydraulic excavator with breaker for removal of slips/ Massive rock slides in between Km 302/000 to 307/000)	
---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--

Estimated cost:-	492694.00
Earnest money:-	9900.00

Time:- One Month

Sr No.	Sub head/Item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Hiring of (L & T comatsu / Bolvo/Hyundai /doosan and other) PC 210 crawler mounted hydraulic excavator with breaker for cutting / excavation/ filling /slips i/c cost of fuel oil lubricant and wages oprating any repair/breakage during operation will be carried out by the contractor /owner at his own risk. Shifting of machinery from one place to other place within site will be absolute responsibility of the contractor and no payment will be made for the same . Only actual working hours will be accounted for the payment. Any loss to the public/ private property during the course of execution of work shall be the sole responsibility of the contractor and will compensated by him at his on risk and cost , cutting in earth / removal of slips in all kinds of soil including loading in Tippers/ Trucks, removal / disposal of the same in all leads and lifts to the entire satisfaction of Engineer-in-charge. No payment will be made for machine lying ideal at site due to no work or non availibility of working hours due to unfavourable climatic conditions.	95.00			Per Hour	
					Total:-	

Note:- Any damage to machinery during the working hours will be responsibility of the contractor and repair charge will be born by him at his own risk and cost.

Executive Engineer,
NH Division HPPWD,
Rampur Bsr.

SCHEDULE OF QUANTITY


Name of work:- R/R damages NH-05 Km 236/0 to 368/0 (SH:- Hiring of hydrolic /excavator with breaker for removal of slips/ Massive rock slides in between Km 335/000 to 340/000)

Estimated cost:- 452872.00
Earnest money:- 9100.00

Time:- One Month

Sr No.	Sub head/Item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Hiring of (L & T comatsu / Bolvo/Hyundai /doosan and other) PC 210 crawler mounted hydraulic excavator with breaker for cutting / excavation/ filling /slips i/c cost of feul oil lubricant and wages oprating any repair/breakage during operation will be carried out by the contractor /owner at his own risk. Shifting of machinery from one place to other place within site will be absolute responsibility of the contractor and no payment will be made for the same . Only actual working hours will be accounted for the payment. Any loss to the public/ private property during the course of excution of work shall be the sole responsibility of the contractor and will compensated by him at his on risk and cost , cutting in earth / removal of slips in all kinds of soil including loading in Tippers/ Trucks, removal / disposal of the same in all leads and lifts to the entire satisfaction of Engineer-in-charge. No payment will be made for machine lying ideal at site due to no work or non availbility of working hours due to unfavourable climatic conditions.	86.00			Per Hour	
Total:-						

Note:- Any damage to machinery during the working hours will be responsibility of the contractor and repair charge will be born by him at his own risk and cost


Executive Engineer,
NH Division HPPWD,
Rampur Bsr.

SCHEDULE OF QUANTITY

Name of work:- R/R damages on NH-05 Km 236/000 to 368/000 (SH:- C/O PCC B/wall above the existing B/wall at RD 272/140 to 272/155)

Estimated cost:- 353258.00
Earnest money:- 7100.00
Time:- One month

Sr No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	Cutting in earth work in all kinds of soils such as pick work, jumper work, soft and hard rock i.e. chiselling and wedging out of rock if required and saturated soils and their intermediate classifications in all heights and depths. Stacking the useful stone/materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charge including loading of truck for carrying the unserviceable materials. Any loss of public/private property during the course of execution shall be the sole responsibility of the contractor which shall have to be duly compensated by him at his own cost in all cases, the work shall be carried out as per clause 301 of section 300 of MORTH specifications to the entire satisfaction and direction of Engineer-in-Charge.	42.90			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated cement concrete M-15 containing minimum contents of cement is 5.50 bags per cum in all heights and depth as per drawing and technical specifications in foundation of retaining walls complete as per MORTH specification No.1500,1700 & 2100 including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	49.50			Per cubic metre	
3	Providing and laying 100mm diameter (Hundred millimeter) P. V.C. pipe in weep holes in R/wall in requisite slopes for drainages as per the direction of the Engineer-in-charges including carriage of materials in all leads and lifts with mechanical means.	28.50			Per running metre	
	Total:-					


 Executive Engineer,
 NH Division HPPWD,
 Rampur Bsr.

SCHEDULE OF QUANTITY


Name of work:- R/R damages on NH-05 Km 236/000 to 368/000 (SH:- C/O PCC B/wall at RD 279/620 to 279/636)

Estimated cost:- 492365.00
Earnest money:- 9900.00

Time:- One month

Sr No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Cutting in earth work in all kinds of soils such as pick work, jumper work, soft and hard rock i.e. chiselling and wedging out of rock if required and saturated soils and their intermediate classifications in all heights and depths. Stacking the useful stone/materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges including loading of truck for carrying the unserviceable materials. Any loss of public/private property during the course of execution shall be the sole responsibility of the contractor which shall have to be duly compensated by him at his own cost in all cases, the work shall be carried out as per clause 301 of section 300 of MORTH specifications to the entire satisfaction and direction of Engineer-in-Charge.	45.44			Per cubic metre	
2	Earth work in excavation for structure in all depth as per drawing and technical specification Clause 304 of section 300 of MORTH specification in all kind of soils i.e pick work, jumper work, blasting work in soft and hard rock and intermediate classification of soil including chiselling and wedging out of rock with in all depths and heights ,stacking the useful materials and disposal of unserviceable materials upto the indentified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	11.36			Per cubic metre	

3	Providing and laying mechanically mixed and vibrated cement concrete M-15 containing minimum contents of cement is 5.50 bags per cum in all heights and depth as per drawing and technical specifications in foundation of retaining walls complete as per MORTH specification No.1500,1700 & 2100 including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	68.80				Per cubic metre	
4	Providing and laying 100mm diameter (Hundred millimeter) P. V.C. pipe in weep holes in R/wall in requisite slopes for drainages as per the direction of the Engineer-in-charges including carriage of materials in all leads and lifts with mechanical means.	32.00				Per running metre	
						Total:-	


 Executive Engineer,
 NH Division HPPWD,
 Rampur Bsr.