

Himachal Pradesh
Public Works Department

NO/PW/SNG/CB/E-16/Tender/2023-24- 3403-12 Dated: - 05/8/23

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.
cc-pwd-hp@nic.in


Subject: -Publication of Tender Notice.

Sir,

Enclosed please find herewith notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per notification Pr. Secy (PW) to the Govt of Himachal Pradesh Letter No. PBW(B)A(3)1/2020 dated Shimla -2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.


Encl: -NIT and Schedule of Quantity

Yours faithfully,


Executive Engineer
Sangrah Division
HPPWD Sangrah

Copy forwarded to the following for information and necessary action :-

1. The Engineer -in- Chief, , HPPWD Shimla-2 please
2. The Chief Engineer (SZ), HPPWD Shimla-2 please.
3. The Deputy Commissioner, Sirmour Distt. Sirmour at Nahan Please.
4. The SDM Sangrah please.
5. The Superintending Engineer, 12th Circle HPPWD Nahan please.
6. The BDO Sangrah please.
7. All the Assistant Engineers under this division to display on their respective Notice Boards.
8. The Notice Board.


Executive Engineer
Sangrah Division
HPPWD Sangrah

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
SHORT TERM NOTICE INVITING TENDERS**

Sealed item rate tender on from 6 & 8 are hereby invited by the Executive Engineer, Sangrah Division, HP.PWD. Sangrah on behalf of the Governor of H.P. for the following works from the approved and eligible contractors enlisted with HPPWD under revised rules:-

Tender Schedule:-

Date and time of receipt of application for tender form-16.08.2023 up to 04:00 PM

Date and time of issue/Sale of tender form-17.08.2023 up to 04:00 PM

Date and time of receipt of tender form-18.08.2023 up to 11:00 AM

Date and time of opening tender form-18.08.2023 at 11:30 AM

The tender form can be had from the office of the Executive Engineer against Cash **(Non-refundable)**. The earnest money should be in the shape of National Saving Certificate/Time deposit/Saving Account in any of the Post office in H.P. duly pledged in favour of the Executive Engineer Sangrah Division HPPWD Sangrah must accompany each tender. Conditional tender and the tender received without earnest money will summarily be reject. The offer will be kept open for **75 days**. The Executive Engineer reserves the right to reject one or all tenders without assigning any reason.

Sr. No.	Name of work	Estimated cost	EMD	Cost of Tender	Time Allowed	Class of Contractor
1.	Restoration of rain damages on Danoi Khud Drabil Road Km. 0/00 to 18/945 under Jarag Section(SH:- Hiring of JCB for removal of slips, Cleaning of drains, improvement of shoulders & Dressing of berms various RD,s)	1,98,000/-	4,000/-	Rs. 350/-	03 Months	Class C & D only.
2.	Restoration of rain damages on Khalla Kiar section in various road (SH:- Hiring of JCB for removal of slips, Cleaning of drains, improvement of shoulders & Dressing of berms)	1,98,000/-	4,000/-	Rs. 350/-	03 Months	Class C & D only.
3.	Restoration of rain damages on Nahan Dadahu Haripurdhar Road & Various road under Renuka section (SH:- Hiring of JCB for removal of slips, Cleaning of drains, improvement of shoulders & Dressing of berms)	1,98,000/-	4,000/-	Rs. 350/-	03 Months	Class C & D only.

4.	Restoration of rain damages on Rajana section in various road (SH:- Hiring of JCB for removal of slips, Cleaning of drains, improvement of shoulders & Dressing of berms)	1,98,000/-	4,000/-	Rs. 350/-	03 Months	Class C & D only.
5.	Restoration of rain damages under Renuka Section -2 various roads (SH:- Hiring of JCB for removal of slips, Cleaning of drains, improvement of shoulders & Dressing of berms)	1,98,000/-	4,000/-	Rs. 350/-	03 Months	Class C & D only.
6.	R/R damages on Charna Bhawai Sangrah Road km. 0/00 to 14/00 (SH:- Hiring of JCB for removal of slips, cleaning of drain, Improvement of shoulders & and dressing of berms)	199800/-	4,000/-	Rs. 350/-	03 Months	Class C & D only.
7.	R/R damages on verious road under Nohradhar Sub-Division (SH:- Hiring of JCB for removal of slips, cleaning of drain, Improvement of shoulders & and dressing of berms)	2,07,000/-	4,200/-	Rs. 350/-	03 Months	Class C & D only.
8.	R/R damages Solan Meenus Road km. 61/00 to 92/00 (SH:- C/O R/wall in PCC from RD. 85/823 to 85/830)	4,03,393/-	8,100/-	Rs. 350/-	03 Months	Class C & D only.
9.	R/R damages on Solan Meenus Road km. 92/00 to 110/00 (SH:- Improvement of curve from RD. 90/435 to 90/505)	4,12,181/-	8,300/-	Rs. 350/-	03 Months	Class C & D only.
10.	R/R damages on Nohra Bogdhar Methli Road km. 0/00 to 34/00 (SH:- Hiring of JCB for removal of slips, cleaning of drain, Improvement of shoulders & and dressing of berms)	1,98,000/-	4,000/-	Rs. 350/-	03 Months	Class C & D only.
11.	Restoration of rain damages on various roads under Bogdhar Sub Division (SH - Hiring of Tipper for removal of debris).	1,48,500/-	3,000/-	Rs. 350/-	03 Months	Class C & D only.

12.	R/R damages on verious road under Bogdhar Sub-Division (SH:- Hiring of JCB for removal of slips, cleaning of drain, Improvement of shoulders & and dressing of berms)	2,02,500/-	4,100/-	Rs. 350/-	03 Months	Class C & D only.
13.	R/R damages on link road from village Sangna to Govt. Sen. Sec. School Sangna Sathan km. 0/00 to 4/00 (SH:- Hiring of JCB for removal of slips, cleaning of drain, Improvement of shoulders & and dressing of berms)	1,12,500/-	2,300/-	Rs. 350/-	03 Months	Class C & D only.
14.	R/R damages on Kuffer dadar to Koli Ka Bag km. 0/00 to 7/365 (SH:- Hiring of JCB for removal of slips, cleaning of drain, Improvement of shoulders & and dressing of berms)	2,02,500/-	4,100/-	Rs. 350/-	03 Months	Class C & D only.
15.	R/R damages on L/R to village Kajwa km. 0/00 to 2/165 & L/R to village Gajwa km. 2/555 (SH:- Hiring of JCB for removal of slips, cleaning of drain, Improvement of shoulders & and dressing of berms)	1,99,800/-	4,000/-	Rs. 350/-	03 Months	Class C & D only.
16.	Restoration of rain damages on various roads under Haripurdhar Sub Division (SH - Hiring of Tipper for removal of debris).	1,48,500/-	3,000/-	Rs. 350/-	03 Months	Class C & D only.
17.	Restoration of rain damages on Dalyanoo Pullilani Nainidhar RAos km 0/00 to 22/800 under Gattadhar Section (SH:- Hiring of JCB for removal of slips, cleaning of drain, Improvement of shoulders & and dressing of berms at various RD's)	144000/-	3000/-	Rs. 350/-	03 Months	Class C & D only.
18.	Restoration of rain damages on various roads under Renuka Sub Division HPPWD Renuka (SH - Hiring of Tipper for removal of debris).	148500/-	3000/-	Rs. 350/-	03 Months	Class C & D only.

19.	Restoration of rain Damages on Nahan Dadahu Haripurdhar road Km. 36/00 to 87/00 (SH:- C/O PCC R/Wall at RD.54/980 to 54/990)	4,30,863/-	9,000/-	Rs. 350/-	03 Months	Class C & D only.
20.	Restoration of rain Damages on Nahan Dadahu Haripurdhar road Km. 36/00 to 87/00 (SH:- PCC Retaining Wall at RD 62/430 to 62/440)	465176/-	9500/-	Rs. 350/-	03 Months	Class C & D only.


Certificate: - It is certified that the tenders of above works are exigency /emergent nature and in public interest.

Terms and conditions:-

1. The contractors shall produce their latest registration/ renewal of their registration/ latest GST No / EPF No. and earnest money should be accompanied with application. Application without earnest money will not be entertained.
2. Ambiguous/ telegraphic/Conditional tenders or tender by fax/ E- mail shall not be entertained/ considered and will summarily be rejected. Tender received after due date and time will be rejected.
3. The offer shall remain valid up to 75 days.
4. The contractor should not have more than two contracts within Division at a time tender. If the contractor has already two works in hand then the tender not excepted at the time of opening of tender and the same will be rejected technical evaluations.
5. If the contractors found lowest more than two works during the opened of bid then two works awarded to contractor at the one time and then opportunity will be given to next lowest bidder.
6. The contractor/bidder should quoted in percentage in words as well as in figures failing which XEN reserves the right to accept/ reject any or all tenders.
7. The contractor /bidders must inspect the site to ascertain /familiar the site conditions, accessibility etc. before quoting the bid/tender.
8. The tender documents shall be issued to only those contractors who does not have more the two works in hand in any HPPWD Circle/Division worth Rs. 1.00 Crore each.
9. That all your rates are inclusive of GST as such you will pay whole of it and you would not claim anything extra on this account from the Department.
10. The provisions of notification issued vide Additional Chief Secretary (PW) to the Govt. of HP. Shimla notification No. PBW (B) A (3)1/2018 dated 13.04.2021 shall also be applicable.

Provisions of the Addl. Chief Secretary (PW) to the Govt. of HP letter No. PBW(B)C(17)2/2012 dated 07.08.2018 are applicable.

The bidders are requested to submit their bid as per Notification issued by the Principal secretary PW to the Govt. of HP vide No.PBW(B)A(3)1/2020 dated 22.07.2020 & Govt. of HP vide No. PBW(B)A(3)1/2020-I dated 07.10.2021 and Engineer-in-Chief HPPWD Shimla-2 letter No. PW/CTR/32-20/Genl. Inst. CPWD/2020-37996-38095 dated 13.03.2023.


Executive Engineer,
Sangrah Division,
HP.PWD; Sangrah.

NO/PW/SNG/CB/E-16/Tender/23-24-

Dated:-

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, HP.PWD, Shimla-2 please.
2. The Chief Engineer (SZ) HPPWD Shimla-2 please.
3. The Deputy Commissioner Distt. at Nahan please.
4. The Superintending Engineers 12th Circle HPPWD Nahan please.
5. The SDM/BDO, Sangrah please.
6. All the Assistant Engineers under this Division.
7. The Drawing Branch of this office.
8. Notice Board.


Executive Engineer,
Sangrah Division,
HP.PWD, Sangrah.

Schedule Of Quantity

Name of work:- Restoration of rain damages on Danoi Khud Drabil Road Km. 0/00 to 18/945 under Jarag Section(SH):- Hiring of JCB for removal of slips,Cleaning of drains,Improvement of shoulders & Dressing of berms various RD,s)

Estimated Cost:-1,98,000/-

Earnest Money:-4,000/-

Time Period:- 3/0

S.No	Description of Item	Quantity	Unit	Rate		Amount
				In figure	In words	
1	Hiring of Excavator-cum-loader for cutting in hill roads in all kinds of silps, removal of debris,dressing of berms and clearing of drains with minimum capacity 18 to 25.00 cum/ per hours & minimum 6 hours per days including pay of operators, POL charges. Maintenance or any minor or major accident and other damages to private and govt property is the whole responsibility of the contractor. The work shall be executed as per the PWD specification and the direction of Engineer-in-Charge.	220.00	Hrs	900.00	(Rs. Nine hundred & paise Nil)only	198000
Total:-						198000


Executive Engineer
H.P. P.W.D. Division
Sangrah - 173023

Schedule Of Quantity

Name of work:- Restoration of rain damages on Khalla Kiar section in various road (SH:- Hiring of JCB for removal of slips,Cleaning of drains,Improvement of shoulders & Dressing of berms)

Estimated Cost:- 1,98,000/-

Earnest Money:- 4,000/-

Time Period:- 3 M

S.No	Description of Item	Quantity	Unit	Rate		Amount
				In figure	In words	
1	Hiring of Excavator-cum-loader for cutting in hill roads in all kinds of slips,removal of debris,dressing of berms and clearing of drains with minimum capacity 18 to 25.00 cum/ per hours & minimum 6 hours per days including pay of operators, POL charges. Maintenance or any minor or major accident and other damages to private and govt property is the whole responsibility of the contractor. The work shall be executed as per the PWD specification and the direction of Engineer-in-Charge. .	220.00	Hrs per Hours	900.00	(Rs. Nine hundred & paise Nil)only	198000
Total:-						198000


Executive Engineer
H.P. P.W.D. Division
Sangrath - 173023


Schedule Of Quantity							Estimated Cost:-1,98,000/-
Name of work:- Restoration of rain damages on Nahar Dadahu Haripurdhar Road & Various road under Renuka section (SH:- Hiring of JCB for removal of slips,Cleaning of drains,Improvement of shoulders & Dressing of berms)							Earnest Money:-4,000/-
							Time Period:- 3 rd
S.No	Description of Item	Quantity	Unit	Rate		Amount	
				In figure	In words		
1	Hiring of Excavator-cum-loader for cutting in hill roads in all kinds of slips,removal of debris,dressing of berms and clearing of drains with minimum capacity 18 to 25.00 cum/ per hours & minimum 6 hours per days including pay of operators, POL charges. Maintenance or any minor or major accident and other damages to private and govt property is the whole responsibility of the contractor. The work shall be executed as per the PWD specification and the direction of Engineer-in-Charge.	220.00	Hrs per Hours	900.00	(Rs. Nine hundred & paise Nil)only	198000	
Total:-						198000	


 Executive Engineer
 H.P. P.W.D. Division
 Sangrah - 173023

Schedule Of Quantity
Name of work:- Restoration of rain damages on Rajana section in various road (SH:- Hiring of JCB for removal of slips, Cleaning of drains, Improvement of shoulders & Dressing of berms)

Estimated Cost:-1,98,000/-
Earnest Money:-4,000/-
Time Period:- 3 M

S.No	Description of Item	Quantity	Unit	Rate		Amount
				In figure	In words	
1	Hiring of Excavator-cum-loader for cutting in hill roads in all kinds of slips, removal of debris, dressing of berms and clearing of drains with minimum capacity 18 to 25.00 cum/ per hours & minimum 6 hours per days including pay of operators, POL charges. Maintenance or any minor or major accident and other damages to private and govt property is the whole responsibility of the contractor. The work shall be executed as per the PWD specification and the direction of Engineer-in-Charge.	220.00	Hrs	900.00	(Rs. Nine hundred & paise Nil) only	198000
	Total:-					198000


Executive Engineer
H.P. P.W.D. Division
Sangrah - 173023

Schedule Of Quantity					Estimated Cost:-1,98,000/-
Name of work:- Restoration of rain damages under Renuka Section -2 various roads (SH:- Hiring of JCB for removal of slips,Cleaning of drains,Improvement of shoulders & Dressing of berms)					Earnest Money:-4,000/-
					Time Period:- 3 ^
S.No	Description of Item	Quantity	Unit	Rate	Amount
				In figure & in words	
1	Hiring of Excavator-cum-loader for cutting in hill roads in all kinds of slips,removal of debris,dressing of berms and clearing of drains with minimum capacity 18 to 25.00 cum/ per hours & minimum 6 hours per days including pay of operators, POL charges. Maintenance or any minor or major accident and other damages to private and govt property is the whole responsibility of the contractor.The work shall be executed as per the PWD specification and the direction of Engineer-in-Charge.	220.00	Hrs per Hours	900.00 (Rs. Nine hundred & paise Nil)only	198000
Total:-					198000


 Executive Engineer
 H.P. P.W.D. Division
 Sangraha - 173023

Schedule of Quantity

Name of work:- R/R damages on Charna Bhawai Sangrah Road km. 0/00 to 14/00 (SH:- Hiring of JCB for removal of slips, cleaning of drain, Improvement of shoulders & and dressing of berms)

Estimated Cost: 1,99,800/-

Earnest Money: 4,000/-

Time Limit: ~~Two~~ Month

S.No	Description of Item	Quantity		Unit		Rate		Amount
						In Figure	In Word	
1	Hiring of excavator-cum-loader for cutting in hill roads in all kinds of soil removal of slips, removal of debris, dressing of berms and clering of drains with minimum capacity 18 to 25.00 cum/ per hour & minimum 6 hours per day including services of operating staff as required including full time chowkidar for guarding the machine, POL charges & maintenance. Any loss or damage causes to machinery during transit or at site of work shall be borne by the contractor at his own cost. Any type of damage to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the HP.PWD specifications and the direction of Engineer-in-charge.	222.00	Hrs	per Hour		900.00	Rupees Nine Hundred & paise Zero	199800
Total:-								199800

Executive Engineer
H.P.P.W.D. Division
Sangrah - 173023

Schedule of Quantity				Estimated Cost: 2,07,000/-			
Name of work:-R/R damages on various road under Nohradhar Sub-Division (SH:- Hiring of JCB for removal of slips, cleaning of drain, Improvement of shoulders & and dressing of berms)				Earnest Money: 4,200/-			
				Time Limit: Two Month			
S.No	Description of Item	Quantity	Unit	Rate		Amount	
				In Figure	In Word		
1	Hiring of excavator-cum-loader for cutting in hill roads in all kinds of soil removal of slips, removal of debris, dressing of berms and clerling of drains with minimum capacity 18 to 25.00 cum/ per hour & minimum 6 hours per day including services of operating staff as required including full time chowkidar for guarding the machine, POL charges & maintenance. Any loss or damage causes to machinery during transit or at site of work shall be borne by the contractor at his own cost. Any type of damage to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the HP.PWD specifications and the direction of Engineer-in-charge.	230.00	Hrs	per Hour	900.00	Rupees Nine Hundred & paise Zero	207000
Total:-							207000


 Executive Engineer
 H.P. P.W.D. Division
 Sangrah - 173023



SCHEDULE OF QUANTITY

Name of Work:- R/R damages Solan Meenus Road Km. 61/00 to 92/00 (SH:- C/O R/wall in PCC from RD. 85/823 to 85/830)

Estimated Cost :- 4,03,393/-
 Earnest Money :- 8,100/-
 Time Limit :- 3 month

Sr. No	Description of Item	Net Quantity	Unit	Rate		Amount	
				In Figure	In Words		
1	Excavation in soil in hilly area in all depths using manual means as per drawing and technical specification ministry of Rural Development for rural roads August 2004. (Two thousands four) clause 305.1 (three hundred five point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials including dressing of sides and bottom and back filling in trenches with excavated suitable materials and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials by all modes of transportations in all leads and lifts at specified places in specified manner, systematically with level consideration to avoiding a diverse effects on environment, trimming filling of unevenness blind age and finishing of the road to specified dimension or as directed by the Engineer-in-Charge, any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his on cost in all cases including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer-in - Charge.	36.61	cubic metre	Per cubic metre	328.00	Rupees (Three Hundred Twenty Eight & Paise Zero) Only	12008
2	Excavation in foundation, trenches etc. in earth work in all heights and depths in all kinds of soil, including saturated soil comprising of pick work, jumper work and blasting work both in soft and hard rock with chiselling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where ever required, setting out to required lines, levels as shown on the drawings and as directed by the Engineer-in-Charge at site, according to the HPPWD specification of 1990-Volume-I and spotting out useful and un-useful materials and stacking the same in all leads, lifts and transportations of the useful materials for filling in roadways embankments for grades improvements and levelling to required grades and then disposing of surplus excavated earth in acquired width of road on or approved dumping sites through all modes of transportations including head load animal load or mechanical means alongwith its levelling fine dressing and all labour, mechaneries materials, tools equipments and incidental necessary to complete the work by mechanized means and labour(if any required) All useful materials such as stone single, aggregate and slates shall be sorted out and stacked along road side to the maximum possible extends in all leads, lifts through all modes of transportation and all others incidental charges any loss to the public and private properties during the course of execution and disposal of serviceable and un-serviceable materials shall be the absolute responsibility of the contractors and shall have to be duly compensated by him in all respect including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer-in - Charge.	16.24	cubic metre	Per cubic metre	489.00	Rupees (Four Hundred eighty Nine & Paise Zero) Only	7941

3	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202 and 1203 1-4 8 (One Cement : Four Sand Eight Graded materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer-in - Charge	83.86	cubic metre	Per cubic metre	4421.01	Rupees (Four Thousand four hundred twenty One & Paise one) Only	370746
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia pvc pipe extending through the full width of the structure with slopes of (V) 20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204, 3.7.	30	No's	Each	271.00	Rupees (two Hundred Seventy one & Paise zero) Only	8130
5	Providing back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204, 3.8.	5.25	cubic metre	Per cubic metre	870.00	Rupees (Eight hundred seventy & Paise zero) Only	4568
Total							403393


Executive Engineer
H.P. P.W.D. Division
Sangrah - 173023



Name of Work:-R/R damages on Solan Meenus Road km. 92/00 to 110/00 (SH:- Improvement of curve from RD. 90/435 to 90/505)

Estimated cost: 4,12,181/-
 Earnest Money: 4,000/-
 Time limit: Three Month

Sr. No	Description of Item	Net Quantity	Unit	Rate		Amount	
				In Figure	In Words		
1	Excavation in earth work in in hilly area all height and depths and in all kinds of soils including saturated soil comprising of mixed soil ordinary rock and hard rock. All works road rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion damage to hill side water pollution etc. and to protect stability of hill side. Rock shall be excavated with chieseling and wedging out rock(where blasting is prohibited). All earth work in cutting/ excavation, including rock excavation shall be carried out true to lines grades sides slopes,width, camber,super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge in conformity with the requirement of technical specification of Rural road August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable cut material and specified manner,including arrangement of dumping site trimming,filling of unvenness blindage and finishing of the road to specified diamensions including disposal of surplus materials with all leads, and lifts at the locatuion specified in the tender document or as directed by the Engineer-in-Charge for smooth riding. The recovery for stones where useful or not i.e. 235.66(TWO HUNDRED THIRTY FIVE POINT SIXTY SIX)cubic metre @ 170/- (Rs. ONE HUNDRED SEVENTY) only per cubic metre shall be effected on pro-rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him at his on cost in all cases including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	707.00	cubic metre	Per cubic metre	583.00	Rupees (Five Hundred eighty three & Paise zero) Only	412181
Total:-							412181


Executive Engineer
 H.P. P.W.D. Division
 Sangraha - 173023

Schedule of Quantity

Name of work:- R/R damages on Nohra Bogdhar Methli Road km. 0/00 to 34/00 (SH:- Hiring of JCB for removal of slips, cleaning of drain, Improvement of shoulders & and dressing of berms)

Estimated Cost: 1,98,000/-
Earnest Money: 4,000/-
Time Limit: ~~Three~~ Month

S.No	Description of Item	Quantity	Unit		Rate		Amount
					In Figure	In Word	
1	Hiring of excavator-cum-loader for cutting in hill roads in all kinds of soil removal of slips, removal of debris, dressing of berms and clerling of drains with minimum capacity 18 to 25.00 cum/ per hour & minimum 6 hours per day including services of operating staff as required including full time chowkidar for guarding the machine, POL charges & maintenance. Any loss or damage causes to machinery during transit or at site of work shall be borne by the contractor at his own cost. Any type of damage to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the HP.PWD specifications and the direction of Engineer-in-charge.	220.00	Hrs	per Hour	900.00	Rupees Nine Hundred & paise Zero	198000 ✓
Total:-							198000


Executive Engineer
H.P. P.W.D. Division
Sangrah - 173023

Schedule of Quantity				Estimated Cost: 1,48,500/-		
Name of work -Restoration of rain damages on various roads under Bogdhar Sub Division (SH - Hiring of Tipper for removal of debris).				Earnest Money: 3,000/-		
				Time Limit: 100 Month		
S.No	Description of Item	Quantity	Unit	Rate		Amount
				In Figure	In Word	
1	Hiring of tipper for removal of debris including pay of operators, POL Charges, maintenance of any minor or major accidents and other damages to private and govt. property is the whole responsibility of the Contractor. The work shall be executed as per the PWD specification and the direction of Engineer-in-charge.	30.00	Per Day	4950.00	Rupees four thousand Nine Hundred fifty & paise Zero	148500
Total:-						148500


 Executive Engineer
 H.P. P.W.D. Division
 Sangraha - 173023

Schedule of Quantity		Estimated Cost: 2,02,500/-	
Name of work:-R/R damages on various road under Bogdhar Sub-Division (SH:- Hiring of JCB for removal of slips, cleaning of drain, Improvement of shoulders & and dressing of berms)		Earnest Money: 4,100/- Time Limit: Three Month	

S.No	Description of Item	Quantity	Unit		Rate		Amount
					In Figure	In Word	
1	Hiring of excavator-cum-loader for cutting in hill roads in all kinds of soil removal of slips, removal of debris, dressing of berms and clering of drains with minimum capacity 18 to 25.00 cum/ per hour & minimum 6 hours per day including services of operating staff as required including full time chowkidar for guarding the machine, POL charges & maintenance. Any loss or damage causes to machinery during transit or at site of work shall be borne by the contractor at his own cost. Any type of damage to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the H.P.PWD specifications and the direction of Engineer-in-charge.	225.00 Hrs	per Hour		900.00	Rupees Nine Hundred & paise Zero	202500 ✓
Total:-							202500 ✓


 Executive Engineer
 H.P.P.W.D. Division
 Sangraha - 173023



11.5.19

Schedule of Quantity


Name of work:-R/R damages on link road from village Sangna to Govt. Sen. Sec. School Sangna Sathan km. 0/00 to 4/00 (SH):- Hiring of JCB for removal of slips, cleaning of drain, Improvement of shoulders & and dressing of berms)

Estimated Cost: 1,12,500/-

Earnest Money: 2,300/-

Time Limit: ~~Three~~ Month

S.No	Description of Item	Quantity	Unit		Rate		Amount
					In Figure	In Word	
1	Hiring of excavator-cum-loader for cutting in hill roads in all kinds of soil removal of slips, removal of debris, dressing of berms and clerling of drains with minimum capacity 18 to 25.00 cum/ per hour & minimum 6 hours per day including services of operating staff as required including full time chowkidar for guarding the machine, POL charges & maintenance. Any loss or damage causes to machinery during transit or at site of work shall be borne by the contractor at his own cost. Any type of damage to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the HP.PWD specifications and the direction of Engineer-in-charge.	125.00	Hrs	per Hour	900.00	Rupees Nine Hundred & paise Zero	112500
Total:-							112500


 Executive Engineer
 H.P. P.W.D. Division
 Sangraha - 173023

Schedule of Quantity

Name of work:- R/R damages on Kuffer dadar to Koli Ka Bag km. 0/00 to 7/365 (SH:- Hiring of JCB for removal of slips, cleaning of drain, Improvement of shoulders & and dressing of berms)

Estimated Cost: 2,02,500/-
Earnest Money: 4,100/-
Time Limit: ~~Three~~ Month

S.No	Description of Item	Quantity	Unit		Rate		Amount
					In Figure	In Word	
1	Hiring of excavator-cum-loader for cutting in hill roads in all kinds of soil removal of slips, removal of debris, dressing of berms and clerling of drains with minimum capacity 18 to 25.00 cum/ per hour & minimum 6 hours per day including services of operating staff as required including full time chowkidar for guarding the machine, POL charges & maintenance. Any loss or damage causes to machinery during transit or at site of work shall be borne by the contractor at his own cost. Any type of damage to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the HP.PWD specifications and the direction of Engineer-in-charge.	225.00	Hrs	per Hour	900.00	Rupees Nine Hundred & paise Zero	202500
Total:-							202500


Executive Engineer
H.P. P.W.D. Division
Sangrah - 173023

Schedule of Quantity

Name of work:- R/R damages on L/R to village Kaiwa km. 0/00 to 2/165 & L/R to village Gajwa km. 2/555 (SH:- Hiring of JCB for removal of slips, cleaning of drain, Improvement of shoulders & and dressing of berms)


Estimated Cost: 1,99,800/-
Earnest Money: 4,000/-
Time Limit: ~~Three~~ Month

S.No	Description of Item	Quantity	Unit	Rate		Amount	
				In Figure	In Word		
1	Hiring of excavator-cum-loader for cutting in hill roads in all kinds of soil removal of slips, removal of debris, dressing of berms and clerling of drains with minimum capacity 18 to 25.00 cum/ per hour & minimum 6 hours per day including services of operating staff as required including full time chowkidar for guarding the machine, POL charges & maintenance. Any loss or damage causes to machinery during transit or at site of work shall be borne by the contractor at his own cost. Any type of damage to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the HP.PWD specifications and the direction of Engineer-in-charge.	222.00	Hrs	per Hour	900.00	Rupees Nine Hundred & paise Zero	199800
Total:-							199800



Executive Engineer
H.P. P.W.D. Division
Sangraha - 173023



Schedule of Quantity					Estimated Cost: 1,48,500/-	
Name of work -Restoration of rain damages on various roads under Haripurdhar Sub Division (SH - Hiring of Tipper for removal of debris).					Earnest Money: 3,000/- Time Limit: Two Month	
S.No	Description of Item	Quantity	Rate		Amount	
			Unit	In Word		
1	Hiring of tipper for removal of debris including pay of operators, POL Charges, maintenance of any minor or major accidents and other damages to private and govt. property is the whole responsibility of the Contractor. The work shall be executed as per the PWD specification and the direction of Engineer-in-charge.	30.00	Per Day	4950.00 Rupees four thousand Nine Hundred fifty & paise Zero	148500 ✓	
Total:-					148500 ✓	


 Executive Engineer
 H.P. P.W.D. Division
 Sangrah - 173023

Schedule Of Quantity						Estimated Cost:-1,44,000/-
Name of work:- Restoration of rain damages on Dalvanoo Pullilani Nanidhar Road Km. 0/00 to 22/800 under Gattadhar section (SH:- Hiring of JCB for removal of slips, Cleaning of drains, Improvement of shoulders & Dressing of berms various RD,s)						Earnest Money:-3,000/-
						Time Period:- 03/11
S.No	Description of Item	Quantity	Unit	Rate		Amount
				In figure	In words	
1	Hiring of Excavator-cum-loader for cutting in hill roads in all kinds of slips, removal of debris, dressing of berms and clearing of drains with minimum capacity 18 to 25.00 cum/ per hours & minimum 6 hours per days including pay of operators, POL charges. Maintenance or any minor or major accident and other damages to private and govt property is the whole responsibility of the contractor. The work shall be executed as per the PWD specification and the direction of Engineer-in-Charge.	160.00	Hrs per Hours	900.00	(Rs. Nine hundred & paise Nil) only	144000
Total:-						144000


Executive Engineer
H.P. P.W.D. Division
Sangrah 173023

Schedule of Quantity						Estimated Cost: 1,48,500/-	
Name of work - Rostoration of rain damages on various roads under Renuka Sub Division HPPWD Renuka (SH -						Earrest Money: 3,000/-	
Hiring of Tipper for removal of debris).						Time Limit: Three Month	
S.No	Description of Item	Quantity		Rate		Amount	
			Unit	In Figure	In Word		
1	Hiring of tipper for removal of debris including pay of operators, POL Charges, maintenance of any minor or major accidents and other damages to private and govt. property is the whole responsibility of the Contractor. The work shall be executed as per the PWD specification and the direction of Engineer-in-charge.	30.00	Per Day	4950.00	Rupees four thousand Nine Hundred fifty & paise Zero	148500	
Total:-						148500	



H.P. P.W.D. Division
Sangrah 173023

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Nahan Dadahu Haripurdiar Road Km.36/00 to 87/00(SH:-C/O PCC RWall at RD.54/980 to 54/990)


Estimated Cost:-4,30,863/-
Earnest Money:-9,000/-
Time Period:-03

Sr. No	Description of Item	Net Quantity	Unit	Rate		Amount
				In Figure	In Words	
1	Excavation in soil in hilly area by manual means including cutting and trimming of and disposing of excavated earth a lift upto 1.5 mtr and a lead of 20mts as per technical specification clause 1603.1 including all leads lifts and carriage of materials.	21.00	Cubic metre	328.00	Rs. Three Hundred twenty eight & Paise nil) Only.	6888.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 metres dressing of sides and bottom and back filling trenches with excavated suitable material including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge.	4.80	Cubic metre	489.00	Rs. Four Hundred Eighty nine & Paise nil) Only.	2347.00
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and specification clause 802,803,1202 & 1203 PCC 1:4:8 40mm including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge.	93.22	Cubic metre	4308.60	Rs. Four thousand three Hundred Eight & Paise sixty Only.	401648.00
4	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 with granular material including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charges.	18.00	Cubic metre	870.00	Rs. Eight Hundred seventy & Paise nil) Only.	15660.00
5	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extending through the full width of the structure with slopes of (1V):20(H) towards as per drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charges	16	Nos	270.00	Rs. Two Hundred seventy & Paise nil) Only.	4320.00
Total:-						430863.00


Executive Engineer
H.P. P.W.D. Division
Sangraha - 173023

SCHEDULE OF QUANTITY				Estimated Cost:-4,65,179/-
Name of Work:-Restoration of rain damages on Nahan Dadahu Haripurthar Road Km.55/00 to 79/00(SH:-C/O PCC R/Wall at RD.62/430 to 62/440)				Earnest Money:-9500/-
				Time Period:- Three months

Sr. No	Description of Item	Net Quantity		Unit	Rate		Amount
		In Figure	In Words		In Figure	In Words	
1	Excavation in soil in hilly area by manual means including cutting and trimming of and disposing of excavated earth a lift upto 1.5 mtr and a lead of 20mts as per technical specification clause 1603.1 including all leads lifts and carriage of materials.	41.70	Cubic metre	Per Cubic metre	328.00	Rs. Three Hundred twenty eight & Paise nil) Only.	13678.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 metres dressing of sides and bottom and back filling trenches with excavated suitable material including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge.	21.00	Cubic metre	Per Cubic metre	489.00	Rs. Four Hundred Eighty nine & Paise nil) Only.	10269.00
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and specification clause 802, 803, 1202 & 1203 PCC 1:4:8 40mm including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge.	98.40	Cubic metre	Per Cubic metre	4308.00	Rs. Four thousand three Hundred Eight & Paise nil) Only.	423907.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 with granular material including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charges.	7.50	Cubic metre	Per Cubic metre	870.00	Rs. Eight Hundred seventy & Paise nil) Only.	6525.00
5	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extending through the full width of the structure with slopes of (1V):20(H) towards as per drawing face complete as per drawing and technical specification clause 614.709, 1204.3.7 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charges	40.00	Nos	Each	270.00	Rs. Two Hundred seventy & Paise nil) Only.	10800.00
Total:-							465179.00


 Executive Engineer
 H.P. P.W.D. Division
 Sangrah 173023