

Himachal Pradesh
Public Works Department
NOTICE INVITING TENDER

Sealed tenders on item rates on PWD form 6&7 are hereby invited by the Executive Engineer, Tauni Devi Division, and HPPWD Tauni Devi for the following works. The tender shall be received in this office on or before 07.08.2023 up to 11:00 AM and the same shall be opened on the same day at 11:30 AM in the presence of the contractor /firms. The application for the issue of tender document shall be received on dated 05.08.2023 up to 1:30 PM and the tender form will be sold on cash payment (Non refundable) on dated 05.08.2023 from 2.30 AM to 5.00 PM.

Sr. No.	Name of Work	Estimated Cost (Rs.)	Earnest Money	Time limit	Cost of form
1.	C/o link road Kakkar to Bakkar Khad via Ghodlamber from km 0/00 to 2/640 (SH:- C/O Cement concrete pavement at RD 2/415 to 2/530) Under BASP G.P.Bherda	486916/-	10000/-	Two months	350/-
2.	C/o link road Kakkar to Bakkar Khad via Ghodlamber from km 0/00 to 2/640 (SH:- C/O Cement concrete pavement at RD 0/600 to 0/650, 0/755 to 0/800 and 1/090 to 1/130) Under BASP G.P.Bherda	489941/-	10000/-	Two months	350/-
3.	C/o link road Kakkar to Bakkar Khad via Ghodlamber from km 0/00 to 2/640 (SH:- C/O Cement concrete pavement at RD 2/415 to 2/530,) Under BASP G.P.Bherda	486916/-	10000/-	Two months	350/-
4.	C/o link road Kakkar to Bakkar Khad via Ghodlamber from km 0/00 to 2/640 (SH:- C/O Cement concrete pavement at RD 1/605 to 1/720,) Under OTMNP	480021/-	10000/-	Two months	350/-
5.	C/o link road Kakkar to Bakkar Khad via Ghodlamber from km 0/00 to 2/640 (SH:- C/O Cement concrete pavement at RD 2/300 to 2/415,) Under OTMNP BASP	486916/-	10000/-	Two months	350/-
6.	R/R damages on Kahanuli Kheri Bhatlamber Dudla via Mahesqual road km 0/0 to 9/460 (SH:- P/L interlocking concrete block pavement 50M long between at RD.1/350 to 1/400)	424248/-	10000/-	Two months	350/-
7.	R/R damages on Sujampur to Sandhol road 3/00 to 20/00.(SH:- C/o PCC retaining wall at RD 15/585 to 15/593.50)	490377/-	9800/-	Two months	350/-
8.	R/R damages on Sujampur to Sandhol road 3/00 to 20/00.(SH:- C/o PCC retaining wall at RD 15/705 to 15/713.50)	490377/-	9800/-	Two months	350/-
9.	R/R damages on Baru Tapre road km .5/265 to 8/705. (Sh:- C/o Un-lined surface drain and dressing of berms) (Section-II).	316684/-	6300/-	Two months	350/-
10.	R/R damages link road from Jhanikar to Barin village km 0/00 to 1/300 (Sh:-C/O retaining wall at RD 0/970 to 0/980 and 1/105 to 1/027)	255405/-	5200/-	Two months	350/-

11	C/o link road Bherda Bajrol via Tholu road km .0/0 to 4/0 (SH:- C/o 900mm dia hume pipe culvert at RD .1/800 with wing wall) (Under SCSP)	388349/-	9300/-	Two months	350/-
12	C/o link road from Chaleli to Tikker via Debra km 0/00 to 3/500 (Sh:- C/O retaining wall at RD 0/175 to 0/185) (Under SCSP)	478616/-	9600/-	Two months	350/-
13	C/o Ambulance Jeepable standard road Lambera to Dhangota Brahmna Km 0/0 to 2/00 (SH:- P/L GSB,WMM and V-shape drain at RD at RD 1/410 to 1/615) (Under OTMNP)	496932/-	9900/-	Two months	350/-
14	C/o Ambulance Jeepable standard road Lambera to Dhangota Brahmna Km 0/0 to 2/00 (SH:- P/L premix carpet surfacing with seal coat at RD 1/035 to 1/495) (Under OTMNP)	494767/-	9900/-	Two months	350/-

The tender documents shall be issued only to those contractors/firms who fulfill the following criteria and submit documents with the application. The valid enlistment/ registration of contractor in appropriate class. Permanent Account Number (PAN). Earnest money in the shape of National saving certificate/ Time deposit Account in any of the Post office in H.P. / F.D.R. from any Nationalized Bank (i/c Kangra Central Cooperative Bank) duly pledged in favour of the Executive Engineer. Other special terms and condition can be seen/obtain in this office on any working day. Any ambiguous /telegraphic conditional tenders by fax shall not be entertained /considered in any case. It is also certified that tenders are urgent work and required early completion.

Executive Engineer,
Tauni Devi Division,
HP:PWD., Tauni Devi

No.PW/TDD/GA/N.I.T./2023-24

Copy forwarded for information & necessary action please:-

1. The Engineer-in-Chief, HP:PWD, Shimla.
2. The Chief Engineer (HZ), HP:PWD, Hamirpur.
3. The Superintending Engineer, 8th Circle, HP:PWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP:PWD.
5. The Deputy Commissioner, Hamirpur.
6. **The Director, Information and Public Relations, Suchna Avam Jan Sampark Bhawan, HP Shimla -2 for information and necessary action.**
7. The Tehsildar, Tauni Devi.
8. The B. D. O. Tauni Devi.
9. The Municipal Committee, Hamirpur.
10. All the Assistant Engineers working under this Division.
11. Accounts Branch/ Drawing Branch/ Notice Board.
12. Lok Mitra, Tauni Devi.
13. Various Contractors/ Firms.

Dated:- 31.07.2023

Executive Engineer,
Tauni Devi Division,
HP: PWD, Tauni Devi

CERTIFICATE

Certified that the tender for job No. 1 to 14 are called vide this office letter No. PW/TDD/GA/2023-24-6752-6786 dated 31.07.2023 are an urgent nature and in public interest.



Executive Engineer,
Tauni Devi Division,
HP:PWD, Tauni Devi.


Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road Kakkar to Bakkar Khad via Ghodlamber from km. 0/00 to 2/640.(SH:- C/O cement concrete pavement at RD. 1/220 to 1/335).

NAME OF WORK:- Restoration of rain damages on link road Kakkar to Bakkar Khad via Ghodlamber from km. 0/00 to 2/640,(SH:- C/O cement concrete pavement at RD. 1/220 to 1/335).								Estimate of Quantity	
Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount		
				Earnest Money:-					
				Time:-					
				Rate	In Words				
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	40.25				Per cubic metre			
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm nominal size) (twenty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	40.25				Per cubic metre			
						Total			

Terms and Condition

1. Work shall be executed as per PWD specification.



 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- C/O link road Kakkar to Bakkar Khad via Ghodlamber from km. 0/00 to 2/646. (SH:- C/O cement concrete pavement at RD. 0/600 to 0/650, 0/755 to 0/800 and 1/090 to 1/130). Under BASP G.P. Bherda.

NAME OF WORK:- C/O link road Kakkar to Bakkar Khad via Ghodlambar from km. 0/00 to 2/646.(SH:- C/O cement concrete pavement at RD. 0/600 to 0/650, 0/755 to 0/800 and 1/090 to 1/130).Under BASP G.P. Bherda.									
Estimate of Quantity									
Sr.No.	Description of Items	Qty.	Estimated Cost:-		Earnest Money:-		Time:-		
			In Fig.	In Words	Unit	Amount	Two Months		
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	40.50			Per cubic metre				
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm nominal size) (twenty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	40.50			Per cubic metre				
Terms and Condition					Total				
Work shall be executed as per BMD.									

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- C/O link road Kakkar to Bakkar Khad via Ghodlamber from km. 0/00 to 2/640.(SH:- C/O cement concrete pavement at RD. 2/415 to 2/530).Under BASP G.P. Bherda.

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Rs. 486916.00	
			Earnest Money:-		Rs. 10000.00	
			Time:-		Two Months	
			In Fig.	Rate	Unit	Amount
				In Words		
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	40.25			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm nominal size) (twenty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	40.25			Per cubic metre	
Terms and Condition					Total	

1. Work shall be executed as per PWD specification.

Amit G.P.
Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Construction of link road Kakkar to Bakkar Khad via Ghodlambar 0/00 to 2/640.(SH:- Construction of Cement concrete pavement at RD 1/605 to 1/720) (Under OTMNP)							Estimated Cost:-	Rs.480021.00
							Earnest Money:-	Rs.9600.00
							Time:-	Two Months
Sr. No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount	
				In Words				
1.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand : six graded as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	39.68				Per cubic metre		
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm(twenty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	39.68				Per cubic metre		
Total								

Terms and Condition

1. Work shall be executed as per PWD specification.



 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Construction of link road Kakkar to Bakkar Khad via Ghodlambar					0/00 to	Estimated Cost:-	Rs.486916.00
2/640.(SH:- Construction of Cement concrete pavement at RD 2/300 to 2/415) (Under OTMNP)						Earnest Money:-	Rs.9800.00
					Time:-	Two Months	
Sr. No.	Description of Items	Qty.	In Fig.	Rate	Unit	Amount	
				In Words			
1.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand : six graded as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	40.25			Per cubic metre		
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm(twenty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	40.25			Per cubic metre		
Total							

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Schedule of Quantity
NAME OF WORK:- Restoration of rain damages on Khanauli Kheri Bhatlambar Dudia via Maheshgual road km. 0/0 to 9/460.(SH:- P/L Interlocking concrete block pavement 50M long between at RD. 1/350 to 1/400).

NAME OF WORK:- Restoration of rain damages on Khanauli Kheri Bhatlambar Duda via Maheshgual road km. 0/0 to 9/460.(SH:- P/L interlocking concrete block pavement 50M long between at RD. 1/350 to 1/400).									
NAME OF QUANTITY									
Sr.No.									
Description of Items									
Qty.									
In Fig.									
Rate									
In Words									
Unit									
Amount									
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m,(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	40.00					Per Cubic metre		
2	Stone soling properly handpacked filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per H.P.P.W.D., specification 100mm (one hundred millimeter) spread thickness finished work including materials and labour, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.	30.00					Per Cubic metre		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	29.00					Per Cubic metre		
4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness and size/ shape, made by table vibratory method using PU mould, laid in required colour and pattern over 50mm (fifty millimetre) thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge,80 mm (eighty millimetre) thick C.C. paver block of M-30 grade with approved color design and pattern, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	200.00					Per Square metre		
Total									
Terms and Condition									
Work shall be executed as per PWD specification									

Terms and Condition
1. Work shall be executed as per PWD specification.

Andar
Executive Engineer,
Tauni Devi Division
HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Sujampur to Sandhol road 3/00 to 20/00. (SH:- Construction of PCC retaining wall at RD 15/585 to 15/593.50)

Sr. No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earnest Money:-	Time:-		
				In Words	Two Months		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	22.53				Per cubic metre	
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	109.91				Per cubic metre	
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) dia PVC pipe De plast /finolex/vectus having pressure 4kg per sqmt (four kilogram) per square meter extending through the full width of the structures with slopes of 1(V): 20(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	35.00				Each	
4.00	Backfilling Granular material behind abutment, wing wall and return wall complete as per drawing& technical specification clause 1204.3.8, and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	11.65				Per cubic meter	
Terms and Condition						Total	

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Sujapur to Sandhol road 3/00 to 20/00. (SH:- Construction of PCC retaining wall at RD 15/705 to 15/713.50)

NAME OF WORK:- Restoration of rain damages on Sujapur to Sandhol road 3/00 to 20/00. (SH:- Construction of PCC retaining wall at RD 15/705 to 15/713.50)									
Estimated Cost:- 490377.00									
Earnest Money:- 9800.00									
Time:- Two Months									
Sr. No.	Description of Items	Qty.	Rate		Unit	Amount			
			In Fig.	In Words					
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	22.53			Per cubic metre				
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	109.91			Per cubic metre				
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) dia PVC pipe De plast /finolex/vectus having pressure 4kg per sqmt (four kilogram) per square meter extending through the full width of the structures with slopes of 1(V): 20(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	35.00			Each				
4.00	Backfilling Granular material behind abutment, wing wall and return wall complete as per drawing& technical specification clause 1204.3.8, and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	11.65			Per cubic meter				
					Total				

Terms and Condition

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tauni Devi Division
HPPWD: Tauni Devi

Amir Kumar

Schedule of Quantity
NAME OF WORK:- Restoration of rain damages on Baru Tapre road km. 5/265 to 8/705. (SH:- C/O un-lined surface drain and dressing of berms), (Section-II).

drain and dressing of berms). (Section-11).						
Sr.No.		Description of Items		Estimated Cost:-		Rs. 316684.00
				Earnest Money:-		Rs. 6300.00
				Time:-		Two Months
		Qty.	In Fig.	Rate	Unit	Amount
				In Words		
1	Construction of un-lined surface drain of average cross sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in in embankments with a lift upto 3mtr. and lead of 50mtr. (average lead 25m) as per technical specification clause 307 (a) By manual means, as per direction of Engineer- in -Charge, including carriage of materials within all leads and lifts and other incidentals.	1535.00			Per running metre	
2	Maintenance of earthen shoulder (filling with fresh selected soil). Making up loss of material/irregularities on shoulders to the design level by adding fresh approves selected soil and compacting it with appropriate equipment at OMC upto all leads and lifts as per technical specification clause 1903, as per direction of Engineer- in -Charge, including carriage of materials within all leads and lifts and other incidentals.	4406.00			Per Square metre	
Terms and Condition						
1. Work shall be executed as per PWD specification.					Total	


 Executive Engineer,
 Tanni Devi Division,
 H.P. PWD: Tanni Devi

NAME OF WORK:-	Schedule of Quantity
Restoration of rain damages link road from Jhankar to Barin Village Km 0/00 to 1/300. (SH:- Construction of retaining wall at RD 0/970 to 0/980 and 1/015 to 1/022)	

Construction of retaining wall at RD 0/970 to 0/980 and 1/015 to 1/027)

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tauri Devi Division
HRAWD: Tauri Devi

NAME OF WORK:- C/O link road Behirda Bairol via Tholu road km. 0/0 to 4/0.(SH:- C/O 900mm dia hume pipe culvert at RD. 1/800 with wing wall). (Under SCS).

Schedule of Quantity

Sr.No.		Description of Items		Estimated Cost:-		Earnest Money:-		Rs. 467406.00 - 3,18,81,249/-	
				Time:-					
				Rate					
				In Words					
				Unit					
				Amount					
1	Excavation work by mechanical means (hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqmt(ten square metre on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	Qty.	In Fig.	Rate	Unit	Amount			
		95.96			Per cubic metre				
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.61			Per cubic metre				
3	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement: five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	59.39			Per cubic metre				
4	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars joined with stiff mixture of cement mortar in the proportion of 1:2 (one cement : two fine sand) including testing of joints etc. complete 900mm (nine hundred millimeters) dia RCC pipe as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	7.50			Per running metre				
5	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe De-plastic/index/ vedus pipe having pressure 4kg per centimeter square, (four kilogram per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	20.00			Each				
Total									
Terms and Condition									
1. Work shall be executed as per PWD specification.									


 Executive Engineer,
 Tauni Devl Division
 HPPWD: Tauni Devl

Schedule of Quantity

NAME OF WORK:- Construction of link road from Chaleli to Tikker via Debra Km 0/00 to 3/500. (SH:- Construction of retaining wall at RD 0/175 to 0/185) (Under SCSP)

Estimated Cost:- Rs.478616.00

Earnest Money:- Rs.9600.00

Time:- Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre) on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m(one point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within all leads (Ordinary rock)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government	37.85			Per cubic metre	
2.00	Providing and laying cement concrete 1:5:10 (one cement : five coarse sand: ten graded stone aggregate 40 mm(forty millimetre) nominal size curing complete the cost of form work plain/reinforced concrete in retaining walls, breast walls as per drawing and HPPWD Technical Specification direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government	110.08			Per cubic metre	
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) dia PVC pipe De plast /finolex/vectus having pressure 4kg per sqmt (four kilogram) per square meter extending through the full width of the structures with slopes of 1(V): 20(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government	27.00			Each.	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:-Construction of Ambulance Jeepable standard road Lamhera to Dhungola Brahmana Km 0/0 to 2/00. (SH:- Providing and laying GSB, WMM and V-Shape drain at RD 1/410 to 1/615)(Under OTMNP)

Estimated Cost:- Rs.496932.00
Earnest Money:- Rs.9900.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete with material conforming to Grade-1 (size range 75 mm(seventy five millimetre) to 0.075 mm(zero point zero seven five millimetre) having CBR Value-30(thirty) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	108.16			Per cubic metre	
2.00	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm(fifty three millimetre) to 0.075 mm(zero point zero seven five millimetre) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub-base / base course on well prepared surface and compacting with vibratory roller of 8(eight) to 10(ten) tonne capacity to achieve the desired density, complete as per technical specification clause 302.3 direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	65.65			Per cubic metre	
3.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand : six graded stone aggregate 20 mm (twenty millimetre) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	26.60			Per cubic metre	
	Total					

Terms and Condition

1. Work shall be executed as per PWD specification.

A.2000
Executive Engineer,
Tauni Devi Division,
HP
PWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:-Construction of Ambulance Jeepable standard road Lamhera to Dhangota Brahmana Km 0/0 to 2/00. (SH-1)
Providing and laying premix carpet surfacing with seal coat at RD 1/035 to 1/495)(Under OTMNP)

Estimated Cost:- Rs.494767.00
Earnest Money:- Rs.9900.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Providing and applying primer coat with bitumen emulsion(SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer @ 0.70-1.0 kilogram (zero point seven zero to one point zero kilogram per square metre) using mechanical means as per technical specification clause-503 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	1403.00			Per Square metre	
2.00	Providing and applying tack coat with bitumen emulsion using emulsion (RS-1) distributor at the rate of 0.25 to 0.30 Kg (zero point two five to zero point three zero kilogram) per Square metre on the prepared granular surfaces treated primer and cleaned with hydraulic Broom as per technical specification clause 503 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	1403.00			Per Square metre	
3.00	2 cm(two centimetre) premix carpet surfacing with 2.25 cum(two point twenty five cubic metre) and 1.12 cum(one point nine twelve cubic metre) of stone chippings of 13.2 mm(thirteen point two millimetre) size and 11.2 mm(eleven point two millimetre) size respectively per 100 sqm(one hundred square metre) and 52 kg(fifty six kilogram) and 56 kg(fifty six kilogram) of hot bitumen per cum of stone chippings of 13.2 mm(thirteen point two millimetre) and 11.2 mm(eleven millimetre) size respectively, including a tack coat with hot straight run bitumen, including consolidation with road roller of 6(six) to 9(nine) tonne capacity etc. complete (tack coat to be paid for separately) With paving Asphalt grade VG - 30 with no solvent as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	1403.00			Per Square metre	
4.00	Providing and laying seal coat of premixed fine aggregate (passing 2.36 mm(two point thirty six millimetre) and retained on 180(one hundred eighty) micron sieve) with bitumen using 128 kg(one hundred twenty eight kilogram) of bitumen of grade VG - 30 bitumen per cum of fine aggregate and 0.60 cum(zero point sixty cubic metre) of fine aggregate per 100 sqm(one hundred square metre) of road surface, including rolling and finishing with road roller all complete. as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	1403.00			Per Square metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

Amir Khan
Executive Engineer,
Tajpuri Devi Division,
HPWD, Tauni Devi