



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tenders on forms 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **04.10.2023** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **03.10.2023 between 2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **30.09.2023 up to 12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of work.	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	C/O Tashizong to Chandpur road Km 0/00-2/500 i/c Bridge over Pun Khad and C/O Foot Bridge over Binwa Khad at Baijnath (Near Kheer Ganga Ghat (SH: Preparation of Detail project report of road and Preparation of Hydraulic datas for C/O Bridge over Pun Khad and Binwa Khad)	Rs.1,69,500/-	Rs.3,390/-	Rs.350/-	Three Months
2	R/D on Various road under Bir Sub-Division, HPPWD Bir (SH: Supply and Stacking of hard fuel wood for patch work)	Rs.2,25,000/-	Rs.4,500/-	Rs.350/-	One Month
3	Construction R/Wall at Govt. High School Sehla (SH: Construction of R/Wall at Km 0/00 to 0/05 west side)	Rs.4,59,500/-	Rs.9,200/-	Rs.350/-	One Month
4	C/O Govt. Ayurvedic Collage at Paprola Distt. Kangra (H.P) (SH: Providing and Fixing wire Mesh Fencing at RD 0/180 to 0/310)	Rs.4,80,029/-	Rs.9,700/-	Rs.350/-	Two Months
5	Construction of Various Road under NABARD (SH: Purchase 1 No.s Computer System i/c Laser Printer of H.P. Model in O/O HPPWD Division Baijnath against contingency)	Rs.71,736/-	Rs.1,500/-	Rs.350/-	Two Months

Terms and conditions:-

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The Pan Number, latest Income Tax clearance certificate and EPF No(Where applicable) duly attached with the application.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
- In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- The application form should accompany the earnest money in the shape of FDR/NSC duly pledged in favour of Executive Engineer, PWD Baijnath otherwise no forms will be issued.
- The contractor will also have to attach the labour employer license from the labour office with the application.
- Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
- The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
- The contractor shall have all required machinery such as Truck/ Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
- The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an undertaking viz he will get complete the works in hand before award of work with in schedule time.
- All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
- The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.

For & On behalf of the governor of H.P.

NO:-PWD/BD/TA/NIT/2023-24/-


Dated:- 20-09-2023

- Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.

DNIT


Name of Work: C/O Tashzong to Chandpur road KM 0/00-2/500 i/c Bridge over Pun Khad and C/O Foot Bridge over Binwa Khad at Baijnath (Near Kheer Ganga Ghat (Sh: Preparation of Detail project report of road and Preparation of Hydraulic datas for C/O Bridge over Pun Khad and Binwa Khad)						Estimated Cost:-	169500.00
						Earnest Money:-	3400.00
						Time Limit :-	Three Months
Sr. No	Description of work	Qty	Unit	Rate		AMOUNT	
				Figure	Words	Rs.	P
1	Preparation of Detailed Project Report of road with Digital total station /Dual frequency DGPS complete in all respect in manuscript form and submission of the same to higher office for approval. If any correction/amendment has desired by the head office the same may be corrected as desired and directed by the Engineer - Incharge . After approval the same should be submitted in fair form complete.the payment excludes any soil investigation and shall be made as per actual length of road.The payment excludes any kind of soil investigation and shall be made as per actual length of road.	2.500	Per KM				
2	Preparation of Hydraulic data with Digital total station /Dual frequency DGPS for construction of Bridge over Pun Khad at Chandpur Complete in all respect .during approval of hydraurlic data from competent authourity .If any correction/amendment has desired by the head office the same may be corrected as desired and directed by the Engineer - Incharge . After approval the same should be submitted in fair form etc. complete.	1.00	Per Job L.S				
3	Preparation of Hydraulic data with Digital total station /Dual frequency DGPS for construction of Foot Bridge over Binwa Khad (Near Kheer Ganga Ghat)at Baijnath Complete in all respect .during approval of hydraurlic data from competent authourity .If any correction/amendment has desired by the head office the same may be corrected as desired and directed by the Engineer - Incharge . After approval the same should be submitted in fair form etc. complete.	1.00	Per Job L.S				
Total:-							


 Executive Engineer
 Baijnath Division
 H.P.P.W.D. Baijnath

SCHEDULE OF QUANTITY							
Name of Work: R/D on Various Road under Bir Sub Division, HPPWD Bir (SH: Supply and Stacking of hard fuel wood for patch work).				Estimated Cost: Rs. 225000/- Earnest Money: Rs. 4500/- Time Limit : One Month			
SCHEDULE OF WORKS							
S No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT	
				Figure	Words	Rs.	P
1	Supplying and stacking at site of work hard fuel wood (Bansoo wood) free from moisture and decay as approved by the Engineer-in-Charge within all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government including GST.	300.00	Per Qtl				

NOTE:-

1. The fuel wood of deodar/kail/mango and other local soft wood will not be accepted by the department and logs of the wood weighing less 40kg. will be accepted.


Executive Engineer
Bajjnath Division,
H.P.P.W.D. Bajjnath (H.P.)

3

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- Construction of R/wall at Govt High School Sehla (SH :- Construction of R/wall at km 0/00 to 0/05 west side).				Estimate Cost: 4,59,500.00/- Earnest Money: 9,200.00/- Time Limit : one Month		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	23.20	Per Cum			
2	Providing and laying cement concrete 1:5:10 (one cement, five sand, ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and M.O.R.D technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	78.05	Per Cum			
3	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1604.7 and section 300, as per direction of Engineer-In-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	9.30	Per Cum			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	12.00	Each			
Total						


Executive Engineer
Bajinath Division
H.P.W.D. Bajinath

SCHEDULE OF QUANTITY

Name of work:- C/O Govt Ayurvedic Collage at Paprola Distt. Kangra (H.P).
(SH:- Providing and Fixing Wire Mesh Fencing at RD 0/180 to 0/310).

Estimated Cost 480029.00
Earnest Money 9,700.00
Time limit Two Month

Sr No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT Rs. P	
				Figure	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m (one point fifty meter) in width or 10 sqm). including dressing of sides and ramming of bottoms, lift upto 1.5 m. (one point fifty meter) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m(Fifty meter).All kinds of soil.with in all leads by any mode of trasportation and other incidental .as per direction and entire satisfasation of Engineer -in - charge.The rate is including octroi. royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.68	Per Cubic metre				
2	Providing concrete for plain / reinforced concrete PCC Grade M-20 Nominal Mix 1:2:4 (one cement two sand four graded stone aggregate 20mm nominal size) in pavements, laid to required slop and camber in panels required including consolidation finishing and temping complete as per the direction of Engineer-in-charge including entire carriage of materials within all leads and lifts and other incidentals.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.68	Per Cubic metre				
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. as per direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3255.00	Per Kilo Gram				
4	Painting Steel work with Deluxe MultiSurface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (zero point nine zero liters per ten squire meter) over an under coat of primer applied @ 0.80 ltr/ 10 sqm (zero point eight zero liters per ten squire meter) of approved brand and manufacture. as per direction of Engineer - in- Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	131.63	Per Square Meter				
TOTAL							


Executive Engineer
Bajjnath Division
H.P.P.W.D. Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: - Construction of Various Road under NABARD.

(SH: Purchase 1 No.s Computer System i/c Laser Printer of H.P Model in O/O HPPWD Division Baijnath against contingency).


Estimate Cost: 71,736.00

Earnest Money: 1,500.00

Time Limit : One Month

SCHEDULE OF WORKS

Sl. No.	Description of work	No.or Qty.	Unit	Rate to be entered by the Bidder		AMOUNT Rs. P
				Figures	Words	
1	HP make AIO Desktop model HP 200 G4 with Intel core i3 -1215U-12th Gen process 8GB DDR4 Ram expandable upto 16 GB , 1 TB HDD (7200 RPM) , 21 " antiglare LED display with FHD (1920 X 1080) Integrated HD Graphics & Webcam 2 x USB 3.0 ,2 x USB 2.0 Audio port / VGA /HDMI / DP Port ,10/100 1 1000 M IPV6 Complaint LAN , USB ,Keyboard & USB Mouse , Internal speaker , 1 x 802.11 b/g/n/ac , PL- windows 10 pro 64 bit O.S. With three years on site warranty . The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate including of tolltax, GST & other taxes imposed by the government.	1.00	Each			
2	Mono Chrome Multi Function Laser Printer HP Laser MFP 136 a Printer A4 Size Paper , Printing Speed 20 PPM , Scan Speed black and Colour 6 PPM & 3 PPM Paper Tray Capacity 150 Pages , with one year warranty .The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge The rate including of tolltax, GST & other taxes imposed by the government	1.00	Each			


 Executive Engineer
 Baijnath Division,
 H.P.P.W.D. Baijnath (H.P.)