



E- Mail id – ee-bit2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

“NOTICE INVITING TENDERS”

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 13/09/2023 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 12/09/2023 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be outrightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

Sr. No.	Name of work	Estimated of cost	Earnest Money	Cost form	Time limit
1	Restoration of Rain damages on link road Swarghat to Manjher via Matnoh Km. 0/0 to 5/950 (SH:- C/o wire carte as R/wall at RD 3/885 to 3/895)	Rs. 3,64,476/-	Rs. 7,300/-	Rs. 350/-	Three Month
2	Restoration of Rain damages on damages on link road Bhuwai Km. 0/0 to 2/285 (SH:- C/o P.C.C. as RD 0/125 to 0/132)	Rs. 1,90,584/-	Rs. 3,900/-	Rs. 350/-	Three Month
3	Restoration of Rain damages on link road Harizen Basti Tiun Khas Km. 0/0 to 3/0 (SH:- C/o wire crate a R/wall at RD 0/900 to 0/910).	Rs. 3,14,452/-	Rs. 6,300/-	Rs. 350/-	Three Month
4	Restoration of Rain damages on Barm pukher to Shelli road Km. 0/0 to 11/300 (SH:- C/o R/wall at RD 5/740 to 5/755)	Rs. 4,91,152/-	Rs. 9,900/-	Rs. 350/-	Three Month
5	Restoration of Rain damages on link road Swarghat to Manjher via Matnoh Km. 0/0 to 5/950 (SH:- C/o wire carte as R/wall at RD 3/870 to 3/880)	Rs. 3,61,583/-	Rs. 7,300/-	Rs. 350/-	Three Month
6	A/R & M/O office Building HPPWD Division No. II in Distt. Bilaspur (HP) (SH:- Balance work of PVC Panelling)	Rs. 1,40,334/-	Rs. 2,900/-	Rs. 350/-	Three Month
7	Restoration of rain damages on Deoth to Jamli road Km. 0/0 to 8/0 (SH:- C/o R/wall at RD 0/090 to 0/105)	Rs. 4,70,750/-	Rs. 9,500/-	Rs. 350/-	Three Month
8	Restoration of Rain damages on link road Haizen Basti Tiun Khas Km. 0/0 to 3/0 (SH:- C/o wire crate as a R/wall at RD 0/915 to 0/925).	Rs. 3,12,978/-	Rs. 6,300/-	Rs. 350/-	Three Month
9	Restoration of Rain damages on Barm pukher to Shelli road Km. 0/0 to 11/300 (SH:- C/o R/wall at RD 5/300 to 5/320)	Rs. 2,98,096/-	Rs. 6,000/-	Rs. 350/-	Three Month
10	Restoration of Rain damages on Deoth to Lagghat Jamli road Km. 0/0 to 13/180 (SH:- C/o R/wall in wire crate at RD 9/215 to 9/235) under Stage-II	Rs. 4,49,856/-	Rs. 9,000/-	Rs. 350/-	Three Month
11	Restoration o Rain Damages on Sh. Naina Devi ji Bhakra road km. 0/0 to 37/300 (SH:- C/o B/wall and V-shape drain at RD 28/480 to 28/495)	Rs 1,87,271/-	Rs. 3,800/-	Rs. 350/-	Three Month
12	Restoration of Rain damages on Rajpura Chilla Charanmore road Km. 0/0 to 5/210 (SH:-C/o R/wall at RD 1/070 to 1/077 & B/wall at RD 1/215 to 1/230)	Rs 3,62,932/-	Rs. 7,300/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.

2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

No.PW/NBT/CB/Tender-State/EA-1/2023-

Dated:-

6199-6204

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

Date: 02-09-2023

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.3,64,476/-Only.

Earnest Money :- Rs.7,300/-

Time:- Three Months.

NAME OF WORK:-Restoration of Rain Damages on link road Swarghat to Manjher via Matnoh km 0/00 to 5/950 (SH:- C/o wire crate as R/wall at RD 3/885 to 3/895)

Description of items.

Sr No.	Quantity	Rates in		Unit	Amount
		Figure.	Words.		
1	24.20	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3	cubic metre	Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.00	Cubic metre.	Per Cubic Metre	
3	Providing and laying of boulder apron laid in wire crates with 4mm (Four Millimeter) dia GI wire conforming to IS:280 and IS:4826 in 100mm (One hundred Millimeter) x100mm (One hundred Millimeter) mesh(Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301. including cost of form work and curing complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	89.84	Cubic metre	Per Cubic metre	
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.40	Cubic metre.	Per Cubic Metre	
				Total:-	

Executive Engineer:
Bilaspur Division No. 1
P.W.D. Bilaspur

SCHEDULE OF QUANTITY.						Estimated cost:- Rs.1,90,584/-Only.	
NAME OF WORK:- Restoration of Rain Damages on link road Bhuwai km 0/00 to 2/285 (SH:- C/o P.C.C as a R/wall at RD 0/125 to 0/132)						Earnest Money :- Rs.3,900/-	
Description of items.						Time:- Three Months.	
Sr No.		Quantity	Rates in		Unit	Amount	
			Figure.	Words.			
1	1	3	4	5	6	7	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.70	cubic metre		Per cubic metre		
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	37.03	Cubic metre		Per Cubic metre		
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.69	Cubic metre.		Per Cubic Metre		
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess ,royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00	Nos.		Each		
	Total:-						

Executive Engineer,
Bilaspur Division
H.P.W.D., Bilaspur

SCHEDULE OF QUANTITY.							Estimated cost:- Rs.3,14,452/-Only.
							Earnest Money :- Rs.6,300/-
							Time:- Three Months.
NAME OF WORK:-Restoration of Rain Damages on link road Harizan Basti Tiun Khas km 0/00 to 3/00 (SH:- C/o wire crate as a R/wall at RD 0/900 to 0/910)							
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount	
			Figure.	Words.			
1	2	3	4	5	6	7	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.10	cubic metre		Per cubic metre		
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four Millimeter) dia GI wire confirming to IS:280 and IS:4826 in 100mm (One hundred Millimeter) x100mm (One hundred Millimeter) mesh(Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301. including cost of form work and curing complete including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	98.00	Cubic metre		Per Cubic metre		
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.00	Cubic metre.		Per Cubic Metre		
					Total:-		

Executive Engineer.
Bilaspur Division No. 11
P.W.D., Bilaspur

SCHEDULE OF QUANTITY.				Estimated cost:- Rs.4,91,152/-Only.			
				Earnest Money :- Rs.9,900/-			
				Time:- Three Months.			
NAME OF WORK:- Restoration of Rain Damages on Brampukhar to Shelli Road km 0/00 to 11/300 (SH:- C/o R/wall at RD 5/740 to 5/755)							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
		Figure.	Words.	Figure.	Words.		
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.50	cubic metre			Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	72.00	Cubic metre			Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate) 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.00	Cubic metre.			Per Cubic Metre	
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.25	Cubic metre.			Per Cubic Metre	
5	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.00	Nos.			Each	
Total:-							

Executive Engineer.
Bilaspur Division No. 11
P. PWD., Bilaspur R.P.

SCHEDULE OF QUANTITY.

NAME OF WORK:-Restoration of Rain Damages on link road Swarghat to Manjher via Matnoh km 0/00 to 5/950 (SH:- C/o wire crate as R/wall at RD 3/870 to 3/880)		Estimated cost:- Rs.3,61,583/-Only.	
Sr Description of items.		Earnest Money :- Rs.7,300/-	
No.		Time:- Three Months.	
		Quantity	
		Rates in	
		Unit	
		Amount	
1	2	Figure.	Words.
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3	24.50
			cubic metre
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.00	Cubic metre.
3	Providing and laying of boulder apron laid in wire crates with 4mm (Four Millimeter) dia GI wire conforming to IS:280 and IS:4826 in 100mm (One hundred Millimeter) x100mm (One hundred Millimeter) mesh(Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301. including cost of form work and curing complete including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	89.84	Cubic metre
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.90	Cubic metre.
			Per Cubic Metre
			Total:-

Engineer.
Bilaspur Division No 11
P.W.D., Bilaspur

SCHEDULE OF QUANTITY.						
						Estimated Cost:- Rs. =1,40,334/-Only.
						Earnest Money:- Rs.=2,900/-
						Time:- One Months.
Name of Work:- A/R & M/O Office Building HPPWD Division No.-II in Distt. Bilaspur (HP) (SH:- Balance work of PVC Panelling)						
Sr No.	Description of items.	Quantity	Rates in		Unit.	Amount.
			Figure.	Words.		
1	2	3	4	5	6	7
1	P/F PVC Panelling 8mm (Eight Milimeter) thick with decorative surface on one face with butt jointing and screw etc. in walls,ceilling including carriage of material with in all leads and lifts and other incidentals.The rate includes octori, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	75.77			Per Square metre.	
2	P/F beading for PVC antistatics very lining on walls/ceilling including carriage of materials , within all leads and lifts and other incidentals . The rate includes octori, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	99.04			Per Running Metre	
	Total					

Executive Engineer,
Bilaspur Division No. II
P.W.D., Bilaspur

SCHEDULE OF QUANTITY.							Estimated cost:- Rs.4,70,750/-Only.	
							Earnest Money :- Rs.9,500/-	
							Time:- Three Months.	
NAME OF WORK:- Restoration of Rain Damages on Deoth to Jamli road km 0/00 to 8/00 (SH:- C/o R/wall at RD 0/090 to 0/105)								
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount	
				Figure.	Words.			
1	2	3		4	5	6	7	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	41.70	cubic metre			Per cubic metre	7	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	99.00	Cubic metre			Per Cubic metre		
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification,1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.35	Cubic metre.			Per Cubic Metre		
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess ,royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.00	Nos.			Each		
Total:-								

Executive Engineer.
Bilaspur Division No. 11
P.W.D., Bilaspur

SCHEDULE OF QUANTITY.				Estimated cost:- Rs.3,12,978/-Only.		
				Earnest Money :- Rs.6,300/-		
				Time:- Three Months.		
NAME OF WORK:-Restoration of Rain Damages on link road Harizan Basti Tiun Khas km 0/00 to 3/00 (SH:- C/o wire crate as a R/wall at RD 0/915 to 0/925)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	25.10			Per cubic metre	7
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four Millimeter) dia GI wire conforming to IS:280 and IS:4826 in 100mm (One hundred Millimeter) x100mm (One hundred Millimeter) mesh(Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301. including cost of form work and curing complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	98.00			Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.50			Per Cubic Metre	
					Total:-	

Executive Engineer,
Bilaspur Division No. 11,
H.P. PWD., Bilaspur

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.2,98,096/-Only.

Earnest Money :- Rs.6,000/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on Brampukhar to Shelli Road km 0/00 to 11/300 (SH:- C/o R/wall at RD 5/300 to 5/320)

Description of items.

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.40	cubic metre			Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	63.00	Cubic metre			Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.20	Cubic metre.			Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.00	Nos.			Each	
	Total:-						

Executive Engineer,
Bilaspur Division No. 11
JP PWD., Bilaspur

SCHEDULE OF QUANTITY.						Estimated cost:- Rs.4,49,856/-Only.	
						Earnest Money :- Rs.9,000/-	
						Time:- Three Months.	
NAME OF WORK:- Restoration of Rain Damages on Deoth to Lagghat Jamii road 0/00 to 13/180 (SH:- C/o R/wall in wire crate at RD 9/215 to 9/235) (under Stage-II)							
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount	
			Figure.	Words.			
1	2	3	4	5	6	7	
1	Providing and laying of boulder apron laid in wire crates with 4mm (Four Millimeter) dia GI wire confirming to IS:280 and IS:4826 in 100mmx100mm (one hundred millimeter one hundred millimeter) mesh (Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301. including cost of form work and curing complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	156.20	Cubic metre	Per Cubic metre			
Total:-							

Executive Engineer,
Bilaspur Division No. 11
P.W.D., Bilaspur (M.P.)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.1,87,271/-Only.

Earnest Money :- Rs.3,800/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on Sh. Naina Devi Bhakra Road km 0/00 to 37/300(SH:- C/o B/wall and V-Shape Drain at Rd 28/480 to 28/495)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
		Figure.	Words.	Figure.	Words.		
1	2	3	4	5	6	7	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.40	cubic metre			Per cubic metre	
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.80	cubic metre			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	35.26	Cubic metre			Per Cubic metre	
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and other service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.69	Cubic metre.			Per Cubic Metre	

Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge The rates includes octroi,royalty, Malkana toll tax goods and service tax ,building and other construction work, welfare cess ,royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00	Nos.		Each	
Total:-					

Executive Engineer,
Bilaspur Division No. II
H.P.W.D., Bilaspur

SCHEDULE OF QUANTITY.					
Estimated cost:- Rs.3,62,932/-Only.					
Earnest Money :- Rs.7,300/-					
Time:- Three Months.					
NAME OF WORK:- Restoration of Rain Damages on Rajpura Chilla Charnmore road km 0/00 to 5/210 (SH:- C/O R/wall at Rd 1/070 to 1/077 & B/wall at RD 1/215 to 1/230)					
Sr No.	Description of items.	Quantity	Rates in		Unit
			Figure.	Words.	
1	2 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 16.17	4 cubic metre	5 	6 Per cubic metre
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.68	cubic metre		Per cubic metre
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	81.17	Cubic metre		Per Cubic metre
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.61	Cubic metre.		Per Cubic Metre

5	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess ,royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.00	Nos.			Each	
Total:-							

Security/Engineering
 Master Division No. 9
 DWD Bilaspur-1400