

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed item rate tender on form NO. 6&8 are hereby invited by the Executive Engineer, Bilaspur Division No. 1, HP.PWD., Bilaspur on behalf of Governor of Himachal Pradesh from the approved and eligible contractors enlisted in PWD Department so as to reach in this office on or before 27/09/2023 up to 10.30 A.M. and will be opened on the same day at 11.00 A.M. in the presence of the intending contractors or their authorized representatives who may like to be present. If it happens to be holiday on that day tenders will be opened on next working day. The application for obtaining the tender forms will be received up to 25/09/2023 up to 5.00 PM and the tender form can be had from this office on 26/09/2023 during the office hours.

The Earnest money in the shape of National Saving Certificate Time deposit Accounts/FDR of any Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, Division No. 1, HP.PWD., Bilaspur must be accompanied with each application for obtaining the tenders. The tender application received without earnest money /cost of tender forms will similarly be rejected. The undersigned reserves the right to reject the tenders without assigning any reason.

Sr. No.	Name of Work	Amount	Earnest Money	Cost of tender form	Time
1	A/R & M/O to residential building in Changer Sector Bilaspur. (SH:- P/F pre-painted sheet shed at SE residence).	446147	9000	350	2 Months
2	A/R & M/O to residential building in Changer Sector Bilaspur. (SH:- P/F pre-painted sheet shed at SE residence).	442444	9000	350	2 Months
3	Restoration of Rain Damages on Dhar Darober Sarain Ghati road Km. 0/0 to 9/300. (SH:- C/O R/wall at RD. 7/645 to 7/650.35).	493612	10000	350	3 Months
4	Restoration of Rain Damages on Dhar Darober Sarain Ghati road Km. 0/0 to 9/300. (SH:- C/O R/wall at RD. 8/300 to 8/312.40).	498566	10000	350	3 Months
5	Balance work for the Development of plot at Jamthal Tehsil Sadar Distt. Bilaspur (H.P) for NTPC Ltd. Koldam Project Barmana (Jamthal). (SH:- F/C 5/7 mtr at Km. 0/0 to 0/525, C.D, R/Wall, B/Wall, cutting of plot etc. (Protection work i.e wire crate wall in valley side below road at RD. 0/070 for retaining of debris).	484629	10000	350	3 Months
6	Repair of approach road road to Indoor Stadium & Kehlloor sports complex Km. 0/0 to 0/265. (SH:- P/L Interlocking paver block from RD, 0/142 to 0/168 & 0/213 to 0/265).	485655	9800	350	1 Month
7	Construction of Helipad at Bilaspur Luhnau Bilaspur. (SH:- C/O Balance work of Helipad)	370668	7500	350	3 Months
8	Restoration of rain damages on Harlog Hawan Behal Nanawin road Km. 0/0 to 14/0. (SH:- C/O wire crate at RD. 1/510 to 1/539.50).	479316	10000	350	3 Months
9	Restoration of rain damages on Harlog Hawan Behal Nanawin road Km. 0/0 to 14/0. (SH:- C/O wire crate at RD. 1/480 to 1/510).	484418	10000	350	3 Months

	Restoration of rain damages on Harlog Hawan Behal Nanawin road Km. 0/0 to 14/0. (SH:- C/O wire crate at RD. 1/539.50 to 1/569).	482749	10000	350	3 Months
11	Restoration of rain damages on Harlog Hawan Trifalghat road Km. 0/0 to 14/0. (SH:- C/O wire crate at RD. 1/569 to 1/599).	484513	10000	350	3 Months
12	Restoration of rain damages on Panoh Harlog Samaila road Km. 0/0 to 22/615. (SH:- C/O wire crate at RD. 5/060 to 5/075).	487578	10000	350	3 Months
13	Restoration of rain damages on Panoh Harlog Samaila road Km. 0/0 to 22/615. (SH:- C/O wire crate at RD. 6/070 to 6/085).	474960	10000	350	3 Months
14	Restoration of rain damages on Harlog Ghattu Trifalghat road Km. 0/0 to 20/0. (SH:- C/O wire crate at RD. 8/052 to 8/082).	479316	10000	350	3 Months
15	Restoration of rain damages on Harlog Ghattu Trifalghat road Km. 0/0 to 20/0. (SH:- C/O wire crate at RD. 11/050 to 11/085).	482749	10000	350	3 Months
16	Restoration of rain damages on Harlog Ghattu Trifalghat road Km. 0/0 to 20/0. (SH:- C/O wire crate at RD. 1/715 to 1/745).	487578	10000	350	3 Months
17	Restoration of rain damages on Harlog Ghattu Trifalghat road Km. 0/0 to 20/0. (SH:- C/O wire crate at RD. 1/745 to 1/775).	486937	10000	350	3 Months
18	Restoration of rain damages on Kuhghat to Amarsinghpura road Km. 0/0 to 8/735. (SH:- C/O R/wall at RD. 4/100 to 4/108).	445316	10000	350	2 Months
19	Restoration of rain damages on Kuhghat to Amarsinghpura road Km. 0/0 to 8/735. (SH:- C/O Gabion wall (crate wire wall) at RD. 4/100 to 4/120).	214036	4300	350	2 Months
20	Restoration of rain damages on Kuhghat to Amarsinghpura road Km. 0/0 to 8/735. (SH:- C/O R/wall at RD. 4/108 to 4/115).	390640	8000	350	3 Months
21	Restoration of rain damages on Kothi Tarrer road Km. 0/0 to 7/200. (SH:- C/O R/Wall (crate wire) at RD. 6/755 to 6/775).	495183	10000	350	2 Months
22	Restoration of rain damages on Kothi Tarrer road Km. 0/0 to 7/200. (SH:- C/O R/Wall (crate wire) at RD. 6/385 to 6/408).	497349	10000	350	2 Months
23	Restoration of rain damages on Kandruar Saloo Barmana road Km. 0/0 to 12/150. (SH:- C/O R/Wall at RD. 5/550 to 5/562).	498869	10000	350	3 Months
24	Restoration of rain damages on Kothi Tarrer road Km. 0/0 to 7/200. (SH:- C/O B/Wall at RD. 4/370 to 4/390).	233154	5000	350	2 Months

	Restoration of rain damages on Kothi Tarrer road Km. 0/0 to 7/200. (SH:- C/O R/Wall along house of Sh. Ram Rattan RD. 3/586 to 3/596 and B/Wal at RD. 3/586 to 3/600 with side drain).	444983	8900	350	2 Months
26	Restoration of rain damages on Patta Morsinghi road Km. 0/0 to 11/070. (SH:- C/O wire crate at RD. 8/900 to 8/914 both side)	474178	9500	350	3 Months
27	Restoration of rain damages on Patta Morsinghi road Km. 0/0 to 11/070. (SH:- C/O wire crate at RD. 9/230 to 9/240).	338967	6800	350	2 Months
28	Restoration of rain damages on Delag to Chalama road Km. 0/0 to 5/500. (SH:- C/O crate wire R/Wall at RD. 3/500 to 3/517.50).	495065	10000	350	2 Months
29	Restoration of rain damages on Bhatoli Malyawar road Km. /0 to 4/0. (SH:- C/O wire crate at RD. 0/30 to 0/60).	474185	10000	350	3 Months
30	Restoration of rain damages on Bhatoli Malyawar road Km. /0 to 4/0. (SH:- C/O wire crate at RD. 0/300 to 0/330)	484417	9700	350	3 Months

TERMS & CONDITIONS:-

1. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
2. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactorily including adherence to quality future work will be awarded to him. All undertaking that is not having more than two works in hand must be recorded in the application, failing which application of such contractor shall be rejected without any notice to him.
3. Earnest money should be accompanied with application. Application without earnest money will not be Entertained.
4. The photo copy of Pan Number/renewal should be attached with the application otherwise tender form will not be issued.

Executive Engineer,
Bilaspur, Division No.1
HP.PWD, Bilaspur.

NO.PW-BLP-FCB-EA-1-Tender/ 2023-

11036-60

Dated: 19/9/2023

Copy forwarded to the following for information please.

1. The Engineer-in-Chief, HP.PWD; Shimla-I.
2. The Chief Engineer (HZ) HP.PWD, Hamirpur.
3. The Superintending Engineer, 10th Circle, HP.PWD, Bilaspur.
4. The Executive Engineer (IT) O/o the Engineer-in-Chief, HP.PWD, Shimla through email:- eeict-pwd-shi@hp.gov.in alongwith copies of Schedule of quantities for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. All the contractors as per record of this office.
9. Accounts Branch/ Drawing Branch/Supdt. in this office.
10. Notice Board.

Executive Engineer,
Bilaspur, Division No.1
HP.PWD, Bilaspur.

Schedule of quantity							Estimated cost Rs. 4,46,147/-only
							Earnest Money Rs. 9,000/- only.
							Time Limit = Two month
Name of work:- A/R & M/O to residential building in Changer Sector Bilaspur. (SH:- P/F pre-painted sheet shed at SE residence).							
Sr No	Description of items.	Qty.	Rates		Unit	Amount	
			In Figure	In Word			
1	2	3	5	6	7	8	
1	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	2050.50			Kilogram		
2	Providing and fixing 0.60mm (Zero point sixty millimeter) thick pre-painted steel sheet of TATA / DURO SHINE in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) micron over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J ope L hooks, bolts and nuts 6mm diameter with pre-painted limpet and rubber washers complete with all accessories. as per HP PWD Specification. including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	102.53			Per Square Meter		
3	Providing ridges or hips of width 60 cm (Sixty centimetre) overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.63 mm (Zero point sixty millimeter) thick with zinc coating not less than 275 gm/m ² (Two hundred seventy five grmae / square metre). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	34.80			Runing Metre		
4	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.34			Per Square Metre		
5	Providing and fixing M.S. BP Sheet 1.60mm to 2mm (one point sixty six millimetre to two millimetre) thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.34			Per Square Mtr		

6	Disemballing roofing including ridges, hips valley and gutters etc. and stacking the material with in 50 metres lead. including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	102.53				Per Cubic Metre
TOTAL						

Amge Lal

[Signature]
Executive Engineer
Bilaspur Division No.1
HBPWD Bilaspur

Schedule of quantity

Schedule of quantity

Name of work:- A/R & M/O to residential building in Changer Sector Bilaspur. (SH:- P/F pre-painted sheet shed at SE residence).

Description of items.	Qty.	Rates	Unit	Amount
Sr No		In Figure	In Word	
		3	6	8
1	2	2209.80		Kilogram
1	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.			
2	Providing and fixing 0.60mm (Zero point sixty millimeter) thick pre-painted steel sheet of TATA / DURO SHINE in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) micron over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J opr L hooks, bolts and nuts, 6mm diameter with pre-painted limpet and rubber washers complete with all accessories. as per HP PWD Specification. including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	110.49		Per Square Meter
3	Providing ridges or hips of width 60 cm (Sixty centimetre) overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.63 mm (Zero point sixty millimeter) thick with zinc coating not less than 275 gm/m ² . (Two hundred seventy five gramme / square metre). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	31.30		Running Metre
4	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.04		Per Square Metre
5	Providing and fixing M.S. BP Sheet 1.66mm to 2mm(one point sixty six millimetre to two millimeter) thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.04		Per Square Mtr

Estimated cost Rs. 4,42,444/-only
Earnest Money Rs. 9,000/- only.
Time Limit. = Two month

6	Dismantling roofing including ridges, hips valley and gutters etc. and stacking the material with in 50 metres lead. including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	110.49					Per Cubic Metre
TOTAL							

Executive Engineer
Bilaspur Division No.1
H.P.W.D., Bilaspur

SCHEDULE OF QUANTITY.							
Estimated cost Rs. = 4,93,612/-only							
Earnest Money Rs. = 10,000/- only.							
Time Limit = Three Month							
Name of Work:- Restoration of Rain Damages on Dhar Darober Sarain Ghati road Km. 0/0 to 9/300. (SH:- C/O R/wall at RD. 7/645 to 7/650.35).							
Sr No	Description of items.	Qty.		Rates		Amount	
		3	4	In Figure	In words		
1	2	3	4	5	6	8	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (Ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (Fifty metre) and lift upto 1.5 m, (One point five metre) as directed by Engineer-in-Charge. The rate includes carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	52.48	Cubic Metre				
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.00	Square Metre				
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	101.44	Cubic Metre				
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Nos.				

5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.84	Cubic metre			
TOTAL						


 Executive Engineer
 Bilaspur Division No.1
 HP.2WD Bilaspur

SCHEDULE OF QUANTITY.					Estimated cost Rs. = 4,98,566/-only	
					Earnest Money Rs. = 10,000/- only.	
					Time Limit. = Three Month	
Name of Work:- Restoration of Rain Damages on Dhar Darober Sarain Ghati road Km. 0/0 to 9/300. (SH:- C/O R/wall at RD. 8/300 to 8/312.40).						
Sr No	Description of items.	Qty.	Rates		Amount	
			In Figure	In words		
1	2	3	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centemere) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (Ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (Fifty metre) and lift upto 1.5 m, (One point five metre) as directed by Engineer-in-Charge. The rate includes carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.62	Cubic Metre			
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	76.25	Square Metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	98.67	Cubic Metre			
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Nos.			

5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.61	Cubic metre			
TOTAL						


 Executive Engineer
 Bilaspur Division No.1
 HPDWD, Bilaspur

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.									
Estimated cost Rs. = 4,84,629/-only									
Earnest Money Rs. = 10,000/- only.									
Time Limit. = Three Month									
Balance work for the Development of plot at Jamthal Tehsil Sadar Distt. Bilaspur (H.P) for NTPC Ltd. Koldam Project Barmana (Jamthal). (SH:- F/C 5/7 mtr at Km. 0/0 to 0/525, C.D, R/Wall, B/Wall, cutting of plot etc. (Protection work i.e wire crate wall in valley side below road at RD. 0/070 for retaining of debris).									
Sr No	Description of items.	Qty.		Rates		Amount			
		In Figure	In words						
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centemere) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (Ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (Fifty metre) and lift upto 1.5 m. (One point five metre) as directed by Engineer-in-charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3	4	5	6	8			
2	Providing & making Gabion structure with Mechanically Woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012.MORTH Clause 2500. of required size. Mesh Type 10x12 (Ten into twelve) (D=100 mm (One hundred millimetre) with tolerance of ± 2% (Two percent) Zinc coated, Mesh wire diameter 3.0 mm (Three millimetre) mechanically edged/selvedged with partitions at every 1m interval and shall have minimum 10 (Ten) numbers of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2mm, (Two point two millimetre) supplied @ 3% (Three percent) by weight of Gabion boxes, filled with boulders with least dimension of 200 mm, (Two hundred millimetre) as per drawing, all complete as per direction of Engineer-in-charge.. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.45	Cubic Metre						
		148.44	Cubic Metre						
TOTAL									

Executive Engineer
Bilaspur Division No.1
HRDWD, Bilaspur

SCHEDULE OF QUANTITY.		Estimated cost Rs. = 4,85,655/-only Earnest Money Rs. = 9,800/- only. Time Limit. = One Month				
Name of Work:- Repair of approach road to Indoor Stadium & Kehloor sports complex Km. 0/0 to 0/265. (SH:- P/L Interlocking paver block from RD, 0/142 to 0/168 & 0/213 to 0/265).						
Sr No	Description of items.	Qty.		Rates		Amount
				In Figure	In words	
1	2	3	4	5	6	8
1	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm (Fifty millimetre) thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and weeping extra sand. complete all as per direction of Engineer-in Charge 80 mm (Eighty milimetre) thick C.C. paver block of M-50 (M-fifty) grade with approved color design and pattern. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other constnuction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	330.50	Square metre			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (One Cement : Three coarse sand) : Six graded stone aggregate 20 mm (twenty millimetre) nominal size). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other constnuction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.32	Cubic metre			
TOTAL						

Executive Engineer
Bilaspur Division No.1
HPPWD, Bilaspur

SCHEDULE OF QUANTITY.

		Name of Work:- C/O Helipad at Bilaspur Luhnu Bilaspur. (SH:- C/O Balalnce work of Helipad).				Estimated cost Rs. = 3,70,668/-only Earnest Money Rs. = 7,500/- only. Time Limit. = Three Month		
Sr No	Description of items.	Qty.	Rates		Amount			
			In Figure	In words				
		3	4	5	6			
1	2	3	4	5	6			
1	Providing and laying design mix cement concrete of M-30 grade, in roads/ taxi tracks/ runways, using cement content as per design mix, using coarse sand and graded stone aggregate of 40 mm nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeve/ tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/ camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/ expansion, construction & longitudinal joints (10 mm (Ten millimetre) wide x 50 mm (Fifty millimetre) deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineer-in-charge (Item of joint fillers, sealants, dowel bars with sleeve/ tie bars to be paid separately). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	31.43	Cubic Metre					
2	Providing and laying of hot applied thermoplastic compound 2.5 mm (Two point five millimetre) thick including reflectorising glass beads @ 250 gms (Two hundred fifty grams) per sqm area, thickness of 2.5 mm (Two point five millimetre) is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	107.01	Square Metre					
3	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. On concrete work. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	330.00	Square Metre					

4	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over and under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	330.00	Square Metre			
TOTAL						

Executive Engineer
Bilaspur Division No.1
HRD, Bilaspur

SCHEDULE OF QUANTITY.						
Estimated cost Rs. = 4,79,316/-only						
Earnest Money Rs. = 10,000/- only.						
Time Limit. = Three Month						
Name of Work:- Restoration of rain damages on Harlog Hawan Behal Nanawin road Km. 0/0 to 14/0. (SH:- C/O wire crate at RD. 1/510 to 1/539.50).						
Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	2 Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	66.97	Cubic Metre	5	6	8
2	Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GI. wire conforming to ISI 280 and ISI 4026 in 150 mm (One hundred fifty millimetre) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps ad joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	138.28	Cubic Meter			
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.47	Cubic metre			
		TOTAL				


 Executive Engineer
 Bilaspur Division No.1
 HP-PWD Bilaspur

SCHEDULE OF QUANTITY.					
Name of Work:- Restoration of rain damages on Harlog Hawan Behal Nanawin road Km. 0/0 to 14/0. (SH:- C/O wire crate at RD. 1/480 to 1/510).					
Estimated cost Rs. = 4,84,418/-only					
Earnest Money Rs. = 10,000/- only.					
Time Limit. = Three Month					
Sr No	Description of items.	Qty.		Rates	
		3	4	In Figure	In words
1	2			5	6
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	56.85	Cubic Metre		
2	Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GL wire conforming to ISI 280 and ISI 4826 in 150 mm (One hundred fifty millimetre) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps ad joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes. octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	140.63	Cubic Metre		
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.35	Cubic metre		
TOTAL					

Executive Engineer
Gillaspur Division No.1
HP. PWD, Gillaspur

Sr No		Description of items.	Qty.		Rates		Amount	
					In Figure	In words		
Name of Work:- Restoration of rain damages on Harlog Hawan Behal Nanawin road Km. 0/0 to 14/0. (SH:- C/O wire crate at RD. 1/539.50 to 1/569).								
1	1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3	72.42	4	5	6	8
2		Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GL wire conforming to ISI 280 and ISI 4826 in 150 mm (One hundred fifty millimetre) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps ad joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	138.28		Cubic Meter			
3		Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.24		Cubic metre			
TOTAL			TOTAL					


 Executive Engineer
 Bilaspur Division No.1
 HP PWD, Bilaspur

SCHEDULE OF QUANTITY.			Estimated cost Rs. = 4,84,513/-only Earnest Money Rs. = 10,000/- only. Time Limit. = Three Month			
Name of Work:- Restoration of rain damages on Harlog Hawan Trifalghat road Km. 0/0 to 14/0. (SH:- C/O wire crate at RD. 1/569 to 1/599).						
Sr No	Description of items.	Qty.	Rates		Amount	
			In Figure	In words		
1	2	3	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ranning of bottoms. lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	70.20	Cubic Metre			
2	Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GL wire conforming to ISI 280 and ISI 4826 in 150 mm (One hundred fifty millimetre) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps and joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	140.63	Cubic Metre			
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.10	Cubic metre			
		TOTAL				

Executive Engineer
Bilaspur Division No.1
HRDWD, Bilaspur

SCHEDULE OF QUANTITY.					Estimated cost Rs. = 4,87,578/-only	
					Earnest Money Rs. = 10,000/- only.	
					Time Limit. = Three Month	
Name of Work:- Restoration of rain damages on Panoh Harlog Samaila road Km. 0/0 to 22/615. (SH:- C/O wire crate at RD. 5/060 to 5/075).						
Sr No	Description of items.	Qty.		Rates		Amount
		In Figure	In words	In Figure	In words	
1	2	3	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	73.80	Cubic Metre			
2	Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GL wire conforming to ISI 280 and ISI 4826 in 150 mm (One hundred fifty millimetre) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps ad joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	140.63	Cubic Meter			
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.90	Cubic metre			
TOTAL						


 Executive Engineer
 Bilaspur Division No.1
 HPPWD, Bilaspur

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.					Estimated cost Rs. = 4,74,960/-only	
					Earnest Money Rs. = 10,000/- only.	
					Time Limit. = Three Month	
Name of Work:- Restoration of rain damages on Panoh Harlog Samaila road Km. 0/0 to 22/615. (SH:- C/O wire crate at RD. 6/070 to 6/085).						
Sr No	Description of items.	Qty.	Rates		Amount	
			In Figure	In words		
		3	5	6	8	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and running of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	71.55	4	Cubic Metre		
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	50.97		Square Metre		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.25		Cubic Metre		
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (V): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00		Nos.		
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.85		Cubic metre		

6	Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GL wire conforming to ISI 280 and ISI 4826 in 150 mm (One hundred fifty millimetre) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps and joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes, ourrei, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	70.31	Cubic Meter			
TOTAL						


 Executive Engineer
 Bilaspur Division No.1
 HPWD, Bilaspur

SCHEDULE OF QUANTITY.							
Estimated cost Rs. = 4,79,316/-only							
Earnest Money Rs. = 10,000/- only.							
Time Limit. = Three Month							
Name of Work:- Restoration of rain damages on Harlog Ghattu Trifalghat road Km. 0/0 to 20/0. (SH:- C/O wire crate at RD. 8/052 to 8/082).							
Sr No	Description of items.	Qty.		Rates		Amount	
				In Figure	In words		
1	2	3	4	5	6	8	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, (One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	66.97	Cubic Metre				
2	Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GL wire conforming to ISI 286 and ISI 4826 in 150 mm (One hundred fifty millimetre) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps ad joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	138.28	Cubic Metre				
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.47	Cubic metre				
TOTAL							

Executive Engineer
 Bilaspur Division No.1
 H.P.W.D. Bilaspur

SCHEDULE OF QUANTITY.						
Name of Work:- Restoration of rain damages on Harlog Ghattu Trifalghat road Km. 0/0 to 20/0. (SH:- C/O wire crate at RD. 11/050 to 11/085).						
Sr No						
1	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	2 Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	72.42	Cubic Metre	5	6	8
2	Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GL wire conforming to ISI 280 and ISI 4826 in 150 mm (One hundred fifty millimetre) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps ad joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	138.28	Cubic Meter			
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 (including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.24	Cubic metre			
TOTAL						


 Executive Engineer
 Bilaspur Division No.1
 H.P.W.D. Bilaspur

SCHEDULE OF QUANTITY.		Estimated cost Rs. = 4,87,578/-only				
		Earnest Money Rs. = 10,000/- only.				
		Time Limit. = Three Month				
Name of Work:- Restoration of rain damages on Harlog Ghattu Trifalghat road Km. 0/0 to 20/0. (SH:- C/O wire crate at RD. 1/715 to 1/745).						
Sr No	Description of items.	Qty.		Rates		Amount
				In Figure	In words	
1	2	3	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, (One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	73.80	Cubic Metre			
2	Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GL wire conforming to ISI 280 and ISI 4826 in 150 mm (One hundred fifty millimetre) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps ad joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	140.63	Cubic Meter			
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.90	Cubic metre			
TOTAL						


 Executive Engineer
 Bilaspur Division No.1
 H.P. WD, Bilaspur

SCHEDULE OF QUANTITY.		Estimated cost Rs. = 4,86,937/-only Earnest Money Rs. = 10,000/- only. Time Limit. = Three Month					
Name of Work:- Restoration of rain damages on Harlog Ghattu Trifalghat road Km. 0/0 to 20/0. (SH:- C/O wire crate at RD. 1/745 to 1/775).							
Sr No	Description of items.	Qty.		Rates		Amount	
		In Figure	In words	In Figure	In words		
1	2	3	4	5	6	8	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and running of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	76.05	Cubic Metre				
2	Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GL wire conforming to ISI 280 and ISI 4826 in 150 mm (One hundred fifty millimetre) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps and joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	140.63	Cubic Meter				
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.00	Cubic metre				
TOTAL							



 Executive Engineer
 Bilaspur Division No.1
 H.P.W.D. Bilaspur

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.							Estimated cost Rs. = 4,45,316/-only	
							Earnest Money Rs. = 10,000/- only.	
							Time Limit. = Three Month	
Name of Work:- Restoration of rain damages on Kuhghat to Amarsinghpura road Km. 0/0 to 8/735. (SH:- C/O R/wall at RD. 4/100 to 4/108).								
Sr No	Description of items.	Qty.		Rates		Amount		
		In Figure	In words	In Figure	In words			
1	2	3	4	5	6	8		
1	Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (Ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (Fifty metre) and lift upto 1.5 m, (One point five metre) as directed by Engineer-in-charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	32.60	Cubic Metre					
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	124.28	Square Metre					
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	83.04	Cubic Metre					
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall. return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.00	Nos.					
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.52	Cubic metre					
TOTAL								

Executive Engineer
Bilaspur Division No.1
Bilaspur

SCHEDULE OF QUANTITY.									
Estimated cost Rs. = 2,14,036/-only									
Earnest Money Rs. = 4,300/- only.									
Time Limit. = Two Month									
Name of Work:- Restoration of rain damages on Kuhghat to Amarsinghpura road Km. 0/0 to 8/735. (SH:- C/O Gabion wall (crate wire wall) at RD. 4/100 to 4/120).									
Sr No	Description of items.	Qty.		Rates		Amount			
		In Figure	In words						
1	2	3	4	5	6	8			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	75.00	Cubic Metre						
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.80	Cubic Metre						
3	Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GL wire conforming to ISI 280 and ISI 4826 in 150 mm (One hundred fifty millimetre) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps ad joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	62.50	Cubic Meter						
TOTAL									


 Executive Engineer
 Bilaspur Division No.1
 BWD, Bilaspur

SCHEDULE OF QUANTITY.									
Estimated cost Rs. = 3,90,640/-only									
Earnest Money Rs. = 8,000/- only.									
Time Limit. = Three Month									
Name of Work:- Restoration of rain damages on Kuhghat to Amarsinghpura road Km. 0/0 to 8/735. (SH:- C/O R/wall at RD. 4/108 to 4/115).									
Sr No	Description of items.	Qty.	Rates		Amount				
			In Figure	In words					
1	2	3	4	5	6	8			
1	Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (Ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (Fifty metre) and lift upto 1.5 m, (One point five metre) as directed by Engineer-in-charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	28.53	Cubic Metre						
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	111.34	Square Metre						
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	72.66	Cubic Metre						
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00	Nos.						
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.58	Cubic metre						
		TOTAL							

SCHEDULE OF QUANTITY.						Estimated cost Rs. = 4,95,184/-only	
						Earnest Money Rs. = 10,000/- only.	
						Time Limit. = Two Month	
Name of Work:- Resoration of rain damages on Kothi Tarrer road Km. 0/0 to 7/200. (SH:- C/O R/Wall (crate wire) at RD. 6/755 to 6/775)							
Sr No	Description of items.	Qty.		Rates		Amount	
		3	4	In Figure	In words		
1	2	3	4	5	6	8	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	86.30	Cubic Metre				
2	Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GL wire conforming to ISI 280 and ISI 4826 in 150 mm (One hundred fifty millimetre) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps ad joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	132.81	Cubic Meter				
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	41.20	Cubic metre				
		TOTAL					


Executive Engineer
Bilaspur Division No.1
HP.PWD Bilaspur

SCHEDULE OF QUANTITY.									
Estimated cost Rs. = 4,97,349/-only									
Earnest Money Rs. = 10,000/- only.									
Time Limit. = Two Month									
Name of Work:- Resoration of rain damages on Kothi Tarrer road Km. 0/0 to 7/200. (SH:- C/O R/Wall (crate wire) at RD. 6/385 to 6/408)									
Sr No	Description of items.	Qty.		Rates		Amount			
				In Figure	In words				
1	2	3	4	5	6	8			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	98.90	Cubic Metre						
2	Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GL wire conforming to ISI 280 and ISI 4826 in 150 mm (One hundred fifty millimeter) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps ad joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes, octroi, Malkhana , Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	131.81	Cubic Metre						
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	43.24	Cubic metre						
TOTAL									


 Executive Engineer
 Bilaspur Division No.1
 HPPWD, Bilaspur

SCHEDULE OF QUANTITY.							
Name of work:- Resoration of rain damages on Kandroun Salnoo Barmana road Km. 0/0 to 12/150. (SH:- C/O R/Wall at RD. 5/550 to 5/562).							
Estimated cost Rs. = 4,98,869/-only							
Earnest Money Rs. = 10,000/- only.							
Time Limit. = Three Month							
Name of work:- Resoration of rain damages on Kandroun Salnoo Barmana road Km. 0/0 to 12/150. (SH:- C/O R/Wall at RD. 5/550 to 5/562).							
Sr No	Description of items.	Qty.	Rates		Amount		
			In Figure	In words			
1	2	3	4	5	6	8	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	35.42	Cubic Metre				
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	128.76	Square Metre				
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	93.42	Cubic Metre				
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Nos.				
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.54	Cubic metre				

SCHEDULE OF QUANTITY.									
Name of work:- Resoration of rain damages on Kothi Tarrer road Km. 0/0 to 7/200. (SH:- C/O B/Wall at RD. 4/370 to 4/390).									
Estimated cost Rs. = 2,33,154/-only									
Earnest Money Rs. = 5,000/- only.									
Time Limit. = Two Month									
Name of work:- Resoration of rain damages on Kothi Tarrer road Km. 0/0 to 7/200. (SH:- C/O B/Wall at RD. 4/370 to 4/390).									
Description of items.									
Qty.									
In Figure									
In words									
Amount									
1	2	3	4	5	6	8			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	31.00	Cubic Metre						
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.20	Cubic Metre						
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.00	Nos.						
4	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.32	Cubic metre						


 Executive Engineer
 Bilaspur Division No.1
 PWD, Bilaspur

SCHEDULE OF QUANTITY.							
Estimated cost Rs. = 4,44,983/-only							
Earnest Money Rs. = 8,900/- only.							
Time Limit. = Two Month							
Name of work:- Resoration of rain damages on Kothi Tarrer road Km. 0/0 to 7/200. (SH:- C/O R/Wall along house of Sh. Ram Rattan RD. 3/586 to 3/596 and B/Wal at RD. 3/586 to 3/600 with side drain).							
Sr No	Description of items.	Qty.		Rates		Amount	
				In Figure	In words		
1	2	3	4	5	6	8	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	45.70	Cubic Metre				
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (One Cement : Three coarse sand) : Six graded stone aggregate 20 mm (Twenty millimetre) nominal size). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.79	Cubic metre				
3	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	163.64	Square Metre				
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	74.54	Cubic Metre				
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.84	Cubic metre				

6	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	35.00	Nos.			
---	--	-------	------	--	--	--


 Executive Engineer
 Bilaspur Division No.1
 HP. BMD, Bilaspur

SCHEDULE OF QUANTITY.									
Estimated cost Rs. = 4,74,178/-only									
Earnest Money Rs. = 9,500/- only.									
Time Limit. = Three Month									
Name of Work:- Restoration of rain damages on Patta Morsinghi road Km. 0/0 to 11/070. (SH:- C/O wire crate at RD. 8/900 to 8/914 both side)									
Sr No	Description of items.	Qty.		Rates		Amount			
				In Figure	In words				
1	2	3	4	5	6	8			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	64.40	Cubic Metre						
2	Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GL wire conforming to ISI 280 and ISI 4826 in 150 mm (One hundred fifty millimetre) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps and joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	153.13	Cubic Meter						
		TOTAL							


 Executive Engineer
 Bilaspur Division No.1
 H.B.PWD, Bilaspur

SCHEDULE OF QUANTITY.						
Name of Work:- Restoration of rain damages on Patta Morsinghi road Km. 0/0 to 11/070. (SH:- C/O wire crate at RD. 9/230 to 9/240).						
Estimated cost Rs. = 3,38,967/-only						
Earnest Money Rs. = 6,800/- only.						
Time Limit. = Two Month						
Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	2	3	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and rumping of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhanas, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.20	Cubic Metre			
2	Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GL wire conforming to ISI 280 and ISI 4826 in 150 mm (One hundred fifty millimetre) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps and joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes, octroi, Malkhanas, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	109.38	Cubic Meter			
TOTAL						

Executive Engineer
Bilaspur Division No.1
H.P.W.D., Bilaspur

SCHEDULE OF QUANTITY.							
Estimated cost Rs. = 4,95,065/-only							
Earnest Money Rs. = 10,000/- only.							
Time Limit. = Two Month							
Name of Work:- Resoration of rain damages on Delag to Chalama road Km. 0/0 to 5/500. (SH:- C/O crate wire R/Wall at RD. 3/500 to 3/517.50).							
Sr No	Description of items.	Qty.		Rates		Amount	
		In Figure	In words				
1	2	3	4	5	6	8	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.03	Cubic Metre				
2	Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GL wire conforming to ISI 280 and ISI 4826 in 150 mm (One hundred fifty millimetre) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps ad joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	136.71	Cubic Meter				
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	39.38	Cubic metre				
TOTAL							


 Executive Engineer
 Bilaspur Division No.1
 HPDWD, Bilaspur

SCHEDULE OF QUANTITY.

		Estimated cost Rs. = 4,74,185/-only Earnest Money Rs. = 10,000/- only. Time Limit. = Three Month			
Name of Work:- Restoration of rain damages on Bhatoli Malyawar road Km. /0 to 4/0. (SH:- C/O wire crate at RD. 0/30 to 0/60).					
Sr No	Description of items.	Qty.	Rates		Amount
			In Figure	In words	
1	2	3	4	5	6
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	55.52	Cubic Metre		8
2	Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GL wire conforming to ISI 280 and ISI 4826 in 150 mm (One hundred fifty millimetre) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps and joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes, octroi, Malikhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	137.34	Cubic Metre		
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malikhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.77	Cubic metre		
		TOTAL			


 Executive Engineer
 Bilaspur Division No.1
 HP4PWD, Bilaspur

SCHEDULE OF QUANTITY.						
Name of Work:- Restoration of rain damages on Bhatoli Malyawar road Km. /0 to 4/0. (SH:- C/O wire crate at RD. 0/300 to 0/330).						
				Estimated cost Rs. = 4,84,417/-only		
				Earnest Money Rs. = 9,700/- only.		
				Time Limit. = Three Month		
Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	2			5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	56.83	Cubic Metre			
2	Providing and laying of boulder apron laid in wire crate with 4mm (Four Millimeter) dia GL wire conforming to ISI 280 and ISI 4826 in 150 mm (One hundred fifty millimetre) to 150 mm (One hundred fifty Millimeter) mesh including 10% extra for laps ad joints laid with stone boulders weighing not less than 25kg. (Twenty five Kilogram) each. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	140.63	Cubic Meter			
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.35	Cubic metre			
		TOTAL				

Executive Engineer
Bilaspur Division No.1
HWPWD, Bilaspur