



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**Tel.01899-299219.**

**eepwd-chowari@hp.gov.in**

**No. PWD-CHW/Tender /2023-24-**

**To**

**5350-52**

**Dated:-**

**05-09-2023**

**The Executive Engineer (IT Cell)  
Nigam Bihar Shimla-2**

**Subject: - Publishing of Tender Notice.**

**Dear Sir,**

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.  
DA/ As above.

**Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.**


Copy forwarded to the Superintending Engineer, 7<sup>th</sup> Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

**Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.**

**Certificate**

Certified that the tenders called vide this office letter No. PWD-CHW/Tender /2023-24-... S3 So. 52 dated. 8/9/23 is emergent nature and in Public interest.

  
Executive Engineer,  
Chowari Division,  
HPWD, Chowari.





Tel.01899-299219.  
cepwd-chowari@hp.gov.in

## HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

### "NOTICE INVITING TENDERS"

Scaled percentage/item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Chowari Division, HPPWD, Chowari on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 75 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

- 1 Date of receipt of application for the tender  
Form A/W requisite documents: -
- 2 Date of issued/sale of tender form against  
Cash payment (non refundable).

18/09/2023

19/09/2023

The tender shall be received up to 11.00 AM on 20/09/2023 and will be opened on the same day at 12.00 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on 20/09/2023.

The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Chowari Division, HPPWD, Chowari must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost tender of	Time Limit	Class
1.	Restoration of rain damage on Chowari Mandhiar Baloh Fagot road Km 0/0 to 13/330 (SH:- C/o CC Pustha in R/wall and wire crate at Rd 10/950 to 10/965).	487312/-	9746/-	350/-	Three month	Class D &c
2.	Restoration of rain damage on Patka Dalhousie road Km 14/0 to 32/0 ( SH:- C/o R/wall with Pustha at Rd 17/890 to 17/898).	483038/-	9661/-	350/-	Three month	Class D &c
3.	Restoration of rain damage on Shahpur Sihunta Chowari Jot Chamba road Km 40/0 to 76/00 ( SH:- C/o R/wall in CC Pustha at Wire crate at Rd 51/700 to 51/712.50).	483233/-	9700/-	350/-	Three month	Class D &c
4	Restoration of Rain Damage on Dharta Mode to Naloh Road km 0/0 to 3/810 (SH:- C/o R/wall at RD 1/035 to 1/046.50)	4,85,516.00	9700/-	350/-	Three month	Class D &c
5	Name of work:- Restoration of rain damage on Balera to Dhar Road km 0/0 to 1/500 ( SH:- Construction of Retaining walls at RD 0/930 to 0/939 and 0/970 to 0/977)	4,84,968.00	9700/-	350/-	Three month	Class D &c
6	Restoration of Rain Damage on Dharta Mode to Naloh Road km 0/0 to 3/810 (SH:- C/o B/wall at RD 1/035 to 1/065)	4,30,208.00	9700/-	350/-	Three month	Class D &c
7	Restoration of rain damage on Chowari to Kainthly Road km 000 to 12/00(SH:- Construction of B/wall at RD 3/780 to 3/800)	4,11,146.00	9700/-	350/-	Three month	Class D &c
8	Restoration of rain damage on Bounkharymour to Nagali Road km 6/0 to 12/0 (SH:- Construction of R/wall at RD 8/525 to 8/533 & 9/270 to 9/275)	4,02,584.00	9700/-	350/-	Three month	Class D &c
9	Restoration of rain damage on Dhalog to Chambi road km 0/0 to 9/00 (SH:- C/O wire crate R/Wall at 3/185 to 3/195)	3,93,612.00	9700/-	350/-	Three month	Class D &c
10	Restoration of rain damage on Dhalog to Chambi road km 0/0 to 9/00 (SH:- C/O wire crate R/Wall at 2/110 to 2/122.20)	4,97,033.00	9700/-	350/-	Three month	Class D &c
11	Restoration of rain damage on Tundi (Dharoon) Banet road km 0/0 to 10/00 ( SH:- Construction of Breast walls at RD 7/540 to 7/565)	4,94,067.00	9700/-	350/-	Three month	Class D &c

12	Restoration of rain damage on Samote to Surpra Road km 0/0 to 5/0 ( SH:- Construction of Breast walls at RD /465 to 4/480)	3,61,131.00	9700/-	350/-	Three month	Class D &c
13	Restoration of rain damage on Gola to Bhiora Road km 0/0 to 3/00( SH:- Construction of R/ walls at RD 1/150 tp 1/165)	4,98,582.00	9700/-	350/-	Three month	Class D &c
14	Restoration of rain damage on Samote to Dramnala road km 0/0 to 12/435 ( SH:- C/o R/ wall at RD 11/570 to 1/582)	3,95,403.00	9700/-	350/-	Three month	Class D &c
15	Restoration of rain damage on Samote to Dramnala road km 0/0 to 12/435 ( SH:- C/o R/ wall at RD 0/195 to 0/210)	3,75,267.00	9700/-	350/-	Three month	Class D &c
16	Restoration of rain damage on Kuddi to Hobar Road km 0/0 to 3/150 ( SH:- Construction of R/ walls in wire crate at RD 2/620 to 2/635)	4,65,322.00	9700/-	350/-	Three month	Class D &c
17	Restoration of Rain Damage on Parchhore to Nadal Road km 0/0 to 3/0 ( SH :-C/o B/wall at RD 0/110 to 0/142)	4,78,508.00	9700/-	350/-	Three month	Class D &c
18	Restoration of rain damage on Chowari to Mandhiar Baloh Fagot Road km 0/0 to 13/330 (SH:- C/o CC Pusta in R/wall at RD 10/930 to 10/937 & wire crate at RD 10/917 to 10/927)	4,89,775.00	9700/-	350/-	Three month	Class D &c
19	Restoration of rain damage on chowari to Kainthly Road km 0/0 to 12/570 ( SH:- C/o R/wall at RD 5/810 to 5/822)	4,68,504.00	9700/-	350/-	Three month	Class D &c
20	Restoration of rain damage on Samote to Dramnala road km 0/0 to 12/435 ( SH:- C/o R/ wall at RD 7/180 to 7/184.80)	4,89,897.00	9700/-	350/-	Three month	Class D &c
21	Restoration of rain damage on Samote to Dramnala road km 0/0 to 12/435 ( SH:- C/o R/ wall at RD 11/720 to 11/730)	2,00,023.00	9700/-	350/-	Three month	Class D &c
22	Restoration of rain damage on Motla Gola via Kathla road km 0/0 to 7/00 ( SH:- C/o B/wall and U-shape drain at RD 6/165 to 6/120)	4,99,746.00	9700/-	350/-	Three month	Class D &c
23	Restoration of rain damage on Tunnuhatti to Rohni Road km 0/0 to 2/800 ( SH:- C/o R/wall at RD 1/810 to 1/825)	4,59,792.00	9700/-	350/-	Three month	Class D &c

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
2. The Contractor should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.
3. GST No./Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
4. Application without all documents will not be entertained.
5. Proxy application will not be entertained.

Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.

No. PWD-CHW/Tender /2023-24- 5353-5403

Copy forwarded to the following for information and necessary action please:-

- 1 Engineer-in-Chief, HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 The BDO Bhattiyat.
- 7 Sub Divisional Magistrate/B.D.O/Tehsildar Chowari.
- 8 Notice Board of this office.

Dated:- 05-09-2023

Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.



## Schedule of Quantity

Estimated Cost	RS 901212/-
Earnest Money	RS 9746/-
Time Limit	Three months

Name of work:- Restoration of rain damage on Chowari Mandhhar Daloh Fagot road km 0/0 to 13/330 (SIF:- Construction of C.C. Pusta in R/wall and wire crate at RD 10/950 to 10/965)

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	41.25			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimeter) mesh (woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 40kg (Forty Kilogram) each as per drawing and technical specifications Clause 1301 and as per directions of including the octroi, royalty Malkana, toll tax sales taxes GST or any taxes imposed by the Government.	93.75			Per cubic metre	
3	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate w/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	36.00			Per cubic metre	
Total						

Executive Engineer  
Chowari Division  
Hppwd Chowari

**Schedule of Quantity**

Name of work:- Restoration of rain damage on Patka to Dalhousie Road km 14/00 to 32/00 (SII:- Construction of Retaining walls with pusta at RD 17/890 TO 7/898)

Estimated Cost	Rs 483038/-
Earnest Money	Rs 9661/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	28.56			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty; Malkana toll tax, sales tax or any other taxes imposed by the Govt.	89.12			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V): 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-in-charge, i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty; Malkana toll tax, sales tax or any other taxes imposed by the Govt.	23.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	19.84			Per cubic metre	
Total						

Executive Engineer



## Schedule of Quantity

Name of work:- Restoration of rain damage on Shahpur Silhunta Chowari Jot Chamba Road km 40/0 to 76/00 (Silt:- Construction of Retaining walls in CC pusta at wire crate at RD 51/700 to 51/712.50)

Estimated Cost	Rs 483235/-
Financed Money	Rs 9665/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other detritious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	43.50			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 40kg (Forty Kilogram) each as per drawing and technical specifications Clause 1301 and as per directions of including the octroi, royalty Malkana, toll tax sales taxes GST or any taxes imposed by the Government.	58.59			Per cubic metre	
3	Providing and laying concrete for Plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	60.00			Per cubic metre	
Total						

Executive Engineer  
Chowari Division  
Hippud Chowari

# Schedule of Quantity

Estimated cost  
Estimated Money  
Time Limit  
Rs. 485516/-  
Rs. 9710/-  
Three months

Name of work: Restoration of Rain Damage on Dharta Nivale to Nalini Road km 0.70 to 3.810 (Silt - C/o B/wall at RD 1045 to 1046.50)

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 104.1 including setting out, construction of shoring and bracing removal of stumps and other debris material and disposal upto any level, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the direction of the Engineer in Charge. Including carriage of material within all loads and lifts and other incidental. The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	37.24			Per cubic metre	
2	Providing and laying concrete for Plain reinforced concrete in open foundation complete as per drawing and technical specifications clause 102, 803, 1202, and 1203 (P.C.C. Normal size 1:3:6) with all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all loads lifts and other incidentals. The rate for the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	45.54			Per cubic metre	
3	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS-280 and IS-4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 40kg (Forty Kilogram) each as per drawing and technical specifications Clause 1301 and as per directions of including the octroi, royalty Malkana, toll tax sales tax, GST or any taxes imposed by the Government.	71.88			Per cubic metre	
4	Providing weep holes in brick masonry stone masonry plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V) : 20(H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204, 3.7 as per the directions of the Engineer-in-Charge. i.e. carriage of materials with in all loads lifts and other incidentals. The rate for the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	10.00			Each	
5	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge i.e. carriage of materials with in all loads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	15.87			Per cubic metre	
Total						

11-1  
Executive Engineer  
Chowari Division



(5)

**Schedule of Quantity**

Name of work:- Restoration of rain damage on Bakers to Dhar Road km 0/0 to 1/500 (Sili:- Construction of Retaining walls at RD 0/730 to 0/739 and 0/770 to 0/777)

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 1205.1 including setting out, construction of shoring and bracing removal of stumps and other detritous material and disposal upto any level, dressing of sides and bottom and back filling in trenches with excavated suitable material, as per the direction of the Engineer in Charge, including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	47.82			Per cubic metre	
2	Providing and laying concrete for Plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Normal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	94.56			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( IV ) 1, 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204 3, 7 as per the directions of the Engineer-in-charge, i.e carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	38.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	15.72			Per cubic metre	
Total						


Executive Engineer

## Schedule of Quantity

**Name of work:- Restoration of Rain Damage on Dharta Mode to Naloh Road km 0/0 to 3/810 (SII:- C/o Breast wall at RD 1/035 to 1/065)**

Estimated Cost	Rs 430208/-
Earnest Money	Rs 9700/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per technical specification clause 1603.1 as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	55.80			Per cubic metre	
2	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other detritous material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	32.70			Per cubic metre	
3	Providing and laying concrete for Plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	84.18			Per cubic metre	
4	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V), 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204 3.7 as per the directions of the Engineer-in-charge, i.e carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	28.00			Each	
Total						


  
 Executive Engineer  
 Chowari Division



## Schedule of Quantity

Name of work:- Restoration of Rain Damage on Chowari Kalinthy Road km 0/0 to 12/570 (Sill:- C/O Brest wall at RD 3/760 to 3/800)		Estimated Cost	Rs 411146/-
		Earnest Money	Rs 9700/-
		Time Limit	Three months

S.No	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of slumps and other deleterious material and disposal upto any level, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	32.56			Per cubic metre	
2	Providing and laying concrete for Plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	81.40			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia P.V.C pipe extending through the full width of the structures with slope of ( 1V ). 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-in-charge. i.e carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	32.00			Each	
Total						

  
 Executive Engineer  
 Chowari Division  
 Hppud Chowari

## Schedule of Quantity

Name of work:- Restoration of rain damage on Rounbharymour to Nagah Road km 6/0 to 12/0 (Silt)- Construction of Retaining walls at RD 8/525 to 8/533 and 9/270 to 9/275)

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other detritus material and disposal upto any head, dressing of sides and bottom and back filling in trenches with excavated suitable material, as per the direction of the Engineer in Charge, including Carriage of material within all leads and lifts and other incidental The Rate including octroi royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	30.62			Per cubic metre	
2	Providing and laying concrete for Plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Normal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	76.44			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( IV ) : 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204, 3.7 as per the directions of the Engineer-in-charge, i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	30.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	17.76			Per cubic metre	
Total						

Executive Engineer  
 Chowari Division  
 Hppwd Chowari




## Schedule of Quantity

Name of work:- Restoration of Rain Damage on Dhulog to Chambi km 0/0 to 9/00 (Silt:- 1/10 wire crate R/wall at Rs 3/184 to 3/195)

Estimated Cost	Rs 996612/-
Finest Money	Rs 3872/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of clumps and other detritus material and disposal upto any level, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the direction of the Engineer in Charge. Including (carriage of material within all basins and lifts and other incidental The Rate including extra, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	48.70			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 40kg (Forty Kilogram) each as per drawing and technical specifications Clause 1301 and as per directions of including the extra, royalty, Malkana, toll tax sales taxes GST or any taxes imposed by the Government.	129.60			Per cubic metre	
<b>Total</b>						

  
**Executive Engineer**  
 Chowari Division  
 Hppwd Chowari

## Schedule of Quantity

**Name of work:- Restoration of Rain Damage on Dhalog to Chambl km 0/0 to 9/00 (SII:- C/o wire crate R/wall at RD 2/110 to 2/122.20)**

Estimated Cost	Rs 393612/-
Earnest Money	Rs 7872/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other detritous material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	71.13			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimeter) mesh (woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 40kg (Forty Kilogram) each as per drawing and technical specifications Clause 1301 and as per directions of including the octroi, royalty Malkana, toll tax sales taxes GST or any taxes imposed by the Government.	162.00			Per cubic metre	
<b>Total</b>						

**Executive Engineer**  
 Chowari Division  
 Hppwd Chowari



# **Schedule of Quantity**

**Name of work:- Restoration of rain damage on Tundi (Dharron) Baner road km 0/0 to 10/00 (Sft:- Construction of Breast walls at RD 7/540 to 7/565)**

Estimated Cost	Rs 4940671/-
Earned Money	Rs 98811/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per technical specification clause 1603.1 as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	49.40			Per cubic metre	
2	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and back filling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	21.80			Per cubic metre	
3	Providing and laying concrete for Plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C. Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	96.16			Per cubic metre	
4	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( IV ): 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614.709, 1204.3.7 as per the directions of the Engineer-in-charge, i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	69.00			Each	
<b>Total</b>						


**Executive Engineer**  
 Chowari Division  
 Hppwd Chowari

## Schedule of Quantity

Name of work:- Restoration of rain damage on Samote to Sarupna Road km 0/0 to 5/00 ( Sili:- Construction of Breast walls at RD 4/465 to 4/480

Estimated Cost	Rs 361131/-
Earnest Money	Rs 7223-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per technical specification clause 1603.1 as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	35.44			Per cubic metre	
2	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other detrituous material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	13.20			Per cubic metre	
3	Providing and laying concrete for Plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	71.64			Per cubic metre	
4	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( 1V ) : 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614.709, 1204.3.7 as per the directions of the Engineer-in-charge, i.e carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	39.00			Each	
Total						

  
 Executive Engineer  
 Chowari Division  
 Hppwd Chowari



### Schedule of Quantity

Name of work:- Restoration of rain damage on Gola to Dholera Road km 0/0 to 3/00( SII):- Construction of R/ walls at RD 1/150 (p 1/165)

Estimated Cost	Rs 498582/-
Earnest Money	Rs 9972/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other detritious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi royalty; Malkana Toll tax sale tax or other taxes imposed by the Govt.	46.28			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C. Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty; Malkana toll tax, sales tax or any other taxes imposed by the Govt.	82.60			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( 1V ): 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204 3, 7 as per the directions of the Engineer-in-charge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty; Malkana toll tax, sales tax or any other taxes imposed by the Govt.	21.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	52.00			Per cubic metre	
Total						


Executive Engineer

## Schedule of Quantity

**Name of work:- Restoration of rain damage on Samote to Dramanala road km 0/0 to 12/435 ( Sit:- C/o R/ wall at RD 11/570 to 11/582)**

Estimated Cost	Rs 393,403/-
Earnest Money	Rs 7908/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other detritus material and disposal upto any level, dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including Carriage of material within all loads and lifts and other incidental The Rate including octroi royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	36.90			Per cubic metre	
2	Providing and laying concrete for Plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all loads and lifts as per the direction of Engineer in Charge including carriage of materials with in all loads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	73.58			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with battered masonry dia PVC pipe extending through the full width of the structures with slope of ( 1V ): 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204 3.7 as per the directions of the Engineer-in-charge. i/c carriage of materials with in all loads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	30.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge i/c carriage of materials with in all loads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	9.72			Per cubic metre	
Total						

  
 Executive Engineer  
 Chowari Division  
 Hppud Chowari



(25)

### Schedule of Quantity

Name of work:- Restoration of rain damage on Sainiole to Dhanmala road km 0/0 to 12/35 ( Sit:- C/o H/ wall at RD 0/195 to 0/210)

Estimated Cost	Rs 195403/-
Earnest Money	Rs 7908/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 excluding setting out, construction of shoring and bracing, removal of stumps and other obstructions material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including carriage of material within all leads and lifts and other incidental. The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	35.70			Per cubic metre	
2	Providing and laying concrete for Plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	70.05			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( 1" : 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204, 3, 7 as per the directions of the Engineer-in-charge, i.e carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	39.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204, 3, 8 or as directed by the Engineer-in Charge i.e carriage of materials with in all leads, lifts and other incidentals. The Rate excluding octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	10.35			Per cubic metre	
Total						


Executive Engineer  
Chowari Division  
Hppud Chowari

## Schedule of Quantity

Name of work:- Restoration of rain damage on Kuddi to Hobar Road km 0/0 to 3/150 (SII:- Construction of R/ walls in wire crate at RD 2620 to 2635)

Estimated Cost	Rs 465322/-
Earnest Money	Rs 93066/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other detritious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	46.95			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimeter) mesh (woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 40kg (Forty Kilogram) each as per drawing and technical specifications Clause 1301 and as per directions of including the octroi, royalty Malkana, toll tax sales taxes GST or any taxes imposed by the Government.	140.64			Per cubic metre	
3	Back filling with granular material behind abutment's return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	10.20			Per cubic metre	
Total						

  
 Executive Engineer  
 Chowari Division  
 Hppvd Chowari




## Schedule of Quantity

Name of work:- Restoration of Rain Damage on Parbhore to Nadi Road km 0/0 to 3/0 (SII :-C/O B/wall at RD 0/110 to 0/142)

Estimated Cost	Rs. 172,568/-
Earnest Money	Rs. 9570/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 802.1 including setting out, construction of shoring and bracing removal of slumps and other determined material and disposal upto any head, dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including Cartage of material within all leads and lifts and other incidental The Rate including octroi royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	37.80			Per cubic metre	
2	Providing and laying concrete for Plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C. Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including cartage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	96.00			Per cubic metre	
3	Providing weep holes in brick masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1" : 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204, 3.7 as per the directions of the Engineer-in-charge. i.e cartage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	40.00			Each	
Total						

  
 Executive Engineer  
 Chowari Division  
 Hppwd Chowari

# Schedule of Quantity

Name of work:- Restoration of rain damage on Chowari Mandhlar Baloh Fagol road km 0/0 to 13/330 (SII:- Construction of C.C. Pusta in R/wall and wire crate at RD 10/950 to 10/965)

Estimated Cost	Rs 489775/-
Earnest Money	Rs 9796/-
Time Limit	Three months

S.No	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other detritious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	41.25			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 40kg (Forty Kilogram) each as per drawing and technical specifications Clause 1301 and as per directions of including the octroi, royalty Malkana, toll tax sales taxes GST or any taxes imposed by the Government.	93.75			Per cubic metre	
3	Providing and laying concrete for Plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	36.00			Per cubic metre	
4	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( 1V ). 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204, 3.7 as per the directions of the Engineer-in-charge, i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	14.00			Each	
Total						

Executive Engineer  
Chowari Division  
Hppnd Chowari



Estimated Cost	R\$ 468,994.
Earmark Amount	R\$ 9370.
Time Limit	Three months

Time Limit	Three months
------------	--------------


11-1  
Executive Engineer  
Chowari Division  
Himnath Chowari

# Schedule of Quantity

Name of work:- Restoration of rain damage on Samote to Dramasha road km 0.0 to 12.435 (SH-12) C/O R/ wall at RD 7/1/80 to 7/1/84, 20)

Estimated Cost	Rs 489897/-
Earned Money	Rs 9798/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Laidwork in excavation for structures as per drawing and technical specifications clause 303.1 including setting out, construction of shoring and bracing removal of slumps and other defective material and disposal upto any level, dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental. The Rate including octroi, royalty, Malikana Toll tax sale tax or other taxes imposed by the Govt.	17.74			Per cubic metre	
2	Providing and laying concrete for Plain reinforced concrete in open foundation complete as per drawing and technical specifications clause 802, 803, 1202, and 1203 (P.C.C. Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malikana toll tax, sales tax or any other taxes imposed by the Govt.	93.07			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ palm reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( 1V : 20 H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204, 3.7 as per the directions of the Engineer-in-charge, i/c carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malikana toll tax, sales tax or any other taxes imposed by the Govt.	20.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malikana Toll tax Sale tax or any other taxes imposed by the Govt.	9.22			Per cubic metre	
Total						

  
 Engineer  
 Chowari Division  
 Hapur Chowari



# Schedule of Quantity

Name of work:- Restoration of rain damage on Samote to Drammala road km 0/0 to 12/435 (Sili:- C/o R/ wall at RD 11/720 to 11/730)

Estimated Cost	Rs 200023/-
Financed Money	Rs 4000/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other detritious material and disposal upto any lead, dressing of sides and bottom and back filling in trenches with excavated suitable material, as per the direction of the Engineer in Charge, including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	17.10			Per cubic metre	
2	Providing and laying concrete for Plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	35.80			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V): 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614.709, 1204.3.7 as per the directions of the Engineer-in-charge, i/c carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	16.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	6.30			Per cubic metre	
Total						

Executive Engineer  
Chowari Division  
Hppwd Chowari

# Schedule of Quantity

Name of work:- Restoration of rain damage on Molli Gola via Kaibla road km 0/0 to 7/00 (Sill:- C/O B/wall and U-shape drain at RD 6/165 to 6/120)				Estimated Cost	Rs 497746/-
				Earnest Money	Rs 9973/-
				Time Limit	Three months
S.No	Description	Quantity	Rate		Amount
			In Fig.	In Word	
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a head upto 20 m as per technical specification clause 1603.1 as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidentals. The Rate including octroi, royalty, Malakana Toll tax sale tax or other taxes imposed by the Govt.	43.65			Per cubic metre
2	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of mounds and other detritus material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidentals. The Rate including octroi, royalty, Malakana Toll tax sale tax or other taxes imposed by the Govt.	54.90			Per cubic metre
3	Providing and laying concrete for Plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Normal size 1:3:6) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials within all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malakana toll tax, sales tax or any other taxes imposed by the Govt.	6.69			Each
4	Providing and laying concrete for Plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Normal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials within all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malakana toll tax, sales tax or any other taxes imposed by the Govt.	94.50			Per cubic metre
5	Providing wirey holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of 1 IV to 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204, 3.7 as per the directions of the Engineer-in-charge. i/c carriage of materials within all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malakana toll tax, sales tax or any other taxes imposed by the Govt.	30.00			Each
Total					

11-1



# Schedule of Quantity

Name of work:- Restoration of rain damage on Nollia Gola via Kaithla road km 0/0 to 7/00 (Silt):- C/O B/wall and U-shape drain at RD 6/165 to 6/120)

Estimated Cost	Rs. 159792/-
Earnest Money	Rs. 9200/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per technical specification clause 1603.1 as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental. The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	33.73			Per cubic metre	
2	Earthwork in excavation for structures as per drawing and technical specifications clause 805.1 including setting out, construction of shoring and bracing removal of stumps and other detritus material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental. The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	18.90			Per cubic metre	
3	Providing and laying concrete for Plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C. Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	96.25			Per cubic metre	
4	Providing weep holes in brick masonry/ pallen reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structure with slope of (1V:1.20(H)) towards drawings face complete as per drawing & technical specifications clauses 614, 709, 1204, 3.7 as per the directions of the Engineer-in-charge. i.e carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	49.00			Each	
Total						

Executive Engineer  
Chowari Division  
Hppwd Chowari