

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

01899-240618, 292000
Fax No. 01899-240618

E-mail- ee-dal-hp@nic.in

No. PWD-Dal/TA/Tender /2023-24-

5285-87

Dated: - 06-09-2023

To

The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2


Subject: -

Publishing of Tender Notice.

Dear Sir,


Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.


**Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.**

Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.


**Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie**

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed percentage/item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Dalhousie Division, HPPWD, Dalhousie on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

5. Date of receipt of application for the tender
Form a/w requisite documents:- 06.09.2023
6. Date of issued/sale of tender form against
Cash payment (non refundable). 14.09.2023

The tender shall be received upto 3:00 PM on 15.09.2023 and will be opened on the same day at 3:30 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on 14.09.2023.

The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Dalhousie Division, HPPWD, Dalhousie must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1.	Restoration of Rain damage on Dalhousie Jandrigat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Construction of Retaining wall at RD. 7/359 to 7/362.50 and Providing and laying Inter locking paver block at R.D. 4/610 to 4/660)	481671/-	9700/-	Rs. 350/-	Three Months	Class-D & C
2.	Restoration of Rain damage on Dalhousie Cantt. to Bathri road K.m 0/0 to 4/700 (SH:-Providing and laying C.C.1:4:8 and CC Pavement at R.D. 1/500 to 1/559.	493281/-	10000/-	Rs. 350/-	Three Months	Class-D & C
3	Restoration of Rain damage on Patha Chawari Dalhousie road K.m. 54/0 to 73///0 (SH:-C/o Retaining wall at R.D. 67/640 to 67/652	465526	9500/-	Rs. 350/-	Three Months	Class-D & C
4	Restoration of Rain damage on link road to village Ruliyani K.m. 0/0 to 1/0 (SH:-Providing and Laying CC Pavement from R.D. 0/300 to 0/375	499228	10000/-	Rs. 350/-	Three Months	Class-D & C

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
2. The Contractor should have executed two similar type of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.
3. GST No./Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
4. Application without all documents will not be entertained.
5. Proxy application will not be entertained.

Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

No. PWD/TA/Tender /2023-24-

Copy forwarded to the following for information and necessary action please:-


- 1 Engineer-in-Chief, HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 BDO Bhattiyat.
- 7 Sub Divisional Magistrate/Tehsildar Dalhousie.
- 8 Notice Board of this office.

Dated: - 06-09-2023

Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie

Certificate

Certified that the tenders called vide this office letter No. PWD-/TA/Tender /2023-24:-5288-5338 dated 06-09-2023 is emergent nature and in Public interest.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

Schedule of Qty.

Estimated Cost:- Rs. 481671.00

Earnest Money :- Rs. 10000.00

Time Limit :- Three Months

Name of work: -Restoration of Rain damage on Dalhousie Jandrightat Chamba via Kohlari road Km. 0/0 to 11/040 (SH:- Construction of Retaining wall at RD. 7/359 to 7/362.50 and Providing and Laying Interlocking Paver Block at RD. 4/610 to 4/660).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	23.410			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all hights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sales tax , GST or any other taxes imposed by the Government.	50.61			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	5.09			Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	10.00			Each	
5	Providing and Laying plain cement concrete 1:4:8 (one cement is to four sand isto eight graded crushed stone aggregate with nominal mix in open foundations complete as per drawing and technical specifications clauses 802, 803, 1202 & 1203 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	15.80			Per Cubic Metre	

6	Providing and laying heavy duty precast cement concrete 80 mm (Eighty millimetre) thick inter locking paver block pavement including boarder or Curve block with vibration technology in PVC/Fibre moulds upto M-40 (Forty) grade confirming to IS 15658:2006 complete as per technical specification section 1500 as per IS-SP-63 Paver block and as per the direction of the engineer-in-charge. The rates are inclusive cost and carriage by all mode of transportation of materials within all leads, lifts and other incidentals, inclusive of octroi, GST royalty, Malkana, toll tax GST or any other taxes imposed by the Government.	158.00					Per Square Metre	
							Totals: -	


 Executive Engineer
 Dalhousie Division
 H.P.R.W.D. Dalhousie

Schedule of Qty.

Job No. 02 TS No. 20

Estimated Cost: - Rs. 493281.00

Earnest Money :- Rs. 10000.00

Time Limit :- Three Months

Name of work: - Restoration of Rain damage on Dalhousie Cantt. Bathri road Km. 0/0 to 4/700 (SH: - Providing and Laying CC 1:4:8 and CC Pavement)

RD. 1/500 to 1/559.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Providing and laying mechanically mixed plain cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed / broken stone aggregate 25 mm (twenty five millimetre) nominal size) and curing complete excluding the cost of form work in foundation and plinth in breast and retaining walls etc. as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	22.39			Per Cubic Metre	
2	Construction of un - reinforced, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 (forty three) grade cement or any other type as per Clause 1501.2.2 M 30 (thirty) (grade) coarse and fine aggregates conforming to IS: 383 (three hundred eighty three) maximum size of coarse aggregate not exceeding 25 mm, (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, admixtures as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and Technical specification clause 1501as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkana toll tax sale tax, GST or other taxes imposed by the Government.	44.78			Per Square Metre	
Total: -						


Engineer
Dalhousie Division
H.P.P.W.D. Dalhousie

Schedule of Qty.

Job No. 03 TS 21

Estimated Cost: - Rs. 465526.00
Earnest Money :- Rs. 9500.00
Time Limit :- Three Months

Name of work: - Restoration of Rain damage on Patka Chowari Dalhousie road Km. 54/0 to 73/0 (SH: - Construction of Retaining wall at RD. 67/6-40 to 67/652).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	9.960			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement into five sand into ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all heights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	86.04			Per Cubic Metre	
3	Government. Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	13.56			Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	19.00			Each	
Total: -						

Executive Engineer
Dalhousie Division
H.P.W.D Dalhousie

Schedule of Qty.

Job No. 04 TS No. 22

Estimated Cost: - Rs. 499228.00

Earnest Money :- Rs. 10000.00

Time Limit :- Three Months

Name of work: - Restoration of Rain damage on link road to village Ruliyani Km. 0/0 to 1/0 (SH: -Providing and Laying CC Pavement at RD. 0/300 to 0/375)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	86.36			Per Cubic Metre	
2	Providing and laying stone soling properly hand-packed filling interstices with Khazariya stone spreading watering and rolling of binding materials moorum or earth etcetra complete as per H.P.P.W.D specification 100 mm (one hundred millimetre) spread thickness (finished work including materials and labour) and as per direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	36.00			Per Cubic Metre	
3	Construction of un - reinforced, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 (forty three) grade cement or any other type as per Clause 1501.2.2 M 30 (thirty) (grade) coarse and fine aggregates conforming to IS: 383 (three hundred eighty three) maximum size of coarse aggregate not exceeding 25 mm, (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge / culvert and construction joints, admixtures as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and Technical specification clause 1501as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkana toll tax sale tax, GST or other taxes imposed by the Government.	43.80			Per Squire Metre	

4	Providing and laying plain cement concrete 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and includes the cost of form work curing complete as per drawing and technical specifications clause 802, 803, 1202 and 1203 or as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	7.20				Per Cubic Metre	
						Total: -	


 Executive Engineer
 Dalhousie Division
 H.P.P.W.D. Dalhousie