

Himachal Pradesh
Public Works Department

Registered

NO:- PW-DKD-N.I.T/2023-24 1310

Dated:- 01/09/2023

To

✓ The Executive Engineer (IT Cell)
Nigam Vihar Shimla.

Subject:-


Publication of Tender notice.

Jai Haind

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. Of Himachal Pradesh letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th. July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

DA:- Notice inviting tender & Sechedule of Quantity.


Executive Engineer,
B&R Division HP.PWD,
Dodra Kwar.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed item rate tenders on form No. 6 & 8 are hereby invited by the Executive Engineer B&R Division HP.PWD, Dodra kwar for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HP.PWD, so as to reach in the office as per time Schedule given below:-

1. Date of receipt of application for tenders forms:-

14.09.2023

2. Dated of Issue /sale of tender forms:-

14.09.2023

3. Date of receipt of tender:-

15.09.2023 up to 10:30AM

4. Date of opening of tender:-

15.09.2023 at 11.AM

Sr. No.	Name of Work	Estimated Cost	EMD (Rs.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1.	Name of Work: R/R Damage to Link road village Jiskoon km 0/00 to 8/00 (SH:- C/o R/wall in PCC 1:3:6 with wire crate at RD 6/810 to 6/825)	4,83,570/-	9671/-	350/-	Two months	Calss "A,B,C&D"
2.	Name of Work: R/R Damage to Link road village Jiskoon km 0/00 to 8/00 (SH:- C/o B/wall in wire crate at Rd 5/440 to 5/460 & 5/810 to 5/830)	3,88,641/-	7773/-	350/-	Two months	Calss "A,B,C&D"
3.	Name of Work: R/R Damage to Link road village Kiterwari km 0/00 to 2/900 (SH:- C/o B/wall in wire crate at Rd 2/430 to 2/470)	3,88,382/-	7768/-	350/-	Two months	Calss "A,B,C&D"
4.	Name of Work: C/o Link road Helipad to Sharidhar km 0/00 to 2/500 (SH:- C/o B/wall in wire crate at RD 0/180 to 0/200)	1,95,458/-	3909/-	350/-	Two months	Calss "C&D"
5.	Name of Work: R/R Damage to RCD road km 0/00 to 92/695 (SH:- C/o R/wall in wire crate at RD 77/505 to 77/520, 77/270 to 77/295 & 77/675 to 77/695)	4,86,281/-	9726/-	350/-	Two months	Calss "A,B,C&D"
6.	Name of Work :- Restoration of approach road to foot bridge at Gosangu (SH:- C/o wire crate at foot Bridge Gosangu on approach road Kwar side)	2,73,850/-	5477/-	350/-	Two months	Calss "A,B,C&D"
7.	Name of Work :- C/o Link road Helipad to Govt.Sr.Sec. School Kwar 0/00 to 2/00 (SH:- C/o R/wall in PCC 1:3:6 at RD 1/720 to 1/735)	3,70,708/-	7414/-	350/-	Two months	Calss "C&D"
8.	Name of Work: C/o Link road Kimti Nalvai km 0/00 to 2/500 (SH:- F/C 5/7 mtr wide road at Rd 0/600 to 0/900)	4,91,896/-	9838/-	350/-	Two months	Calss "C&D"
9.	Name of Work:- C/o Link road Helipad to Sharidhar road km 0/00 to 2/500 (SH:- C/o R/wall in PCC 1:4:8 at Rd 0/320 to 0/340)	3,99,322/-	7986/-	350/-	Two months	Calss "C&D"
10.	Name of Work:- C/o Link road from RCD to Larot Bangla Via Larot km 0/00 to 0/750 (SH:- F/C 5/7 mtr wide road at RD 0/00 to 0/525)	4,98,576/-	9972/-	350/-	Two months	Calss "C&D"
11.	Name of Work :- C/o Link road from RCD to Larot Bangla Via Larot km 0/00 to 0/750 (SH:- F/C 5/7 mtr wide road at RD 0/525 to 0/675 & Kharanja Stone Soling at RD 0/00 to 0/150)	4,95,123/-	9902/-	350/-	Two months	Calss "C&D"
12.	Name of Work :- R/R Damage to RCD road km 0/00 to 92/695 (SH:- Hiring of Tipper for carriage of muck/stone in km 21/195 to 92/695 and other link roads)	4,34,000/-	8680/-	350/-	Three months	Calss "A,B,C&D"
13.	Name of Work :- R/R Damage to RCD road km 0/00 to 92/695 (SH:- Hiring of Tipper for carriage of muck/stone in km 21/195 to 92/695 and other link roads)	4,20,000/-	8400/-	350/-	Two months	Calss "A,B,C&D"
14.	Name of Work :- R/R Damage to RCD road km 0/00 to 92/695 (SH:- Hiring of Tipper for carriage of muck/stone in km 21/195 to 92/695 and other link road link road village Jiskoon)	4,90,000/-	9800/-	350/-	Three months	Calss "A,B,C&D"
15.	Name of Work: A/R & M/O RCD road km 0/00 to 92/695 (SH:- Hiring of JCB for removal of slips/drain & dressing of	4,75,000/-	9500/-	350/-	Two months	Calss "C&D"

	road surface in km 21/195 to 92/695 and other link roads)					
6	Name of Work: A/R & M/O RCD road km 0/00 to 92/695 (SH:- Herring of JCB for removal of slips/drain & dressing of road surface in km 21/195 to 92/695 and other link roads)	4,50,000/-	9000/-	350/-	Two months	Calss "C&D"
17	Name of Work: R/R Damage to RCD road km 0/00 to 92/695 (SH:- Herring of JCB for removal of slips/drain & dressing of road surface in km 21/195 to 92/695 and other link roads)	4,65,000/-	8000/-	350/-	Two months	Calss "A,B,C&D"
18	Name of Work: R/R Damage to RCD road km 0/00 to 92/695 (SH:- Herring of JCB for removal of slips/drain & dressing of road surface in km 21/195 to 92/695 and other link roads)	4,62,500/-	9250/-	350/-	Two months	Calss "A,B,C&D"
19	Name of Work:- C/o RCD road km 0/00 to 92/695 (SH:- P/L Kharanja Stone soling at Various km 32/00 to 40/00)	4,91,408/-	9828/-	350/-	One Month	Calss "C&D"
20	Name of Work:- C/o RCD road km 0/00 to 92/695 (SH:- P/L Kharanja Stone soling at Various km 40/00 to 50/00)	4,91,408/-	9828/-	350/-	One Month	Calss "C&D"
21	Name of Work :- C/o Link road Shiladesh to Thalather road km 0/00 to 2/00(SH:- P/L Kharanja stone soling at Km 0/810 to 1/050)	491408/-	9828/-	350/-	One Month	Calss "C&D"
22	Name of Work:- A/R & M/O Various Non Residential building at HPPWD Dodra kawat (SH:- Binding of old record files of Division Office)	487500/-	9750/-	350/-	One Month	Calss "C&D"
23	C/o link village Jiskoon km 0/00 to 8/00(SH:- C/o B/wall at RD 7/030 to 7/125)	476524/-	9530/-	350/-	Two Month	Calss "C&D"

Certified that the tender ment

ioned in the notice is exigencies/emergency are urgent nature and in public interest

TERMS AND CONDITIONS:-

5. The Earnest money for the above works should be submitted with the application for the application for the purchase of the tender-documents.
6. The Contractors should quoted the rates of the items in the tenders both in figures and words.
7. Income tax & G.S.T. No. Latest clearance certificate.
8. The contractor/firms shall accompany his enlistment/renewal & EPF submit before the award of tender.
9. The Contractors should apply for two works only at a time for tenders.
10. Work should be completed by the contractor within stipulated period.
11. The Executive Engineer reserves the right to accept/rejected any tender/application or all tenders without assigning any reason.


Executive Engineer
B&R Division HP.PWD,
Dodra Kawar

Dated 01/09/2023

NO:- PW-DKD-CB-Tender/2022-23 :- 1311-20
Copy forwarded for information and wide publicity to:-

12. The Chief Engineer (S) HPPWD Shimla-2
13. The S.E 14th Circle HPPWD Rohru
14. All the EE's under 14th Circle HPPWD Rohru
15. All the A.E's working under this Division (B&R)
16. The Sub Divisional Magistrate Dodra Kawar
17. The BDO Dodra Kawar.
18. The Naib tehsildhar Dodra Kawar
19. A/B and D/B in this office
20. Notice Board


Executive Engineer
B&R Division HP.PWD,
Dodra Kawar

Schedule of Qty

Name of Work:- R/R Damage to Link road village Jiskoon km 0/00 to 8/00				ESTIMATED COST		483570
				EARNEST MONEY		9671
Name of Work:- SH- C/o R/wall in PCC 1:3:6 with wire crate at Rd 6/810 to 6/825				TIME LIMIT:		2 Months
Sr. No	Description of items.	Qty	Unit	Rate In Fig.	In Words	Amount
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	21.3	cum			
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	13.5	cum			
3	Providing concrete for plain/reinforced concrete in open foundation/R-walls complete as per drawing and technical specification clause 802,803,1202 & 1203 grade (1:3:6 nominal mix), 1 cement :3Sand :6graded stone aggregate	31.25	cum			
4	Providing concrete for plain/reinforced concrete in open foundation/R-walls complete as per drawing and technical specification clause 802,803,1202 & 1203 grade (1:3:6 nominal mix), 1 cement :3Sand :6graded stone aggregate	52.20	cum			
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8	8.10	cum			
Total						


 Executive Engineer
 B&R Division HPPWD
 Dodra Kanwar

Schedule of Qty

Name of Work:- R/R Damage to link road village Jiskoon km 0/00 to 8/00

388641

ESTIMATED COST

(S.H:- C/o B/wall at RD 5/440 to 5/460 & 5/810 to 5/830

7773

EARNST MONEY

Sr. No Description of Items.

2 Months

TIME LIMIT:

Amount.

Rate

In Flg.

In Words

7

Qty	Unit	Rate	In Flg.	In Words	Amount.
3	4	5	6	7	
28.8	cum				
16.8	cum				
125.00	cum				
Total					

1 Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1

2 Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.

3 Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301

Executive Engineer
B&R Division HPPWD
Dadra Nagar

Name of Work:- R/R Damage to Link road village Kiterwari km 0/00 to 2/900									
Schedule of Quantity									
SH:-C/o B/wall in wire crate at Rd 2/430 to 2/470									
Sr. No	Description of items.	Qty	Unit	ESTIMATED COST			EARNEST MONEY		
				Rate	In Flg.	In Words	Amount	Time Limit	
1	2	3	4	5	6	7	8	9	10
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	28.8	cum						
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	16.8	cum						
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	125.00	cum						
Total									


 Executive Engineer
 B&R Division HPPWD
 Dodra Kwar

Schedule of Qty										
Namre of Work :- C/o Link road helpad to Sharidhar km 0/00 to 2/500										
SH:- C/o B/wall in wire crate at RD 0/180 to 0/200										
Sr. No	Description of items.	Qty	Unit	ESTIMATED COST						
				EARNEST MONEY						
				TIME LIMIT:						
				Rate						
				In Fig.	In Words					
				5	6					
									Amount.	7
1	2	3	4							
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	21.2	cum							
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	8.4	cum							
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	62.5	cum							
Total										


 Executive Engineer
 B&R Division HPPWD
 Dodra Kanan

Name of Work:- R/R Damage to BCD road km 0.00 to 0.80	Schedule of Quantity

SH:-C/o R/wall in wire crate at pd 77/50.

77/695 to 77/695 to 77/505 to 77/520, 77/270 to 77/295 & 77/675 to

Sr. No	Description of items.	Qty	Unit	Rate	In Words	Amount	2 Months
				In Fig.			
1	2	3	4	5	6	7	
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	14.25	cum				
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	55.65	cum				
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	140.63	cum				
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8	24.3	cum				
	Total						

Executive Engineer
B&R Division HPPWD
Dodra Kagar

Schedule of Qty

Name of Work:- Restoration of approach road to foot bridge at Gosangu				ESTIMATED COST		273850
(S.H):- C/o wire crate at foot bridge at Gosangu on approach road Kavar side				EARNEST MONEY		5477
Description of Items.				TIME LIMIT:		4 Months
Sr. No		Qty	Unit	Rate In Fig.	In Words	Amount.
1	2	3	4	5	6	7
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, reconstruction of abutment and bracing, removal of concrete and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material	16.72	cum			
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia G.I. wire conforming to IS 280 and IS 4826 in 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 120.1	83.94	cum			
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 120.4.3 B	5.70	cum			
Total						


 Executive Engineer
 R&R Division HBB/WD
 Dindra Nagar

Schedule of Quantity

Name of Work:-C/o Link road Helipad to Govt.Sr.School Kavar 0/00 to 2/00

370708

7414

SH:-C/oR/wall in PCC 1:3:6 at Rd 1/720 to 1/735

2 Months

ESTIMATED COST

EARNEST MONEY

TIME LIMIT:

Sr. No	Description of items.	Qty	Unit	Rate		In Words	Amount
				In Fig.			
1	2	3	4	5	6	7	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	18.23	cum				
2	Providing concrete for plain/reinforced concrete in open foundationR/B-walls complete as per drawing and technical specification clause 802,803,1202 & 1203 grade M10 (1:3:6 nominal mix), 1 cement :3 Sand :6 graded stone aggregate	47.29	cum				
3	Backfilling behind abutment,wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8	14.4	cum				
4	Providing weepholes in brick masonry/ Stone masonry,plain/reinforced concrete aboutment ,wing wall,return wall with 100 mm dia AC pipe extending though the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7	20	each				
Total							


 Executive Engineer
 B&R Division HPPWD
 Dodra Kavar

Schedule of Qty
Name of Work :- C/O Link road kimiti nalval km 0/00 to 2/500 (SH:- F/C 5/7 mtr wide road at Rd 0/600 to 0/900

Sr No	Sub Head/items of work.	Qty	Rate in figures	Rate in world	Unit.	Estimated Cost	
						Earnest Money	Two Month
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1, 1603.2, Sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including cartage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 197.88cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified dimension in all leads and lift as per the direction of Engineer in charge.	2198.70			Cum		491896 9838
Total							


 Executive Engineer,
 B&R Division HP PWD
 Dodra Kanan

Schedule of Quantity

Name of Work:- C/o Link road Helipad to Sharidhar road km 0/00 to 2/500

SH:- C/o R/wall in PCC 1:4:8 at Rd 0/320 to 0/340

ESTIMATED COST

EARNEST MONEY

399322

7986

2 Months

Sr. No

Description of items.

Qty

Unit

Rate

In Flg.

In Words

Amount

1

2

3

4

5

6

7

Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1

22.4

cum

Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.

13.4

cum

Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301

62.50

cum

Providing and Laying concrete concrete 1:4:8 (Cement: 4 sand: 8 graded stone aggregate 40mm nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including all leads and lifts, as per HPPWD, specification of 1990 volume-I or as directed by the Engineer-In-Charge

30.00

cum

Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1

18.00

cum

Total

(Signature)
Executive Engineer
B&R Division HPPWD
Dodra Kargil

Schedule of qty						
Name of Work :- C/o Link road from RCD to Larot bangla via Larot Km 0/00 to 0/750 (Sh:- F/C 57 mtr wide road at Rd 0/00 to 0/525						
		Estimated Cost		498576		
		Earnest Money		9972		
		Time		Two Month		
Sr No	Sub Head/Items of work.	Qty	Rate in figures	Rate in word	Unit.	Amount
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1, 1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 200.57cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified dimension in all leads and lift as per the direction of Engineer in charge.	2228.55			Cum.	
		Total				


 Executive Engineer,
 B&R Division HP, PWD
 Dodra Kayer

Schedule of Qty

Name of Work :- C/O Link road from RCD to Larot bangla via Larot Km 0/00 to 0/750 (Sh:- FIC 5/7 mtr wide road at Rd 0/525 to 0/675 & Kharania stone soling at Rd 0/00 to 0/150)

Sr No		Sub Head/items of work	Qty	Rate in figures	Rate in word	Unit	Amount
		Estimated Cost					495123
		Earnest Money					9902
		Time					Two Month
1		Excavation in hilly-area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1, 1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful materials for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale-tax or other taxes imposed by the Government. A recovery of useful stones-898.8cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified dimension in all leads and lift as per the direction of Engineer in charge.	898.80			Cum.	
2		Preparation of sub-grade by dressing to combor (Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HP.PWD specifications and as directed by the Engineer in Charge.	552.75			sqm	
3		Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and re-rolling the sub-grade completed as per HP PWD Specifications and as directed by the Engineer in Charge.	552.75			sqm	
4		Stone soling properly hand-packed Tilling interstices with Kharania stone and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification, 150 mm spread thickness (finished work including materials and labour) including all leads and lifts, as per HP.PWD specification of 1990 Volume-I, as directed by the Engineer-in-Charge.	127.13			Cum.	
		Total					


 Executive Engineer
 B&R Division HP.PWD
 Doda Kargil

Schedule of Qty			
	Estimate Cost	434000.00	
	Earnest Money	8680.00	
	Time	Three Month	

Name of Work:- R/R Damage to RCD road km 0/00 to 92/695 (Sh:- Hiring of Tipper for carriage of muck / stone in km 21/195 to 92/695 and other link roads)

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit
1	Hiring of Tipper for carriage of material having capacity 400 cft. including P.O.L charge and other ancillary equipments as required at the site of work. The work shall to be carried out as per ministry of transport as per instructions of the Engineer-in-Charge including all leads and lifts.	62.00			Per Day
Total					


Executive Engineer
B&R Division HPPWD
Dodra Kwar

Schedule of Qty

Estimate Cost	420000.00
Earnest Money	8400.00
Time	Two Month

Name of Work:- R/R Damage to RCD road km 0/00 to 92/695 (Sh:- Hiring of Tipper for carriage of muck / stone in km 21/195 to 92/695 and other link roads)

Sr. No.	Sub-Head and Item of works	Quantity	Rate in figures	Rate in words	Unit
1	Hiring of Tipper for carriage of material having capacity 400 cft including P O L change and other ancillary equipments as required at the site of work. The work shall to be carried out as per ministry of transport as per instructions of the Engineer-in-Charge including all leads and lifts	60.00			Per Day
Total					


Executive Engineer
B&R Division HPPWD
Dodra Kwar

Schedule of Qty			
		Estimate Cost	490000.00
		Earnest Money	9800.00
		Time	Three Month
Name of Work:- R/R Damage to RCD road km 0/00 to 92/695 (Sh:- Hiring of Tipper for carriage of muck / stone in km 21/195 to 92/695 and other link roads and link road village Jiskoon)			

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit
1	Hiring of Tipper for carriage of material having capacity 400 cft. including P.O.L charge and other ancillary equipments as required at the site of work. The work shall to be carried out as per ministry of transport as per instructions of the Engineer-in- Charge including all leads and lifts.	70.00			Per Day
Total					


 Executive Engineer
 B&R-Division HPPWD
 Dodra Kwar

Schedule of Qty					
			Estimate Cost	475000	
			Earnest Money	9500	
			Time	Two Month	
Name of Work : A/R & M/O RCD road km 0/00 to 92/695 (SH:-Hiring of JCB removal of slips/drain & dressing of road surface 21/195 to 92/695 and other link roads)					
Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	380.00			Per Hours
			Total:-		


 Executive Engineer
 B&R Division HPPWD,
 Dodra Kwar

Schedule of Qty					
			Estimate Cost	450000	
			Earnest Money	9000	
			Time	Two Month	
Name of Work : A/R & M/O RCD road km 0/00 to 92/695 (SH:-Hiring of JCB removal of slips/drain & dressing of road surface 21/195 to 92/695 and other link roads)					
Sr.No.	Sub-Item and Item of works	Quantity.	Rate in figures.	Unit	Amount.
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	360.00		Per Hours	
Total:-					


 Executive Engineer
 B&R Division HPPWD,
 Doda Kwar

Schedule of Qty				
			Estimate Cost	465000
			Earnest Money	9300
			Time	Two Month
Name of Work : R/R Damage RCD road km 0/00 to 92/695 (SH:-Hiring of JCB removal of slips/drain & dressing of road surface 21/195 to 92/695 and other link roads)				
Sr.No.	Sub-Head and Item of works	Quantity	Rate in figures.	Unit
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-in-charge including all leads and lifts.	372.00		Per Hours
			Total:-	


 Executive Engineer
 B&R Division HPWD,
 Dodra Kwar

Schedule of Qty						
				Estimate Cost		462500
				Earnest Money		9250
				Time		Two Month
Name of Work : R/R Damage to RCD road km 0/00 to 92/695 (SII:-Hiring of JCB removal of slips/drain & dressing of road surface 21/195 to 92/695 and other link roads)						
Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount
1.	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	370.00			Per Hours	
					Total:-	


 Executive Engineer
 B&R Division HPPWD,
 Doda Kwar

Schedule of Qty									
Name of Work :-C/o RCD road km 0/00 to 92/695					ESTIMATED COST				
SH:- P/L Kharanja Stone Soling at Various RD 32/00 to 40/00					EARNEST MONEY				
Description of items.					TIME LIMIT:				
Sr. No					Rate	In Fig.	In Words	Amount.	
1	2	Qty	Unit			5	6	7	
1	Preparation of sub grade by dressing to combor(Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HPPWD specification.	3 884.4	4 cum						
2	Consolidation of sub grade with roller including making good the undulation etc.with earth or quarry soil etc. and rerolling the sub-grade completed as per HPPWD Specification.	884.4	cum						
3	Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HPPWD specification 230mm spread thickness(finished work including materials and labour)	203.41	cum						
Total									


 Executive Engineer
 B&R Division HPPWD
 Dodra Kwar

Schedule of Qty						
Name of Work :- C/o RCD road km 0/00 to 92/695				ESTIMATED COST		491408
SH:- P/L Kharanja Stone Soling at Various RD 40/00 to 51/00				EARNEST MONEY		9828
Description of items.				TIME LIMIT:		2 Months
Sr. No		Qty	Unit	Rate In Fig.	In Words	Amount
1	2	3	4	5	6	7
1	Preparation of sub grade by dressing to combor(Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HPPWD specification.	884.4	cum			
2	Consolidation of sub grade with roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub-grade completed as per HPPWD Specification.	884.4	cum			
3	Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HPPWD specification 230mm spread thickness(finished work including materials and labour)	203.41	cum			
Total						


 Executive Engineer
 B&R Division HPPWD
 Dodra Kwar

1/2
 udi
 Di
 31

COST
 ONEY

Schedule of Quantity						
Name of Work :- C/o Link road Shiladesh to Thalather road km 0/00 to 2/00						
SH:- P/L Kharanja Stone Soling at km 0/810 to 1/050					ESTIMATED COST	491408
Description of items.					EARNEST MONEY	9828
					TIME LIMIT:	2 Months
Sr. No	Qty	Unit	Rate In Fig.	In Words	Amount	
1	3	4	5	6		7
1	884.4	Sqm				
2	884.4	Sqm				
3	203.41	cum				
Total						

Handwritten Signature
 Executive Engineer
 B&R Division HPPWD
 Dodra Kwar

Schedule of Qty

ESTIMATED COST:Rs. 487500.00
 Earnest Money :- 9750.00
 TIME :- One Month

Name of Work:- A/R & M/O Various Non-Residential building at HPPWD Dodra kwar (SH:- Binding of old record files of Division Office)

Sr No.	Sub-Head and Item of works.	Quantity.	Rate in figures.	Rate in words.	Unit	Amount
1	Binding of office record file with card board on both side of file, fixing binding cloth on one edge of the file and abary paper on face of the card board with proper adhesive like fevivvol glue etc. and sewing the file duble and hard thread of suitable size including labour so as to make it in good condition in all respects as per the direction of Engineer - In-Charge with in all leads and lifts All branch					
		2500.00			Nos	
	Total:-					


 Executive Engineer
 B&R Division, HP PWD
 Dodra Kwar

Schedule of Qty						
Name of work:- C/o Link road village Jiskoon km 0/00 8/00				ESTIMATED COST		476524
SH:- C/o B/wall in wire crate at RD 7/030 to 7/125				EARNEST MONEY		9530
Description of Items.				TIME LIMIT:		2 Months
Sr. No		Qty	Unit	Rate	In Words	Amount
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	62.1	cum			
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	37.8	cum			
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS-200 and IS-4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1101	148.44	cum			
Total						


 Executive Engineer
 BAR Division HPPWD
 Dadra Kavar