

Himachal Pradesh  
Public Works Department

Registered

NO:- PW-DKD-N.I.T/2023-24

1404

Dated:-

14/9/2023

To

✓ The Executive Engineer (IT Cell)  
Nigam Vihar Shimla.

Subject:-


Publication of Tender notice.

Jai Haind

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. Of Himachal Pradesh letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16<sup>th</sup>. July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

DA:- Notice inviting tender & Sechedule of Quantity.

  
Executive Engineer,  
B&R Division HP.PWD,  
Dodra Kwar.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**NOTICE INVITING TENDER**

Sealed Percentage rate tenders on form No. 6 & 8 are hereby invited by the Executive Engineer B&R Division HP.PWD, Dodra kwar for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HP.PWD, so as to reach in the office as per time Schedule given below:-

1. Date of receipt of application for tenders forms:-

22.09.2023

2. Dated of Issue /sale of tender forms:-

22.09.2023

3. Date of receipt of tender:-

23.09.2023 up to 10:30AM

4. Date of opening of tender:-

23.09.2023 at 11.AM

Sr. No.	Name of Work	Estimated Cost	EMD (Rs.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1.	Name of Work: C/o Link road Harli to Gosangu ( Gaon Pujarli to Tall Pool) km 0/00 to 2/500( SH:- F/C 5/7 mtr wide road at RD 0/00 to 0/210)	4,92,783/-	9856/-	350/-	Two months	Calss "C&D"
2.	Name of Work: R/R Damage to Dodra Chamdhar Lagnu road km 0/00 to 6/00(SH:-C/o B/wall in PCC 1:3:6 at RD 0/090 to 0/110)	3,43,930/-	6879/-	350/-	Two months	Calss "C&D"
3.	Name of Work: A/R & M/O RCD road km 0/00 to 92/695 ( SH:- Hiring of JCB removal of slips/drain & dressing of road surface km 21/195 to 92/695 and other link roads)	4,80,000/-	9600/-	350/-	Two months	Calss "C&D"
4.	Name of Work: A/R & M/O RCD road km 0/00 to 92/695 ( SH:- Hiring of JCB removal of slips/drain & dressing of road surface km 21/195 to 92/695 and other link roads)	4,60,000/-	9200/-	350/-	Two months	Calss "C&D"
5.	Name of Work: A/R & M/O RCD road km 0/00 to 92/695 ( SH:- Hiring of JCB removal of slips/drain & dressing of road surface km 21/195 to 92/695 and other link roads)	4,70,000/-	9400/-	350/-	Two months	Calss "A,B,C&D"
6.	Name of Work: A/R & M/O RCD road km 0/00 to 92/695 ( SH:- Hiring of JCB removal of slips/drain & dressing of road surface km 21/195 to 92/695 and other link roads)	4,75,000/-	9500/-	350/-	Two months	Calss "C&D"
7.	Name of Work :- A/R & M/O RCD road km 0/00 to 92/695 ( SH:- Hiring of Tipper for carriage of muck/stone in km 21/195 to 92/695 and other link roads)	4,90,000/-	9800/-	350/-	Two months	Calss "C&D"
8.	Name of Work :- A/R & M/O RCD road km 0/00 to 92/695 ( SH:- Hiring of Tipper for carriage of muck/stone in km 21/195 to 92/695 and other link roads)	4,90,000/-	9800/-	350/-	Two months	Calss "C&D"
9.	Name of Work :- C/o Link road village Jiskoon km 0/00 to 8/00 (SH:- C/o B/wall in wire crate at RD 5/310 to 5/335 & 6/090 to 6/115)	4,84,134/-	9683/-	350/-	Two months	Calss "C&D"
10	Name of Work :- C/o Link road Bakora to Gharatkhad Dogri rajpat Jarkot road km 0/00 to 3/00 (SH:- C/o B/wall in PCC 1:3:6 at RD 1/160 to 1/188)	4,81,451/-	9628/-	350/-	Two months	Calss "C&D"

ertified that the tender ment

ned in the notice is exigencies/emergency are urgent nature and in public interest

**TERMS AND CONDITIONS:-**

5. The Earnest money for the above works should be submitted with the application for the purchase of the tender-documents.
6. The Contractors should quoted the rates of the items in the tenders both in figures and words.
7. Income tax & G.S.T. No. Latest clearance certificate.
8. The contractor/firms shall accompany his enlistment/renewal & EPF submit before the award of tender.
9. The Contractors should apply for two works only at a time for tenders.
10. Work should be completed by the contractor within stipulated period.
11. The Executive Engineer reserves the right to accept/rejected any tender/application or all tenders without assigning any reason.



Executive Engineer  
B&R Division HP.PWD,  
Dodra Kwar

NO:- PW-DKD-CB-Tender/2022-23 :- 1405-14  
Copy forwarded for information and wide publicity to:-

Dated 14/9/23

12. The Chief Engineer (S) HPPWD Shimla-2
13. The S.E 14<sup>th</sup> Circle HPPWD Rohru
14. All the EE's under 14<sup>th</sup> Circle HPPWD Rohru
15. All the A.E's working under this Division (B&R)
16. The Sub Divisional Magistrate Dodra Kwar
17. The BDO Dodra Kwar.
18. The Naib tehsildhar Dodra Kwar
19. A/B and D/B in this office
20. Notice Board



Executive Engineer  
B&R Division HP.PWD,  
Dodra Kwar



JOB NO:-01

## Schedule of Qty

Name of Work:-C/o Link road from Harli to Gosangu ( Gaon Pujari to tall Pool) km 0/00 to 2/500 ( SH:- F/C 5/7 mtr wide road at Rd 0/00 to 0/210)

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY	TIME LIMIT:	Two Month
1	2	3	4	Rate	In Words	Amount
				In Fig.	6	7
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded with cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300,1603.1,1603.2, sorting out useful material for filling stacking the same in all leads and lifts in acquired width of the road and transportation of useful material to required in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 310.83 cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified dimension in all leads and lift as per the direction of Engineer in charge.	1549.73	cum	317.9799	Rupees Three Hundred & Seventeen - Paise Ninety Eight Only	492783
Total						492783

Condition:-  
1 The rates Should be quoted for all heights including all lead and lifts.

2 The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/ - )

% qgc

Quoted rate Words ( +/ - )

% qgc

Signature of the Contractor with full address:-

*[Signature]*  
 Executive Engineer  
 B&R Division HPPWD  
 Dodra Kwar

JOB NO:-02

## Schedule of Qty

Name of Work:-R/R Damage to Dodra Chamdhar Lagnu road km 0/00 to 6/00 (SH:- C/o B/wall at RD 0/090 to 0/110)

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY		
				TIME LIMIT:		
1	2	3	4	Rate	In Words	Amount
				In Fig.	6	7
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	18.94	cum	450	Rupees Four Hundred & Fifty Only	8523
2	Providing concrete for plain/reinforced concrete in open foundation R/B-walls complete as per drawing and technical specification clause 802,803,1202 & 1203 grade M10 (1:3:6 nominal mix) .1 cement :3 Sand :6 graded stone aggregate including all lead and lifts.	47.6	cum	6977.26	Rupees Six Thousand Nine Hundred & Seventy Seven Paise Twenty	332118
3	Providing weepholes in brick masonry/ Stone masonry, plain/reinforced concrete aboutment ,wing wall,return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204,3.7 including all lead and lifts.	8	each	411.29	Rupees Four Hundred & Eleven - Paise Twenty Nine Only	3290
Total						343930

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

2 The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.


Quoted rate Figure ( +/ - )

%

Quoted rate Words ( +/ - )

%

Signature of the Contractor with full address:-

  
**Executive Engineer**  
**B&R Division HPPWD**  
**Dodra Kwar**



JOB NO:-03

## Schedule of Qty

Name of Work:A/R & M/O RCD road km 0/00 to 92/695(SH:-Hiring of JCB removal of slips/drain & dressing of road surface 21/195 to 92/695 and other link roads)				ESTIMATED COST		480000
				EARNEST MONEY		9600
				TIME LIMIT:		Two Month
Sr. No	Description of items.	Qty	Unit	Rate In Fig.	In Words	Amount.
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	384	Per Hours	1250	Rupees One Thousand Two Hundred & Fifty Only	480000
Total						480000

Condition:-

- 1 The rates Should be quoted for all heights including all lead and lifts.
- 2 The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Executive Engineer  
B&R Division HPPWD  
Dodra Kawayar

Quoted rate Figure (+/-)  
90 %

Signature of the Contractor with full address:-

Job No. ④

**Schedule of Qty**

Name of Work: A/R & M/O RCD road km 0/00 to 92/695 (SH:- Hiring of JCB removal of slips/drain & dressing of road surface 21/195 to 92/695 and other link roads)

Schedule of Qty							ESTIMATED COST	460000
							EARNEST MONEY	9200
							TIME LIMIT:	Two Month
Sr. No	Description of items.	Qty	Unit	Rate		In Words	Amount	
				In Fig.				
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	368	Per Hours	1250		Rupees One Thousand Two Hundred & Fifty Only	460000	
Total								460000

Rate

Condition:-

- 1 The rates Should be quoted for all heights including all lead and lifts.
- 2 The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/- )

Quoted rate Words ( +/- )

Signature of the Contractor with full address:-

*(Signature)*  
**Executive Engineer**  
**B&R Division HPPWD**  
**Dodra Kayar**

JOB NO:-05

Schedule of Qty						
Name of Work: A/R & M/O RCD road km 0/00 to 92/695 (SH:- Hiring of JCB removal of slips/drain & dressing of road surface 21/195 to 92/695 and other link roads)						
Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY		TIME LIMIT:
				Rate In Fig.	In Words	Amount.
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	376	Per Hours	1250	Rupees One Thousand Two Hundred & Fifty Only	470000
Total						470000

Condition:-

- 1 The rates Should be quoted for all heights including all lead and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Dodra Kagar



JOB NO:-06

**Schedule of Qty**

Name of Work: A/R & M/O RCD road km 0/00 to 92/695 (SH:- Hiring of JCB removal of slips/drain & dressing of road surface 21/195 to 92/695 and other link roads)

Schedule of Qty						
Name of Work:A/R & M/O RCD road km 0/00 to 92/695(SH:-Hiring of JCB removal of slips/drain & dressing of road surface 21/195 to 92/695 and other link roads)				ESTIMATED COST		475000
				EARNEST MONEY		9500
				TIME LIMIT:		Two Month
Sr. No	Description of items.	Qty	Unit	Rate	In Words	Amount.
				In Fig.		
1	2	3	4	5	6	7
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L. charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	380	Per Hours	1250	Rupees One Thousand Two Hundred & Fifty Only	475000
Total						475000

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

2 The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-


*(Signature)*  
Executive Engineer  
B&R Division HPPWD  
Dodra Kwar

**JOB NO:-07**

**Schedule of Qty**

**Name of Work:**A/R & M/O RCD road km 0/00 to 92/695(SH:-Hiring of Tipper for carriage of muck/stone in km 21/195 to 92/695 and other link roads)

Schedule of Qty						
Name of Work:A/R & M/O RCD road km 0/00 to 92/695(SH:-Hiring of Tipper for carriage of muck/stone in km 21/195 to 92/695 and other link roads)						
Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY	TIME LIMIT:	Two Month
				Rate In Fig.	In Words	Amount.
1	Hiring of Tipper for carriage of material having capacity 400 cft. including P.O.L charge and other ancillary equipments as required at the site of work. The work shall to be carried out as per ministry of transport as per instructions of the Engineer-in- Charge including all leads and lifts.	3	4	5	6	7
		70	Per Day	7000	Rupees Seven Thousand Only	490000
Total						490000

Signature: 

Engineer

Condition:-

- 1 The rates Should be quoted for all heights including all lead and lifts.
- 2 The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

*(Signature)*  
**Executive Engineer**  
**B&R Division HPPWD**  
**Dodra Kawar**



JOB NO:-08

**Schedule of Qty**

Name of Work: A/R & M/O RCD road km 0/00 to 92/695 (SIH:-Hiring of Tipper for carriage of muck/stone in km 21/195 to 92/695 and other link roads)

Sr. No	Description of Items.	Qty	Unit	ESTIMATED COST	
				EARNEST MONEY	Two Month
1	Hiring of Tipper for carriage of material having capacity 400 cft. including P.O.L charge and other ancillary equipments as required at the site of work. The work shall to be carried out as per ministry of transport as per instructions of the Engineer-in-Charge including all leads and lifts.	70	Per Day	7000	Rupees Seven Thousand Only
Total					490000

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/- )

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kwar

Signature of the Contractor with full address:-

1000000  
900000

JOB NO:-09

**Schedule of QTY**

Name of Work:- C/o Link road village Jiskoon km 0/00 to 8/00 (SH:- C/o B/wall in wire crate at RD 5/310 to 5/335 & 6/090 to 6/115)

Sr. No	Description of Items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY	TIME LIMIT:	Amount
1	2	3	4	Rate In Fig.	In Words	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	42	cum	186.32	Rupees One Hundred & Eighty Six - Paise Thirty	7825
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	21	cum	450	Rupees Four Hundred & Fifty Only	9450
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	156.25	cum	2987.9	Rupees Two Thousand Nine Hundred & Eighty Seven - Paise Ninety Only	466859
Total						484134

Executive Engineer  
B&R Division HPPWD  
Dodra Kwar

- Condition:-
- 1 The rates Should be quoted for all heights including all lead and lifts.
  - 2 The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.
- Quoted rate Figure (+/-)
- Quoted rate Words (+/-)
- Signature of the Contractor with full address:-



JOB NO:-10

## Schedule of Qty

Name of Work:-C/o Link road Bakora to Gharatkhad Dogri Raipat Jarkot road km 0/00 to 3/00(SH:- C/o B/wall in PCC  
1:3:6 at RD 1/160 to 1/188)

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY	TIME LIMIT:	Amount
				In Fig.	In Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	3	4	5	6	7
2	Providing concrete for plain/reinforced concrete in open foundationR/B-walls complete as per drawing and technical specification clause 802,803,1202 & 1203 grade M10 (1:3:6 nominal mix) , 1 cement :3 Sand :6 graded stone aggregate including all lead and lifts.	26.52	cum	450	Rupees Four Hundred & Fifty Only	11934
3	Providing concrete for plain/reinforced concrete in open foundationR/B-walls complete as per drawing and technical specification clause 802,803,1202 & 1203 grade M10 (1:3:6 nominal mix) , 1 cement :3 Sand :6 graded stone aggregate including all lead and lifts.	66.64	cum	6977.26	Rupees Six Thousand Nine Hundred & Seventy Seven Paise Twenty	464965
4	Providing weepholes in brick masonry/ Stone masonry,plain/reinforced concrete aboutment ,wing wall,return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204,3.7 including all lead and lifts.	11	each	411.29	Rupees Four Hundred & Eleven - Paise Twenty Nine Only	4524
Total						343930

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.


9/088  
70082

2 The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kwar