

**Himachal Pradesh
Public works Department**

Notice inviting Tender

Sealed Item rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD: Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **22-09-2023 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non refundable) up to 5.00 P.M. on **21-09-2023**. The applications for issue of tender forms will be received up to **2.00 P.M. on 20-09-2023**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

| Sr. No. | Name of road/work | Estimated Cost | Earnest Money | Time limit | Class of contract or |
|---------|--|----------------|---------------|--------------|----------------------|
| 1 | Construction of Padhru to Kainchadi road (Portion Masyana to kainchadi km 0/000 to 1/500) (SH: 5/7 wide formation cutting in km 1/030 to 1/330) under MMSY | 4,79,617/- | 10000/- | Three Months | D |
| 2 | Construction of Padhru to Kainchadi road (Portion masyana to kainchadi km 0/000 to 1/500) (SH: 5/7 mtr wide formation cutting in km 1/330 to 1/500) under MMSY | 2,94,709/- | 6000/- | Three Months | D |
| 3 | Construction of Padhru to Kainchadi road (Portion masyana to kainchadi km 0/000 to 1/500) (SH: 5/7 mtr wide formation cutting in km 1/810 to 1/030) under MMSY | 4,80,580/- | 10000/- | Three Months | D |
| 4 | A/R & M/O on Assistant Engineer office Building at Dhanotu Sub- Division, Tehsil Sunder Nagar, Distt. Mandi H.P. (SH: Providing and fixing paneling and Almirah work etc) | 4,96,146/- | 10000/- | Three Months | D |
| 5 | A/R & M/O on Assistant Engineer office Building at Dhanotu Sub- Division, Tehsil Sunder Nagar, Distt. Mandi H.P. (SH: Providing fixing paneling and flooring 1 st floor and Almirah work etc) | 4,25,146 | 10000/- | Three Months | D |

Certified that tender of above works are being called for emergent nature in exigency of public interest.

GENERAL CONDITIONS:-

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the rates of all the items in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form, for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in- Chief office letter No. PW-CTR/22-25/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10.05.2023. Beside this the additional performance security will have to be borne by the bidders as per the said notifications.
7. The contractor can apply only for one work at a time.
8. Conditional and incomplete tenders shall be rejected.
9. The Executive Engineer reserves the right to accept or reject the tender without any reason.

Executive Engineer,
Gohar Division (B&R),
HPPWD Gohar

Dated 11/9/2023

No. PW-GHR-Tender/NIT/2023 **6953-72**
Copy along with Tender inviting Notice forwarded for information to:

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP PWD Shimla
3. The Superintending Engineer 1st Circle, HP PWD Mandi
4. The Executive Engineer (IT Cell) O/o Engineer-in-Chief, HPPWD Nirman Bhawan, Nirman Vihar, Shimla-2 for uploading the NIT on departmental website please
5. The Sub- Divisional Officer (Civil) Chandioli at Gohar
6. The Block Development Officer, Gohar.
7. The Assistant Engineer HPPWD Sub- Division Gohar
8. Various contractors
9. Notice board/ D.O. etc

Executive Engineer,
Gohar Division (B&R),
HPPWD Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs. 4,79,617/- only

Earnest Money: Rs 10,000/- only

Time : Three month

Name of work :- Construction of Padhru to Kainchdi road (Portion Masyana to Kainchadi km 0/00 to 1/500) (SH:- 5/7 mtr wide
Formation cutting in km 1/030 to 1/330) Under MMSY

| S. No. | Sub Head and item of work | Qty. | Rate in | | Unit | Amount |
|--------|--|-------------|---------|------|-----------------|--------|
| | | | Figure | Word | | |
| 1 | Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required setting out to the required line grades , side slopes trimming bottom and level as shown on drawings as directed by the Engineer -in charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in roads ways , embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries , materials , tools equipment's and safety measures and incidentals necessary to complete the work by all means (if any required) recovery for 119.51 cubic metre @ Rs. 300.00 per cubic metre amount 35853/- shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor , which shall have to be duly compensated by him in all respect including all leada and lifts and materials and as per direction of Engineer in charge . | 2796.60 cum | | | per cubic metre | |
| | | | | | Total | |


 Executive Engineer
 B & R Division
 H.P.R.W.D Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs. 2,94,709/- only

Earnest Money: Rs 6,000/- only

Time : Three month

Name of work :- Construction of Padhru to Kainchdi road (Portion Masyana to Kainchadi km 0/00 to 1/500) (SH:- 5/7 mtr wide
Formation cutting in km 1/330 to 1/500) Under MMSY

| S. No. | Sub Head and item of work | Qty. | Rate in | | Unit | Amount |
|--------|---|---------|---------|------|-----------------|--------|
| | | | Figure | Word | | |
| 1 | Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required setting out to the required line grades , side slopes trimming bottom and level as shown on drawings as directed by the Engineer -in charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in roads ways , embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries , materials , tools equipment's and sefety measures and incidentals necessary to complete the work by all means (if any required) recovery for 76.63 cubic metre @ Rs. 300.00 per cubic metre amount 22989/- shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor , which shall have to be duly compensated by him in all respect including all leada and lifts and materials and as per direction of Engineer in charge . | 1701.75 | | | per cubic metre | |
| | | | | | Total | |


 Executive Engineer
 B & R Division

SCHEDULE OF QUANTITY

3


Estimate Cost: Rs. 4,80,580/- only

Earnest Money: Rs 10,000/- only

Time : Three month

Name of work :- Construction of Padhru to Kainchdi road (Portion Masyana to Kainchadi km 0/00 to 1/500) (SH:- 5/7 mtr wide
Formation cutting in km 0/810 to 1/030) Under OTMNP

| S. No. | Sub Head and item of work | Qty. | Rate in | | Unit | Amount |
|--------|--|-------------|---------|------|-----------------|--------|
| | | | Figure | Word | | |
| 1 | Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required setting out to the required line grades , side slopes trimming bottom and level as shown on drawings as directed by the Engineer in charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all loads and lifts and transportation of the un-useful materials for filling in roads ways , embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries , materials , tools equipment's and safety measures and incidentals necessary to complete the work by all means (if any required) recovery for 119.51 cubic metre @ Rs. 300.00 per cubic metre amount 35853/- shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor , which shall have to be duly compensated by him in all respect including all leads and lifts and materials and as per direction of Engineer in charge . | 2995.20 cum | | | per cubic metre | |
| | | | | | Total | |


 Executive Engineer
 B & R Division
 H.P.P.W.D Gohar

Name of work:- A/R& M/O on Assistant Engineer office Building at Dhanotu sub-Division Teh. SNR. Distt. Mandi (H.P.) (SH:- Providing and fixing paneling and Almirah work Etc.)

DRAFT SCHEDULE OF QUANTITY

Estimated Cost:- 496146.00


Earnest Money :- 10000.00

Time :- Three month

| S.No | Description of item | Quantity | Rate | | Unit | Amount |
|------|---|----------|-----------|---------|------------------|--------|
| | | | In figure | In word | | |
| 1 | Providing and Fixing 19mm (nineteen millimeter) thick prelaminated MDF (Medidum Density Fiber board) board in shelves/box for cup board and paneling with butt joints and fixing with nails and screws etc. including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge. | 63.13 | | | Per square metre | |
| 2 | Providing and Fixing 19mm (nineteen millimeter) thick water proof commercial board in shelves/box for cup board with butt joints and fixing with nails and screws etc. including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge. | 65.16 | | | Per square metre | |
| 3 | Providing and Fixing 19mm (nineteen millimeter) thick commercial board water proof shutters for cup boards and box including fixing with nickle plated pinoo hinges with screw etcetera including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge. | 19.57 | | | Per square metre | |
| 4 | Providing and Fixing hydraulic auto hinges of superior quality with screws etc. complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge. | 88.00 | | | Each | |
| 5 | Providing and Fixing door closures with necessary screws etc. including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge. | 2.00 | | | Each | |
| 6 | Providing and Fixing stainless steel L-Boutton (SS) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge. | 112.00 | | | Each | |
| 7 | Providing and Fixing brass door latch with necessary screws etc. including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge. | 56.00 | | | Each | |
| 8 | Providing and Fixing steel lock with accessories including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge. | 10.00 | | | Each | |

(11)

| | | | | | | |
|----|--|--------|--|--|-------------------|--|
| 9 | Providing and Fixing PVC Tape thick and 3/4 wide including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge. | 205.48 | | | Per running metre | |
| 10 | Providing and Fixing 1.00mm (one millimeter) thick colored or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc. complete including carriage of material with in all leads and lifts and other incidentals charges complete in all respect and as per the direction of the Engineer-in charge. | 127.10 | | | Per square metre | |
| | | | | | Total | |


 Executive Engineer
 B & R Division
 H.P.R.W.D Gohar

DRAFT SCHEDULE OF QUANTITY

me of work :- A/R& M/O on Assistant Engineer office Building at Dhanotu sub-Division ~~74-514~~ Distt. Mandi (H.P.)
 t:- ~~Providing~~ Fixing paneling and flooring 1st floor and Almirah etc.)

Estimated Cost:- 425146 /-only

Earnest Money:- 10000/-only

Time :- Three Months

| No | Description of item | Qty. | Rate | | Unit | Amount |
|------|---|-------|---------|---------|------------------|--------|
| | | | In Fig. | In word | | |
| 1.00 | 2 | 3 | 4 | 5 | 6 | 7 |
| 1 | Providing and laying wiparquat laminate (nature structure textured surface AC-4- 1286 x 194 x 8mm) flooring of approved brand and manufacture over cement concrete base with polythene and foam sheet curtain below as per specification including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in- charge. | 32.03 | | | Per square metre | |
| 2 | Providing and Fixing 2mm (two millimeter) thick PVC anti staticventyl flooring plain or coloured, carved or mosaic / matalied finishlaid with approved adhesive on sub-floor (damp proofing treatment to bepaid for separately on as per specification including carrage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge. | 6.32 | | | Per square metre | |
| 3 | Providing and Fixing 10mm (ten millimeter) thick PVC paneling with all accessories of panels of various size of approved section as per specification including carrage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge. | 37.61 | | | Per square metre | |
| 4 | Providing and Fixing 19mm (nineteen millimeter) thick water proof commercial board in ssbelves/ box for cup board with butt joints and fixing with nails and screws etc.including ckarrage,of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge. | 25.50 | | | Per square metre | |
| 5 | Providing and Fixing 19mm (nineteen millimeter) thick commercial board water proof shutters for cup boards and box including fixing withnickle plated pino hinhes with screws etc.including carrage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge. | 11.16 | | | Per square metre | |
| 6 | Providing and Fixing hydraulic auto hinges of superior quality with screws etc. complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge. | 32.00 | | | Each | |
| 7 | Providing and Fixing door closures with necessary screws etc. including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge. | 2.00 | | | Each | |
| 8 | Providing and Fixing stainless steel L-Boutton (SS) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge | 36.00 | | | Each | |
| 9 | Providing and Fixing brass door latch with necessary screws etc. including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge. | 21.00 | | | Each | |
| 10 | Providing and Fixing steel lock with accessones including carrage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer -in charge. | 3.00 | | | Each | |

| | | | | | |
|------|---|-------|--|--|-------------------|
| 11 | Providing and Fixing PVC Tape thick and 3/4 wide including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in charge. | 64.70 | | | Per running metre |
| 12 | Providing and Fixing heavy duty aluminum handle (Barrel type) anodized transparent or dyed to required shade and color with screws etcetra complete in all respect including carriage of materials with in all leads and lifts complete and as per the direction of the Engineer-in charge. | | | | |
| 12.1 | 1.- 300mmX10mm | 13.00 | | | Each |
| 12.2 | 2.- 150mm 10mm | 27.00 | | | Each |
| 13 | Providing and Fixing 4mm (four millimeter) thick PVC sheet finish laid with approved adhesive on cup board/ paneling in shelves/ box /paneling for damp proofing treatment as per direction of Engineerp boards and box including fixing withnickle plated piano hinges with screws etc.including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in charge of material with in all leads, lifts and other incidental charges complete in all respect | 11.25 | | | Per Square metre |
| 14 | Providing and Fixing 1.00mm (one millimeter) thick colored or plain lamination sheet (summica) on boards/ply wood sheets with approved adhesive and nails etc. complete including carriage of material with in all leads and lifts and other incidentals charges complete in all respect and as per the direction of the Engineer-in charge. | 25.50 | | | Each |
| 15 | Providing and Fixing heavy duty aluminum tower bolt (Barrel type) anodized transparent or dyed to required shade and color with screws etcetra complete in all respect including carriage of material with in all leads and lifts complete in all respect and other incidentals charges complete in all respect and as per the direction of the Engineer-in charge. | 40.00 | | | Each |
| 16 | Providing and Fixing 4mm (four millimeter) thick PVC sheet finish laid with approved adhesive on cup board/ paneling in shelves/ box /paneling for damp proofing treatment as per direction of Engineer-in charge including carriage of material with in all leads, lifts and other incidental charges complete in all respect | 90.70 | | | Per square metre |
| 17 | Providing and Fixing 19mm (nineteen millimeter) water proof board for door frame with in all leads, lifts and other incidental charges complete in all respect as per the Engineer-in charge. | 2.19 | | | Per square metre |
| 18 | Providing and Fixing 40mm (forty millimeter) thick commercial board water proof shutters for cup-boards and box including fixing with nickle plated piano hinges with screws etcetra including carriage of material with in all leads, lifts and other incidental charges complete in all respect as per the Engineer-in charge. | 1.50 | | | Per square metre |
| 19 | Providing and Fixing first class deodar wood plain square edged cover fillets (Beading) 40X12Xmm (Forty into twelve millimeter) section with wood screws in ceiling and lining including mitring at junction including carriage of material with in all leads, lifts and other incidental charges complete in all respect as per the Engineer-in charge. | 98.20 | | | Per running metre |
| | | | | | Total- |

Executive Engineer
B & R Division
H.P.W.D Gohar