



Office of

Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030 Email ee-jaipwd-hp@gov.in

"CERTIFICATE"

Certified that the tenders for the works as called vide this office letter No. PWD/JSD/TA/NIT/ 2023-24- 7282-7320 dated 18-09-2023 are of urgent nature and in public interest.

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur.



"NOTICE INVITING TENDERS"

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **26.09.2023** up to **11:30 A.M.** and the same shall be opened on the same day at 04:00 P.M. in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **25.09.2023** up to **4:00 PM** and the application for issue of tender from shall be received on **25.09.2023** up to **11:30 AM**. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office/ Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD Division Jaisinghpur.


The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days:-

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time Limit
1	Restoration of rain damages to Bahroo Nadli Gharchindi Malli Road KM 0/0 to 13/200 (SH:- Improvement of culvert curves at RD 7/415 to 7/455)	486703/-	9800/-	Two month
2	Restoration of rain damages to Bahroo Nadli Gharchindi Malli Road KM 0/0 to 13/200 (SH:- Improvement of culvert curves at RD 7/460 to 7/500)	473222/-	9500/-	Two month
3	Improvement, widening & strengthening of Jhamoon to Jaisinghpur road KM 8/0 to 18/300 (SH:- P/L interlocking paver block at RD 8/801.50 to 8/811 and 9/261.8 to 9/309.80)	488239/-	9800/-	Two month
4	C/O Bahroo Nadli Gharchindi Malli road KM 0/0 to 13/200 (SH:- Improvement of road at KM 9/532 to 9/405) SCDP	494567/-	9900/-	Two month
5	Improvement, widening & strengthening of Jhamoon to Jaisinghpur road KM 8/0 to 18/300 (SH:- P/L interlocking paver block at RD 8/743.50 to 8/800)	492464/-	9900/-	Two month

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal ellisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK.



 Executive Engineer
 Jaisinghpur Division
 HPPWD Jaisinghpur.
 (On behalf of Governor of Himachal Pradesh)
 Dated:- **18/09/2023**

No. PW/JSD/TA/Tender/NIT/2023-24-

7282-7320

Copy to the following for information and necessary action:-

1. The Principal Secy. (PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief HPPWD, Shimla.
3. The Chief Engineer (K.Z.) HPPWD Dharamshala.
4. The Director, Information & Publications Department, H.P. Shimla.
5. ✓ The Executive Engineer (IT) Nigam Vihar Shimla-2 for information. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. All the S.E.s / E.E.s under Kangra Zone.
9. The Sub Divisional Officer (C) Jaisinghpur
10. The Block Development office Lambagaon
11. All the Assistant Engineer under this Division.
12. The Drawing /Accounts Branch in this office.
13. The Contractors concerned.
14. Notice Board.


 Executive Engineer
 Jaisinghpur Division
 HPPWD Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages to Bahroo Nadli Gharchindi Malli Road Km 0/00 to 13/200 (SH:- Improvement of of curves at Rd 7/415 to 7/455)					Estimated cost Rs.	486703.00
					Earnest Money Rs.	9800.00
					Time Limits	Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock,soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 139.45 (one hundred thirty nine decimal four five) cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1621.91			Per cubic metre	
					Total	



Executive Engineer,
Jaishingpur Division
HP PWD Jaishingpur.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages to Improvement of curves at Rd 7/460 to 7/500)

Improvement of curves at Rd 7/460 to 7/500 (SH:- Bahroo Nadli Gharhindi Malli Road Km 0/00 to 13/200)						
S. N.	Description of Item	Quantity	Rate		Unit	Estimated cost Rs.
			In Figures	In Word		Earnest Money Rs.
						Time Limits
						Two month Amount
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock,soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 125.38 (one hundred twenty five decimal three eight) cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1393.10			Per cubic metre	
						Total

Chen

Executive Engineer,
Jaisinghpur Division
QHP.PWD Jaisinghpur.

(3)

SCHEDULE OF QUANTITY

Name of work :- Improvement, Widening & Strengthening of Jhamon to Jaisinghpur road Km.8/0 to 18/300 (SH:- P/L Interlocking paver block at RD 8/801.50 to 8/811 and 9/261.8 to 9/309.80)

P/L Interlocking paver block at RD 8/801.50 to 8/811 and 9/261.8 to 9/309.80)										Estimated cost Rs.		488239.00
										Earnest Money Rs.		9800.00
										Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount						
			In Figures	In Word								
1	Providing and laying mechanically mixed and vibrated plain cement concrete 1:4:8 (one cement is to four sand is to eight graded crushed stone aggregate 40 mm (forty millimeter) nominal size) and curing complete excluding the cost of form work in foundation and plinth as per specifications approved drawing , design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	21.56			Per cubic metre							
2	Providing and laying 80 mm thick Interlocking M-40 grade Concrete paver block pavement conforming to ISI 15658:2006 having thickness 80mm (eighty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shell be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	287.50			Per square metre							
3	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishing and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty millimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.73			Per Cubic Metre							
									Total			




Executive Engineer,
Jaisinghpur Division
J.P.W.D Jaisinghpur.

4

SCHEDULE OF QUANTITY

Name of work :- C/O Bahroo Nadli Gharchindi Malli Road Km 0/00 to 13/200 (SH:-Improvement of road at Km 9/352 to 9/405) SCDP

		Estimated cost Rs.		494567.00
		Earnest Money Rs.		9900.00
		Time Limits		Two month
S. N.	Description of Item	Quantity	Rate	
			In Figures	In Word
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual/mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of unuseful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 118.01 (one hundred eighteen decimal zero one) cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1733.62		Per cubic metre
				Total



Executive Engineer,
Jaisinghpur Division
J.P.W.D Jaisinghpur.

5

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
Name of work :-Improvement, Widening & Strengthening of Jhamon to Jaisinghpur road Km.8/0 to 18/300 (SH:- P/L Interlocking paver block at RD8/743.50 to 8/800)		Estimated cost Rs.		492464.00		
		Earnest Money Rs.		9900.00		
		Time Limits		Two month		
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying mechanically mixed and vibrated plain cement concrete 1:4:8 (one cement is to four sand is to eight graded crushed stone aggregate 40 mm (forty millimeter) nominal size) and curing complete excluding the cost of form work in foundation and plinth as per specifications approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	21.75			Per cubic metre	
2	Providing and laying 80 mm thick, Interlocking M-40 grade Concrete paver block pavement conforming to ISI 15658:2006 having thickness 80mm (eighty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shell be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	290.00			Per square metre	
3	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishig and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty millimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.74			Per Cubic Metre	
					Total	

[Signature]

Executive Engineer,
Jaisinghpur Division
CHP PWD Jaisinghpur.