



Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908 222033 E-Mail:- ee-jog-hp@nic.in

" SHORT TERMS NOTICE INVITING TENDER "

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 27-10-2023 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office 25-10-2023 up to 10.00 A.M. to 12:30 P.M. and tender form can be had from this office on 26-10-2023 from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1.	Restoration of damages due to laying of OFC on link road from Dhelu Har to Sarkari Bagicha km. 0/00 to 1/00 (SH:- Providing and laying Cement Concrete pavement at km. 0/670 to 0/955).	Rs.4,95,826/-	Rs. 9,900/-	Rs. 350/-	Class "D"	Three months
2.	Restoration of damages due to laying of OFC on Baijnath Lad Bharol Kandapattan road (SH:- Removal of land slide/slips in km. 36/0 to 38/500).	Rs. 4,86,030/-	Rs. 9,700/-	Rs. 350/-	Class "D"	Three months
3.	Restoration of damages due to laying of OFC on Baijnath Lad Bharol Kandapattan road (SH:- Removal of land slide/slips in km. 39/720 to 43/318)	Rs. 4,95,513/-	Rs. 9,900/-	Rs. 350/-	Class "D"	Three months
4.	Restoration of rain damages on Panjalag to Fagla road km., 0/0 to 5/0 (SH:- Construction of breast wall at km. 1/125 to 1/145).	Rs. 2,52,686/-	Rs. 5,700/-	Rs. 350/-	Class "D"	Three months
5.	Construction and metalling of Chakrod to Roparu road. (Sub Head:- Providing and laying kharanja stone soling and cement concrete pavement in Km. 0/0 to 0/075).	Rs. 2,75,011/-	Rs. 5,500/-	Rs.350/-	Class "D"	Three months
6.	Restoration of Rain Damages on Machhyal Bhararu Bihun road km. 0/00 to 11/00 (SH:- Construction of Breast wall for protection of Existing house of Ram Lal at km. 9/900 to 9/920)	Rs. 2,65,791/-	Rs. 5,300/-	Rs.350/-	Class "D"	Three months
7.	Improvement of Baijnath Lad Bharol Kandapattan road km. 0/00 to 46/0 (SH:- C/o Retaining wall at km. 29/710 to 29/720).	Rs. 1,76,646/-	Rs. 3,500/-	Rs.350/-	Class "D"	Three months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest due to heavy rain damaged.

Terms and conditions:-

- The contractor should produce a copy of enlistment / renewal letter at time of application.
- Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
- The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
- The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
- No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
- The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
- The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-/NIT/Press/2023-24-

17263-52

Dated:-

14-09-2023

- Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-Chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- All the Contractor working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder

SCHEDULE OF QUANTITY

Name of Work : Restoration of damages due to laying of OFC on link road from Dhelu Har to Sarkari Bagicha km 0/00 to 1/00 (S.H. : Providing and laying Cement Concrete pavement at km 0/670 to 0/955)				Estimate Cost: 4,95,826.00 Earnest Money: 9,900.00 Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate	
				Figures	Words
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	74.81	Per Cubic metre		
Total					AMOUNT Rs. P

Executive Engineer
B & R Division HP.PWD,
Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Damages due to Laying of OFC on Baijnath Lad Bharol Kandapattan Road km 0/00 to 46/00 (SH: Removal of Slips in km 36/00 to 38/500)					Estimate Cost: Earnest Money: Time Limit :		4,86,030.00 9,700.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate	Amount		Rs.	P
					Figures	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material as per technical specification clause 302.3.5 and 1611. including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	3277.34	Per cubic metre					
	Total							


 Executive Engineer
 B & R Division HP, PWD,
 Jodhpur Nagar.

SCHEDULE OF QUANTITY

Name of Work : Restoration of Damages due to Laying of OFC on Baijnath Lad Bharol Kandapattan Road km 0/00 to 46/00 (SH: Removal of Slips in km 39/720 to 43/318)					Estimate Cost: Earnest Money: Time Limit :		4,95,513.00 9,900.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate	Figures	Words	AMOUNT Rs.	P
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material as per technical specification clause 302.3.5 and 1611. including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	3341.29	Per cubic metre					
Total								


 Executive Engineer
 B & R Division HP.PWD.
 Jodhpur Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Panjalag to Fagla road km 0/00 to 5/00 (SH: Construction of Breast wall at km 1/125 to 1/145)				Estimate Cost: 2,52,686.00 Earnest Money: 5,100.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	33.20	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	23.20	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	47.00	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	20.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD.,
 Jyoti Nagarkar

SCHEDULE OF QUANTITY

Name of Work- Construction and Metalling of Chakrod to Roparu Road (Sub Head:- Providing and Laying Kharanja Soling and Cement Concrete Pavement from km 0/00 to 0/075)				Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred milimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.	35.44	Per Cubic metre			2,75,011.00
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge.	29.54	Per Cubic metre			5,500.00
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Machyal Bhararu Bihun road km 0/00 to 11/00 (SH: Construction of Breast wall for protection of Existing house of Ram Lal at km 9/900 to 9/920)				Estimate Cost: Earnest Money: Time Limit :			2,65,791.00 5,300.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate			AMOUNT Rs. P
				Figures	Words		
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	4.10	Per cubic metre				
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	51.00	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	22.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work : Improvement of Black Spot on Baijnath Lad Bharol Kandapattan Road km 26/00 to 29/720 (SH: Construction of Retaining wall at km 29/710 to 29/720)				Estimate Cost: 1,76,646.00 Earnest Money: 3,500.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earthwork in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost.	13.05	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORID technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	31.54	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge.	18.00	Each			
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals.	5.85	Per cubic metre			
	Total					


 Executive Engineer
 B & R Division HP, PWD,
 Jalandhar Nagar