



Office of

Short term Notice

Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Work
Department Jaisinghpur 176095 Phone No. 01894-228030 Email ee-jaipwd-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on 13.09.2023 up to 11:30 A.M. And the same shall be opened on the same day at 04:00 P.M. in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on 12.09.2023 up to 4:00 PM and the application for issue of tender form shall be received on 11.09.2023 up to 12:00 noon. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office/ Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. N.	Name of work	Estimated Cost	Earnest Money	Time Limit
1	Restoration of Rain damages to Bhuana Ashapuri road Km 0/00 to 12/100 (SH:- C/O Wire crate B/wall in slide Prone Area Km 0/615 to 0/630)	265511/-	5400/-	One month
2	Restoration of Rain damages to Bhuana Ashapuri road Km 0/00 to 12/100 (SH:- C/O Wire crate B/wall in slide Prone Area Km 0/870 to 0/898)	495621/-	10000/-	One month
3	Restoration of rain damages to Panchrukhi Lambagaon road Km 0/00 to 22/100 (SH:- C/O Pusta for wire crate B/wall at RD 11/605 to 11/640)	467775/-	9400/-	One month
4	Restoration of rain damages to Haler to Ropa, Guhan Rananagar Chatter (Dalu) Road road km 0/00 to 4/00 (SH:- C/O B/wall at RD 2/730 to 2/770)	486219/-	9800/-	One month
5	C/O Link road from main road HSTM to Old HSTM road Km 0/00 to 0/175 (SH:-C/O R/wall at RD 0/05 to 0/023) (Deposit 3.00 Lakh)	279854/-	5600/-	One month
6	Improvement of black spot on Tikker to Ridkal road Km 0/00 to 4/00 (SH:- P/F W Metal Beam Crash Barrier at RD 1/525 to 1/575)	222474/-	4500/-	One month
7	C/O Tinbar to Lugat road Km 0/00 to 2/060 (SH:-C/O R/wall at RD 0/960 to 0/967) (MNP)	176866/-	3600/-	One month
8	Restoration of rain damages on Ropri to Umber road Km 0/00 to 6/500 (SH:- C/O W/wall of 900 mm dia hume pipe culvert at Rd 0/255)	354182/-	7100/-	One month
9	Restoration of rain damages on link road to Village Rananagar Km 0/00 to 5/00 (SH:- C/O B/wall at RD 4/650 to 4/670 and edge wall with U-shape drain 4/870 to 4/920)	444909/-	8900/-	One month
10	Restoration of Rain Damages on Dharamshala Dadh Palampur Holta Chadhia Sandhole road Km 0/00 to 90/00 (SH:- C/O Approaches of existing 1.00 mtr. Span RCC slab culvert at RD 46/630)	492370/-	9900/-	One month
11	Restoration of rain damages to Jangal to Oach Kallan Road Km 0/00 to 11/0 (SH:- P/F Steel Grating over culvert at RD 0/315 to 0/323,	444749/-	8900/-	One month

	C/O U-shape drain with edge wall at RD 0/323 to 0/353 & U-shape drain at RD 0/353 to 0/455)			
12	Improvement and widening of road from Panchrukhi Pahra road to Tatchal Majbeen (via Thinkurwara) Km 0/00 to 1/800 (SH:- C/O R/wall at RD 1/456 to 1/470)	342674/-	6900/-	One month
13	Repair of Bhawarna Jhunga Devi road portion Kehra to Jhunga Devi Km 15/00 to 26/150 (SH:- C/O R/wall at RD 26/100 to 26/120)	494122/-	9900/-	One month
14	Improvement, Widening & Strengthening of Jhamon to Jaisinghpur road Km. 8/0 to 18/300 (SH:- Supply and stacking of sign boards)	495700/-	10000/-	One month
15	Restoration of rain damages to various roads under Sub-Division Jaisinghpur (SH:- Hiring of JCB for rainy season 2023 in Jalag Section	495000/-	9900/-	One month
16	Restoration of rain damages to various roads under Sub-Division Jaisinghpur (SH:- Hiring of JCB for rainy season 2023 in Sari Section	495000/-	9900/-	One month
17	Restoration of rain damages to various roads under Sub-Division Jaisinghpur (SH:- Hiring of JCB for rainy season 2023 in Jaisinghpur Section	495000/-	9900/-	One month
18	Restoration of rain damages to various roads under Sub-Division Jaisinghpur (SH:- Hiring of JCB for rainy season 2023 in Balakrupi Section	440000/-	8800/-	One month
19	Restoration of rain damages on Alampur to Harsipattan road Km 0/00 to 26/00 (SH:- Hiring of Excavator cum Pock line (Tata Hitachi) for removal of slips between Km 0/00 to 26/00)	302400/-	6100/-	One month
20	Restoration of rain damages to Dharamshala Dadh Palampur Holta Chudhar sari Harsi sandhole road Km 0/00 to 90/00 (SH:- Improvement & widening between Km 77/600 to 77/720)	487810/-	9800/-	One month
21	Restoration of rain damages to Dagruhi Chandron Kachhera road Km 0/00 to 3/645 (SH:- Removal of Slips between Km 0/00 to 6/355)	336970/-	6800/-	One month
22	Restoration of rain damages on Tinbar to Jaisinghpur road Km 0/00 to 18/300 (SH:- C/O R/wall at RD 11/905 to 11/920)	376535/-	7600/-	Two month
23	Restoration of rain damages on Tinbar to Jaisinghpur road Km 0/00 to 18/300 (SH:- C/O R/wall at RD 12/754 to 12/755)	433085/-	8700/-	Two month
24	C/O Haroti pul to Jalet Bhatti via Nallian road Km 0/00 to 2/985) (SH:- C/O V-shape drain with edge wall at RD 1/950 to 2/100)	403960/-	8100/-	Two month
25	C/O Bhuana Ashapuri road Km 0/00 to 12/135 (SH:- P/L CC pavement between RD 10/325 to 10/445) (SCDP)	450031/-	9100/-	Two month
26	Restoration of rain damages to Panchrukhi Lambagoan road Km 0/00 to 22/00 (SH:- C/O R/wall at RD 12/937.50 to 12/945)	354187/-	7100/-	Two month
27	C/O Amb Nee Malli road Km 0/00 to 2/00 (SH:- Formation cutting between Km 1/480 to 1/645) (MNP)	484260/-	9700/-	Two month
28	C/O Andreta to Richards Bahroo via Naura road Km 0/00 to 1/250 (SH:- P/L CC pavement between RD 0/420 to 0/500 and U-shape drain at RD 0/215 to 0/300)	499651/-	10000/-	Two month
29	C/O Link road from Dhuupkiara to Mahasa basti via Saral Patt Km 0/00 to 1/750 (SH:- P/L WBM-I (90-45mm) between Km 0/700 to 1/750) (MNP)	455400/-	9200/-	Two month
30	C/O Link road to Village Kathla Km 080 to 0/300 (SH:- P/L 80mm Thick interlocking paver RD 0/0 to 0/075	382665/-	7700/-	Two month

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal ellisted in EPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.

4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur.

HIMSUCHANA AVAM & JAN SAMPARK (On behalf of Governor of Himachal Pradesh)

No. PW/JSD/TA/Tender/NIT/2023-24 - 6556-69

Dated: 04-09-2023

Copy to the following for information and necessary action:-

1. The Principal Secy. (PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief HPPWD, Shimla.
3. The Chief Engineer (KZ) HPPWD Dharamshala.
4. The Director, Information & Publications Department, H.P. Shimla.
5. The Executive Engineer (IT) Nigam Vihar Shimla-2 for information. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle: HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. All the S.E.s / E.E.s under North Zone.
9. The Sub Divisional Officer (C) Jaisinghpur
10. The Block Development office Lambaon
11. All the Assistant Engineer Under This Division.
12. The Drawing /Accounts Branch in this office.
13. The Contractors concerned.
14. Notice Board.

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur.



Office of

Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Work
Department Jaisinghpur 176095 Phone No. 01894-228030 Email ee-jaipwd-hp@gov.in

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS CALLED
VIDE THIS OFFICE LETTER No. PWD/JSD/TA/NIT/2023-24/- 6556-69 DATED 04.09.2023
ARE URGENT NATURE AND PUBLIC INTEREST

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of Rain damages to Bhuana Ashapuri road Km 0/00 to 12/100 (SH:- C/O Wire crate B/wall in slide Prone Area Km 0/615 to 0/630)

Estimated cost Rs.	265511.00
Earnest Money Rs.	5400.00
Time Limits	One month

S. N.	Description of Item	Quantity	Rate		Unit
			In Figures	In Word	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	47.25			Per cubic metre
2	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (hundred millimeters into hundred millimeters) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogram) each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In -Charge including carriage of materials within all leads and lifts and other incidental.The rate includes octroi, royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	86.40			Per cubic metre
					Total



Executive Engineer,
Jaisinghpur Division
H.P.P.W.D Jaisinghpur.

2

SCHEDULE OF QUANTITY


Name of work :- Restoration of Rain damages to Bhuana Ashapuri road Km 0/00 to 12/100 (SH:- C/O Wire crate B/wall in slide Prone Area Km 0/870 to 0/898)					Estimated cost Rs.		495621.00
					Earnest Money Rs.		10000.00
					Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	88.20			Per cubic metre		
2	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (hundred millimeters into hundred millimeters) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogram) each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In -Charge including carriage of materials within all leads and lifts and other incidental.The rate includes octroi, royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	161.28			Per cubic metre		
					Total		

Chand

Executive Engineer,
Jaisinghpur Division
JHP.PWD Jaisinghpur.

SCHEDULE OF QUANTITY


Name of work :- Restoration of rain damages to Panchrukhi Lambagaon road Km 0/00 to 22/100 (SH:- C/O Pusta for wire crate B/wall at RD I I/605 to 11/640)				Estimated cost Rs.		467775.00
				Earnest Money Rs.		9400.00
				Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	119.00			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete 1:4:8 (one cement is to four sand is to eight graded crushed stone aggregate 40 mm (forty millimeter) nominal size) and curing complete excluding the cost of form work in foundation and plinth as per specifications approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	105.00			Per cubic metre	
Total						


 Executive Engineer,
 Jaisinghpur Division
 PWD PWD Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages to Haler to Ropa .Guhan Rananagar Chatter (Dalu) Road road km 0/00 to 4/00 (SH:- C/O B/wall at RD 2/730 to 2/770)					Estimated cost Rs.		486219.00
					Earnest Money Rs.		9800.00
					Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual/mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, culvert, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	35.55			Per cubic metre		
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	31.55			Per cubic metre		

3	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification: section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand: ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	120.85		Per Cubic Metre
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	76.00		Each
				Total



Executive Engineer,
Jaishingpur Division
J.P.PWD Jaishingpur.

5

SCHEDULE OF QUANTITY

Name of work :-C/O Link road from main road HSTM to Old HSTM road Km 0/00 to 0/175 (SH:-C/O R/wall at RD 0/05 to 0/023) (Deposit)					Estimated cost Rs.		279854.00
					Earnest Money Rs.		5600.00
					Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	25.70			Per cubic metre		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge: as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	66.90			Per Cubic Metre		
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	13.89			Per cubic metre.		

4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	40.00			Each	
						Total




Executive Engineer,
Jaisinghpur Division
B.P.W.D Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :-Improvement of black spot on Tikker to Ridkal road Km 0/00 to 4/00 (SH:- P/F W Metal Beam Crash Barrier at RD 1/525 to 1/575)					Estimated cost Rs.	
					Earnest Money Rs.	
					Time Limits	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.32			Per cubic metre	222474.00
2	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishing and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty millimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	6.32			Per Cubic Metre	4500.00

3	Providing and erecting of "W" metal beam crash barrier comprising of 3mm (three millimetre) thick corrugated sheet metal beam rail, 70 cm (seventy centimetre) above road/ground level, fixed on ISMC series channel vertical post. 150x75x5 mm (one hundred fifty into seventy five into five millimetre) spaced 2 mtr.(two metre) center to center. 108 Mtr.(one hundred eight metre) high, 1.10Mtr.(one point ten metre) below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fitting confirm to IS: 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5 mm (one hundred fifty into seventy five into five millimetre) long complete clause 810 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	50.00			Per running metre
					Total



Executive Engineer,
Jaishingpur Division
BP PWD Jaishingpur.

SCHEDULE OF QUANTITY

Name of work :- C/O Tinbar to Lugat road Km 0/00 to 2/060 (SH:-C/O R/wall at RD 0/960 to 0/967) (MNP)

Estimated cost Rs. 176866.00
Earnest Money Rs. 3600.00
Time Limits One month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.71			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	42.91			Per Cubic Metre	
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	13.94			Per cubic metre.	

4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	10.00			Each	
					Total	

Om

Executive Engineer,
Jaisinghpur Division
H.P.PWD Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Ropri to Umber road Km 0/00 to 6/500 (SH:- C/O W/wall of 900 mm dia hume pipe culvert at Rd 0/255)				Estimated cost Rs.	
				Earnest Money Rs.	354,182.00
				Time Limits	7,100.00 One Month
S. N.	Description of Item	Quantity	Rate In Figures In Word	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30.87		Per cubic metre	
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	84.48		Per Cubic Metre	

4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	15.00			Each
5	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	32.70			Per cubic metre.
	G.Total				

Q. no. 1

Executive Engineer,
Jaishingpur Division,
P.W.D. Jaishingpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on link road to Village Rananagar Km 0/00 to 5/00 (SH:- C/O B/wall at RD 4/650 to 4/670 and edge wall with U-shape drain 4/870 to 4/920)					Estimated cost Rs.	
					Earnest Money Rs.	444,909.00
					Time Limits	8,900.00
						One Month
S. N.	Description of Item	Quantity	Rate In Figures	In Word	Unit	Amount
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual/mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 7.85 (seven decimal eight five) cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	157.00			Per Cubic Metre	
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	74.21			Per cubic metre	

3	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete. including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	52.50			Per Cubic Metre
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six: crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	39.75			Per cubic metre
5	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	50.00			Each
	G.Total				

Amir

Executive Engineer,
Jaishingpur Division,
H.P. PWD Jaishingpur

SCHEDULE OF QUANTITY

Name of work :-C/O Dharamshala Dadh Palampur Holta Chadhiar Sandhole road Km 0/00 to 90/00 (SH:- C/O Approaches of existing 3.00 mtr. Span RCC slab culvert at RD 46/630)					Estimated cost Rs.		492,370.00
					Earnest Money Rs.		9,900.00
					Time Limits		One Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	53.20			Per cubic metre		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1 : 5 : 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	118.20			Per Cubic Metre		
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	34.80			Per cubic metre.		

4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all levels, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	40.00			Each
G.Total					

(Signature)

Executive Engineer,
Jaisinghpur Division,
Jp PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages to Jangal to Oach Kallan Road Km 0/00 to 11/0 (SH:- P/F Steel Grating over culvert at RD 0/315 to 0/323, C/O U-shape drain with edge wall at RD 0/323 to 0/353 & U-shape drain at RD 0/353 to 0/455)						Estimated cost Rs.	444,749.00
						Earnest Money Rs.	8,900.00
						Time Limits	One Month
S. N.	Description of Item	Quantity	Rate In Figures	In Word	Unit	Amount	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	110.42			Per cubic metre		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	60.59			Per cubic metre		
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	29.00			Each		

4	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishing and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty millimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	6.88			Per Cubic Metre
5	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete and as per the direction of the Engineer-in-charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	643.32			Per Kilogram
G.Total					



Executive Engineer,
Jaisinghpur Division,
J.P. PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Improvement and widening of road from Panchrukhi Pahra road to Tatehal Majheen (via Thiakurwara) Km 0/00 to 1/800 (SH:- C/O R/wall at RD 1/456 to 1/470)					Estimated cost Rs.	
					Earnest Money Rs.	
					Time Limits	
					One Month	
S. N.	Description of Item	Quantity	Rate In Figures	In Word	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	38.74			Per cubic metre	
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	78.89			Per Cubic Metre	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax of other taxes imposed by the Government.	32.00			Each	

5	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	20.16		Per cubic metre.
6	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	54.93		Per cubic metre
G.Total				



Executive Engineer,
Jaisinghpur Division,
J.P. PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Repair of Bhawarna Jhunga Devi road portion Kehra to Jhunga Devi Km 15/00 to 26/150 (SH:-C/O R/wall at RD 26/100 to 26/120)					
				Estimated cost Rs.	494122.00
				Earnest Money Rs.	9900.00
				Time Limits	One month
S. N.	Description of Item	Quantity	Rate		Unit
			In Figures	In Word	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	58.99			Per cubic metre
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	119.48			Per Cubic Metre
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	22.42			Per cubic metre.

4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	46.00		Each	
				Total	

[Signature]

Executive Engineer,
Jaisinghpur Division
MP PWD Jaisinghpur


(19)

SCHEDULE OF QUANTITY

Name of work :- Improvement, Widening & Strengthening of Jhamon to Jaisinghpur road Km.8/0 to 18/300 (SH:- Supply and stacking of sign boards)					
			Estimated cost Rs.		495700.00
			Earnest Money Rs.		10000.00
			Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Amount
			In Figures	In Word	
1	Providing and erecting 5th Kilometre stone (precast) made of Reinforced cement concrete M-15 (M- fifteen) nominal mix 1:2.5:5 (one cement isto and half sand isto five crushed stone aggregate 40 mm (forty millimetre) nominal size and curing complete including cost of form work and reinforcement for reinforced cement concrete work as per the approved standard design, drawing, sign and size arrangement of letters including painting and lettering as per IRC-8 (eight) and IRC-26 (twenty six) complete as per MORD technical specification section 1700 and fixing at the site complete as per directions of Engineer - in- Charge including carriage of materials with in all leads, lifts and other incidental .The rate is including octroi, royalty, Malkana, toll tax GST or other taxes imposed by the Government.	2.00		Each	
2	Providing and erecting ordinary Kilometre stone (precast) made of Reinforced cement concrete M-15 (M- fifteen) of standard design as per IRC-8 including painting and printing etcetera complete as per drawing and MORD technical specification section 1700 or as per directions of Engineer - in- Charge including carriage of materials with in all leads, lifts and other incidental .The rate is including octroi, royalty, Malkana, toll tax GST or other taxes imposed by the Government.	9.00		Each	
3	Providing and erecting 200 mtr (two hundred metre) stone (precast) made of Reinforced cement concrete M-15 (M- fifteen) of standard design as per IRC-8 including painting and printing etcetera as per drawing and MORD technical specification section 1700 or as per directions of Engineer - in- Charge including carriage of materials with in all leads, lifts and other incidental .The rate is including octroi, royalty, Malkana, toll tax GST or other taxes imposed by the Government.	41.00		Each	

4	Providing and fixing of semi reflective cautionary, mandatory and informatory sign board 600 (six hundred) millimeter equilateral & triangle as per IRC:67 made of 1.5 mm (One decimal Five millimeter) thick MS sheet duly stove enamelled paint white colour in front and gray colour on back with red reflective border of 65 mm (Sixty Five millimeter) width and required letters and figures with reflective tape engineering grade required shade and colour supported and welded on 47mm x 47mm x 12 (Forty seven into forty seven into twelve) SWG sheet tube firmly fixed to the ground by means of properly designed foundations with M-15 grade cement concrete 450 x 450 x 600 mm. (Four Hundred Fifty into Four Hundred fifty into Six Hundred millimeter). 600 mm (six Hundred millimeter) below ground level as per drawing and MORD technical specification section 1700 as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	37.00		Each	
5	Providing and fixing Semi Reflective Traffic Signs Direction and place identification signs more than 0.90 sqm (Zero decimal nine zero square metre) size board as per IRC:67 made of 2mm (Two millimeter) thick M.S. Sheet duly stove enamelled paint white colour in front and gray colour on back with reflective border of 70mm (Seventy millimeter) width and required message, letters, figures with reflective engineering grade tape of required shade and colour. Supported and welded on 47mm x 47mm (Forty Seven into Forty seven millimeter) of 12 SWG Square tube of 3050 mm (three thousand fifty millimetre) height duly strengthened by 25mm x 5 mm (Twenty five into five millimeter) Mild Steel flat iron on edges on back firmly fixed to the ground by means of properly designed foundations with M-15 grade cement concrete 450 mm x 450mm x 600 mm (Four Hundred Fifty into Four Hundred fifty into Six Hundred millimeter), 600 mm (Six hundred millimeter) below ground level as per drawing and MORD technical specification section 1700 including hauling/ carriage of materials to various location through all modes of transportation within all leads, lifts and other incidental complete and as per direction of Engineer-In-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	11.00		Each	

6	Providing and fixing of typical NABARD informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm (one point six millimetre) thick, top and middle plate duly welded with MS flat iron 25mm x 5m (twenty five into five millimetre) size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 3mm. (twenty five into twenty five into five millimetre). The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm (seventy five into seventy five millimetre) of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, (four hundred fifty into four hundred fifty into six hundred millimetre) 600mm (six hundred millimetre) below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm (forty seven into forty seven millimetre) of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause and MORD technical specification section 1700 including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.00			Each
7	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement into three sand into six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	55.80			Per cubic metre
					Total


 Executive Engineer,
 Jaisinghpur Division
 JHP.PWD Jaisinghpur.

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages to various roads under Sub-Division Jaisinghpur (SH:- Hiring of JCB for rainy season 2023 in Jalag Section		Estimated Cost - Rs. 495000.00			
		Earnest Money - Rs.9900.00			
		Time - One Month			
		Quantity	Rate in		Unit
In Figures	In Word				
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	450.00		Per Hour	
				Total	



Executive Engineer,
Jaisinghpur Division,
J.P.P.W.D Jaisinghpur

DRAFT SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages to various roads under Sub-Division Jaisinghpur (SH:- Hiring of JCB for rainy season 2023 in Sari Section		Estimated Cost - Rs. 495000.00			
		Earnest Money - Rs. 9900.00			
		Time - One Month			
		Quantity	Rate in		Unit
In Figures	In Word				
So.No.	Description of Item	Quantity			
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	450.00		Per Hour	
					Total

[Signature]

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

DRAFT SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages to various roads under Sub-Division Jaisinghpur (SH:- Hiring of JCB for rainy season 2023 in Jaisinghpur Section)		Estimated Cost - Rs. 495000.00	
		Earnest Money - Rs.9900.00	
		Time - One Month	
So.No.	Description of Item	Rate in	
		In Figures	In Word
Quantity	Unit	Amount	
450.00	Per Hour		
Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis			
		Total	


 Executive Engineer,
 Jaisinghpur Division,
 H.P.PWD Jaisinghpur

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITY						
Name of work :- Restoration of rain damages to various roads under Sub-Division Jaisinghpur (SH:- Hiring of JCB for rainy season 2023 in Balakrupi Section)		Estimated Cost - Rs. 440000.00				
		Earnest Money - Rs.8800.00				
		Time - One Month				
So.No.	Description of Item	Quantity	Rate in		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	400.00			Per Hour	
					Total	

Qaid
 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

DRAFT SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Alampur to Harsipattan road Km 0/00 to 26/00 (SH:- Hiring of Excavator cum Pock lane (Tata Hitachi) for removal of slips between Km 0/00 to 26/00)		Estimated Cost - Rs. 302400.00				
		Earnest Money - Rs.6100.00				
		Time - One Month				
So.No.	Description of Item	Quantity	Rate in		Unit	Amount
		In Figures	In Word			
1	Hiring of JCB/ Excavator cum Pock lane (Tata Hitachi) for removal of slips, debris and boulders clear from road surface upto any height and depth in all in all kind and classification of soil including rocky portion and saturated soil and then disposal of all un-serviceable materials from the road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-Charge. The JCB/Excavator Cum Rock lane (Tata Hitachi) should minimum 8.00 hours from 9.00 to 5.00 PM daily and excavate at least 100 cum quantity of earth/slips per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the Excavator Cum Pock lane (Tata Hitachi) owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per hour basis	108.00			Per Hour	
					Total	

(Signature)

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages to Dharamshala Dadh Palampur Holta Chadhiar sari Harsi sandhole road Km 0/00 to 90/00 (SH:- Improvement & widening between Km77/600 to 77/720)					Estimated cost Rs.	487810.00
					Earnest Money Rs.	9800.00
					Time Limits	One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 128.29 (one hundred twenty eight decimal two nine) cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1749.30			Per cubic metre	
Total						

Chand

Executive Engineer,
Jaishingpur Division
JHP.PWD Jaishingpur.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages to Dagruhi Chandron Kachhera road Km 0/00 to 3/645(SH:- Removal of Slips between Km 0/00 to 6/355)

Name of work :- Restoration of rain damages to Dagruhi Chandron Kachhera road Km 0/00 to 3/645(SH:- Removal of Slips between Km 0/00 to 6/355)							Estimated cost Rs.		336970.00
							Earnest Money Rs.		6800.00
							Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount			
			In Figures	In Word					
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000 metre as per technical specification 302.3.5 and 1611 (One hours hiring will be justified after removal of 25 cubic metre quantity of disposed material) as per drawing as per the direction of Engineer-in-Charge within all lifts and other lifts and other incidentals. The rate includes octroi,royalty,Malkana, Tol tax, GST or any other taxes imposed by the Government.	3149.25			Per cubic metre.				
						Total			

(Signature)

Executive Engineer,
Jaishingpur Division
HP, PWD Jaishingpur.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Tinbar to Jaisinghpur road Km 0/00 to 18/300 (SH:- C/O R/wall at RD 11/905 to 11/920)					Estimated cost Rs.		376535.00
					Earnest Money Rs.		7600.00
					Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	42.48			Per cubic metre		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	91.71			Per Cubic Metre		
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	15.66			Per cubic metre.		

4	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals . The rate is including octroi, royalty, Malkana, toll tax. GST or other taxes imposed by the Government.	14.49			Per cubic metre
5	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge . The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	36.00			Each
					Total



Executive Engineer,
Jaisinghpur Division
D.P.P.WD Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Tinbar to Jaisinghpur road Km 0/00 to 18/300 (SH:- C/O R/wall at RD 12/754 to 12/755)						Estimated cost Rs.	
						Earnest Money Rs.	
						Time Limits	
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30.24			Per cubic metre		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1 : 5 : 10 (one cement; five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	104.34			Per Cubic Metre		
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	21.78			Per cubic metre.		

4	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	24.78			Per cubic metre
5	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	30.00			Each
					Total



Executive Engineer,
Jaisinghpur Division
JHP PWD Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :- C/O Haroti pul to Jalet Bhatti via Nallian road Km 0/00 to 2/985 (SH:- C/O V-shape drain with edge wall at RD 1/950 to 2/100)					Estimated cost Rs.	
					Earnest Money Rs.	
					Time Limits	
S. N.	Description of Item	Quantity	In Figures	In Word	Unit	
					Rate	Amount
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual/mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of unuseful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	54.00			Per cubic metre	
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.94			Per cubic metre	

3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	73.05			Per cubic metre
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	120.00			Each
					Total

Am

Executive Engineer,
Jaishingpur Division
J.P.W.D Jaishingpur.

SCHEDULE OF QUANTITY

Name of work :-C/O Bhuana Ashapuri road Km 0/00 to 12/135 (SH:- P/L CC pavement between RD 10/325 to 10/445) (SCDP)					Estimated cost Rs.		450031.00
					Earnest Money Rs.		9100.00
					Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	28.82			Per cubic metre		
2	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishing and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty millimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	57.65			Per Cubic Metre		

3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	8.10			Per cubic metre
					Total

[Signature]

Executive Engineer,
Jaisinghpur Division
HP.PWD Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages to Panchrukhi Lambagoan road Km 0/00 to 22/00 (SH:- C/O R/wall at RD 12937.50 to 12/945)					Estimated cost Rs.	
					Earnest Money Rs.	
					Time Limits	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	43.88			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	85.73			Per Cubic Metre	
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	11.25			Per cubic metre.	

4	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.50			Per cubic metre
5	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	37.00			Each
					Total

Chand

Executive Engineer,
Jaisinghpur Division
MP, PWD Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :- C/O Amb Nee Malli road Km 0/00 to 2/00 (SH:- Formation cutting between Km 1/480 to 1/645)				Estimated cost Rs.		484260.00
(MNP)				Earnest Money Rs.		9700.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	In Figures	Rate In Word	Unit	Amount
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual/mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 98.82 (ninety eight decimal eight two) cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1976.57			Per cubic metre	
					Total	


 Executive Engineer,
 Jaisinghpur Division
 HP.PWD Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :- C/O Andreta to Richards Bahroo via Naura road Km 0/00 to 1/250 (SH:- P/L CC pavement between RD 0/420 to 0/500 and U-shape drain at RD 0/215 to 0/300)					Estimated cost Rs.	
					Earnest Money Rs.	
					Time Limits	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of slumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	69.30			Per cubic metre	
2	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K. N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	20.92			Per cubic metre	

3	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishing and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty millimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	41.85			Per Cubic Metre
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge . The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	37.13			Per cubic metre
					Total


(Signature)

Executive Engineer,
Jaisinghpur Division
JHP.PWD Jaisinghpur.

29

SCHEDULE OF QUANTITY

Name of work :- C/O Link road from Dhupkiara to Mahasa basti via Saral Patt Km 0/00 to 1/750 (SH:- P/L WBM)						Estimated cost Rs.	
I (90-45mm) between Km 0/700 to 1/750) (MNP)						Earnest Money Rs.	
						Time Limits	
S. N.	Description of Item	Quantity	Rate		Unit	One month	
			In Figures	In Word		Amount	
1	Preparation of sub grade by dressing to camber (Earth work for the cutting involved for Sub grade to be paid for separately depending upon the classification of soil completed as per HPPWD specifications including hauling of materials in all leads, lifts and other incidentals and as per the entire satisfaction and directions of Engineer-in-charge. The rate including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2462.25			Per square metre		
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub-grade completed as per HP.PWD specifications. The rate including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2462.25			Per square metre		
3	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, watering and screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	234.50			Per cubic metre		
					Total		


 Executive Engineer,
 Jaisinghpur Division
 HP.PWD Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :-C/O Link road to Village Kathla Km 0/00 to 0/300 (SH:- P/L 80 mm thick interlocking paver block RD 0/00 0/075)							Estimated cost Rs.	382665.00
							Earnest Money Rs.	7700.00
							Time Limits	One month
S. N.	Description of Item	Quantity	In Figures	Rate		Unit	Amount	
					In Word			
1	Providing and laying mechanically mixed and vibrated plain cement concrete 1:4:8 (one cement is to four sand is to eight graded crushed stone aggregate 40 mm (forty millimeter) nominal size) and curing complete excluding the cost of form work in foundation and plinth as per specifications approved drawing , design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	14.00				Per cubic metre		
2	Supplying and filling in plinth with sand under floors,including watering, ramming, consolidating and dressing complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	4.20				Per Cubic Metre		
3	Providing and laying 80 mm thick Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 80mm (eighty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	210.00				Per square metre		

4	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishing and reinforcement. All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty millimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	5.63		Per Cubic Metre	
				Total	


 Executive Engineer,
 Jaisinghpur Division
 NP.PWD Jaisinghpur.