



Office of
EXECUTIVE ENGINEER (KULLU DIVISION)
H.P. PUBLIC WORKS DEPARTMENT, KULLU-175101
FAX: 01902-222571, E.mail. ee-kul2-hp@ntc.in

No.PW/KD/TA/Tender/2023-2024-

12113-132

Dated:- 1-9-2023

To

The Executive Engineer, I.T. Cell,
Nigam Bihar Shimla-2.

Subject:- Publishing of Notice inviting tender.

Enclosed please find herewith copies of notice inviting tender for the up loading on department website 12.09.2023 as per notification issued by Secretary (PW) to the Govt. of HP Shimla vide letter No.PBW(S)A(3)1/2020 dated 16.07.2021. As per works mentioned in the Tender Notice is urgent nature of work in the public interest.

DA/As above.


**Executive Engineer,
Kullu Division,
HP. PWD, Kullu.**

Copy alongwith notice inviting tender is forwarded to the following for information and necessary action.

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, (MZ) HP.PWD, Mandi.
3. Superintending Engineer, 6th Circle HP.PWD, Kullu.
4. Supdt./DAO/HDM of this office.
5. Notice Board.

DA/Nil.


**Executive Engineer,
Kullu Division,
HP. PWD, Kullu.**

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

The Executive Engineer, Kullu Division HP.PWD, Kullu on behalf of the Government of Himachal Pradesh invites the **offline tender i.e. on percentage rates** for the following works from the eligible contractors/Firms registered with HP.PWD, department, so as to reach in the office as per time schedule given below:-

1	Date of receipt of application for tender form.		11.09.2023 upto 4:00 PM		
2	Date of issue/sale of tender form.		11.09.2023 upto 4:00 PM		
3	Date of receipt of tender.		12.09.2023 upto 10:30 AM		
4	Date of opening tender.		12.09.2023 upto 11:00 AM		
Sr. No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	2	3	4	5	6
1	Restoration of rain damages on Ruzak Shallang road Km. 0/0 to 7/0 (SH:- Hiring of JCB for the removal of slip/debris at various reaches in Km. 0/0 to 3/500) Job No.1.	1,63,617/-	3,300/-	One month	350/-
2	Restoration of rain damages on Ruzak Shallang road Km. 0/0 to 7/0 (SH:- Hiring of JCB for the removal of slip/debris at various reaches in Km. 3/500 to 7/00) Job No.2.	1,63,617/-	3,300/-	One month	350/-
3	RRD on Kharal Section road at Neoli, Gharan, Tharman/Shrougi Mour Larikot road (SH:- Removal of slips at various RDs).	4,94,208/-	10,000/-	Two months	350/-
4	Restoration of rain damages on Dohranallah to Barahar road Km. 0/0to 10/020 (SH:- C/O Breast wall at RD 0/880 to 0/900).	4,34,943/-	8,800/-	Two months	350/-
5	Restoration of rain damages on Dohranallah to Barahar road Km. 0/0 to 10/020 (SH:- C/O Retaining wall at RD 0/850 to 0/868).	4,83,826/-	9,800/-	Two months	350/-
6	Restoration of rain damages on Dohranallah to Barahar road Km. 0/0 to 10/020 (SH:- C/O Retaining wall at RD 0/868 to 0/886).	4,79,149/-	9,600/-	Two months	350/-
7	Restoration of rain damages on Dohranallah to Barahar road Km. 0/0 to 10/020 (SH:- C/O Crated Breast Wall at RD 0/400 to 0/450).	4,99,270/-	10,000/-	Two months	350/-
8	Restoration of rain damages on Shat Jallugran road Km. 0/0 to 7/00 (SH:- C/O Retaining wall at Km. 4/960 to 4/967.50).	4,38,890/-	8,800/-	Two months	350/-
9	Restoration of rain damages on Dohranallah to Barahar road Km. 0/0 to 10/020 (SH:- Construction of breast wall at RD 0/375 to 0/400).	4,84,428/-	9,700/-	One month	350/-
10	Restoration of rain damages on Dohranallah to Kharihar road Km. 0/0 to 10/120 (SH:- Construction of retaining wall at RD 0/955 to 0/970).	4,87,280/-	9,800/-	Two months	350/-
11	Restoration of rain damages on Bharai Bagan Peej road Km. 0/00 to 7/820 (SH:- C/O R/wall at RD 1/910 to 1/917.50).	4,01,787/-	8,100/-	Two months	350/-
12	Restoration of rain damages on Bharai Bagan Peej road Km. 0/00 to 7/820 (SH:- C/O R/wall at RD 1/917.50 to 1/925).	4,02,107/-	8,100/-	Two months	350/-

E

13	RRD on Bhunter Manikaran road Km. 1/610 to 35/110 (SH:- Construction of Retaining wall at Rd 22/953.75 to 22/970).	4,83,525/-	9,800/-	Two months	350/-
14	RRD on Bhunter Manikaran road Km. 1/610 to 35/110 (SH:- Construction of retaining wall at RD 19/405 to 19/415).	4,97,648/-	10,000/-	Two months	350/-
15	RRD on Bhunter Manikaran road Km. 1/610 to 35/110 (SH:- Construction of retaining wall at RD 19/415 to 19/425).	4,99,630/-	10,000/-	Two months	350/-
16	RRD on Bhunter Manikaran road Km. 1/610 to 35/110 (SH:- Construction of retaining wall at RD 19/425 to 19/435).	4,99,743/-	10,000/-	Two months	350/-
17	RRD on Bhunter Manikaran road Km. 1/610 to 35/110 (SH:- Construction of retaining wall at RD 22/937.50 to 22/953.75).	4,93,530/-	10,000/-	Two months	350/-
18	RRD on Sharni Pinni road Km. 0/00 to 7/500 (SH:- Construction of wire crated B/wall at RD 1/980 to 1/998).	4,65,822/-	9,500/-	Two months	350/-
19	RRD on Bhunter Manikaran road Km. 1/610 to 35/110 (SH:- Construction of wire crated R/wall at RD 11/320 to 11/332).	3,02,868/-	6,200/-	Two months	350/-
20	RRD on Sarsari Chong road Km. 0/00 to 5/300 (SH:- Construction of pushta with wire crated retaining wall at RD 4/900 to 4/910).	4,78,665/-	9,600/-	Two months	350/-
21	Construction of Warehouse for the storage of EVMs and VVPATs at Dhalpur, Tehsil and District Kullu (H.P.) (SH:- Providing and fixing of Vertical Blind).	2,96,000/-	6,000/-	Two months	350/-
22	A/R and M/O CJM L&S residence at Gandhinagar (SH:- Painting distempering & P/I PVC flooring in rooms etc.).	2,85,009/-	5,800/-	Two months	350/-
23	Restoration of rain damages on Bharai Bagan Peej road Km. 0/00 to 7/820 (SH:- C/O R/wall at RD 2/917.50 to 2/925).	4,93,030/-	10,000/-	Two months	350/-
24	Restoration of rain damages on Bharai Bagan Peej road Km. 0/00 to 7/820 (SH:- C/O R/wall at RD 2/910 to 2/917.50).	4,93,801/-	10,000/-	Two months	350/-
25	Restoration of rain damages on Bharai Bagan Peej road Km. 0/00 to 7/820 (SH:- C/O R/wall at RD 1/843 to 1/853).	4,39,142/-	8,800/-	Two months	350/-
26	Restoration of rain damages on Bharai Bagan Peej road Km. 0/00 to 7/820 (SH:- C/O R/wall at RD 7/270 to 7/285).	2,91,498/-	6,000/-	Two months	350/-
27	Restoration of rain damages on Bharai Bagan Peej road Km. 0/00 to 7/820 (SH:- C/O R/wall at RD 4/520 to 4/530).	4,33,227/-	8,800/-	Two months	350/-
28	Restoration of rain damages on Bharai Bagan Peej road Km. 0/00 to 7/820 (SH:- C/O R/wall at RD 4/510 to 4/520).	4,33,678/-	8,800/-	Two months	350/-
29	Restoration of rain damages on Bharai Bagan Peej road Km. 0/00 to 7/820 (SH:- C/O R/wall at RD 3/910 to 3/935).	4,85,802/-	9,800/-	Two months	350/-
30	Restoration of rain damages on Bharai Bagan Peej road Km. 0/00 to 7/820 (SH:- C/O R/wall at RD 3/657.50 to 3/665).	4,74,515/-	9,600/-	Two months	350/-
31	Restoration of rain damages on Bharai Bagan Peej road Km. 0/00 to 7/820 (SH:- C/O R/wall at RD 3/650 to 3/657.50).	4,74,658/-	9,600/-	Two months	350/-

3

32	Restoration of rain damages on Bharai Bagan Peej road Km. 0/00 to 7/820 (SH:- C/O R/wall at RD 3/725 to 3/737).	4,81,661/-	9,800/-	Two months	350/-
33	Restoration of rain damages on various roads under Ruzak Section (SH:- Hiring of Excavator Cum Loader (JCB) for the removal of slips/debris/muck etc.).	1,63,617/-	3,400/-	Two months	350/-
34	Restoration of rain damages on Shat Jallugran road Km. 0/0 to 7/00 (SH:- C/O Retaining wall at RD 0/055 to 0/060).	4,94,918/-	10,000/-	Two months	350/-
35	Restoration of rain damages on Shat Jallugran road Km. 0/0 to 7/00 (SH:- C/O Retaining wall at RD 0/050 to 0/055).	4,95,377/-	10,000/-	Two months	350/-
36	Restoration of rain damages on Shat Jallugran road Km. 0/0 to 7/00 (SH:- C/O Retaining wall at RD 0/080 to 0/085).	4,96,457/-	10,000/-	Two months	350/-
37	Restoration of rain damages on Shat Jallugran road Km. 0/0 to 7/00 (SH:- C/O Retaining wall at RD 0/085 to 0/090).	4,94,150/-	10,000/-	Two months	350/-
38	Restoration of rain damages on Ratocha Dhara road Km. 0/00 to 5/0 (SH:- Construction of wire crated R/wall at RD 0/445 to 0/465).	4,86,431/-	9,900/-	Two months	350/-
39	Restoration of rain damages on Ratocha Dhara road Km. 0/00 to 5/0 (SH:- Construction of wire crated R/wall at RD 0/465 to 0/475).	2,43,311/-	5,000/-	Two months	350/-
40	Restoration of rain damages on Doghri Samana road Km. 0/00 to 3/165 (SH:- Hiring of Excavator cum loader (JCB) for the removal of slips/debris/muck etc.).	1,63,617/-	3,400/-	Two months	350/-
41	Restoration of rain damages on Darka to Bhumteer road Km. 0/00 to 6/800 (SH:- Hiring of Excavator cum loader (JCB) for the removal of slips/debris/muck etc.).	1,63,617/-	3,400/-	Two months	350/-
42	Restoration of rain damages on Kullu Karon road (SH:- Construction of wire crates at RD 2/835 to 2/846.25).	4,98,809/-	10,000/-	One month	350/-
43	Restoration of rain damages on Kullu Karon road (SH:- Construction of wire crates at RD 2/800 to 2/831.25 and 2/862.25 to 2/897.25).	4,94,359/-	9,900/-	One month	350/-
44	Restoration of rain damages on Nagujhour to Thach Mashna road Km. 0/00 to 10/500 (SH:- Hiring of Excavator cum loader (JCB) for the removal of slips/debris/muck etc.).	1,63,617/-	3,400/-	Two months	350/-
45	Restoration of rain damages on Chhurla to Kanipanth road at Km. 0/0 to 7/750 (SH:- Hiring of Excavator cum loader (JCB) for the removal of slips/debris/muck etc.).	1,63,617/-	3,400/-	Two months	350/-
46	Restoration of rain damages on Kullu Karon road (SH:- Construction of wire crates at RD 2/281.25 to 2/897.25).	4,93,633/-	9,900/-	One month	350/-
47	RRD on Bhunter Manikaran road Km. 1/610 to 35/100 (SH:- Providing and laying WEM G-I in the new alternate road (at 25/00) at RD 0/00 to 0/500).	4,99,685/-	10,000/-	Two months	350/-
48	RRD on Bhunter Manikaran road Km.1/610to 35/110 (SH:- Construction of Retaining wall between RD 11/030to 11/045).	3,69,266/-	7,500/-	Two months	350/-

49	RRD on Bhunter Manikaran road Km.1/610to 35/110 (SH:- Construction of Retaining wall between RD 14/260 to 14/270).	4,78,296/-	9,600/-	Two months	350/-
50	RRD on Bhunter Manikaran road Km.1/610to 35/110 (SH:- Construction of Retaining wall between RD 14/270 to 14/280).	4,80,278/-	9,700/-	Two months	350/-
51	RRD on Sainik Chowk Bhunter to Ramshilla road (SH:- C/O PCC R/wall on PCC pushta at RD 7/120 to 7/130).	4,98,375/-	10,000/-	Two months	350/-
52	RRD on Sainik Chowk Bhunter to Ramshilla road (SH:- C/O PCC R/wall on PCC pushta at RD 7/110 to 7/120).	4,89,654/-	9,900/-	Two months	350/-
53	RRD due to laying OFC by Airtel and Reliance Jio on Shamshi Seribehar road Km. 0/00 to 1/150 (SH:- C/O V-shape drain in Km. 0/100 to 1/150).	4,98,654/-	10,000/-	Two months	350/-
54	RRD on Dohranallah to Barahar road Km. 0/00 to 9/700 (SH:- Rapiar of pot hole at various RD (DE Deposti).	4,52,318/-	9,100/-	Two months	350/-

The tender documents shall be issued only to those contractor/firm who fulfill the following documents with the application.

1	The valid enlistment/Registration of contractor in Appropriate Class.
2	Permanent account No. (PAN No.).
3	G.S.T. No.
4	Earnest Money in the shape of National Saving certificate/time deposit account in the any of the post office in HP F.D.R. from any Nationalized Bank duly pleaded in favour of the Executive Engineer, Kullu Division HP.PWD, Kullu.
5	The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
6	The offer of the tender shall remain valid upto 90 days after the opening of tender.
7	Ambiguous/telephonic conditional tenders of tender by fax/E-mail not be considered and will be summarily be rejected.
8	Executive Engineer, reserve the right to reject or cancel any or all tenders without assigning any reasons.
9	If the date given above happens to be holiday the same shall be processed on next working day.
10	The contractor/firm must quote their rates in words as well as in figures failing which XEN reserve the right to accept/reject any or all tenders.
11	The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12	One contractor shall not have more than two major works in hand at a time.
13	Work should be completed by the contractor within stipulated period.
14	The rates beyond over +5% will be rejected, besides this the Additional Performance security will have to borne @ 20% & 30% for unbalanced bid in case rates is lower than 10% but upto 20% & lower than 20% upto 30% respectively. The tender beyond the limit of -30% will also be excepted.

**Executive Engineer,
Kullu Division,
HP.PWD, Kullu.**

Dated: 1-9-2023

No.PW/KD/TA/2023-2024- 12133-214

Copy is forwarded to the following for information and necessary action:-

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, (MZ) HP.PWD, Mandi.
3. Superintending Engineer, 6th Circle HP.PWD, Kullu.
4. All the Executive Engineers, in HP.PWD,.
5. All the Assistant Engineers, working under this Division.
6. All the registered contractors, in HP.PWD.
7. Supdt./DA/HDM of this office.
8. Notice Board.

**Executive Engineer,
Kullu Division,
HP.PWD, Kullu.**

CERTIFICATE

It is certified that the above works are required to be carried out immediately being emergent nature of work in the public interest.


**Executive Engineer,
Kullu Division, 
HP.PWD,  Kullu.**

Estimated cost:- 163617.00

Earnest money :- 3300.00

Time :- One month

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Road Shoulder road km 0/0 to 3/500 (Job -No-1)
(Sub Head :- Hiring of JCB for the removal of slip/debris at various reaches in KM 0/0 to 3/500)

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of J.C.B. / Excavator- cum- loader for removal of snow/ slips/debris / Muck, road side berms, Katcha drain and boulder in all kinds of soil including rocky portion and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine/ JCB should work 6 hours daily and remove at least 25.00 cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel /POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the/ record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 cubic metre per hour. The useful material shall be stacked along the road side as per direction of Engineer-in-charge.	125	1298.55	Rupees Seven hundred eighty seven and paise zero only.	Per Hour	163617.00
					Total:-	163617.00


Executive Engineer,
Kullu Division
HP.PWD Kullu

2

Estimated cost:- 163617.00
 Earnest money :- 3300.00
 Time :- One month.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Rupak Shollang road, km 9 to 7
 (Sub Head :- Hiring of JCB for the removal of slip/debris at various reaches in KM 3/500 to 7/00 (Job -No-2)

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of J.C.B. / Excavator- cum- loader for removal of snow/ slips/ debris / Muck, road side berms, Katcha drain and boulder in all kinds of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine/ JCB should work 6 hours daily and remove at least 25.00 cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel /POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the/ record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 cubic metre per hour. The useful material shall be stacked along the road side as per direction of Engineer-in-charge.	126	1238.55	Rupees Seven hundred eighty seven and paise zero only.	Per Hour	163617.00
					Total:-	163617.00

Executive Engineer,
 Kullu Division
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- RRD on KharaI Section road at Neoli, Gharan, Tharman/ Shrougi mour Larikot road
(SH:- Removal of slips at various RD's).

Estimated cost:- Rs. 4,94,208.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.50 m (One point fifty metre) and lead upto 1000 m (One thousand metre) a sper technical specification 302.5 and 1611 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	3950.50	125.10	Rupees One hundred twenty five and paisa ten only	Per cubic metre	494208.00
					Total	494208.00


Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Dohranallah to Barahar road Km. 0/0 to 10/020.
(SH:- C/O Breast wall at RD 0/880 to 0/900).

Estimated cost:- Rs. 4,34,943.00
Earnest money :- Rs. 8,800.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in ordinary rock by manual means requiring not blasting including cutting and trimming of side, slopes and disposal of excavated earth with a lift of 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all leads and lift of materials and as per direction of Engineer-in-charge.	146.60	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	33476.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	18.20	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	6649.00
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	48.96	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	257160.00
4	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	50.31	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only	Per cubic metre	137658.00
					Total	434943.00


Executive Engineer,
Kullu Division ,
HP.PWD,Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Dohranallah to Barahar road Km. 0/0 to 10/020 .
(SH:- C/O Retaining wall at RD 0/850 to 0/868).

Estimated cost:- Rs. 4,83,826.00
 Earnest money :- Rs. 9,800.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	61.20	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	22359.00
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:6:12 (One cement :Six sand : Twelve graded stone) for nominal mix 25 mm (Twenty five millimetre) aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	8.82	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	39771.00
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	32.40	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	170179.00
4	Providing and laying concrete for plain/enforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	12.96	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	64248.00
5	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	60.47	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only	Per cubic metre	165458.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	13.59	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	21811.00
					Total	483826.00


 Executive Engineer,
 Kullu Division ,
 HP.PWD, Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Dohranallah to Barahar road Km. 0/0 to 10/020 .
(SH:- C/O Retaining wall at RD 0/868 to 0/886).

Estimated cost:- Rs. 4,79,149.00
 Earnest money :- Rs. 9,600.00
 Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Rate in	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	56.70	365.35	Rupees Three hundred sixty five and paise thirty five only		Per cubic metre	20715.00
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:6:12 (One cement :Six sand : Twelve graded stone) for nominal mix 25 mm (Twenty five millimetre) aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	8.82	4509.15	Rupees Four thousand five hundred nine and paise fifteen only		Per cubic metre	39771.00
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	32.40	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only		Per cubic metre	170179.00
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	12.96	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only		Per cubic metre	64248.00
5	Construction of dry stone masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	60.47	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only		Per cubic metre	165458.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	11.70	1604.95	Rupees One thousand four and paise ninety five only		Per cubic metre	18778.00
						Total	479149.00

 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Dohranallah to Barahar road Km. 0/0 to 10/020.
(SH:- C/O crated Breast wall at RD 0/400 to 0/450).

Estimated cost:- Rs. 4,99,270.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Rate in	Unit	Amount
1	Excavation in hilly area in ordinary rock by manual means requiring not blasting including cutting and trimming of side, slopes and disposal of excavated earth with a lift of 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all leads and lift of materials and as per direction of Engineer-in-charge.	241.25	228.35	Rupees Two hundred twenty eight and paise thirty five only		Per cubic metre	55089.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	25.00	365.35	Rupees Three hundred sixty five and paise thirty five only		Per cubic metre	9134.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	156.25	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only		Per cubic metre	435047.00
						Total	499270.00

Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Shat Jallugran road Km. 0/0 to 7/00 .
(SH:- C/O Retaining wall at Km 4/960 to 4/967.50).

Estimated cost:- Rs. 4,38,890.00
Earnest money :- Rs. 8,800.00
Time :- Two months.

Sr. No.	Description of item	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 20 m (Twenty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil upto 3.00 m (Three metre) within all leads and lift of materials and as per direction of Engineer-in-charge.	47.85	365.35	Rupees Three hundred sixty five and paise thirty five only.	Per cubic metre	17482.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	140.63	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	391556.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	18.60	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	29852.00
					Total:-	438890.00


Executive Engineer,
Kullu Division ,
HP.PWD Kullu

Name of work :- Restoration of Rain damages on Dohranallah to Barahar road Km 0/0 to 10/020
Sub Head :- Const of Crated breast wall at Rd 0/375 to 0/400

Earnest Money 484428.00
Earnest Money 9700.00
Time One Month

Schedule of Quantity

S.N.	Description	Qty	Unit	Rate		Amount
				In Figure	In words	
1	Excavation in soil in hilly area by manual mean including cutting and trimming of sides, slopes and disposal of excavated earth with a lift up to 1.50 mtr and lead up to 20 mtr as per drawing and technical specification clause 1603.1.1	176.25	Per Cubic Metre	228.35	Rupees two hundred twenty eight and paise thirty five only	40247.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material up to a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil and as per direction of Engineer -In - Charge	25.00	Per Cubic Metre	365.35	Rupees three hundred sixty five and paise thirty five only	9134.00
3	Providing and laying boulder apron laid in wire crate with 4 mm dia wire confirming to IS 280 and 4826 in 150 x150 mm mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg each as per drawing and technical specification with in all leads and lift of material and as per direction of Engineer -In - Charge	156.25	Per Cubic Metre	2784.30	Rupees two thousand seven hundred eighty four and paise thirty only	435047.00
					Total	484428.00

 Executive Engineer
Kullu Division
HPPWD Kullu

Schedule of Quantity

Name of work :- Restoration of Rain damages on Dohranallah to Kharhar road Km 0/0 to 10/120

Sub Head :- Const of Retaining wall at Rd 0/955 to 0/970

Earnest Money ₹87280.00

Earnest Money 9800.00

Time two months

S.N.	Description	Qty	Unit	Rate		Amount
				In Figure	In words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material up to a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil and as per direction of Engineer -In - Charge	42.90	Per Cubic Metre	365.35	Rupees three hundred sixty five and paise thirty five only	15674.00
2	Providing and laying concrete for plain / reinforcement conc. In open foundation as per drawing and technical specification clause 802,503,1202, and 1203 PCC grade 1:6:12 (one cement : six sand : twelve graded stone aggregate)for nominal mix 40 mm(fourty millimetre) aggregate with in all leads and lift of material and as per direction of Engineer -In - Charge	5.70	Per Cubic Metre	4509.15	Rupees four thousand five hundred nine and paise fifteen only	25702.00
3	Providing and laying concrete for plain / reinforcement conc. In open foundation as per drawing and technical specification clause 802,503,1202, and 1203 PCC grade 1:4:8 (one cement : four sand : eight graded stone aggregate)for nominal mix 25 mm(Twenty five millimetre) aggregate with in all leads and lift of material and as per direction of Engineer -In - Charge	77.55	Per Cubic Metre	4957.40	Rupees four thousand nine hundred fifty seven and paise forty only	384446.00
5	Back filling behind abutment , wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 with granular material with in all leads and lift of material and as per direction of Engineer -In - Charge	23.70	Per Cubic Metre	1604.95	Rupees one thousand six hundred four and paise ninety five only	38037.00
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abulment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification	60	Each	390.35	Rupees three hundred ninety and paise thirty five only	23421.00
					Total	487280.00


 Estimating Engineer
 Works Division
 P.W.D. Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bharai Bagan Peej road Km 0/00 to 7/820.
(SH:- C/O Rwall at RD 1/910 to 1/917.50)

Estimated cost:- Rs. 4,01,787.00
Earnest money :- Rs. 8,100.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in- charge.	31.43	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	11483.00
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement : Four sand : Eight graded stone nominal size in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	20.25	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	100387.00
4	Providing and laying boulder apron laid in wire crate with 4 mm (Four millimetre) dia wire conforming to IS 280 and 4826 in 150 x 150 mm (One hundred fifty x One hundred fifty millimetre) mesh (Woven diagonally) including .10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 within all leads and lift of materials and as per direction of Engineer-in- charge.	93.75	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	261028.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	18.00	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	28889.00
					Total	401787.00

 **Executive Engineer,**
Kullu Division ,
HP.PWD Kullu

12 **SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages on Bharai Bagan Peej road Km 0/00 to 7/820 .
(SH:- C/O R/wall at RD 1/917.50 to 1/925)

Estimated cost:- Rs. 4,02,107.00
Earnest money :- Rs. 8,100.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in- charge.	28.35	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	10358.00
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement : Four sand : Eight graded stone nominal size in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	20.25	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	100387.00
4	Providing and laying boulder apron laid in wire crate with 4 mm (Four millimetre) dia wire confirming to IS 280 and 4826 in 150 x 150 mm (One hundred fifty x One hundred fifty millimetre) mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 within all leads and lift of materials and as per direction of Engineer-in- charge.	93.75	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	261028.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	18.90	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	30334.00
					Total	402107.00


Executive Engineer,
Kullu Division ,
HP.PWD Kullu

13

SCHEDULE OF QUANTITY

Name of work:- RRD on Bhunter Manikaran road Km 1/610 to 35/110.
(SH:- Construction of Retaining wall at RD 22/953.75 to 22/970).

Estimated cost:- Rs. 4,83,525.00
 Earnest money :- Rs. 9,800.00
 Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Rate in	Unit	Amount
1	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 20 m (Twenty metre) dressing of sides and bottom and back filling the excavated suitable soil upto 3.00 m (Three metre) depth material within all leads and lift of materials and as per direction of Engineer-in-charge.	58.99	365.35	Rupees Three hundred Sixty five and paise thirty five only.		Per cubic metre	21552.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 150mm x 150mm (One hundred fifty millimetre into One hundred fifty millimetre) mesh (woven diagonally) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg. (Twenty five kilogram) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge	152.34	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only		Per cubic metre	424160.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift of materials and as per direction of Engineer-in-charge.	23.56	1604.95	Rupees One thousand six hundred four and paise ninety five only		Per cubic metre	37813.00
						Total	483525.00


 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu

14

SCHEDULE OF QUANTITY

Name of work:- RRD on Bhunter Manikaran road Km 1/610 to 35/110 .
(SH:- Construction of Retaining wall at RD 19/405 to 19/415).

Estimated cost:- Rs. 4,97,648.00
Earnest money :- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 20 m (Twenty metre) dressing of sides and bottom and back filling the excavated suitable soil upto 3.00 m (Three metre) depth material within all leads and lift of materials and as per direction of Engineer-in- charge.	56.25	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	20551.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 150mm x 150mm (One hundred fifty millimetre into One hundred fifty millimetre) mesh (woven diagonally) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg. (Twenty five kilogram) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in- charge	156.25	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	435047.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material, within all leads and lift of materials and as per direction of Engineer-in- charge.	26.20	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	42050.00
					Total	497648.00


Executive Engineer,
Kullu Division ,
HP.PWD Kullu

15

SCHEDULE OF QUANTITY

Name of work:- RRD on Bhunter Manikaran road Km 1/610 to 35/110.
(SH:- Construction of Retaining wall at RD 19/415 to 19/425).

Estimated cost:- Rs. 4,99,630.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 20 m (Twenty metre) dressing of sides and bottom and back filling the excavated suitable soil upto 3.00 m (Three metre) depth material within all leads and lift of materials and as per direction of Engineer-in- charge.	59.70	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	21811.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 150mm x 150mm (One hundred fifty millimetre into One hundred fifty millimetre) mesh (woven diagonally) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg. (Twenty five kilogram) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in- charge	156.25	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	435047.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift of materials and as per direction of Engineer-in- charge.	26.65	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	42772.00
					Total	499630.00


Executive Engineer,
Kullu Division ,
HP.PWD Kullu

Name of work:- RRD on Bhunter Manikaran road Km 1/610 to 35/110.
(SH:- Construction of Retaining wall at RD 19/425 to 19/435).

SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,99,743.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Rate in	Unit	Amount
1	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 20 m (Twenty metre) dressing of sides and bottom and back filling the excavated suitable soil upto 3.00 m (Three metre) depth material within all leads and lift of materials and as per direction of Engineer-in-charge.	64.40	365.35	Rupees Three hundred Sixty five and paise thirty five only.		Per cubic metre	23529.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 150mm x 150mm (One hundred fifty millimetre into One hundred fifty millimetre) mesh (woven diagonally) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg. (Twenty five kilogram) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge	156.25	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only		Per cubic metre	435047.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift of materials and as per direction of Engineer-in-charge.	25.65	1604.95	Rupees One thousand six hundred four and paise ninety five only		Per cubic metre	41167.00
						Total	499743.00


Executive Engineer,
Kullu Division ,
HP.PWD Kullu

17

SCHEDULE OF QUANTITY

Name of work:- RRD on Bhunter Manikaran road Km 1/610 to 35/110.

Estimated cost:- Rs. 4,93,530.00
Earnest money :- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in	Unit	Amount
			Figure	Words	
1	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 20 m (Twenty metre) dressing of sides and bottom and back filling the excavated suitable soil upto 3.00 m (Three metre) depth material within all leads and lift of materials and as per direction of Engineer-in-charge.	53.87	365.35	Rupees Three hundred Sixty five and paise thirty five only.	19681.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 150mm x 150mm (One hundred fifty millimetre into One hundred fifty millimetre) mesh (woven diagonally) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg. (Twenty five kilogram) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge	152.34	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	424160.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift of materials and as per direction of Engineer-in-charge.	30.96	1604.95	Rupees One thousand six hundred four and paise ninety five only	49689.00
				Total	493530.00

Don't Schedule of Qty approved for Rs. 4,93,530/-


 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu

18

SCHEDULE OF QUANTITY

Name of work:- RRD on sarni Pinni road Km 0/00 to 7/500 .
(SH):- Construction of wire crated B/wall at RD 1/980 to 1/998).

Estimated cost:- Rs. 4,65,822.00
Earnest money :- Rs. 9,500.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in- charge.	341.37	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	77952.00
2	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 20 m (Twenty metre) dressing of sides and bottom and back filling the excavated suitable soil upto 3.00 m (Three metre) depth material within all leads and lift of materials and as per direction of Engineer-in- charge.	19.71	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	7201.00
3	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 150mm x 150mm (One hundred fifty millimetre into One hundred fifty millimetre) mesh (woven diagonally) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg. (Twenty five kilogram) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in- charge	136.72	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	380669.00
					Total	465822.00

 Executive Engineer,
Kullu-Division ,
HP.PWD,Kullu

19

SCHEDULE OF QUANTITY

Name of work:- RRD on Bhunter Manikaran road Km 1/610 to 35/110.
(SH):- Construction of wire crated B/wall at RD 11/320 to 11/332).

Estimated cost:- Rs. 3,02,868.00
Earnest money :- Rs. 6,200.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 20 m (Twenty metre) dressing of sides and bottom and back filling the excavated suitable soil upto 3.00 m (Three metre) depth material within all leads and lift of materials and as per direction of Engineer-in-charge.	27.00	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	9864.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 150mm x 150mm (One hundred fifty millimetre into One hundred fifty millimetre) mesh (woven diagonally) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg. (Twenty five kilogram) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge	97.66	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	271915.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift of materials and as per direction of Engineer-in-charge.	13.14	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	21089.00
					Total	302868.00

 Executive Engineer,
Kullu Division ,
HP.PWD Kullu

20

SCHEDULE OF QUANTITY

Name of work:- RRD on Sarsari Chong road Km 0/00 to 5/300.

Estimated cost:- Rs. 4,78,665.00

(SH):- Construction of pushta with wire crated Retaining wall at RD 4/900 to 4/910).

Earnest money :- Rs. 9,600.00

Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Rate in	Unit	Amount
1	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 20 m (Twenty metre) dressing of sides and bottom and back filling the excavated suitable soil upto 3.00 m (Three metre) depth material within all leads and lift of materials and as per direction of Engineer-in-charge.	50.00	365.35	Rupees Three hundred Sixty five and paise thirty five only.		Per cubic metre	18268.00
2	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 PCC grade 1:4:8 (One cement :Four sand : Eight graded stone aggregate) for nominal mix within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	25.60	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only		Per cubic metre	126909.00
3	Providing and laying boulder apron laid in wire crate with 4 mm (Four millimetre) dia wire conforming to IS 280 and 4826 in 150 x 150 mm (One hundred fifty x One hundred fifty millimetre) mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge.	109.37	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only		Per cubic metre	304519.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift of materials and as per direction of Engineer-in-charge.	18.05	1604.95	Rupees One thousand six hundred four and paise ninety five only		Per cubic metre	28969.00
						Total	478665.00



Executive Engineer,
Kullu Division ,
HP.PWD Kullu

21

SCHEDULE OF QUANTITY

Name of work:- Construction of Warehouse for the storage of EVMS and VVPATs at Dhalpur, Tehsil and District Kullu (H.P.) .
(SH:- Providing and fixing of Vertical Blind).

Estimated cost:- Rs. 2,96,000.00
 Earnest money :- Rs. 6,000.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing and fixing of vertical blind complete in all respect as per the direction entire specification of Engineer-in Charge, within all leads and lift of materials and as per direction of Engineer-in- charge.	1600.00	185.00	Rupees One hundred eighty five only.	Each	296000.00
					Total	296000.00


 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu

Estimated cost:- Rs. 2,85,009
Earnest money :- Rs. 5,800
Time :- Two months

SCHEDULE OF QUANTITY

Name of work:- A/R and M/O C/JM L&S residence at Gandhinagar.						
(SH:- Painting, distempering & p/l PVC flooring in rooms etc.						
Sr. No.	Description	Qty	Figure	Words	Unit	Amount
1	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm (One point four millimetre) in both directions with wire of dia 0.63 mm (Zero point sixty three millimetre) all complete With 2nd class teak wood beading 62X19 mm (Sixty two x Nineteen millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	3.78	3085.76	Rupees Three thousand eighty five and paise twenty six only.	Per Square metre	11684
2	Renewing glass panes and refixing existing wooden fillets: Float glass panes of nominal thickness 4 mm (Four millimetre) (weight not less than 10kg/sqm (Ten kilogram/ square metre)) with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.87	1160.10	Rupees One thousand one hundred sixty and paise ten only.	Per Square metre	2172
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	337.53	15.36	Rupees Fifteen and paise thirty six only.	Per Square metre	5184
4	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre (Fifty grams/ litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. 13.42.1 Two or more coats on new work Walls with in all leads and lift of materials and as per direction of Engineer-in-charge.	337.53	120.55	Rupees One hundred twenty and paise fifty five only.	Per Square metre	40689
5	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm (One point sixty seven litre/ Ten square metre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (Two point twenty kilogram/ Ten square metre)) with in all leads and lift of materials and as per direction of Engineer-in-charge.	222.06	123.05	Rupees One hundred twenty three and paise zero five only.	Per square metre	27324

6	Providing and applying white cement based putty of average thickness 1 mm (One millimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	118.13	103.40	Rupees One hundred three and paise forty only.	Per Square metre	12215
7	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (Zero point ninety litre/ Ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm (Zero point seventy five litre/ Ten square metre) of approved brand and manufacture with in all leads and lift of materials and as per direction of Engineer-in-charge.	183.18	106.20	Rupees One hundred six and paise twenty only.	Per square metre	19454
8	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (Zero point ninety litre/ Ten square metre) over an under coat of primer applied @ 0.80 ltr/10 sqm (Zero point eighty litre/ Ten square metre) of approved brand and manufacture with in all leads and lift of materials and as per direction of Engineer-in-charge	55.36	111.60	Rupees One hundred eleven and paise sixty only.	Per square metre	6178
9	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre (Ten litre) low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm (Forty millimetre) flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	9379.30	Rupees Nine thousand three hundred seventy nine and paise thirty only.	Each	9379
10	Providing and fixing wash basin with C.I. brackets, 15mm (Fifteen millimetre) dia CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required White Vitreous China Wash basin size 550x400 mm (Five hundred fifty x Four hundred millimetre) with a 15 mm (Fifteen millimetre) CP Brass single hole basin mixer with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	4685.97	Rupees Four thousand six hundred eighty five and paise ninety seven only.	Each	4686
11	Providing and fixing PTMT jet spray of approved quality and colour with one metre tube pipe with necessary fitting etc. complete within all leads and lifts and other incidentals including carriage of materials in all respect with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	990.12	Rupees Nine hundred ninety and paise twelve only	Each	1980

12	Providing and fixing CP soap Dish Holder having length of 138mm (One hundred thirty eight millimetre), breadth 102mm (One hundred two millimetre), height of 75mm (Seventy five millimetre) with concealed fitting arrangements, weighing not less than 106 gms (One hundred six grams) with in all leads and lift of materials and as per direction of Engineer-in-charge.	4.00	477.39	Rupees Four hundred seventy seven and paise thirty nine only	Each	1910
13	Providing and fixing C.P. towel ring trapezoidal shape 215 mm (Two hundred fifteen millimetre) long 200 mm (Two hundred millimetre) wide with minimum distances of 37 mm (Thirty seven millimetre) from wall face with concealed fittings arranged of approved quality and colour weighing not less than 88 gms (Eighty eight grams) with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	636.41	Rupees Six hundred thirty six and paise forty one only.	Each	1273
14	Providing and fixing 600x450 mm (Six hundred x Four hundred fifty millimetre) bevelled sdge mirror of superior glass (of approved quality) complete with 6 mm (Six millimetre) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	1520.94	Rupees One thousand five hundred twenty and paise ninety four only.	Each	1521
15	Providing and fixing 600x120x5 mm (Six hundred x One hundred twenty x Five millimetre) glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm (Forty millimetre) long screws, rawl plugs etc., complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	1138.23	Rupees One thousand one hundred thirty eight and paise twenty three only.	Each	2276
16	Providing and fixing C.P. brass and bib cock of approved quality conforming to IS:8931 15mm (Fifteen millimeter) nominal bore with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	937.14	Rupees Nine hundred thirty seven and paise fourteen only	Each	1874
17	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm (Fifteen millimeter) nominal bore with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	900.24	Rupees Nine hundred and paise twenty four only	Each	1800
18	Providing and fixing uplasticed PVC connection pipe with PTMT nuts, collar and bush of approved quality and colour 15 mm (Fifteen millimetre) nominal bore with 45 cm (Forty five centimetre) length with in all leads and lift of materials and as per direction of Engineer-in-charge.	6.00	183.15	Rupees One hundred eighty three and paise fifteen only	Each	1099
19	Providing and fixing C.P. Centre hole wash basin mixture of approved quality conforming to IS standards and weighing not less than 810 gms (Eight hundred ten grams) 15 mm (Fifteen millimetre) nominal bore with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	2500.00	Rupees Two thousand five hundred only	Each	5000

20	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	2038.15	Rupees Two thousand thirty eight and paise fifteen only.	Each	2038
21	Providing 2 mm (Two millimetre) thick PVC antistatic vinyl Flooring plain or coloured, carbed or mosaic/metallised finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for seperately with in all leads and lift of materials and as per direction of Engineer-in-charge.	78.85	1588.90	Rupees One thousand five hundred eighty eight and paise ninety only.	Per Square metre	125292
	Total					285009


 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu

23

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bharai Bagan Peej road Km 0/00 to 7/820 .
(SH:- C/O R/wall at RD 2/917.50 to 2/925)

Estimated cost:- Rs. 4,93,030.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Rate in	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in- charge.	33.37	365.35	Rupees Three hundred Sixty five and paise thirty five only.		Per cubic metre	12192.00
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement : Four sand : Eight graded stone nominal size in open foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	20.25	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only		Per cubic metre	100387.00
4	Providing and laying boulder apron laid in wire crate with 4 mm (Four millimetre) dia wire conforming to IS 280 and 4826 in 150 x 150 mm (One hundred fifty x One hundred fifty millimetre) mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 within all leads and lift of materials and as per direction of Engineer-in- charge.	128.86	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only		Per cubic metre	358785.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	13.50	1604.95	Rupees One thousand six hundred four and paise ninety five only.		Per cubic metre	21666.00
						Total	493030.00


Executive Engineer,
Kullu Division ,
HP.PWD Kullu

24

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bharai Bagan Peej road Km 0/00 to 7/820 .
(SH:- C/O R/wall at RD 2/910 to 2/917.50)

Estimated cost:- Rs. 4,93,801.00
 Earnest money :- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in- charge.	35.48	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	12963.00
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement : Four sand : Eight graded stone nominal size in open foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	20.25	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	100387.00
4	Providing and laying boulder apron laid in wire crate with 4 mm (Four millimetre) dia wire conforming to IS 280 and 4826 in 150 x 150 mm (One hundred fifty x One hundred fifty millimetre) mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 within all leads and lift of materials and as per direction of Engineer-in- charge.	128.86	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	358785.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	13.50	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	21666.00
					Total	493801.00


Executive Engineer,
 Kullu Division ,
 HP.PWD, Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bharai Bagan Peej road Km 0/00 to 7/820 .
(SH:- Construction of Retaining wall at RD 1/843 to 1/853).

Estimated cost:- Rs. 4,39,142.00
 Earnest money :- Rs. 8,800.00
 Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	21.00	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	7672.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	27.00	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	133850.00
3	Providing and laying boulder apron laid in wire crate with 4 mm (Four millimetre) dia wire conforming to IS 280 and 4826 in 150 x 150 mm (One hundred fifty x One hundred fifty millimetre) mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge.	93.75	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	261028.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	22.80	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	36592.00
					Total	439142.00


 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bharai Bagan Peej road Km 0/00 to 7/820 .
(SH:- Construction of Retaining wall at RD 7/270 to 7/285).

Estimated cost:- Rs. 2,91,498.00
Earnest money :- Rs. 6,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in- charge.	28.05	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	10248.00
2	Providing and laying boulder apron laid in wire crate with 4 mm (Four millimetre) dia wire conforming to IS 280 and 4826 in 150 x 150 mm (One hundred fifty x One hundred fifty millimetre) mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge.	93.75	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	261028.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	12.60	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	20222.00
					Total	291498.00


Executive Engineer,
Kullu Division ,
HP.PWD,Kullu

27 **SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages on Bharaj Bagan Peej road Km 0/00 to 7/820 .
(SH):- Construction of Retaining wall at RD 4/52C to 4/530).

Estimated cost:- Rs. 4,33,227.00
 Earnest money :- Rs. 8,800.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in- charge.	33.80	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	12349.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) within all leads and lift of materials and as per direction of Engineer-in-charge.	27.00	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	133850.00
3	Providing and laying boulder apron laid in wire crate with 4 mm (Four millimetre) dia wire conforming to IS 280 and 4826 in 150 x 150 mm (One hundred fifty x One hundred fifty millimetre) mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge.	93.75	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	261028.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	16.20	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	26000.00
					Total	433227.00

[Signature]
 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bharai Bagan Peej road Km 0/00 to 7/820 .
(SH:- Construction of Retaining wall at RD 4/510 to 4/520).

Estimated cost:- Rs. 4,33,678.00
 Earnest money :- Rs. 8,800.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in-charge.	32.40	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	11837.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) within all leads and lift of materials and as per direction of Engineer-in-charge.	27.00	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	133850.00
3	Providing and laying boulder apron laid in wire crate with 4 mm (Four millimetre) dia wire conforming to IS 280 and 4826 in 150 x 150 mm (One hundred fifty x One hundred fifty millimetre) mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge.	93.75	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	261028.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	16.80	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	26963.00
					Total	433678.00

Executive Engineer,
 Kullu Division ,
 HP.PWD,Kullu

29

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bharai Bagan Peej road Km 0/00 to 7/820 .
(SH:- Construction of Retaining wall at RD 3/910 to 3/935).

Estimated cost:- Rs. 4,85,802.00
 Earnest money :- Rs. 9,800.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead , dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in- charge.	46.75	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	17080.00
3	Providing and laying boulder apron laid in wire crate with 4 mm (Four millimetre) dia wire conforming to IS 280 and 4826 in 150 x 150 mm (One hundred fifty x One hundred fifty millimetre) mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 within all leads and lift of materials and as per direction of Engineer-in- charge.	156.24	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	435019.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	21.00	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	33703.00
					Total	485802.00


 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu


30

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bharai Bagan Peej road Km 0/00 to 7/820 .
(SH:- Construction of Retaining wall at RD 3/657.50 to 3/665).

Estimated cost:- Rs. 4,74,515.00
 Earnest money :- Rs. 9,600.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in-charge.	32.40	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	11837.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802.803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) within all leads and lift of materials and as per direction of Engineer-in-charge.	20.25	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	100387.00
3	Providing and laying boulder apron laid in wire crate with 4 mm (Four millimetre) dia wire confirming to IS 280 and 4826 in 150 x 150 mm (One hundred fifty x One hundred fifty millimetre) mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge.	117.15	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	326180.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	22.50	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	36111.00
					Total	474515.00


 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bharai Bagan Peej road Km 0/00 to 7/820 .
(SH:- Construction of Retaining wall at RD 3/650 to 3/657.50).

Estimated cost:- Rs. 4,74,658.00
 Earnest money :- Rs. 9,600.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in-charge.	52.56	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	19202.00
2	Providing and laying concrete for plain/ri/enforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) within all leads and lift of materials and as per direction of Engineer-in-charge.	20.25	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	100387.00
3	Providing and laying boulder apron laid in wire crate with 4 mm (Four millimetre) dia wire conforming to IS 280 and 4826 in 150 x 150 mm (One hundred fifty x One hundred fifty millimetre) mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge.	117.15	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	326180.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	18.00	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	28889.00
					Total	474658.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

32

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bharai Bagan Peej road Km 0/00 to 7/820 .
(SH:- Construction of Retaining wall at RD 3/725 to 3/737).

Estimated cost:- Rs. 4,81,661.00
 Earnest money :- Rs. 9,800.00
 Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	62.16	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	22710.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate nominal size in open foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	9.48	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	42746.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802.803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	5.65	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	28009.00
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	41.86	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	219867.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportatn within all leads and lift of materials and as per direction of Engineer-in- charge.	54.36	2735.20	Rupees Two thousand seven hundred thirty five and paise twenty only.	Per cubic metre	148685.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	12.24	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	19644.00
					Total	481661.00


 Executive Engineer,
 Kullu Division ,
 HP.PWQ Kullu

33

Estimated cost:- 1,63,617.00
 Earnest money :- 3,400.00
 Time :-Two months.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on various roads under Ruzak Section .
 (SH:- Hiring of Excavator cum loader (JCB) for the removal of slips/debris/muck etc.)

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Hiring of J.C.B. / Excavator- cum- loader for removal of slips/ debries / Muck, road side berms, Katcha drain and boulder in all kinds of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine/ JCB should work 6 hours daily and remove at least 25.00 cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel /POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the/ record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 cubic metre per hour . The useful material shall be stacked along the road side as per direction of Engineer-in-charge.	126	1298.55	Rupees One thousand two hundred ninety eight and paise fifty five only.	Per Hour	163617.00
					Total:-	163617.00

Assistant Engineer,
 Kullu Sub Division
 HP.PWD Kullu.

 Executive Engineer,
 Kullu Division
 HP.PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Shat Jallugran road Km. 0/0 to 7/00 .
(SH:- C/O Retaining wall at RD 0/055 to 0/060).

Estimated cost:- Rs. 4,94,918.00
 Earnest money :- Rs. 10,000.00
 Time :- Two months.

Sr. No.	Description of item	Qty	Figure	Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	33.40	365.35	Rupees Three hundred sixty five and paissa thirty five only.	Per cubic metre	12203.00
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in- charge.	60.00	5212.70	Rupees Five thousand two hundred twelve and paissa seventy only.	Per cubic metre	312762.00
3	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 150mm x 150mm (One hundred fifty millimetre x One hundred fifty millimetre) mesh (woven diagonally) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg. (Twenty five kilogram) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in- charge.	42.97	2784.30	Rupees Two thousand seven hundred eighty four and paissa thirty only.	Per cubic metre	119638.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	31.35	1604.95	Rupees One thousand six hundred four and paissa ninety five only.	Per cubic metre	50315.00
					Total:-	494918.00


 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Shat Jallugran road Km. 0/0 to 7/00 .
(SH):- C/O Retaining wall at RD 0/050 to 0/055).

Estimated cost:- Rs. 4,95,377.00
 Earnest money :- Rs. 10,000.00
 Time :- Two months.

Sr. No.	Description of item	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	33.00	365.35	Rupees Three hundred sixty five and paise thirty five only.	Per cubic metre	12057.00
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803,1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in- charge.	60.00	5212.70	Rupees Five thousand two hundred twelve and paise seventy only.	Per cubic metre	312762.00
3	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 150mm x 150mm (One hundred fifty millimetre x One hundred fifty millimetre) mesh (woven diagonally) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg. (Twenty five kilogram) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in- charge.	46.87	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only.	Per cubic metre	130514.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	24.95	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	40044.00
					Total:-	495377.00


 Executive Engineer,
 Kullu Division ,
 HP.PWD,Kullu

36

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Shat Jallugran road Km. 0/0 to 7/00 .
(SH:- C/O Retaining wall at RD 0/080 to 0/085).

Estimated cost:- Rs. 4,96,457.00
 Earnest money :- Rs. 10,000.00
 Time :- Two months.

Sr. No.	Description of item	Qty	Figure	Words	Rate in	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	305.1	365.35	Rupees Three hundred sixty five and paise thirty five only.		Per cubic metre	11655.00
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803,1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in- charge.	60.00	5212.70	Rupees Five thousand two hundred twelve and paise seventy only.		Per cubic metre	312762.00
3	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 150mm x 150mm (One hundred fifty millimetre x One hundred fifty millimetre) mesh (woven diagonally) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg. (Twenty five kilogram) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in- charge.	42.97	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only.		Per cubic metre	119638.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	32.65	1604.95	Rupees One thousand six hundred four and paise ninety five only.		Per cubic metre	52402.00
						Total:-	496457.00



Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Shat Jallugran road Km. 0/0 to 7/00 .
(SH:- C/O Retaining wall at RD 0/085 to 0/090).

Estimated cost:- Rs. 4,94,150.00
 Earnest money :- Rs. 10,000.00
 Time :- Two months.

Sr. No.	Description of item	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	35.25	365.35	Rupees Three hundred sixty five and paise thirty five only.	Per cubic metre	12879.00
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803,1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in- charge.	60.00	5212.70	Rupees Five thousand two hundred twelve and paise seventy only.	Per cubic metre	312762.00
3	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 150mm x 150mm (One hundred fifty millimetre x One hundred fifty millimetre) mesh (woven diagonally) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg. (Twenty five kilogram) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in- charge.	42.97	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only.	Per cubic metre	119638.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	30.45	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	48871.00
					Total:-	494150.00


 Executive Engineer,
 Kullu Division ,
 HP.PWD, Kullu

38

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Ratocha Dhara road Km 0/00 to 5/0 .
(SH:- Construction of wire crated R/wall at RD 0/445 to 0/465).

Estimated cost:- Rs. 4,86,431.00
 Earnest money :- Rs. 9,900.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation of foundation for structures as per drawing and technical specification including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 20 m (Twenty metre) dressing of sides and bottom and back filling the excavated suitable material within all leads and lift of materials and as per direction of Engineer-in-charge.	56.30	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	20569.00
3	Providing and laying boulder apron laid in wire crate with 4 mm (Four millimetre) dia wire conforming to IS 280 and 4826 in 150 x 150 mm (One hundred fifty x One hundred fifty millimetre) mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge.	156.25	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	435047.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	19.20	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	30815.00
					Total	486431.00

222
 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu

39

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Ratocha Dhara road Km 0/00 to 5/0 .
(SH:- Construction of wire crated R/wall at RD 0/465 to 0/475).

Estimated cost:- Rs. 2,43,311.00
Earnest money :- Rs. 5,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation of foundation for structures as per drawing and technical specification including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 20 m (Twenty metre) dressing of sides and bottom and back filling the excavated suitable material within all leads and lift of materials and as per direction of Engineer-in-charge.	25.30	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	9243.00
3	Providing and laying boulder apron laid in wire crate with 4 mm (Four millimetre) dia wire confirming to IS 280 and 4826 in 150 x 150 mm (One hundred fifty x One hundred fifty millimetre) mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge.	78.13	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	217537.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	10.30	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	16531.00
					Total	243311.00


Executive Engineer,
Kullu Division ,
HP.PWD Kullu

40

SCHEDULE OF QUANTITY

Estimated cost:- 1,63,617.00
Earnest money :- 3,400.00
Time :- Two months.

Name of work:- Restoration of rain damages on Doghri Samana road Km 0/00 to 3/165.
(SH:- Hiring of Excavator cum loader (JCB) for the removal of slips/debris/muck etc.)

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Hiring of J.C.B. / Excavator- cum- loader for removal of slips/ debris / Muck, road side berms, Katcha drain and boulder in all kinds of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine/ JCB should work 6 hours daily and remove at least 25.00 cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel /POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the/ record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 cubic metre per hour. The useful material shall be stacked along the road side as per direction of Engineer-in-charge.	126	1298.55	Rupees One thousand two hundred ninety eight and paise fifty five only.	Per Hour	163617.00
					Total:-	163617.00


Executive Engineer,
Kullu Division
HP.PWD Kullu.

41

Estimated cost:- 1,63,617.00
 Earnest money :- 3,400.00
 Time :- Two months.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Darka to Bhumteer road Km 0/00 to 6/800 .
(SH:- Hiring of Excavator cum loader (JCB) for the removal of slips/debris/muck etc.)

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Hiring of J.C.B. / Excavator- cum- loader for removal of slips/ debris / Muck, road side berms, Katcha drain and boulder in all kinds of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine/ JCB should work 6 hours daily and remove at least 25.00 cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel /POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the/ record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 cubic metre per hour . The useful material shall be stacked along the road side as per direction of Engineer-in-charge.	126	1298.55	Rupees One thousand two hundred ninety eight and paise fifty five only.	Per Hour	163617.00
					Total:-	163617.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu.

42

Schedule of Quantity

Name of work :- Restoration of Rain damages on Kullu Karon Road

Earnest Money 498809.00

Sub Head :- Const of wire crates at Rd 2/835 to 2/846.25

Earnest Money 130000.00

Time One month

S.N.	Description	Qty	Unit	Rate		Amount
				In Figure	In words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material up to a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil and as per direction of Engineer -In - Charge	18.22	Per Cubic Metre	365.35	Rupees three hundred sixty five and paise thirty five only	6657.00
2	Providing and laying boulder apron laid in wire crate with 4 mm dia wire confirming to IS 280 and 4826 in 100 x100 mm mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg each as per drawing and technical specification with in all leads and lift of material and and as per direction of Engineer -In - Charge	164.06	Per Cubic Metre	2884.30	Rupees two thousand seven hundred eighty four and paise thirty only	473198.00
3	Back filling behind abutment , wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 with granular material with in all leads and lift of material and and as per direction of Engineer -In - Charge	11.81	Per Cubic Metre	1604.95	Rupees one thousand six hundred four and paise ninety five only	18954.00
					Total	498809.00


 Executive Engineer
 Kullu Division
 HPPWD Kullu

43

Schedule of Quantity

Name of work :- Restoration of Rain damages on Kullu Karon Road

Earnest Money 494359.00

Sub Head :- Const of wire crates at Rd 2/800 to 2/831.25 and 2/862.25 to 2/897.25

Earnest Money 9900.00

Time One month

S.N.	Description	Qty	Unit	Rate		Amount
				In Figure	In words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material up to a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil and as per direction of Engineer -In - Charge	44.20	Per Cubic Metre	365.35	Rupees three hundred sixty five and paise thirty five only	16148.00
2	Providing and laying boulder apron laid in wire crate with 4 mm dia wire confirming to IS 280 and 4826 in 100 x100 mm mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg each as per drawing and technical specification with in all leads and lift of material and as per direction of Engineer -In - Charge	160.15	Per Cubic Metre	2884.30	Rupees two thousand seven hundred eighty four and paise thirty only	461921.00
3	Back filling behind abutment , wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 with granular material with in all leads and lift of material and as per direction of Engineer -In - Charge	10.15	Per Cubic Metre	1604.95	Rupees one thousand six hundred four and paise ninety five only	16290.00
					Total	494359.00

Executive Engineer
Kullu Division
HPPWD Kullu

Estimated cost:- 1,63,617.00
Earnest money :- 3,400.00
Time :- Two months.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Nagujour to Thach Mashna road Km. 0/00 to 10/500.
(SH:- Hiring of Excavator cum loader (JCB) for the removal of slips/debris/muck etc.)

Sr. No.	Description	Qty	Rate in		Un't	Amount
			Figure	Words		
1	Hiring of J.C.B. / Excavator- cum- loader for removal of slips/ debris / Muck, road side berms, Katcha drain and boulder in all kinds of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine/ JCB should work 6 hours daily and remove at least 25.00 cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel /POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the/ record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 cubic metre per hour. The useful material shall be stacked along the road side as per direction of Engineer-in- charge.	126	1298.55	Rupees One thousand two hundred ninety eight and paise fifty five only.	Per Hour	163617.00
					Total:-	163617.00


Executive Engineer,
Kullu Division
HP.PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Chhurla to Kanipanth road at Km. 0/0 to 7/750 .
(SH):- Hiring of Excavator cum loader (JCB) for the removal of slips/debris/muck etc.)

Estimated cost:- 1,63,617.00
 Earnest money :- 3,400.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of J.C.B. / Excavator- cum- loader for removal of slips/ debris / Muck, road side berms, Katcha drain and boulder in all kinds of soil including rocky portion and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine/ JCB should work 6 hours daily and remove at least 25.00 cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel /POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the/ record entry, if may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 cubic metre per hour . The useful material shall be stacked along the road side as per direction of Engineer-in-charge.	126	1298.55	Rupees One thousand two hundred ninety eight and paise fifty five only.	Per Hour	163617.00
					Total:-	163617.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu.

46

Schedule of Quantity

Name of work :- Restoration of Rain damages on Kullu Karon Road
Sub Head :- Const of wire crates at Rd 2/281.25 to 2/897.25

Earnest Money 493633.00
Earnest Money 9900.00
Time One month

S.N.	Description	Qty	Unit	Rate		Amount
				In Figure	In words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out any dressing removal of stumps and other material up to a lead of 50.00 mtr dressing of sides and bottom and back filling in trenches with excavated material in ordinary soil and as per direction of Engineer -In - Charge	18.75	Per Cubic Metre	365.35	Rupees three hundred sixty five and paise thirty five only	6850.00
2	Providing and laying boulder apron laid in wire crate with 4 mm dia wire confirming to IS 280 and 4826 in 100 x100 mm mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg each as per drawing and technical specification with in all leads and lift of material and as per direction of Engineer -In - Charge	156.25	Per Cubic Metre	2884.30	Rupees two thousand seven hundred eighty four and paise thirty only	450672.00
3	Back filling behind abutment , wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 with granular material with in all leads and lift of material and as per direction of Engineer -In - Charge	22.50	Per Cubic Metre	1604.95	Rupees one thousand six hundred four and paise ninety five only	36111.00
					Total	493633.00

Draft Schedule of quantity approved for Rs 493633/-


Executive Engineer
Kullu Division
HPPWD Kullu

Estimated cost:- 4,99,685.00
Earnest money :- 10,000.00
Time :- Two months

SCHEDULE OF QUANTITY

Name of work:- RRD on Bhunter Maikaran road Km 1/610 to 35/100 .
(SH:- Providing and laying WBM G-I in the new alternate road (at 25/00) at RD 0/00 to 0/500)

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Supplying and stacking at site WBM G-I 90 mm (Ninety millimetre) to 45 mm (Forty five millimetre) size stone aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	214.25	488.75	Rupees Four hundred eighty eight and paise seventy five only	Per Cubic metre	104715.00
2	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening/ binding material to fill up interstices of coarse aggregate, watering and compacting to the required density within all leads and lift of materials and as per direction of Engineer-in-charge.	214.25	1843.50	Rupees One thousand eight hundred forty three and paise fifty only	Per Cubic metre	394970.00
					Total	499685.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

48 **SCHEDULE OF QUANTITY**

Name of work:- RRD on Bhuntar Manikaran road Km 1/610 to 35/110.
(SH:- Construction of Retaining wall between RD 11/030 to 11/045).

Estimated cost:- Rs. 3,69,266.00
Earnest money :- Rs. 7,500.00
Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Rate in	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	54.45	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre		19893.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 150mm x 150mm(One hundred fifty millimetre into One hundred fifty millimetre) mesh (woven diagonally) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg.(Twenty five kilogram) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in- charge	118.20	2660.45	Rupees Two thousand six hundred sixty and paise forty five only	Per cubic metre		314465.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	21.75	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre		34908.00
					Total		369266.00


Executive Engineer,
Kullu Division ,
HP.PWD, Kullu

49 **SCHEDULE OF QUANTITY**

Name of work:- RRD on Bhuntar Manikaran road Km 1/610 to 35/110.
(SH:- Construction of Retaining wall between RD 14/260 to 14/270).

Estimated cost:- Rs. 4,78,296.00
Earnest money :- Rs. 9,600.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	56.25	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	20551.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 150mm x 150mm(One hundred fifty millimetre into One hundred fifty millimetre) mesh (woven diagonally) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg.(Twenty five kilogram) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in- charge	156.25	2660.45	Rupees Two thousand six hundred sixty and paise forty five only	Per cubic metre	415695.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	26.20	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	42050.00
					Total	478296.00

 Executive Engineer,
Kullu Division ,
HP.PWD Kullu

SD

SCHEDULE OF QUANTITY

Name of work:- RRD on Bhuntar Manikaran road Km 1/610 to 35/110 .
(SH:- Construction of Retaining wall between RD 14/270 to 14/280).

Estimated cost:- Rs. 4,80,278.00
Earnest money :- Rs. 9,700.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	59.70	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	21811.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 150mm x 150mm(One hundred fifty millimetre into One hundred fifty millimetre) mesh (woven diagonally) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg.(Twenty five kilogram) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge	156.25	2660.45	Rupees Two thousand six hundred sixty and paise forty five only	Per cubic metre	415695.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	26.65	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	42772.00
					Total	480278.00

Executive Engineer,
Kullu Division ,
HP.PWD,Kullu

51 **SCHEDULE OF QUANTITY**

Name of work:- R.R.D on Sainik Chowk Bhuntar to Ramshilla road.
(SH:- C/O PCC Rwall on PCC pushta at RD 7/120 to 7/130).

Estimated cost:- Rs. 4,98,375.00
Earnest money :- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Rate in	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other material upto lead of 50 mtr (Fifty metre) dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	32.00	365.35	Rupees Three hundred Sixty five and paise thirty five only.		Per cubic metre	11691.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	88.90	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only		Per cubic metre	440713.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	14.05	1604.95	Rupees One thousand six hundred four and paise ninety five only.		Per cubic metre	22550.00
4	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	60	390.35	Rupees Three hundred ninety and paise thirty five only		Each	23421.00
						Total	498375.00

[Signature]
Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- R.R.D on Sainik Chowk Bhuntar to Ramshilla road.
(SH:- C/O PCC R/wall on PCC pushta at RD 7/110 to 7/120).

Estimated cost:- Rs. 4,89,654.00
Earnest money :- Rs. 9,900.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other material upto lead of 50 mtr (Fifty metre) dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	28.60	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	10449.00
2	Providing and laying concrete for plain/ri/enforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	87.10	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	431790.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	14.95	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	23994.00
4	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	60	390.35	Rupees Three hundred ninety and paise thirty five only	Each	23421.00
					Total	489654.00


Executive Engineer,
Kullu Division ,
HP.PWD Kullu

Estimated cost:- 4,98,654.00
Earnest money :- 10,000.00
Time :- Two months

SCHEDULE OF QUANTITY

Name of work:- RRD due to laying OFC by Airtel and Reliance Jio on Shamshi seribehear road Km 0/00 to 1/150. (SH:- C/o V-Shape drain in Km 0/100 to 1/150).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Construction of hill side drain in accordance with the requirement of specification ture to line and grade dimension and other particular as per drawing and technical clause 1608.1 within all leads and lift of materials and as per direction of Engineer-in-charge.	1050.00	434.50	Rupees Four hundred thirty four and paise fifty only	Per Cubic metre	456225.00
2	Providing and laying S&S centrifugally cast (spun) iron pipes (class L4) conforming to IS-1536:300 mm (Three hundred millimetre) dia within all leads and lift of materials and as per direction of Engineer-in-charge.	8.00	5303.70	Rupees Five thousand three hundred three and paise seventy only	Per Running metre	42429.00
					Total	498654.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- RRD on Dohranallah to Barahar road Km. 0/00 to 9/700 .
(SH:- Repair of Pot hole at various RD) (DC Deposit).

Estimated cost:- Rs. 4,52,318.00
 Earnest money :- Rs. 9,100.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing laying spreading and compacting stone aggregate of specific size to water bond macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 Kn in stages to proper grade and camber applying and brooming stone screening/ binding material to fill up the interstices of course aggregate watering and compacting to the required density Grading - III as per tech. specification clause 405 by manual means within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	7.68	3224.80	Rupees Three thousand two hundred twenty four and paise eighty only.	Per Cubic metre	24766.00
2	Providing and laying primer coat with bitumen emulsion SS-1 on prepared granular surface including cleaning of road and spraying of primer @0.70 to 1.00 Kg per sqm (Zero point seventy to One point zero Kilogram per square metre) using mechanical means as per technical specification within all leads and lift of materials and as per direction of Engineer-in-charge	102.35	55.05	Rupees Fifty five and paise zero five only	Per Square metre	5634.00
3	Repair to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2, 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-in-charge.	1073.31	393.10	Rupees Three hundred ninety three and paise ten only.	Per Cubic metre	421918.00
					Total	452318.00


 Executive Engineer,
 Kullu Division ,
 HP.PWD Kullu