

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Sealed item rate tender on form No. 6 & 8 are hereby invited by the **Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan** on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **29.09.2023** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **28.09.2023** up to **4:00 P.M.** and the application for issue of tender form shall be received on **27.09.2023** up to **12:00** noon. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. N.	Name of work	Estimated Cost	Earnest Money	Time limit
1.	Restoration of rain damages on link road from Massal to Sakra Basti Km 0/000 to 1/500 in Distt Kangra (HP) (SH:-Construction of retaining wall ain Km 0/295 to 0/310).	499725/-	10000/-	Two months
2.	Construction of New 120 Nos Girls Hostel in Dr R.P. Govt. Medical College at Tanda in Distt Kangra (HP) (Deposit work) (SH:-Balance work of stainless steel railing and other civil work etc;)	346766/-	6950/-	Two months
3.	Construction of Govt. Veterinary Hospital at Nagrota Bagwan in Distt Kangra (HP) Deposit work (SH:-Balance work of providing and fixing Aluminium grill and painting work etc;)	139394/-	2800/-	Two months
4.	Restoration of rain damages on Malan Ambari Kawari road Km 0/000 to 6/600 in Distt Kangra (HP) (SH:-Construction of U-shape drain in Km 6/180 to 6/280).	133817/-	2700/-	Two months
5.	Restoration of rain damages on link from Bandi Matiyari Km 0/000 to 3/600 in Distt Kangra (HP) (SH:-Providing wire crates protection in Km 3/150 to 3/200).	289992/-	6000/-	Two months
6.	Construction of link road from Mundla to Saini Colony road Km 0/000 to 0/270 in Distt Kangra (HP) (SH:-Providing and laying cement concrete pavement road in Km 0/000 to 0/100).	320025/-	6400/-	Two months
7.	Construction of link road from Ambari to Kawari Km 0/000 to 6/600 in Distt Kangra (HP) (SH:-Construction of 0.60 mtr span RCC slab culvert at RD 4/175 and C/O road side drain at RD 4/175 to 4/250).	209645/-	4200/-	Two months

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
3. If any of the date mentioned above happened \to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK

No.PW/NBD/TA/Tender/NIT/2023-24-

8033-62

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan
(On behalf of Governor of Himachal Pradesh)

Dated/ **14-9-2023**

Copy to the following for information and necessary action:-

1. The Principal Secy. (PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (KZ), HPPWD, Dharamshala.
4. The Director, Information & Publications Department, H.P. Shimla
5. The Executive Engineer (IT), Nigam Vihar Shimla 2 for information. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
7. The Principal, Dr. RPGMC, Tanda.
8. The Deputy Commissioner, Kangra at Dharamshala.
9. All the S.E.s/E.E.s under North Zone.
10. The Sub-Divisional Officer(C) Nagrota Bagwan.
11. The Block Development Office Nagrota Bagwan
12. All the Assistant Engineer under this Division.
13. The Drawing /Accounts Branch in this office.
14. The Contractors concerned.
15. Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

Schedule of Quantity

ESTIMATED COST: - ₹ 499725.00
 EARNEST MONEY :- ₹ 10000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Restoration of rain images on link road from Massal to Sakra Basti Km 0/000 to 1/500 in Distt. Kangra (H.P.).
SUB HEAD :- Construction of Retaining wall in Km 0/295 to 0/310

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	22.15 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (One Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (Forty millimetres) nominal size as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	126.45 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	52.50 Running metres			Per running metre	
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	14.28 Cubic metres			Per cubic metre	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagaria Bagwan.


SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 346766.00
 EARNEST MONEY :- ₹ 6950.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of New 120 Nos. Girls Hostel in Dr. R.P.Govt. Medical College at Tanda in Distt. Kangra (H.P.) (Deposit work).

SUB-HEAD :- Balance work of stainless steel railing and other civil work etc;

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing stainless steel Curtain Rods for pelmet grade 304, curtain rods 20mm dia, 1.00mm thick including brackets and necessary accessories etc; complete including carriage of materials within all leads lifts and other incidentals, and per as directed by the Engineer-in-Charge.	569.60 Running metres			Per cubic metre	
2	Providing and fixing stainless steel knock down railing of KICH AISI Grade 316 of 38mm (Thirty eight millimetres) diameters hand rail fixed on 10x50mm (Ten into Fifty millimetres) SS flats baluster (Design code DT 53-2-163) placed at 1200mm (One thousand two hundred millimetres) centre to centre along with 3(Three) numbers at the rate of 16mm (Sixteen millimetres) mid rails connected at the side of balustered with fixture . The balustered would be fixed on the floor with casted based plate minimum 6mm (Six millimetres) thickness based plates shall be consealed with suitable S.S.316 GRADE covered cap railing hight to be taken at the rate of 85cm (Eighty five centimetres) from floor level. within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge.	20.80 Running metres			Per running metre	
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete as directed by the Engineer-In-charge, including entire carriage of materials within all leads lifts and other incidentals.	1584.00 Kilogram			Per kilo gram	
TOTAL :-						


 Executive Engineer,
 H.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 139394.00
 EARNEST MONEY :- ₹ 2800.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Construction of Govt. Veterinary Hospital at Nagrota Bagwan in Distt. Kangra (H.P.). **DEPOSIT WORK.**

SUB-HEAD :- **Balance work of providing and fixing Aluminium grill and painting work etc;**

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer-in-charge (Only weight of grill to be measured for payment), as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	271.35 Kilo-grams			Per kilo-gram	
2	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	144.76 Square metres			Per square metre.	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST: - Rs. 133817.00
 EARNEST MONEY: - Rs. 2900.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Restoration of rain images on Malan Ambari Kawari road Km 0/000 to 6/600 in Distt. Kangra (H.P.)
SUB HEAD :- Construction of U-Shape drain in Km 6/180 to 6/280

S. No.	Description of items	Quantity	In fig.	Rate	Unit	Amount
			4	In words 5		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	3			6	7
		77.00			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	24.50			Per cubic metre	
		Cubic metres				
TOTAL :-						


 Executive Engineer,
 H.P.P. W.D., Division,
 Tanda at Nagroa Bagwan.

Schedule of Quantity

ESTIMATED COST: - ₹ 289992.00
 EARNEST MONEY :- ₹ 6000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Restoration of rain images on link road from Bandi Matiyari Km 0/000 to 3/600 in Distt. Kangra (H.P.)
SUB HEAD :- Providing wire crates protection in Km 3/150 to 3/200

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	28.50 Cubic metres			Per cubic metre	7
2	Providing & making Gabion structure with Mechanically Woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012, MORTH Clause 2500, of required size, Mesh Type 10x12 (D=100 mm with tolerance of $\pm 2\%$) Zinc coated, Mesh wire diameter 3.0 mm, mechanically edged/selvedged with partitions at every 1m interval and shall have minimum 10 numbers of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2mm, supplied @ 3% by weight of Gabion boxes, filled with boulders with least dimension of 200 mm, as per drawing, all complete as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals.	98.85 Cubic metres			Per cubic metre	
TOTAL :-						



 Executive Engineer,
 H.P.P.W.D., Division,
 Pinda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST: - Rs. 320025.00
 EARNEST MONEY :- Rs. 6400.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of link road from Mundla to Saini Colony road Km 0/0000 to 0/270 in Distt. Kangra (H.P.)
SUB HEAD :- Providing and laying cement concrete pavement road in Km 0/000 to 0/100

S. No.	Description of items	Quantity	In fig.	Rate	Unit	Amount
			4	In words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	3 8.30 Cubic metres		5	6 Per cubic metre	7
2	Providing, laying, spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimeter to forty five millimeter) Grading-II size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 including carriage of materials within all leads and lifts and other incidentals.	24.58 Cubic metres			Per Cubic metres	
3	Providing and laying concrete for plain reinforcement concrete in open foundation including the cost of centering and shuttering complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 PCC Grade (M-20) (M-twenty) nominal mix 1:2:4 (One cement: Two sand: Four graded/crushed stone aggregate) 40mm (Forty millimetres) thickness as per HPPWD technical specification and as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	47.62 Cubic metres			Per cubic metre	
TOTAL :-						



 Executive Engineer,
 H.P.P.W.D., Division,
 Panda at Nagrota Bagawan.

Schedule of Quantity

ESTIMATED COST: - ₹ 209645.00
 EARNEST MONEY :- ₹ 4200.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Construction of link road from Ambari to Kawari Km 0/000 to 6/600 in Distt. Kangra (H.P.).
SUB HEAD :- Construction of 0.60 mtr span RCC slab culvert at RD 4/175 and C/O road side drain at RD 4/175 to 4/250

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	3 76.80 Cubic metres	4	5	6 Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	29.25 Cubic metres			Per cubic metre	
3	Providing and laying concrete for plain reinforcement concrete in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 PCC Grade (M-20) (M-twenty) nominal mix 1:2:4 (One cement: Two sand: Four graded/crushed stone aggregate) 20mm (Twenty millimetres) thickness as per HPPWD technical specification and as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	1.80 Cubic metres			Per cubic metre	
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of materials within all leads, lifts and other incidentals.	419.17 Kilogram			Per kilo gram	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.