

**Himachal Pradesh
Public Works Department**

No.PW/NHPWD/GA/N.I.T./2023-24- **4456-68**
To


Dated:- **4/09/2023**

**The Executive Engineer, (IT Cell),
Nigam Vihar HP Shimla -2.**

Subject:- Publication of Tender Notice


Enclosed please find herewith the six copies of tender notice for the works as given in notice inviting tender for uploading on departmental website. The works mentioned in the tender notice are of urgent nature and in public interest being restoration of rain damages during monsoon season on various National Highways which has been blocked/hindered due heavy rains .

DA :- As above


Executive Engineer,
NH Division, HPPWD
Hamirpur.

Copy to The Superintending Engineer National Highway Circle HP.PWD.,
Shahpur for information please.

Copy to computer Cell O/O Executive Engineer, IT Cell Nigam Vihar Shimla -2 for
information and necessary action.


Executive Engineer,
NH Division, HPPWD
Hamirpur.

and competence of the contractor/ firm applying for issue of tenders shall be final. In case, of any information supplied by the contractor/ firm, is found false at any stage the tender is liable to be rejected and action taken against contractor/ firm.

- 4 Copy of Pan Card. It is certified that tender mentioned above are urgent nature and required early completion.

Executive Engineer,
NH Division, HPPWD
Hamirpur.

NO.PW-NHD-HMR-GA-TENDER/2023-24 4414-65
COPY FORWARDED TO THE FOLOWING for information please:

DATED: 04/9/2

- 1 The Engineer-in-Chief, HPPWD, Shimla-I
- 2 The Chief Engineer (NH), HPPWD, Shimla-I.
- 3 All the Superintending Engineer, NH /B&R in HP.
- 4 The Director of information and public relation ,HP Shimla
- 5 All the Executive Engineer, NH/B&R in HP.
- 6 All the Assistant Engineer, NH/B&R in HP.
- 7 Drawing Branch/ Account Branch/ Notice Board of this office.

Executive Engineer,
NH Division, HPPWD
Hamirpur.

**HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Governor of H.P by **Executive Engineer, NH Division, HPPWD, Hamirpur (H.P)** from the experienced contractor/ firms enlisted in appropriate class with HPPWD for the following works. The tender shall be received in this office on **08-09-2023** up to **11.00 A.M** and the same shall be opened on the same day at **11.30 A.M.** in the presence of Contractor/Firms or their authorized/representatives who wish to be present at the time of opening of tender. The application for issue of tender document shall be received on dated **06.09.2023** up to **12.30 P.M.** on cash payment (Non-Refundable) and tender document will be issued on **06.09.2023** up to **4:00 P.M.** If the office happens to be closed on the scheduled date the tender form document will be sold/ opened on the next working day at the same time and venue.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time	Cost of Tender Form
1	A/R & M/O on NH-20A(New NH-503) Nagrota Bagwan-Ranital-Mubarikpur road Km. 39/00 to 91/0 in the State of Himachal Pradesh (SH:- Repair of Patch/Pot holes in KM 39/0 to 55/0).	457332.00	9500.00	One Month	350/-
2	A/R & M/O on NH-20A(New NH-503) Nagrota Bagwan-Ranital-Mubarikpur road Km. 39/00 to 91/0 in the State of Himachal Pradesh (SH:- Repair of Patch/Pot holes in KM 55/0 to 75/0).	480487.00	9500.00	One Month	350/-
3	A/R & M/O on NH-20A(New NH-503) Nagrota Bagwan-Ranital-Mubarikpur road Km. 39/00 to 91/0 in the State of Himachal Pradesh (SH:- Repair of Patch/Pot holes in KM 76/0 to 91/0).	474441.00	9500.00	One Month	350/-
4	Restoration of rain damage due to heavy rain to the existing kalruhi khad bridge on NH - 70 (New NH- 03) km 58/400 to 114/00. (SH:- Providing Projection layer M-20 to protect the down stream of bridge scoured during disaster in H.P during August Month in km. 72/684 to 72/711 (RHS).	499487.00	10000.00	One Month	350/-
5	Restoration of rain damage due to heavy rain to the existing kalruhi khad bridge on NH - 70 (New NH- 03) km 58/400 to 114/00. (SH:- Providing Projection layer M-20 to protect the down stream of bridge scoured during disaster in H.P during August Month in km. 72/711 to 72/738 (RHS).	499487.00	10000.00	One Month	350/-

Draft notice inviting/ specification special conditions can be seen in this office on any working day between 11:00 AM to 4:00 PM ambiguous/ Telegraphic conditional tenders by fax shall not be entertained/ considered in any case. The contractors/ firms are requested to insert the rate of each item in words as well as in figure, failing which Executive Engineer, reserves the right to accept/ reject any or all tenders. The intending contractors/ firms are requested to see the site of work before submitting the tenders. All the application must accompany with the Earnest Money in the shape of call at deposit/ N.S.C. purchased from any post office in H.P/FDR from any nationalized bank duly pledged in favour of Executive Engineer. The application without earnest money will not be entertained and out rightly rejected.

CONDITIONS: – The following document are required to be attached with the application: -

- 1 A copy of valid enlistment and renewal certificate.
- 2 A copy of GST.3.A copy of EPF
- 3 Any other information as desired by the Executive Engineer. Any application not accompanied by above documents shall not be entertained. The tender shall be issued to those contractors/ firms who are found eligible, suitable and competent. The decision of the Executive Engineer, regarding suitability, eligibility

DNIT/SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 457332.00
Earnest Money:- Rs. 9500.00
Time: - One Month

Name of work :- A/R & M/O on NH-20A(New NH-503) Nagrota Bagwan-Ranital-Mubarikpur road Km. 39/00 to 91/0 in the State of Himachal Pradesh (SH: -Repair of Patch/Pot holes in KM 39/0 to 55.0).

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with paver in sub base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density. By manual means (In area of thorny jungle) including carriage of material in all leads and lifts and as per direction of the Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	9.48	1900.00	Rupees one thousand nine hundred and paise nil only	Per Cubic meter	18012.00
2	Providing and applying prime coat with Bitumen emulsion (SS-1) on prepared surface of granular Base including clearing of road surface and spraying primer at the rate of 0.60 kg/sqm using mechanical means including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	361.43	38.60	Rupees Thirty eight and paise six only	Per square meter	13951.20
3	Clearing and preparing surface and providing & applying the tack coat with bitumen emulsion RS-1 Grade conforming to using emulsion pressure distributor at the rate of 0.25 kg/sqm on prepared surface cleaned with mechanically brooms as per MORTH Specifications (5th revision) .The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	542.15	18.00	Rupees eighteen and paise nil only	Per square meter	9758.70
4	Providing and laying 40mm thick (forty millimetre) bituminous concrete with 60-90 (sixty- ninety) TPH batch type hot mix plant producing an average output of 75 tonne per hour using crushed stone aggregates of specified grading-II, premixed with modified bituminous VG-40 Bulk (Refinery blended)@ 5.4% (Five point four percent) minimum by weight of total mix material and filler, as per job mix formula transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment , rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRT&H specification Item to include all materials, labour, machinery/equipments and incidental charges required to complete the job including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	36.14	11500.00	Rupees Eleven thousand five hundred and paise nil only	Per Cubic meter	415610.00
G. Total						457332.00

Draft Schedule of Quantity Checked and Approved for Rs :-457332- only
(Rupees four lac fifty seven thousand three hundred thirty two only)

Condition

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure cement/steel at their own level from Civil Supply Depott. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

Executive Engineer,
National Highway Division,
H.P.P.W.D., Hamirpur (HP)

DNIT/ SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 480487.00
 Earnest Money:- Rs. 9500.00
 Time:- One Month

Name of work :- A/R & M/O on NH-20A(New NH-503) Nagrota Bagwan-Ranital-Mubarikpur road Km. 39/00 to 91/0 in the State of Himachal Pradesh (SH: -Repair of Patch/Pot holes in KM 55/0 to 75/0).

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with paver in sub base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density. By manual means (In area of thorny jungle) including carriage of material in all leads and lifts and as per direction of the Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	9.96	1900.00	Rupees one thousand nine hundred and paise nil only	Per Cubic meter	18924.00
2	Providing and applying prime coat with Bitumen emulsion (SS-1) on prepared surface of granular Base including clearing of road surface and spraying primer at the rate of 0.60 kg/sqm using mechanical means including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	379.70	38.60	Rupees Thirty eight and paise six only	Per square meter	14656.42
3	Clearing and preparing surface and providing & applying the tack coat with bitumen emulsion RS-1 Grade conforming to using emulsion pressure distributor at the rate of 0.25 kg/sqm on prepared surface cleaned with mechanically brooms as per MORTH Specifications (5th revision) .The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	569.55	18.00	Rupees eighteen and paise nil only	Per square meter	10251.90
4	Providing and laying 40mm thick (forty millimetre) bituminous concrete with 60-90 (sixty- ninety) TPH batch type hot mix plant producing an average output of 75 tonne per hour using crushed stone aggregates of specified grading-II, premixed with modified bituminous VG-40 Bulk (Refinery blended)@ 5.4% (Five point four percent) minimum by weight of total mix material and filler, as per job mix formula transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment , rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRT&H specification Item to include all materials, labour, machinery/equipments and incidental charges required to complete the job.including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	37.97	11500.00	Rupees Eleven thousand five hundred and paise nil only	Per Cubic meter	436655.00
G. Total						480487.00

Draft Schedule of Quantity Checked and Approved for Rs :-480487/- only
 (Rupees four lac eighty thousand four hundred eighty seven only)

Condition

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure cement/steel at their own level from Civil Supply Depott. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.


 Executive Engineer,
 National Highway Division,
 H.P.P.W.D., Hamirpur (HP)

DNIT/SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 474441.00
Earnest Money:- Rs. 9500.00
Time:- One Month


Name of work :-A/R & M/O on NH-20A(New NH-503) Nagrota Bagwan-Ranital-Mubarikpur road Km. 39/00 to 91/0 in the State of Himachal Pradesh (SH: -Repair of Patch/Pot holes in KM 76/0 to 91/0).

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with paver in sub base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density. By manual means (In area of thorny jungle) including carriage of material in all leads and lifts and as per direction of the Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	6.65	1900.00	Rupees one thousand nine hundred and paise nil only	Per Cubic meter	12635.00
2	Providing and applying prime coat with Bitumen emulsion (SS-1) on prepaired surface of granular Base including clearing of road surface and spraying primer at the rate of 0.60 kg/sqm using mechanical means including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	379.90	38.60	Rupees Thirty eight and paise sixth only	Per square meter	14664.00
3	Clearing and preparing surface and providing & applying the tack coat with bitumen emulsion RS-1 Grade conforming to using emulsion pressure distributor at the rate of 0.25 kg/sqm on prepared surface cleaned with mechanically brooms as per MORTH Specifications (5th revision) .The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	569.85	18.00	Rupees eighteen and paise nil only	Per square meter	10257.00
4	Providing and laying 40mm thick (forty millimetre) bituminous concrete with 60-90 (sixty- ninety) TPH batch type hot mix plant producing an average output of 75 tonne per hour using crushed stone aggregates of specified grading-II, premixed with modified bituminous VG-40 Bulk (Refinery blended)@ 5.4% (Five point four percent) minimum by weight of total mix material and filler, as per job mix formula transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment , rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRT&H specification Item to include all materials, labour, machinery/equipments and incidental charges required to complete the job.including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	37.99	11500.00	Rupees Eleven thousand five hundred and paise nil only	Per Cubic meter	436885.00
G. Total						474441.00

**Draft Schedule of Quantity Checked and Approved for Rs :-474441- only
(Rupees four lac seventy four thousand four hundred forty one only)**

Condition

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure cement/steel at their own level from Civil Supply Depott. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill


Executive Engineer,
National Highway Division,
M.P.P.W.D., Hamirpur (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damage due to heavy rain to the existing Kalruhi Khad bridge on NH-70 (New NH-03) Km 58/400 to 114/0. (SH:- Providing Protection Layer M-20 to protect the downstream of bridge scoured during disaster in R.P. during August Month in Km. 72/684 to 72/711 (RHS)


Estimated Cost:-Rs. 499487
Earnest Money:- Rs.10000.00
Time Limit:- One Month

Sr. No.	Description of Items	Qty	Fig.	Rate in Words	Unit	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator/breaker)/manual means over areas exceeding 30 cm (Thirty centimetre) in depth 1.5 m (One point five metre) in width as well as 10 sqm (Ten square metre) on plan including getting out and disposal of excavated earth with in all leads and lifts in ordinary rock and all kinds of soil including chiseling of hard rocks where blasting is prohibited including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	28.35	190.00	Rupees One Hundred Ninety and Paise Zero Only	Per cubic metre	5387.00
2	Providing and laying cement concrete 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm (twenty millimetre) nominal size) in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etcetra up to floor five level, excluding the cost of centering, shuttering and finishing including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge, including all incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	91.50	5400.00	Rupees Five Thousand Four Hundred and Paise Zero Only	Per Cubic metre	494100.00
Total						499487.00

Condition

- The work will be strictly executed as per HPPWD specifications.
- The contractor will procure cement/steel at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary P.W.D. to the Govt. of H.P. vide No. P.W.D. B-1/17-2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- The bills of all materials procured by the contractor in form of mining materials used for execution of work must be submitted to the authority concerned along with contractor bill.

DRAFT SCHEDULE OF QUANTITY CHECKED AND APPROVED FOR Rs. 499487/-
Rupees Four Lakhs Ninety Nine Thousand Four Hundred Eighty Seven and Paise Zero Only


Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damage due to heavy rain to the existing Kalruhi Khad bridge on NH -70 (New NH-03) Km 58.400 to 114.0 (SH) Providing Protection Layer M-20 to protect the downstream of bridge scoured during disaster in H.P during August Month in Km. 72/711 to 72/738 (RHS)

Estimated Cost:-Rs. 499487
Earnest Money:- Rs.10000.00
Time Limit:- One Month

Description of Items

	Qty.	Fig	Rate in	Unit	Amount
			Words		
1. Earth work in excavation by mechanical means (Hydraulic excavator/breaker)/manual means over areas exceeding 30 cm (Thirty centimetre) in depth 1.5 m (One point five metre) in width as well as 10 square meter on plan including getting out and disposal of excavated earth with in all leads and lifts in ordinary rock and all kinds of soil including chiseling of hard rocks where blasting is prohibited including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	28.35	190.00	Rupees One Hundred Ninety and Paise Zero Only	Per cubic metre	5387.00
2. Providing and laying cement concrete 1:2:4 (one cement two coarse sand four graded stone aggregate 20 mm (twenty millimetre) nominal size) in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etcetra up to four five level, excluding the cost of centering, shuttering and finishing including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	91.50	5400.00	Rupees Five Thousand Four Hundred and Paise Zero Only	Per Cubic metre	494100.00
Total					499487.00

Condition

The work will be done as per H.P.P.W.D specifications

The contractor will be responsible at their own level from Civil Supply Depot. After the approval of permit from the competent authority and material will be taken from market as per Department specification issued by the Additional Chief Secretary PW to the Govt. of Himachal Pradesh, R.O. No. 1172/2012 dated 07 August 2012 and all other condition are liable & carriage will be born by the contractor.

The list of all materials provided by the contractor (Material of mining materials used for execution of work must be submitted to the authority concerned and will be liable for toll.

DRAFT SCHEDULE OF QUANTITY CHECKED AND APPROVED FOR Rs. 499487/-
Rupees Four Lakhs Ninety Nine Thousand Four Hundred Eighty Seven and Paise Zero Only

Executive Engineer,
Hamirpur Division,
H.P.W.D. Hamirpur