

Himachal Pradesh
Public Works Department

No. PWP/Agr. Asstt./Tender/2022-23/ 7156-85 Dated/ 18-9-2023

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2.
Himachal Pradesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith the Tender notice of works as given in the Notice inviting Tenders alongwith Schedule of quantities for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of HP letter No. PBW(B) A 9(3) 1/2020 dated Shimla -26th July 2021

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

- 1 The Superintending Engineer 5th Circle, HP.PWD Palampur.
2. The drawing branch in this office.
- 3 All Assistant Engineer working under this Division
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
'SHORT NOTICE INVITING TENDERS'**

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before 03.10.2023 up to 11.00 AM. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 30.09.2023 up to 4.00 P.M and the application for issue of tender form shall be received on 29.09.2023 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	C/o link road to Village Jamwalkar Km 0/00 to 1/00 (SW:- P/L G-III & CC pavement at RD 0/400 to 0/473 (Deposit under VKNNNY (MLALAD 2.00 lac)	Rs 1,99,958/-	Rs. 4000/-	Three Months
2	C/o Community Bhawan/ Mahila Mandal Bhawan unper Dadh Ward No. 3 (SH:- Dismantling of Existing slab, C/o new slab & P/L flooring work (Deposit 2.00 lacs under Head 8443)	Rs. 1,99,054/-	Rs. 4000/-	Three Months
3	C/o Govt. Sr. Secondary School at Sidhpur in Tehsil Palampur (SW:- Balance work of Examination Hall / Two rooms) (DEPOSIT)	Rs. 2,37,835/-	Rs. 4800/-	Three Months
4	C/o Govt. Sr. Secondary School at Khalet in Tehsil Palampur (SW:- Balance work of / Two Class rooms) (DEPOSIT)	Rs. 4,96,917/-	Rs. 9650/-	Three Months
5	Balance work of Tanda Pantehar Dharaman Band Vihar Molichak Kandwari road Km 0/00 to 10/00 (SW:- Providing and laying of Interlocking Paver Block at RD 1/130 to 1/230) (NABARD)	Rs. 4,54,458/-	Rs. 9,100/-	Three Months

Terms & Conditions

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years
8. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand. Next tender will be issued only after completion of previous works in hand.

**Executive Engineer
Palampur Division
HP.PWD Palampur**

DRAFT SCHEDULE OF QUANTITY

Detail of work:- C/o Link road to village Jamwalkar Km 0/00 to 1/00. (SH:- P/L G-II & C.C. Pavement at Rd 0/400 to 0/473). **Deposit**

Estimated cost Rs.	199958.
Earnest Money Rs.	4000.00
Time Limits	Three Months

No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes 63mm to 45mm (sixty three millimeter to forty five millimeter) Grading-II(75mm) seventy five millimeters) thickness to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and canber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405 including carriage of materials within all leads , lifts and other incidentals or as per the directions of Engineer-In-Charge. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	1.26			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation of all type of structure complete Grade M-20 (M-Twenty) nominal mix with minimum cement contents of 325 kgs (Three hundred twenty five kilograms) per cubic meter with 20 mm (Twenty millimetres) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete for all heights / depths as per drawings and MORD technical specifications section 800,900 and 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	33.40			Per cubic metre	

Executive Engineer,
Palampur Division
HP, PWD Palampur.

DRAFT SCHEDULE OF QUANTITY

of work:- C/o Community Bhawan / Mahila Mandal Bhawan Upper Dadh ward No.3. (SH:- Dismantling of existing slab, C/o new & P/L flooring work). **(Deposit 2.00 Lacs under Head 8443)**

of work:- C/o Community Bhawan / Mahila Mandal Bhawan Upper Dadh ward No.3. (SH:- Dismantling of existing slab, C/o new & P/L flooring work). (Deposit 2.00 Lacs under Head 8443)							Estimated cost Rs.	
							Earnest Money Rs.	199054.
							Time Limits	4000.00
								Three N
No.	Description of Item	Quantity	Rate		Unit	Amo		
			In Figures	In Word				
	Demolishing Nominal cement concrete 1:3:6 or richer mix (i/e equivalent design mix) manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. .	5.89			Per cubic metre			
	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	47.13			Per square metre			
	Centering and shuttering including strutting, propping etc. and removal of form for : Edges of slabs and breaks in floors and walls. Under 20 cm wide. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	27.50			Per Running Metre			
	Steel reinforcement for R.C.C. work ready to use "cut and bend" rebars of approved make from factory / workshop to construction site including placing in position and binding all complete upto plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. .	850.00			Per Kilogram			
	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size). The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	5.89			Per Cubic Metre			
	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	68.38			Per square metre			
	6 mm (six millimetre) cement plaster of mix: 1:3 (one cement : three fine sand) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	47.13			Per square metre			
	Government.							

11	Providing and laying 600x600 mm (six hundred into six hundred millimetre) Vitrified tiles in different sizes (thickness to be specified by manufacture), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm (twelve millimetre) thick bed of cement mortar 1:3 (one cement: three coarse sand), jointing with grey cement slurry @ 3.3 (three point three) Per Kilogram/ Per Square Metre including grouting the joint with white cement & matching pigments etc. complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. .	29.20					Per square metre	
----	--	-------	--	--	--	--	------------------	--


 Executive Engineer,
 Palampur Division
 HP.PWD Palampur.

SCHEDULE OF QUANTITY

Name of work:- C/o Govt. Sr. Sec. School at Sidhpur in Tehsil Palampur. (SH:- Balance work of Examination Hall / Two Rooms).

Estimated cost Rs. 237835.00
Earnest Money Rs. 4800.00
Time Limits Three Months

Sl. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	6.55			Per cubic metre	
2	Providing and fixing 35 mm thick Second class teak wood panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	8.51			Per square metre	
3	Providing and fixing 35 mm thick Second class teak wood glazed shutters for doors, windows and clerestory windows using 4 mm thick float glass panes, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	11.00			Per square metre	
4	Providing and fixing 35 mm thick Second class teak wood wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws : The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	6.62			Per square metre	
5	Providing and fixing 150x10 mm aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	40.00			Each	
6	Providing and fixing 100 mm aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	20.00			Each	
7	Providing and fixing 150 mm bright finished brass hard drawn hooks and eyes : The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	20.00			Each	
8	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings / wooden frames with rawl plugs screws etc. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	107.45			Per kilogramme	
9	Providing and fixing precast galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of putties, rafters and trusses and including cutting to size and shape wherever required. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	36.77			Per square metre	
10	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc. including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Electric resistance or induction butt welded tubes. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	203.51			Per kilogramme	
11	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement, 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of match shade complete.	11.10			Per square metre	

12	15 mm cement plaster 1:6 (1 cement: 6 coarse sand) on rough side of single or half brick wall of mix including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	56.32			Per square metre	
13	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	56.32			Per Square Metre	
14	Applying one coat of water thinnable cement primer of approved brand and manufacturer on wall surface including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkana, toll tax, GST and all type of other taxes imposed by the Government.	56.32			Per square metre	
15	Dispersing with oil bound washable distemper of approved brand and manufacturer to give an even shade. New work (two or more coats) over and including water thinnable priming coat with cement primer. The rate is inclusive of octroi, royalty, Malkana, toll tax, GST and all type of other taxes imposed by the Government.	56.32			Per square metre	
16	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacturer in msp sheet ceiling and eaves. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	49.95			Per Square Metre	
17	Applying priming coat With ready mixed pink or Grey primer of approved brand and manufacturer on wood work (hard and soft wood). The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	27.01			Per Square Metre	
18	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacturer. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	28.60			Per Square Metre	
					Total	

Executive Engineer,
Palampur Division
HP.PWD Palampur.

SCHEDULE OF QUANTITY

Name of work:- C/o Govt. Sr. Sec. School at Khalet in Tehsil Palampur. (SH:- Balance work of two class Rooms).

Name of work:- C/o Govt. Sr. Sec. School at Khalet in Tehsil Palampur. (SH:- Balance work of two class Rooms).							Estimated cost Rs.	496917.00
							Earnest Money Rs.	10000.00
							Time Limits	Three Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount		
			In Figures	In Word				
1	Providing and fixing 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	16.20			Per Square metre			
2	Providing and fixing 300x16 mm ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete : The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	4.00			Each			
3	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete : The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.							
i	250x10 mm	8.00			Each			
ii	150x10 mm	56.00			Each			
4	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete : The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.							
i	125 mm	16.00			Each			
ii	100 mm	28.00			Each			
5	Providing and fixing factory made ISI marked steel glazed doors, windows and ventilators, side /top /centre hung, with beading and all members such as F7ID,F4B, K11 B and K12 B etc. complete of standard rolled steel sections, joints mitred and flash butt welded and sash bars tenoned and riveted, including providing and fixing of hinges, pivots, including priming coat of approved steel primer, but excluding the cost of other fittings, complete all as per approved design, (sectional weight of only steel members shall be measured for payment). Fixing with carbon steel galvanised dash fastener of required dia and size (to be paid for separately). The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	377.11			Per kilogramme			
6	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government	791.00			Per Kilogram			
7	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 Per Kilogram/ sqm including grouting the joints with white cement and matching pigments etc., complete size of tile 600*600mm. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	94.87			Per Square Metre			
8	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to IS: 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 Kg/ sqm including grouting the joint with white cement & matching pigments etc. complete Size of Tile 600x600 mm. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	9.45			Per Square Metre			

9	Providing and fixing precast galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS- 277, in 240 mpa steel grade- 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5 x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purfins, rafters and trusses and including cutting to size and shape wherever required. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	26.24			Per square metre	
10	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.63 mm thick with zinc coating not less than 275 gm/m ² . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	5.30			Per Running Metre	
11	15 mm cement plaster 1:6 (1 cement: 6 coarse sand) on rough side of single or half brick wall of mix: including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	139.38			Per square metre	
12	20 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand) The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	187.04			Per square metre	
13	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	430.02			Per Square Metre	
14	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	430.02			Per square metre	
15	Dispersing with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	550.25			Per square metre	
16	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 lit/ 10 sqm over an under coat of primer applied @ 0.80 lit/ 10 sqm of approved brand and manufacture in mshp sheet ceiling and eaves. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	37.20			Per Square Metre	
				Total		

Executive Engineer
Palampur Division
H.P. PWD Palampur.

Draft Schedule of Quantity

Work No. ⑤

Name of Work :- Balance work of Tanda Pantehar Dharaman Band Vihar Millichak Kandwari road 0/00 to 10/00
(Sub Work:- Providing and Laying of Interlocking Paver Block at RD 1/130 to 1/230 (Under NABARD)

Estimated Cost : Rs. 454458/-
Earnest Money : Rs. 9100/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawing and Technical Specification Clause 1504 as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all leads and lift and other incidental .The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the government.	330.00 Square metre			Per Square metre	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the government.	5.48 Cubic metre.			Per Cubic metre	


Executive Engineer
Palampur Division
HP.PWD Palampur