

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT.
NOTICE INVITING TENDER**

Sealed percentage rate tenders are hereby invited on Form No.6 &8 by the undersigned on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, so as to reach in this office on 15-09-2023 upto 11.00 A.M and shall be opened on the same day on 11.30 A. M in the presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non- refundable) during the working hours.

The earnest money in the shape of National Saving Certificate, FDRs/TDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Sarahan must accompany with each applications/tender. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The undersigned reserves the right to reject the any or all tender without assigning any reason.

Sr. No.	Tender Schedule			
1	Last date for tender receipt of application for tender form	13.09.2023 upto 04:00 PM		
2	Last date of sale of tender forms	14.09.2023 upto 04:00 PM		
3	Date of receipt of tender forms	15.09.2023 upto 11:00 AM		
4	Date of opening of tenders	15.09.2023 at 11:30 AM		
Sr. No	Name of Work	Estimated cost	Earnest Money	Time Limit
1	R/R damages on Lawassa Chowki Pteet Nagar road Km 0/0 to 42/0 (SH:- Excavation in earth work in Km 41/765 to 41/900)	494077/-	10000/-	Three Month
2	R/R damages on Banalag Dhemesha road Km 0/00 to 12/00 (SH:- C/o G.I wire crate at RD 2/285 to 2/295)	244528/-	5000	Three Month
3	R/R damages on Lawassa Chowki Preet Nagar road Km 0/0 to 42/00 (SH:- C/O G.I wire crate at RD 41/465 to 41/510)	444580/-	9000	Three Month
4	R/R damages on Dungaghat Kila Klanch road Km 0/0 to 22/0 under Sarahan Sub Division (SH:- Removal of slips and C/o Unlined drain)	407334/-	8500/-	One Month
5	R/R damages on Mari Ka Ghat Kerry Shutiya road Km 0/0 to 23/0 (SH;- C/O PCC, R/Wall at RD 10/650 to 10/665)	271808/-	5500/-	Three Month
6	R/R damages on Mari Ka Ghat Kerry Shutiya road Km 0/0 to 23/0 (SH;- C/O PCC, B/Wall at RD 6/160 to 6/190)	398096/-	8000/-	Four Month
7	R/R damages on Mari Ka Ghat Kerry Shutiya road Km 0/0 to 23/0 (SH;- C/O PCC, R/Wall at RD 8/250 to 8/262)	443388/-	9000/-	Four Month
8	R/R damages on Mari Ka Ghat Kerry Shutiya road Km 0/0 to 23/0 (SH;- C/O PCC, B/Wall at RD 20/350 to 20/380)	382546/-	8000/-	Three Month
9	R/R damages on Mari Ka Ghat Dinger Mathanan road Km 0/0 to 22/0 (SH;- C/O PCC, R/Wall at RD 17/315 to 17/330)	408275/-	8500/-	Three Month

Certificate:-It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application.
3. The contractor/bidder should quoted his rates both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
5. Conditional and telegraphic tender shall be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
7. The tender document shall be issued to only those contractors who does not have more than two works in hand in HPPWD Circle/ Division.
8. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 75 days.

10. The above Job is on present market rates and tender will be processed as per instruction issued by the Add. Chief Secretary (PW) to the Govt. of H.P notification No. PBW (B)A(3)1/2020 dt. 22.07.2020. Regarding adoption of CPWD works manual 2019 & other publication of CWP in HPPWD shall also be applicable.
11. The Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reason.
12. The tender document shall be issued to only those contractors who submit registration of GST No.


No.PW/SRN/Estt-Tender/2022-2

4335-65

Copy forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD.Shimla-171002.
2. The Chief Engineer (South) HP.PWD.Shimla-171002.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. All Head of Branches of this office.
7. All Intending Bidders/Contractors.
8. Notice Board.


Executive Engineer
HPPWD Division Sarahan
Distt Sirmour HP
Dated:- 8/09/23


Executive Engineer
HPPWD Division Sarahan
Distt Sirmour HP
On behalf of Governor of Himachal Pradesh

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs. 4,94,077/-

Name of work:-R/R Daamges on Lawassa Chowki Preet Nagar Road km 0/0 to 42/0 (SH:- Excavation in earth work in km 41/765 to 41/900)

Earnest money:- Rs. 10,000

Time Limit:- Three Month.


Sr. No	Description Items of work	Qty.	Unit	in figures.	Rate		Amount
					in words		
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 0.00 in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	3107.40	Per cubic Metre	159.00	Rupees one hundred fifty nine and paise nil only	6	494077.00
							7
							494077.00

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

494077.00

only.


Executive Engineer
Sarahan Division
HP-PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs. 2,44,528/-

Name of work:- R/R Damages on Banalag Dhamesha road km 0/00 to 12/00 (SH:- C/O G.I wire crate at RD 2/285 to 2/295)

Earnest money:- 5,000

Time Limit:- Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	23.10	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	4481.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of Engineer-in-transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	79.20	Per Cubic Metre.	2846.40	Rupees two thousand eight hundred forty six and paise forty only	225435.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	19.80	Per Cubic Metre.	738.00	Rs. seven hundred thirty eight and paise nil only	14612.00
						244528.00

Ts estimatenos. Letter no. Dated :- DNIT No. For the year 2023-24 Draft Schedule of Quantity approved for Rs. 244528.00 only.


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

Estimated cost:-Rs. 4,44,580/-

DRAFT SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Lawassa Chowki Preet Nagar Road km 0/0 to 42/00 (SH:- C/O G.I wire crate at RD 41/465 and 41/510)

Earnest money:- 9,000

Time Limit:- Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	68.00	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	13192.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	150.00	Per Cubic Metre.	2846.40	Rupees two thousand eight hundred forty six and paise forty only	426960.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in- Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in- Charge.	6.00	Per Cubic Metre.	738.00	Rs. seven hundred thirty eight and paise nil only	4428.00
Ts estimateno.						444580.00

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

444580.00

only.

Dated :-

Letter no.

Ts estimateno.

Executive Engineer
Sarhan Division
HP, PWD, Sarhan

DRAFT SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Dungaghat Kila klanch road km 0/0 to 22/0 under Sarahan Sub-Division (SH:- Removal of slips and C/O unlined drain)

Estimated cost:- Rs. 4,07,334/-

Earnest money:- Rs 8,500

Time Limit:- one Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Removal of landslides /slip clearance. clearance of drain, Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	3575.10	Per Cubic Metre.	91.00	Rupees ninety one and paise nil only	325334.00
2	Construction of unlined surface drain of average cross-sectional area 0.2 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307.	2000.00	Per Running Metre	41.00	Rupees forty and paise zero only	82000.00
						407334.00

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

407334.00

only.

Executive Engineer
Sarahan Division
HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.2,71,808/-

Name of work:- R/R Damages on Mari Ka ghat kerry Shutiya Road km 0/0 to 23/0 (SH:- C/O PCC R/Wall at RD 10/650 to 10/665)

Earnest money:- Rs 5,500

Time Limit:- three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	12.72	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	2468.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications:- C-802, 803, 1202 & 1203 (Clause - Eight hundred Two Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement: Four Sand: Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	53.88	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	254163.00
3	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204:3.7 (Clause Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) including hauling /carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	28.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	7568.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204:3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	10.31	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	7609.00
						271808.00

Ts estimate no. 104 Letter no. 3197-98 Dated :- 01-08-23

DNIT No. For the year 2023-24
Draft Schedule of Quantity approved for Rs.

271808.00 only.


Executive Engineer
Sarahan Division
APP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Name of work:- R/R Damages Mari ka ghat kerry Shutiya road km 0/00 to 23/00 (SH:- C/O PCC B/Wall at RD 6/160 to 6/190)

Estimated cost:- Rs. 3,98,096/-
Earnest money:- Rs 8,000

Time Limit:- Four Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	48.30	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	9370.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	78.60	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	370772.00
3	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	14.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	3784.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	19.20	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	14170.00
Ts estimate no.		Letter no.		Dated :-		
DNIT No.		For the year 2023-24		Draft Schedule of Quantity approved for Rs.		398096.00
						only.


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Name of work:- R/R Damages Mari ka ghat kerry Shutiya road km 0/00 to 23/00 (SH:- C/O PCC & Wall at RD 8/250 to 8/262)


Estimated cost:-Rs. 4,43,388/-
Earnest money:- Rs 9,000
Time Limit:- Four Month.

Sr. No	Description Items of work	Qty.	Unit	in figures.	Rate in words	Amount
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	51.96	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	10080.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	87.72	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	413793.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	26.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	7028.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	16.92	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	12487.00
						443388.00

Ts estimate no. Letter no. Dated :-

DNIT No. For the year 2023-24
Draft Schedule of Quantity approved for Rs.

only.


Executive Engineer
Saraha Division
P.W.D., Saraha

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs3,82,546/-

Name of work:-R/R Damages on Mari ka ghat Bagthan Kerry shutiya road km 0/0 to 23/0 (SH:- C/O B/Wall at RD 20/350 to 20/380)))

Earnest money:- Rs 8,000

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	19.31	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	3746.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	78.64	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	370961.00
3	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	29.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	7839.00
						382546.00

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

382546.00

only.

Dated :-

Letter no.

Ts estimate no.

Executive Engineer
Sarahan Division
HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.4,08,275/-
Earnest money:- Rs 8,500
Time Limit:- three Months.

Name of work:R/R Damges on Mari ka ghat Dinger Mathanan Road km 0/0 to 22/0 (SH:- C/O PCC R/Wall at RD 17/315 to 17/330)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	44.25	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	8585.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C-802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement: Four Sand: Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form-work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	79.50	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	375017.00
3	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	45.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	12164.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical Specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	16.95	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	12509.00
						408275.00

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

only.

Dated :-

Letter no.

Ts estimate no.

408275.00

Executive Engineer
Saraha Division
HP, PWD, Saraha