

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT.
NOTICE INVITING TENDER

Sealed percentage rate tenders are hereby invited on Form No.6 &8 by the undersigned on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, so as to reach in this office on 06-10-2023 upto 11.00 A.M and shall be opened on the same day on 11.30 A. M in the presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non- refundable) during the working hours.


The earnest money in the shape of National Saving Certificate, FDRs/TDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Sarahan must accompany with each applications/tender. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The undersigned reserves the right to reject the any or all tender without assigning any reason.

Sr. No.	Tender Schedule			
1	Last date for tender receipt of application for tender form	04-10-2023 upto 04:00 PM		
2	Last date of sale of tender forms	05-10-2023 upto 04:00 PM		
3	Date of receipt of tender forms	06-10-2023 upto 11:00 AM		
4	Date of opening of tenders	06-10-2023 at 11:30 AM		
Sr. No	Name of Work	Estimated cost	Earnest Money	Time Limit
1	C/O link road to Bajyana to Mohana Sachyali road Km 0/0 to 3/0 (SH:- C/O PCC R/wall at Km 0/135 to 0/150)	497315/-	10000/-	Three Month
2	C/O link road to Bajyana to Mohana Sachyali road Km 0/0 to 3/0 (SH:- C/O PCC R/wall at Km 0/045 to 0/060)	492821/-	10000/-	Three Month
3	C/O link road to Bajyana to Mohana Sachyali road Km 0/0 to 3/0 (SH:- C/O PCC R/wall at Km 0/225 to 0/255)	498939/-	10000/-	Three Month
4	C/O link road to Bajyana to Mohana Sachyali road Km 0/0 to 3/0 (SH:- C/O PCC R/wall at Km 0/510 to 0/534)	499219/-	10000/-	Three Month

Certificate:-It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application.
3. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
4. Conditional and telegraphic tender will not be accepted and rejected straightway. Tender received after due date and time shall not entertained.
5. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
6. The tender document shall be issued to only those contractors who does not have more than two works in hand in HPPWD Circle/ Division.
7. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
8. The Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reason.


Executive Engineer
HPPWD Division Sarahan
Distt Sirmour HP

No.PW/SRN/Estt-Tender/2022-23-

5-24484

Copy forwarded for information and necessary action to:-

Dated:- 26-9-2023

1. The Engineer-in-Chief, HP.PWD.Shimla-171002.
2. The Chief Engineer (South) HP.PWD.Shimla-171002.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental website please.

P.T.O.

- Executive Engineer
HPPWD-Division S
Distt Sirmour HP

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.4,97,315/-

Name of work:-C/O Link road from Bajiyana Mohana Sachyali road km 0/0 to 3/0 (SH:- C/O PCC R/Wall at km 0/135 to 0/150)

Earrest money: - Rs10,000

Time Limit: - Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	3	4	5	6	7
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C-802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement: Four Sand: Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	56.00	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	10864.00
3	Providing weapholes in brick masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ,including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	98.00	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	462286.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	24.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	6487.00
		24.36	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	17978.00
						497615.00

Ts estimate no. Letter no.


Dated :-

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

497615.00

only.


Executive Engineer
Saraha Division
HP, PWD, Saraha

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.4,92,821/-

Name of work:-C/O Link road from Baijyana Mohana Sachyali road km 0/0 to 3/0 (SH:- C/O PCC R/Wall at km 0/045 to 0/060)

Earliest money:- Rs 10,000

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	77.40	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	15016.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	93.60	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	441530.00
3	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204:3:7 (Clause:- Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	31.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	8379.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204:3:8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	37.80	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	27896.00
						492821.00

Ts estimate no. Letter no.

Dated :-

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

492821.00

only.

Executive Engineer
Sarahan Division
HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.4,98,939/-
Earnest money:- Rs 10,000
Time Limit:- Three Months.


Name of work:-C/O Link road from Baiyana Mohana Sachyali road km 0/0 to 3/0 (SH:- C/O PCC R/Wall at km 0/225 to 0/255))

Sr. No	Description Items of work	Qty.	Unit	in figures.	Rate in words	Amount
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	50.40	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	9778.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802,-803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	99.00	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	467003.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	23.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	6217.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 the granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	21.60	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	15941.00
						498939.00

Ts estimate no. Letter no. Dated :-

DNIT No. For the year 2023-24
Draft Schedule of Quantity approved for Rs.

only.


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs.4,99,219/-

Name of work:- C/O Link road from Baiyana Mohana Sachyali road km 0/0 to 3/0 (SH:- C/O PCC R/Wall at km 0/510 to 0/534)

Earnest money:- Rs 10,000

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	in figures:	Rate		Amount
					in words	in figures:	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	3	Per Cubic Metre.	4	194.00	Rupees one hundred ninety four and paise zero only	7
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C: 802: 803: 1202 & 1203 (Clause Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	98.70	Per Cubic Metre.	4	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	465588.00
3	Providing weapholes in brick masonry, plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full width of the structures with slop of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three Seven) including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	22.000	Each	4	270.30	Rs. Two Hundred seventy and paise thirty only	5947.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	25.92	Per Cubic Metre.	4	738.00	Rupees seven Hundred thirty eight and paise zero Only.	19129.00
							499219.00

Ts estimate no. Letter no. Dated :-

DN/IT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

only.

499219.00

Executive Engineer
Saraha Division
H.P. PWD, Saraha