

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT.
NOTICE INVITING TENDER**

Sealed percentage rate tenders are hereby invited on Form No.6 & 8 by the undersigned on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, so as to reach in this office on 08.09.2023 upto 11.00 A.M and shall be opened on the same day on 11.30 A. M in the presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non- refundable) during the working hours.

The earnest money in the shape of National Saving Certificate, FDRs/TDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Sarahan must accompany with each applications/tender. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The undersigned reserves the right to reject the any or all tender without assigning any reason.

Sr. No.	Tender Schedule			
1	Last date for tender receipt of application for tender form	05.09.2023 upto 04:00 PM		
2	Last date of sale of tender forms	06.09.2023 upto 04:00 PM		
3	Date of receipt of tender forms	08.09.2023 upto 11:00 AM		
4	Date of opening of tenders	08.09.2023 at 11:30 AM		
Sr. No	Name of Work	Estimated cost	Earnest Money	Time Limit
1	R/R Damages on Lawassa Chowki Preet Nagar road km 0/0 to 42/00(Sh:- C/O R/Wall between RD 14/600 to 14/620)	467176/-	9500	Three Month
2	R/R Damages Dungaghat Kila Klanch road km 0/0 to 22/0(Sh:-C/O PCC R/Wall at Rd 18/840 to Rd 19/860)	271093/-	5500	Three Month
3	R/R Damages on Sirmouri Mandir Bagthan Road km 0/0 to 10/300 (Sh:-C/O R/Wall at Rd 6/300 to 6/310)	285367/-	6000	Three Month
4	R/R Damages on Sirmouri Mandir Bagthan Road km 0/0 to 10/300 (Sh:-C/O R/Wall at Rd 7/580 to 7/587)	269266/-	5500	Three Month
5	R/R Damages on Lawassa Chowki Preet Nagar road km 0/0 to 42/00(Sh:- C/O G.I wire create at Rd 39/200 to 39/215)	326457/-	6600	Three Month
6	R/R Damages on Lawassa Chowki Preet Nagar road km 0/0 to 42/00(Sh:- C/O G.I wire create at Rd 41/300 to 41/315)	326457/-	6600	Three Month
7	R/R Damages on Lawassa Chowki Preet Nagar road km 0/0 to 42/00(Sh:- C/O G.I wire create at Rd 38/190 to 38/200)	324536/-	6600	Three Month
8	R/R Damages on Lawassa Chowki Preet Nagar road km 0/0 to 42/00(Sh:- C/O G.I wire create at Rd 40/030 to 40/040)	238575/-	5000	Three Month
9	R/R Damages on Lawassa Chowki Preet Nagar road km 0/0 to 42/00(Sh:- C/O PCC R/wall at Rd 8/900 to 8/915)	356388/-	7500	Three Month
10	R/R damages on Mari ka ghat Kerry Shytiya road km 0/0 to 23/0(Sh:-C/O PCC R/Wall at Rd 6/240 to 6/272)	426816/-	8500	Four Month
11	R/R damages on Sarahan Charech Matahan Road Km 0/0 to 7/0 (SH:-C/O R/Wall at RD 1/115 to 1/135)	490271/-	10000	Four Month
12	R/R damages on various roads under SarahanSub Division (SH:- Removal of slips in Sarahan –I Section)	266716/-	5500	One Month
13	R/R damages on various roads under SarahanSub Division (SH:- Removal of slips in Sarahan –II Section)	362089/-	7500	One Month
14	C/O Dungaghat Kila Klanch road Km 0/0 to 22/10 (SH:- C/O PCC R/wall at RD 21/940 to 21/955)	484299/-	10000	Three Month

Certificate:-It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application.
3. The contractor/bidder should quoted his rates both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.

5. Conditional and telegraphic tender shall be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
7. The tender document shall be issued to only those contractors who does not have more than two works in hand in HPPWD Circle/ Division.
8. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 75 days.
10. The above Job is on present market rates and tender will be processed as per instruction issued by the Add. Chief Secretary (PW) to the Govt. of H.P notification No. PBW (B)A(3)1/2020 dt. 22.07.2020. Regarding adoption of CPWD works manual 2019 & other publication of CWP in HPPWD shall also be applicable.
11. The Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reason.
12. The tender document shall be issued to only those contractors who submit registration of GST No.


Executive Engineer
HPPWD Division Sarahan
Distt Sirmour HP

on behalf of Governor of Himachal Pradesh


No.PW/SRN/Estt-Tender/2022-23-

Copy forwarded for information and necessary action to:-

4049-99

Dated:- 1-9-2023

1. The Engineer-in-Chief, HP.PWD.Shimla-171002.
2. The Chief Engineer (South) HP.PWD.Shimla-171002.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. All Head of Branches of this office.
7. All Intending Bidders/Contractors.
8. Notice Board.


Executive Engineer
HPPWD Division Sarahan
Distt Sirmour HP

on behalf of Governor of Himachal Pradesh

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs. 4,67,176/-

Name of work:- R/R Damages on Lawassa Chowki Preet Nagar road km 0/0 to 42/00 (SH:- C/O R/Wall between RD 14/600 to 14/620)

Earnest money:- Rs 9,500

Time Limit:- Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	19.95	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	3870.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C-802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Three, 1.4.8, (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	93.40	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	440586.00
3	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7, (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	36.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	9731.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	17.60	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	12989.00
						467176.00

Ts estimatenos. 89 Letter no. 3201-02 Dated :- 01-08-2023 DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs. 467176.00 only.


Executive Engineer
Sarahan Division
PHD, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs. 2,71,093/-
Earnest money:- Rs 5,500
Time Limit:- Four Month.

Name of work:-R/R Damages Dungaghat Kila Klanch road km 0/0 to 22/0 (SH:- C/O PCC R/Wall at RD 19/840 to RD 19/860)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	32.33	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	6272.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	53.33	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	251568.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	14.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	3784.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	12.83	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	9469.00
Ts estimate no.		Letter no.		DNIT No.		271093.00
				For the year 2023-24		271093.00

Draft Schedule of Quantity approved for Rs. 271093.00 only.


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Sirmouri mandir Bagthan Road km 0/00 to 10/300 (SH:- C/O R/wall at RD 6/300 to 6/310) Estimated cost:- Rs. 2,85,367/-
 Earnest money:- Rs 6,000
 Time Limit:- three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	3 29.50	4 Per Cubic Metre.	5 194.00	6 Rupees one hundred ninety four and paise zero only	7 5723.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications: C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1-4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportation: in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	55.79	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	263173.00
3	Providing weapholes in brick masonry / stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204-3-7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) including hauling /carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	30.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	8109.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3-8 in granular material and as per direction of the Engineer-in- Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in- Charge.	11.33	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	8362.00
						285367.00

Ts estimate no. Letter no.

Dated :-

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

285367.00

only.


 Executive Engineer
 Sarahan Division
 PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs. 2,69,266/-

Name of work:- R/R Damages on Sirmour mandir Bagthan Road km.0/0 to 10/300 (SH:- C/O R/Wall at RD-7/580 to RD-7/587)

Earnest money:- Rs 5,500

Time Limit:- three Month.

Sl. No	Description Items of work	Qty.	Unit	in figures:	Rate		Amount
					in words		
1	2	3	4	5	6	7	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	30.31	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	5880.00	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	53.08	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	250389.00	
3	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return walls with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	21.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	5676.00	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause: 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	9.92	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	7321.00	
							269266.00

Ts estimate no. Letter no.

Dated :-

DNIT No. For the year 2023-24

Draft-Schedule of Quantity approved for Rs.

269266.00

only.

Executive Engineer
Sarhan Division
P.W.D. Sarhan

DRAFT SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Lawassa Chowki Preet Nagar Raod km 0/0 to 42/0 (SH:- C/O G.I wire crate at RD 39/200 to 39/215)

Estimated cost:-Rs. 3,26,457/-

Earnest money:-6,600

Time Limit:- Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	29.70	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	5762.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of engineer-in-transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	108.00	Per Cubic Metre.	2846.40	Rupees two thousand eight hundred forty six and paise forty only	307411.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	18.00	Per Cubic Metre.	738.00	Rs. seven hundred thirty eight and paise nil only	13284.00
Ts estimateno.		Letter no.		326457.00		326457.00

Ts estimateno. Letter no. Dated :- DNIT No. For the year 2023-24 Draft Schedule of Quantity approved for Rs. 326457.00 only.


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Name of work:- -R/R Damages on Lawassa Chowki Preet Nagar road km 0/0 to 42/0 (Sh:- C/O G.I wire crate at RD 41/300 to 41/315)

Estimated cost:-Rs. 3,26,457/-

Earnest money: - 6,600

Time Limit: - Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	29.70	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	5762.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	108.00	Per Cubic Metre.	2846.40	Rupees two thousand eight hundred forty six and paise forty only	307411.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	18.00	Per Cubic Metre.	738.00	Rs. seven hundred thirty eight and paise nil only	13284.00
Ts estimateno.		Letter no.		Dated :-		

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

326457.00

only.

Executive Engineer
Sarahaan Division
HP, PWD, Sarahaan

DRAFT SCHEDULE OF QUANTITY

Name of work:- -R/R Damages on Lawassa Chowki Preet Nagar Raod km 0/0 to 42/0 (SH:- C/O G.I wire crate at RD 38/190 to 38/200)

Estimated cost:-Rs. 3,24,536/-

Earnest money:- -6,600

Time Limit:- Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	19.80	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	3841.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	108.00	Per Cubic Metre.	2846.40	Rupees two thousand eight hundred forty six and paise forty only	307411.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	18.00	Per Cubic Metre.	738.00	Rs. seven hundred thirty eight and paise nil only	13284.00
Ts estimateno.		Letter no.		Dated :-		

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

324536.00

only.


Executive Engineer
Saraha Division
HP, PWD, Saraha

DRAFT SCHEDULE OF QUANTITY

Name of work:- -R/R Damages on Lawassa Chowki Preet Nagar Raod km 0/0 to 42/0 (SH:- C/O G.I wire crate at RD 40/030 to 40/040)

Estimated cost:-Rs. 2,38,575/-

Earnest money: -5,000

Time Limit: - Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	19.80	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	3841.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	79.20	Per Cubic Metre.	2846.40	Rupees two thousand eight hundred forty six and paise forty only	225435.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	12.60	Per Cubic Metre.	738.00	Rs. seven hundred thirty eight and paise nil only	9299.00
						238575.00

Ts estimatenos. Letter no.

Dated :-

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

238575.00

only.


Executive Engineer
Sarahaan Division
HP, PWD, Sarahaan

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 3,56,388/-

Name of work:- R/R Damages on Lawassa Chowki Preet Nagar Road km 0/0 to 42/0 (SH:- C/O PCC R/Wall at RD 8/900 to 8/915)

Earnest money:- Rs 7,500

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	29.92	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	5804.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	70.05	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	330440.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	28.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	7568.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	17.04	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	12576.00
						356388.00

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

only.

Ts estimate no. Letter no.

Dated :-

356388.00


Executive Engineer
Saraha Division
HP, PWD, Saraha

DRAFT SCHEDULE OF QUANTITY

Name of work:- R/R Damages Mari ka ghat kerry Shutiya road km 0/00 to 23/00 (SH:- C/O PCC B/Wall at RD 6/240 to 6/272)

Estimated cost:- Rs. 4,26,816/-

Earliest money:- Rs 8500

Time Limit:- Four Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	51.52	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	9995.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	83.84	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	395490.00
3	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	23.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	6217.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	20.48	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	15114.00
						426816.00

Ts estimate no. Letter no. Dated :-

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

426816.00

only.


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs. 4,90,271/-
Earnest money:- Rs 10,000
Time Limit:- Four Month.

Name of work:-R/R Damages on Sarahan Charech Matahan Road km 0/0 to 7/0 (SH:- C/O R/Wall at RD 1/115 to 1/135)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	59.00	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	11446.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	95.22	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	449172.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	48.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	12974.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	22.60	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	16679.00
						490271.00

Ts estimate no. Letter no. Dated :- DNIT No. For the year 2023-24
Draft Schedule of Quantity approved for Rs.

490271.00 only.


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Various road under Sarahan Sub-Division (SH:- Removal of slips in Sarahan-I Section)

Estimated cost:-Rs. 2,66,716/-

Earnest money:- Rs 5,500

Time-Limit:- one Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Removal of landslides /slip clearance. clearance of drain ,Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	2930.95	Per Cubic Metre.	91.00	Rupees ninety one and paise nil only	266716.00
						266716.00

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

266716.00

only.


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Various road under Sarahan Sub-Division (SH:- Removal of slips in Sarahan-II Section)

Estimated cost:-Rs. 3,62,089/-

Earnest money:- Rs 7,500

Time Limit:- one Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Removal of landslides /slip clearance. clearance of drain ,Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	3979.00	Per Cubic Metre.	91.00	Rupees ninety one and paise nil only	362089.00
						362089.00

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

362089.00

only.


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Dungagaht Kila Klanch road km 0/0 to 22/0 (SH:-C/O PCC R/Wall at RD 21/940 to 21/955)

Estimated cost:-Rs. 4,84,299/-

Earnest money:- Rs 10,000

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	55.20	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	10709.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	94.42	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	445398.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	40.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	10812.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	23.55	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	17380.00
						484299.00

Ts estimate no. Letter no. Dated :-

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

484299.00

only.

Executive Engineer
Saraha Division
H.P, PWD, Saraha