



OFFICE OF THE EXECUTIVE ENGINEER

B & R DIVISION, HPPWD, SOLAN-173212

TEL.NO:- 01792-223811 E-MAIL:- ee-sol-hp@nic.com

No.PW-SD/CB-Tender/-2023-24 **8829-34**

Dated:- **26/9/23**


To

The Executive Engineer (IT Cell),
Nigam Vihar, Nirman Bhawan,
HPPWD, Shimla-2,
Email ID:-cc-pwd-hp@nic.in

Subject: - Publication of e-Tender Notice.


Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2020 dated: 19th June, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl: - Schedule of quantities.


Executive Engineer,
B&R Division,
HP.PWD, Solan.

Copy along with tender notice forwarded for information and necessary action please to:-

1. The Chief Engineer (S.Z), HP.PWD, Nirman Bhawan, Nigam Vihar, Shimla.
2. The Superintending Engineer, 3rd HP.PWD, Solan.
3. The Drawing Branch & Accounts Branch of this office.
4. Notice Board.


Executive Engineer,
B&R Division,
HP.PWD, Solan.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER
(Exigency)**

Sealed item rate tenders are hereby invited on Form No.6 & 8 by the Executive Engineer, Solan B&R Division, H.P. PWD, Solan (H.P.) on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act.1968. The important dates of tender are as under:

Sr.No.	Tender Schedule	Dates	Time
1	The last date for receipt of application for tender form.	03.10.2023	Upto 3.00 P.M.
2	The last date sale of tender forms.	04.10.2023	Upto 4.00 P.M.
3	The date for receipt of tender forms.	05.10.2023	Upto 10.30 A.M.
4	The date of opening of tender	05.10.2023	At 11.00 A.M.


The tender shall be received upto 11.00 A.M. on 05.10.2023 and will be opened on the same day at 11.00 AM in the presence of office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly intending contractors or their authorized representatives who may like to be present. The tender form can be had from this pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Solan must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estimated Cost. (Rs.)	Earnest Money (Rs.)	Time	Cost of Form
1.	Repair and maintenance of Damaged road on Solan Rajragh bye pass road km 0/0 to 5/410 (SH: Providing and laying GSB, WMM & CC M-20 Grade at RD 1/490 to 1/510)	Rs. 418767/-	Rs. 8400/-	Two Months	Rs.350/-
2.	Re-alignment and construction of bridge on Kehlog Basha road in km 0/280 to 0/700 under MNP (SH: C/o cantilever wall in RCC at RD 0/660 to 0/665)	Rs. 477758/-	Rs. 9600/-	Two Months	Rs.350/-
3.	Restoration of rain damages on Kiari Banglow Malga via Manjhol road km 0/0 to 7/00 (SH: C/o PCC R/wall at RD 0/660 to 0/675)	Rs. 402396/-	Rs. 8000/-	Two Months	Rs.350/-
4.	Restoration of rain damages on Mumligh Domchar road km 9/400 to 18/750 (SH: C/o R/wall in wire crate at RD 14/045 to 14/052.50)	Rs. 386387/-	Rs. 7750/-	Two Months	Rs.350/-
5.	Restoration of rain, damages on various roads under Kandaghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slips) Kandaghat section- I	Rs. 498750/-	Rs. 10000/-	Two Months	Rs.350/-

Restoration of rain damages on various roads under Kandaghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slips) Chhausha section- I	Rs. 498750/-	Rs. 10000/-	Two Months	Rs.350/-
Restoration of rain damages on various roads under Solan sub-division (SH: Hiring of JCB/loader cum excavator for removal of slips)	Rs. 498750/-	Rs. 10000/-	Two Months	Rs.350/-

TERMS & CONDITIONS:-

1. The tender form will not be issued to those contractors whose performance has been found unsatisfactory.
2. The contractor should have submitted the proof of registration, EPF No. & GST No. at the time of tender application. Failure should not be issued tender forms.
3. Application without earnest money will not be entertained.
4. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.


Executive Engineer
B&R Division
HPRWD, Solan

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :-				Estimated Cost :-		418767.00
				Earnest Money :-		8400.00
				Time limit :-		Two months
Name of Work :- Repair and maintenance of Damaged road on Solan Rajgarh Bye pass km.0/00 to 5/410 (SH:- Providing and laying GSB, WMM & CC M-20 Grade at Rd.1/490 to 1/510)						
1	Dismantling of flexible pavements and disposal of dismantled materials upto a lead of 100 m, stacking serviceable and unserviceable materials separately as per Technical Specification Clause 202(Two Hundred Two) as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.					
a	Bituminous courses	13.60	Per Cubic Meter	1063.21	Rupees One Thousand Sixty Three and Paise Twenty One Only	14460.00
b	Water Bound Macadam pavements	72.24	Per Cubic Meter	897.10	Rupees Eight Hundred Ninety Seven and Paise Ten Only	64807.00
2	Granular sub-base/base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408(Four Hundred Eight only) as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	30.10	Per Cubic Meter	1221.32	Rupees One Thousand Two Hundred Twenty One and Paise Thirty Two Only	36762.00
3	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and Technical Specification Clause 406 (Four Hundred Four) as per Technical Specification Clause 408(Four Hundred Eight only) as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	34.40	Per Cubic Meter	2202.25	Rupees Two Thousand Two Hundred Two and Paise Twenty Five Only	75757.00

4	Providing and laying cement concrete of M-20 grade, in roads / taxi tracks/ runways, using cement content as per design mix, using coarse sand and graded stone aggregate of 20mm nominal size in appropriate proportions laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/ expansion, complete all as per direction of Engineer-in- charge including carriage of materials with in all leads and lifts and other incidentals.	29.75	Per Cubic Meter	7629.60	Rupees Seven Thousand Six Hundred Twenty Nine and Paise Sixty Only	226981.00
Total:-						418767.00
Rupees Four Lakhs Eighteen Thousand Seven Hundred Sixty Seven Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No.145 for the 2023-24.

Sr. No. 232 for the year 2023-24

Executive Engineer
B&R Division, HP.PWD. Solan.

Draft Schedule of Quantity

Draft Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
				Job No. :- 2.		
				Estimated Cost :-		477758.00
				Earnest Money :-		9600.00
				Time limit :-		Two months
Name of Work :- Re-alignment and Construction of bridge on Kehlog Basha road in Km. 0/280 to 0/700 under MNP (SH:- Construction of cantilever wall in RCC at Rd.0/660 to 0/665)						
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited). Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	42.00	Per Cubic Meter	290.15	Rupees Two Hundred Ninety and Paise Fifteen Only	12186.00
2	Centering and shuttering including strutting, propping etc. and removal of form work as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.					0.00
a	Foundations, footings, bases of columns, etc. for mass concrete	8.15	Per Square meter	216.45	Rupees Two Hundred Sixteen and Paise Forty Five Only	1764.00
b	Walls (any thickness) including attached pilasters, butteresses, plinth and string courses etc.	66.36	Per Square meter	411.15	Rupees Four Hundred Eleven and Paise Fifteen Only	27284.00

3	Providing and laying cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts , including all incidental charges.	23.78	Per Cubic Meter	7107.10	Rupees Seven Thousand One Hundred Seven and Paise Ten Only	169007.00
4	Steel reinforcement for R.C.C. Mild steel and Medium Tensile steel bars work including straightening, cutting, bending, placing in position and binding all complete upto plinth level as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts , including all incidental charges.	2853.00	Per Kg	85.80	Rupees Eighty Five and Paise Eighty Only	244787.00
5	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	16.00	Each	236.00	Rupees Two Hundred Thirty Six Only	3776.00
6	Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per HP.PWD. Specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	18.00	Per Cubic Meter	1053.00	Rupees One Thousand Fifty Three Only	18954.00
Total:-						477758.00
Rupees Four Lakhs Seventy Seven Thousand Seven Hundred Fifty Eight Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No.156 for the 2023-24.

Sr. No. 31 for the year 2023-24

A. Patel
Executive Engineer

B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 3				Estimated Cost: -		402396.00
				Earnest Money: -		8000.00
				Time limit : -		Two months
Name of Work :- Restoration of rain damages on Kiari Banglow Malga via Manjhol road Km.0/00 to 7/00 (SH- Construction of PCC Retaining wall at Rd.0/660 to 0/675)						
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited). Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	37.05	Per Cubic Meter	387.00	Rupees Three Hundred Eighty Seven Only	14338.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty milimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	5.70	Per Cubic Meter	3721.00	Rupees Three Thousand Seven Hundred Twenty One Only	21210.00

3	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five milimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	79.35	Per Cubic Meter	4225.00	Rupees Four Thousand Two Hundred Twenty Five Only	335254.00
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	26.00	Each	231.00	Rupees Two Hundred Thirty One Only	6006.00
5	Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per HP.PWD. Specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	24.30	Per Cubic Meter	1053.00	Rupees One Thousand Fifty Three Only	25588.00
Total:-						402396.00
Rupees Four Lakhs Two Thousand Three Hundred Ninety Six Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No.154 for the 2023-24.

Sr. No. 29 for the year 2023-24

Executive Engineer

B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 4.					Estimated Cost :-	386387.00
					Earnest Money :-	7750.00
					Time limit :-	Two months
Name of Work :- Restoration of rain damages on Mumligh Domehar road Km.9/400 to 18/750 (SH:- Construction of Retaining wall in wire crate at Rd.14/045 to 14/052.50)						
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited). Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	45.53	Per Cubic Meter	387.00	Rupees Three Hundred Eighty Seven Only	17620.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	117.20	Per Cubic Meter	3014.40	Rupees Three Thousand Fourteen and Paise Forty Only	353288.00

3	Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per HP.PWD. Specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	14.70	Per Cubic Meter	1053.00	Rupees One Thousand Fifty Three Only	15479.00
Total:-						
Quoted Percentage rate upto Three Digits :-						
				(+) / (-)		
Rupees Three Lakhs Eighty Six Thousand Three Hundred Eighty Seven Only						386387.00

T/S No.155 for the 2023-24.
Sr. No. 230 for the year 2023-24

Executive Engineer
B&R Division, HP.PWD. Solan.

SCHEDULE OF QUANTITY.				Estimated Cost: -		498750.00
				Earnest Money: -		10000.00
				Time Limit: -		Two Months.
Job No. <u>5</u> .						
Name of work: - Restoration of Rain damages on various roads under Kandaghat Sub- Division (SH :- Hiring of JCB / loader cum-excavator for removal of slips (Kandaghat Section-1)						
Sno.	Description of items	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
1	2	3.00	4	5	6	7
1	Hiring of JCB / loader cum-excavator .	525.00	Per hour.	950.00	Rupees nine hundred fifty & paise nil only.	498750.00
Terms and Conditions :-						
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.					
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.					
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.					
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour					

Sr. No. 22 for the year 2023-24.

Executive Engineer,
Solani B&R Division,
H.P. P.W.D.; Solani

Job No. 6

SCHEDULE OF QUANTITY.

Estimated Cost: -	498750.00
Earnest Money: -	10000.00
Time Limit: -	Two Months.

Name of work: - Restoration of Rain damages on various roads under Kandaghat Sub- Division (SH :- Hiring of JCB / loader cum-excavator for removal of slips (Chhausha Section.).

Sno.	Description of items	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
1	2	3.00	4	5	6	7
1	Hiring of JCB / loader cum-excavator .	525.00	Per hour.	950.00	Rupees nine hundred fifty & paisa nil only.	498750.00
Terms and Conditions :-						
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.					
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.					
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.					
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour.					
Total in words.						Rupees Four lacs Ninety eight thousand seven hundred fifty only.
Quoted Percentage rate upto Three Digits :-						(+) / (-)

Sr. No. 227 for the year 2023-24.

Executive Engineer,
Solani B&R Division,
H.P.P.W.D; Solani.

SCHEDULE OF QUANTITY.					Estimated Cost: -	498750.00
Job No. 7.					Earnest Money: -	10000.00
					Time Limit: -	Two Months.
Name of work: - Restoration of Rain damages on various roads under Solan Sub- Division (SH :- Hiring of JCB / loader cum-excavator for removal of slips).						
Sno.	Description of items	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
1	2	3.00	4	5	6	7
1	Hiring of JCB / loader cum-excavator .	525.00	Per hour.	950.00	Rupees nine hundred fifty & paisa nil only.	498750.00
Terms and Conditions :-						
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.					
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.					
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.					
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour.					
						Total:- 498750.00
		Total in words. Rupees Four lacs Ninety eight thousand seven hundred fifty only.				
Quoted Percentage rate upto Three Digits :-		(+) / (-)				

Sr. No. 228 for the year 2023-24.


Amit
Executive Engineer,
Solan B&R Division,
H.P.P.W.D. Solan.

Exigency Certificate

It is certified that the tenders which were invited vide this office
NTT No.PW-SD/CB-Tender/2023-24- ~~8829-34~~ Dated: ~~26-09-23~~ are of emergent nature of work and in
public interest.

Dated:- 27.09.2023

Place:- Solan


Executive Engineer
B&R Division
HPWD, Solan