



Himachal Pradesh
Public Works Department
NOTICE INVITING TENDER

Sealed tenders on item rates on PWD form 6 & 7 are hereby invited by the Executive Engineer, Tauni Devi Division, and HPPWD Tauni Devi for the following works. The tender shall be received in this office on or before 26.09.2023 up to 11:00 AM and the same shall be opened on the same day at 11:30AM in the presence of the contractor/firs. The application for the issue of tender document shall be received on dated 23.09.2023 upto 2:30PM and the tender form will be sold on cash payment (non refundable) on dated 25.09.2023 from 11.30 AM to 4:00 PM

Sr. No.	Name of Work	Estimated Cost (Rs.)	Earnest Money	Time Limit	Cost of form
1	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road from 15/00 to 30/915 (Sh:- P/L wire crate at km 25/650 to 25/665)	462872/-	9200/-	Two Months	350.00
2	R/R damages on link road from Mehloroo to village Lohar Bali km 0/00 to 2/00(Sh:- C/O brest wall in km 0/636 to 0/648,retaining wall in km 0/590 to 0/600)	481149/-	9600/-	Two Months	350.00
3	R/R damages on link road from Mehloroo to village Lohar Bali km 0/00 to 2/00(Sh:- C/O brest wall in km 0/666 to 0/632,)	475942/-	9600/-	Two Months	350.00
4	C/o link road Bhalana to Chaleli km 0/0 to 2/0 (SH:- C/O R/wall at RD 1/140 to 1/160 and 1/170 to 1/182) (Under SCSP)	397712	8000/-	Two Months	350.00
5	R/R damages on link road Ree to Gartholi via Balyana km 0/0 to 2/700 (C/O R/wall at RD 0/240 to 0/252)	496771/-	10000/-	Two Months	350.00
6	R/R damages on link road Chabutra to Nihari Dargod Balhi km 0/0 to 3/0 (Sh:- F/C from RD.0/825 to 0/846)	480346/-	9600/-	Two Months	350.00
7	R/R damages on link road Chabutra to Nihari Dargod Balhi km 0/0 to 3/0 (Sh:- F/C from RD.0/865 to 0/900)	418040/-	8400/-	Two Months	350.00
8	R/R damages on link road Chabutra to Nihari Dargod Balhi km 0/0 to 3/0 (Sh:- F/C from RD.0/846 to 0/865)	467891/-	9500/-	Two Months	350.00
9	R/R damages on Bohani Chheorian Kakriar road km 0/0 to 4/905 (C/O R/wall at RD 3/615 to 3/392 and V-shape drain at RD 3/585 to 3/590)	298421/-	6000/-	Two Months	350.00
10	Repair and maintance of various Bridge,s under Kakkar Sub-Division (SH:-Priming coat & painting of RCC railing of bridge i.e 61.25 mtr.Span Bridge over papehad Khad ,21.55 mtr.Span bridge over Bajhar khad 300.00mtr .span bridge over Bakkar khad on sujanpur sandhol road km 3/00 to 20/00 (MDR-38) & 35.00 mtr.span 22.62 mtr, 6.00 mtr.span bridges over Chamarda road km 0/00 to 3/00)	352704/-	7000/-	Two Months	350.00
11	A/R & M/O on Sujanpur to Sandhol road 3/00 to 20/00 (SH:- C/O soild causeway at Bajhar at Km 17/300)(MDR-38)	281202/-	5700/-	Two Months	350.00
12	R/R damages on Kalanghari Kangri road km .0/0 to 8/00 (SH:- C/O R/wall at RD .2/070 to 2/080 and 4/660 to 4/670)	351043/-	7000/-	Two Months	350.00
13	R/R damages on Dulwana Gujera to Dhangota Brahamana km 0/00 to 2/500(SH:- C/O B/wall at RD .2/250 to 0/275)	264357/-	5300/-	Two Months	350.00
14	C/O link road Dhail to Naglamber km .0/0 to 3/450 RIDF-XXIII (SH:- Supplying and installation of 3 No. Computer 3 No. .printer and Photo state Machine HP:PWD, Sub Division Sujanpur under HP:PWD, Tauni Devi Division (HP)	496550/-	10000/-	Two Months	350.00

17	R/R damages on Kakkar Sachuhi road km 0/0 to 8/500(SH:- C/O R/wall at RD 7/439 to 7/447)(Deposit Work)	452176/-	9000/-	Two Months	350.00
18	R/R damages on Kakkar Sachuhi road km 0/0 to 8/500(SH:- C/O R/wall at RD 7/430 to 7/438)(Deposit Work)	452176/-	9000/-	Two Months	350.00
19	C/o link road Kakkar to Bakkar Khad via Ghodlamber km 0/00 to 2/650(SH:- P/L wire crate R/wall at RD 2/510 to 2/533) (Under OTMNP)	482673/-	9700/-	Two Months	350.00
20	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Baeri road km 15/0 to 30/915(Sh:- C/O C.C causeway at RD 20/102 to 20/104)	481124/-	9600/-	Two Months	350.00
21	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Baeri road km 15/0 to 30/915(Sh:- C/O PCC R/wall at RD 20/095 to 20/099.20)	485971/-	10000/-	Two Months	350.00
22	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Baeri road km 15/0 to 30/915 (Sh:- C/O C.C causeway at RD 20/105 to 20/107)	482181/-	9600/-	Two Months	350.00
23	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Baeri road km 15/0 to 30/915 (Sh:- C/O PCC R/wall at RD ,20/107 to 20/111.20)	485899/-	10000/-	Two Months	350.00
24	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Baeri road km 15/0 to 30/915 (Sh:- C/O PCC R/wall at RD ,20/099 to 20/101)	482181/-	9600/-	Two Months	350.00
25	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Baeri road km 15/0 to 30/915 (Sh:- C/O PCC R/wall at RD ,20/090 to 20/094.20) (LHS of Road)	488871/-	10000/-	Two Months	350.00
26	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Baeri road km 15/0 to 30/915 (Sh:- C/O C.C causeway at RD 20/112 to 20/114)	495331/-	10000/-	Two Months	350.00
27	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Baeri road km 15/0 to 30/915 (Sh:- C/O C.C causeway at RD 20/101 to 20/102 and 20/104 to 20/105)	497674/-	10000/-	Two Months	350.00
28	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Baeri road km 15/0 to 30/915 (MDR-105) (Sh:- Backfilling behind PCC R/wall from RD20/990 to 20/101.50)	432894/-	8700/-	Two Months	350.00
29	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Baeri road km 15/0 to 30/915 (MDR-105) (Sh:- Backfilling behind PCC R/wall from RD 20/103 to 20/114)	432726/-	8700/-	Two Months	350.00
30	C/O link road Nanot to Bakkar Khad via Jamli km .00/ to 4/0(SH:- P/L GSB at RD .3/500 to 4/00)OTMNP Head	347883/-	7000/-	Two Months	350.00
31	R/R damages on Sujampur Sandhol road (MDR-38) km 3/00 to 20/00 (Sh:- C/O wire crates near Jangal bridge approach at km 10/135 to 10/155)	487722/-	9000/-	Two Months	350.00
32	R/R damages on Sujampur Sandhol road (MDR-38) km 3/00 to 20/00 (Sh:- C/O wire crates near Sachuhi Junction at km 17/960 to 17/975)	493632/-	9900/-	Two Months	350.00
33	R/R damages on Sujampur Sandhol road (MDR-38) km 3/00 to 20/00 (Sh:- C/O wire crates at km 15/100 to 15/115)	499261/-	10000/-	Two Months	350.00
34	R/R damages on Uhal to Baghera via Jandroo road km 0/00 to 28/00 (Sh:- ROFD and imp of curves at RD 18/315 to 18/375	398482/-	8000/-	Two Months	350.00
35	R/R damages on Nanot to Bakkar Khad via Jamli road in km 0/00 to 4/00 (Sh:- C/O R/wall at RD 1/480 to 1/499)	448688/-	9000/-	Two Months	350.00
36	R/R damages on Kahnauli Kheri Bhatlamber Dudhla via Mahesgal road km 0/0 to 9/460(SH:- C/O PCC R/wall at RD 1/950 to 1/959) Deposit work	286461/-	5700/-	Two Months	350.00

39	R/R damages on Uhal to Baghera via Jandroo road (Sh:- C/O PCC R/wall at RD 22/220 to 22/229.50)	459984/-	9200/-	Two Months	350.00
40	R/R damages on Jhanikar to Palahal Kuan via Kohalwin road km 0/00 to 2/450 (Sh:- C/O PCC R/wall at RD 2/380 to 2/390)	258976/-	5200/-	Two Months	350.00
41	R/R damages Tauni Devi Uhal Kakkr Bajrol Jungle Beri road km 0/00 to 30/915 (Sh:- C/O R/wall at RD 2/110 to 2/120 and 2/130 to 2/142)	332496/-	6500/-	Two Months	350.00
42	R/R damages on link road Nadiana Sadiana to village Chowki Bahal km 0/0 to 4/00 (Sh:- C/O R/wall at RD 2/690 to 2/705)	349082/-	7000/-	Two Months	350.00
43	R/R damages on Hamirpur Sujanpur road (MDR-86) km 2/600 to 16/0 (Sh:- C/O R/wall at RD 12/415 to 12/435)	479531/-	9600/-	Two Months	350.00
44	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road from 15/00 to 30/915 (Sh:- P/L wire crate at km 25/640 to 25/650 & 25/665 to 25/674)	465159/-	9400/-	Two Months	350.00
45	R/R damages on Barara to Bakkar Khad via Patnoun road km .2/00 to 8/00 (SH:- C/O R/wall at RD .2/840 to 2/858)	285431/-	5700/-	Two Months	350.00

TERMS AND CONDITIONS:-

The tender documents shall be issued only to those contractors/firms who fulfill the following criteria and submit documents with the application. The valid enlistment/registration of contractor in appropriate class. Permanent Account Number (PAN). Earnest money in the shape of National saving certificate/Time deposit Account in any of the Post office in H.P./F.D.R from any Nationalized Bank (i/c Kangra Central Cooperative Bank) duly pledged in favour of the Executive Engineer. Other speical terms and condition can be seen/obtain in this office on any working day. Any ambiguous/telegraphic conditional tenders by fax shall not be

Excutive Engineer
TauniDevDivision,
HPPWDTauniDevi.

No. PW/TDD/GA/N.I.T./2023-24

9507-52

Dated:- 20-09-2023


Copy forwarded for infromation & necessary action.

- 1 The Engineer-in-Chief, HP:PWD , Shimla.
- 2 The Chief Engineer (HZ), HP:PWD, Hamirpur.
- 3 The Superintending Engineer, 8th Circle, HP:PWD Hamirpur.
- 4 All the Superintending Engineers/Executive Engineers in HP:PWD.
- 5 The Deputy Commissioner, Hamirpur(HP)
- 6 ✓ The Director, Information and Public Relations, Suchna Avam Jan Sampark Bhawan, HP Shimla-2 .
- 7 The Tehsildar, Tauni Devi.
- 8 The B.D.O Tauni Devi.
- 9 The Municipal Committee, Hamirpur(HP)
- 10 All the Assistant Engineers working under this Division.
- 11 Account Branch/Drawing Branch/Notice Board.
- 12 Lok Mitra, Tauni Devi.
- 13 Various Contractors/ Firms.

Excutive Engineer
TauniDevDivision,
HPPWDTauniDevi.

CERTIFICATE

Certified that the tender for job No. 1 to 45 are called vide this office letter No. PW/TDD/GA/2023-24-9503-52 dated 20.09.2023 are an urgent nature and in public interest.


Executive Engineer,
Tauni Devi Division,
HP:PWD, Tauni Devi.

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungel Beri road from 15/00 to 30/915. (SH:- Providing and laying wire crate at Km 25/650 to 25/665)

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungel Beri road from 15/00 to 30/915. (SH:- Providing and laying wire crate at Km 25/650 to 25/665)						Estimated Cost:-		Rs.462872.00		
Sr. No.						Qty.	Earnest Money:-		Rs9200.00	
							Time:-		Two Months	
Description of Items						In Fig.	Rate		Unit	Amount
							In Words			
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.					56.25			Per cubic metre	
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming ot IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10(ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogram) each as per drawing and technical specifications Clause 1301as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.					145.31			Per cubic metre	
Total										

Terms and Condition

1. Work shall be executed as per PWD specification.

Amit Kumar
Executive Engineer,
Tauni Devi Division,
H.P.PWD: Tauni Devi

NAME OF WORK:-	Schedule of Quantity
Restoration of rain damages on link road from Meharnoo to Village Lohar Bali Km 0/00 to 2/00. (SH:-	
Construction of breast wall in Km 0/636 to 0/648, retaining wall in Km 0/590 to 0/600	

1. Work shall be executed as per PWD specification.

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tauni Devi Division,
HPWD: Tauni Devi.

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road from Mehairoo to Village Lohar Bali Km 0/00 to 2/00. (SH:- Construction of breast wall in Km 0/600 to 0/632)


Estimated Cost:- Rs.475942.00
Earnest Money:- Rs9600.00

Time:- Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	67.20			Per cubic metre	
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : four coarse sand) : eight graded stone aggregate 40 mm(forty millimetre) nominal size) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	84.48			Per cubic metre	
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred ten millimeter) dia PVC pipe De plast /finolex/vectus having pressure 4kg per sqmt (four kilogram) per square meter extending through the full width of the structures with slopes of 1(V): 20(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30.00			Each.	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 H.P.W.D. Tauni Devi

Schedule of Quantity

NAME OF WORK:- C/O link roa 1 Bhalana to Chaleli km. 0/0 to 2/0.(SH:- C, O R/Wall at RD. 1/140 to 1/160 and 1/170 to 1/182). (Under SCS).)

NAME OF WORK:- C/O link roa : Bhalana to Chaleli km. 0/0 to 2/0.(SH:- C, O R/Wall at RD. 1/140 to 1/160 and 1/170 to 1/182). (Under SOSP).							Estimated Cost:-		Rs. 397712.00
							Earnest Money:-		Rs. 8000.00
							Time:-		Two Months
Sr.No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount		
				In Words					
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (one point five metre) in width or 10 sqm (ten square metre on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	45.30				Per cubic metre			
5	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	85.38				Per cubic metre			
	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe. De-plas/index/ vecus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	24.00				Each			
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and MORD technical specifications clause 1204.3.8 as per direction of Engineer- in -Charge, including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	23.04				Per cubic metre			
						Total			


Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tarni Devi Division,
 HP PWD, Tarni Devi

Schedule of Quantity
NAME OF WORK:- Restoration of rain damages on link road Ree to Gartholi via Balyana krr. 0/0 to 2/700.(SH:- C/O R/Wall at RD.0/240 to 0/252).

NAME OF WORK:- Restoration of rain damages on link road Ree to Gartholi via Balyana kr. 0/0 to 2/7'00. (SH- C/O R/Wall at RD.0/240 to 0/252).									
SECURE TO QUANTITY									
Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount			
			Earnest Money:-	Rs. 10000.00					
			Time:-	Two Months					
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqmt ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	49.44	In Fig.	In Words	Per cubic metre				
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (four millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	113.76			Per cubic metre				
3	Providing weep holes in brickstone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/Inolex vectus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3,7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	25.00			Each.				
Terms and Condition							Total		
Work shall be executed as per PWD specification.									


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi


Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road Chabutra to Nihari Dargod Balhi km. 0/0 to 3/00.(SH:- Formation cutting from RD. 0/825 to 0/846).

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Earnest Money:-	
			In Fig.	In Words	Unit	Amount
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1,1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e. 187.68/-cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs.56,304/-only.	1126.12			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 H.P.PWD: Tauni Devi


Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road Chabutra to Nihari Dargod Balhi km. 0/0 to 3/00.(SH:- Formation cutting from RD. 0/865 to 0/900).

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earnest Money:-	Rs. 418040.00		
				Time:-	Two Months		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1,1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e. 163.34/-cubic metre shall be made from the contractor @ Rs. 300/-(three hundred only per cubic metre) amounting to Rs.49002/-only.	980.05				Per cubic metre	
Total							

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HP PWD: Tauni Dev

NAME OF WORK-	Schedule of Quantity
Restoration of rain damages on link road Chabutra to Nihari Dargod Balhi km. 0/0 to 3/00.(SH:- Formation cutting RD. 0/846 to 0/865).	

1. Work shall be executed as per PWD specification.

Amey Desai
Executive Engineer,
Tanni Devi Division,
HPPWD: Tanni Devi

Schedule of Quantity


NAME OF WORK:- Restoration of rain damages on Bohni Chherion Kakriar road KM 0/0 to 4/905. (SH:- Construction of retaining wall at RD 3/615 to 3/932 and V-Shape drain at RD 3/585 to 3/590)

NAME OF WORK:- Restoration of rain damages on Bohni Chherion Kakriar road KM 0/0 to 4/905. (SH:- Construction of retaining wall at RD 3/615 to 3/932 and V-Shape drain at RD 3/585 to 3/590)									
SCHEDULE OF QUANTITIES									
Sr. No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount		
				Earnest Money:-					
				Rate	In Words				
1.00	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre) on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m(one point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within all leads (Ordinary rock)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	31.68				Per cubic metre			
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	55.74				Per cubic metre			
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed/broken stone aggregate 40mm (forty millimetre) nominal and below size in or under water including curing complete, pumping or bailing out water, dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all height/depths including the cost of form work, as per drawings and technical specifications Clause 802,803,1202 & 1203 including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	7.61				Per cubic metre			
4.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) dia PVC pipe De plast /finolex/vecutis having pressure 4kg per sqmt (four kilogram) per square meter extending through the full width of the structures with slopes of 1(V): 20(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	32.00				Each.			

5.00	Backfilling Granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8, and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	11.90				Per cubic meter	
Total							

Terms and Condition

1. Work shall be executed as per PWD specification.



 Executive Engineer,
 Tauni Devi Division
 H.P.W.D.: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Repair and Maintance of various Bridge's under Kakkar Sub-Division. (SH:- Priming coat & painting of RCC railing of bridge i.e 61.25mtr. Span bridge over Paplehad Khad, 21.55 mtr. Span bridge over Bajahar Khad, 300.00 mtr. span bridge over Bakkar Khad on Sujampur Sandhol road Km 3/00 to 20/00 (MDR-38) & 35.00mtr. span, 22.62mtr, 6.00mtr. span bridges over Chamarda road Km 0/00 to 3/00)					Estimated Cost:-	Rs.352704.00
					Earnest Money:-	Rs.7000.00
					Time:-	Two Months
Sr. No.	Description of Items	Qty.	In Fig.	Rate In Words	Unit	Amount
1.00	Applying one priming coat with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content with water thinnable cement primer on wall surface having VOC content less than 50(fifty) grams/litre or as per drawing and technical specification Clause 1301 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2779.38			Per cubic metre	
2.00	Finishing walls with water proofing cement paint of required shade New work (Two or more coats applied @ 3.84 kg/10 sqm(three point eighty four kilogram per ten square metre) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2779.38			Per square metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division
 HPPWD: Tauni De

Schedule of Quantity


NAME OF WORK:- A/R & M/O on Sujapur to Sandhol road 3/00 to 2q00 (SH:- Construction of solid causeway at Bajahar at Km 17/300) (MDR-38)

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
			Time:- Estimate money:- RS.5 / 00.00			
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	61.88			Per cubic metre	
2.00	Stone soling properly hand packed filling interstices with spalls and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP:PWD, specification 100mm(one hundred millimeters) spread thickness as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	15.75			Per cubic metre	
3.00	Providing concrete for plain/reinforced concrete in P.C.C grade M-10(M-ten) nominal mix 1:3:6 (one cement: three sand: six graded crushed stone aggregate) 20mm (twenty millimeters) nominal size in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203 and as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	10.50			Per cubic metre	
4.00	Providing concrete for reinforced concrete in sub-structure complete as per drawings and technical specification clause 802,803,1202 and 1203 1:1.5:3 (one cement: one point five sand: three graded crushed stone as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	15.75			Per cubic metre	

5.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10(ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogram) each as per drawing and technical specifications Clause 1301 as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	31.25					Per cubic metre	
							Total	

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD, Tauni Devi

Schedule of Quantity
NAME OF WORK:- Restoration of rain damages on Kalanghari Kangri road km. 0/0 to 8/00.(SH- C/O R/Wall at RD. 2/070 to 2/080 and 4/660 to 4/670).

Estimate of Quantity									
NAME OF WORK:- Restoration of rain damages on Kalanghari Kangri road km. 0/0 to 8/00,(SH.-C/O R/Wall at RD. 2/070 to 2/080 and 4/660 to 4/670).									
Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount			
			Earnest Money:-	Rs. 351043.00					
			Time:-	Two Months					
			Rate	In Words					
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m,(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	31.60			Per Cubic metre				
2	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills,fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	80.21			Per Cubic metre				
4	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plastifiolex/ vecdus pipe having pressure 4kg/per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	30.00			Each				
Total									

Terms and Condition

Work shall be executed as per PWD specification.

Terms and Condition
 1. Work shall be executed as per PWD specification.

Amit Kumar
 Executive Engineer,
 Tauni Devi Division,
 HPWD: Tauni Devi

Schedule of Quantity
NAME OF WORK:- Restoration of rain damages on Dalwana Gajera to Dhangota Brahmana km. 0/00 to 2/500.(SH:- C/O
B/Wall at RD. 0/250 to 0/275).


B/Wall at RD. 0/250 to 0/275).									
anges on Daiwana gujera to Dhangota Brahamana km. 0/00 to 2/500.(SH:- C/O									
Sr.No.	Description of Items	Qty.	Estimated Cost:-		Rs. 264357.00				
			Earnest Money:-	Rs. 5300.00					
			Time:-	Two Months					
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm(thirty centimetre) in depth, 1.5 m(one point five metre) in width as well as 10 sqm(ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m(fifty metre) and lift upto 1.5 m(one point five metre), as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	27.50	In Fig.	In Words	Unit	Amount			
					Per Cubic metre				
2	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan), including dressing of sides and rammings of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m, (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	14.50			Per Cubic metre				
3	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	58.85			Per Cubic metre				
4	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/linolex/ vecus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204, 3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	37.00			Each				
Total									

Terms and Condition

Work shall be executed as per PWD specification

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPMWD: Tauni Devi


Schedule of Quantity

NAME OF WORK:- C/O link road Dhail to Naglambar km. 0/0 to 3/450 RIDF-XXIII. (SH:- Supplying and installation of 3No. Computers 3No. Printers and Photo State Machine HP:PWD., Sub-Division Sujampur under HP:PWD., Tauni Devi Division (HP).

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earnest Money:-	Rs. 496550.00		
				Time:-			
				In Words	Two Months		
1	Desktop 15 11" generation processor/8ab DDR, 4 Ram 512GB SSD/Win-11/office 2021/Avirus 22" display monitor (FHD) Usb keyboard mouse as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.	3.00				Each	
2	Laser jet all in one print/copy/scan, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.	3.00				Each	
3	UPS 1 KVA, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.	3.00				Each	
4	Kyocera Taskalfa 2020 multifunctional photocopier with duplex print/copy/scan A3 size, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.	1.00				Each	
	Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

Schedule of Quantity

NAME OF WORK:- C/O link road Dhail to Naglambar km. 0/0 to 3/450 RIDF-XXIII. (SH:- Supplying and installation of 1No. Computer 1No. Printer, 2Nos. UPS at Patlander Section HP:PWD, Sub-Division Sujampur).

Estimated Cost:- Rs. 163500.00

Earnest Money:- Rs. 3300.00

Time:-

Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Dell desktop 15 11th Generation processor 8 GM DDR-4 RAM 512 GB SSD Win-11 office 2021 Antivirus 22" display monitor (FHD) USB keyboard mouse, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.	1.00			Each	
2	Laser jet all in one printer scanning/printing/photo state, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.	1.00			Each	
3	UPS 1 KVA, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.	2.00			Each	
					Total	

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tadai Devi Division,
HP:PWD: Tauni Devt.

Schedule of Quantity
NAME OF WORK:- C/O link road Kakkar to Bakkar Khad via Ghodlamber km. 0/00 to 2/650. (SH:- P/L wire crate R/Wall at RD. 2/600 to 2/623). (Under OTMNP).

NAME OF WORK:- C/O link road Kakkar to Bakkar Khad via Ghodlamber km. 0/00 to 2/650.(SH:- P/L wire crate R/Wall at RD.											
2/600 to 2/623).(Under OTMNP).				Estimated Cost:-		Rs.482673.00					
				Earnest Money:-		Rs.9700.00					
				Time:-		Two Months					
Sr.No.		Description of Items		Qty.		Rate		Unit		Amount	
						In Fig.		In Words			
1		Excavation work by mechanical means (Hydraulic excavator/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ranning of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m,(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and its and other incidentals.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.		12.00						Per cubic metre	
2		Providing and laying laid in wire crates with 4mm (four millimeters) dia G.I. wire conforming to IS:280 and IS: 4826 in 100x100mm (one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (twenty five kilogram) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and its and other incidentals.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.		143.72						Per cubic metre	
Terms and Condition										Total	
1. Work shall be executed as per PWD specification.											

1. Work shall be executed as per PWD specification.

Arun Devi
 Executive Engineer,
 Tauni Devl Division,
 HPPWD: Tauni Devl.

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Kakkar Sachhi road km. 0/00 to 8/500.(SH:- C/O PCC R/Wall at RD. 7/439 to 7/447). (Deposit Work).

NAME OF WORK:- Restoration of rain damages on Kakkar Sachchi road km. 0/00 to 8/500,(SH:- C/O PCC R/Wall at RD. 7/439 to 7/447). (Deposit Work).									
			Estimated Cost:-		Rs. 452176.00				
			Earnest Money:-		Rs. 9000.00				
			Time:-		Two Months				
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount			
			In Fig.	In Words					
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m,(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	28.56			Per Cubic metre				
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one cement: four sand: eight graded stone aggregated 40mm (forty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	76.08			Per Cubic metre				
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vecus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	21.00			Each				
					Total				

Terms and Condition

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tauni Devi Division
HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Kakkar Sachhi road km. 0/00 to 8/500.(SH:- C/O PCC R/Wall at RD. 7/430 to 7/438). (L-2 PCC R/Wall)

Estimated Cost:- Rs. 452176.00
Earnest Money:- Rs. 9000.00

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan).Including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m,(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	28.56			Per Cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one cement: four sand: eight graded stone aggregated 40mm (forty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	76.08			Per Cubic metre	
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1/V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	21.00			Each	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


Amir Ali
Executive Engineer,
Tauni Devi Division,
HPPWD, Tauni Devi

Schedule of Quantity

NAME OF WORK:- C/O link road Kakkar to Bakkar Khad via Ghodlamber km. 0/00 to 2/650. (Sh:- P/L wire crate R/Wall at RD. 2/510 to 2/533). (Under OTMNP).

NAME OF WORK:- C/O link road Kakkar to Bakkar Khad via Chodiambher km. 0/00 to 2/650.(SH:- P/L wire crate R/Wall at RD. 2/510 to 2/533).(Under OTMNP).										ESTIMATE OF QUANTITY	
Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount	Terms and Condition			
				Earnest Money:-				Total			
				Time:-	Rate						
				In Words							
1	Excavation work by mechanical means (hydraulic excavator/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan).including dressing of sides and ramming of bottoms, lift upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	12.00			Per cubic metre						
2	Providing and laying laid in wire crates with 4mm (four millimeters) dia G.I. wire conforming to IS:280 and IS: 4826 in 100x100mm (one hundred into one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (Twenty five kilogramme) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	143.72			Per cubic metre						
							Total				

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi


Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 15/0 to 30/915.(SH:- C/O cement concrete causeway at RD. 20/102 to 20/104).

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 15/0 to 30/915.(SH:- C/O cement concrete causeway at RD. 20/102 to 20/104).									
Sr.No.	Description of Items	Qty.	Estimated Cost:-			Unit	Amount		
			In Fig.	Rate	In Words				
								Earnest Money:-	Time:-
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	44.10				Per Cubic metre			
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	70.86				Per Cubic metre			
						Total			

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division
 HPWB, Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakhtar Bajrol Jungle Beri road km. 15/0 to 30/915.(SH:- C/O PCC R/Wall at RD. 20/095 to 20/099,20).

Estimated Cost:- Rs. 485971.00
Earnest Money:- Rs. 100000.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ranning of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	30.31			Per Cubic metre	
2	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills,filets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	85.72			Per Cubic metre	
3	Providing weep holes in brickstone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm/ one hundred ten millimeter) dia PVC pipe De-plastifinolex/ vecus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	45.00			Each	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tauni Devi Division
HP/PWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 15/0 to 30/915.(SH:- C/O cement concrete causeway at RD. 20/105 to 20/107).

Estimated Cost:- Rs. 482181.00


Earnest Money:- Rs. 9600.00

Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	44.10			Per Cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	71.02			Per Cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kaikar Bajrol jungle Bert road km. 15/0 to 30/915.(SH:- C/O PCC R/Wall at RD, 20/107 to 20/111.20).

NAME OF WORK:- Restoration of rain damages on Tanni Devi Uhal Kakkar Bairol Jungle Beri road km. 15/0 to 30./915.(SH- C/O									
PCC R/Wall at RD, 20/107 to 20/111.20).									
Sr.No.									
Description of Items									
Qty.									
In Fig.									
In Words									
Rate									
Estimated Cost:-									
Earnest Money:-									
Time:-									
Two Months									
Unit									
Amount									
1	Excavation work by mechanical means (hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	33.06					Per Cubic metre		
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills,filets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	85.72					Per Cubic metre		
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plas/Inolex/ vectus pipe having pressure 4kg/per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204,3,7 as per direction of Engineer- in -Charge, including entire cartage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	42.00					Each		
Total									

Terms and Condition

1. Work shall be executed as per PWD specification.


Executive Engineer,
Tauni Devi Division,
HVVMD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 15/0 to 30/915 (SH:- C/O cement concrete causeway at RD. 20/099 to 20/101).

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol jungle Beri road km. 15/0 to 30/915.(SH:- C/0)									
cement concrete causeway at RD. 20/099 to 20/101).									
		Estimated Cost:-		Rs. 482181.00					
		Earnest Money:-		Rs. 9600.00					
		Time:-		Two Months					
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount			
			In Fig.	In Words					
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of slides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and fits and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	44.10			Per Cubic metre				
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and fits and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	71.02			Per Cubic metre				
					Total				
Terms and Condition									

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HP PWD, Tauni Devi

Schedule of Quantity


NAME OF WORK:- Restoration of rain damages on Tanni Devi Uhal Kalikar Bajrol Jungle Berl road km. 15/0 to 30/915.(SH:- C/O PCC R/Wall at RD, 20/090 to 20/094.20).(LHS of road).

Estimated Cost:- Rs. 488871.00
Earnest Money:- Rs. 10000.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ranning of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	30.31			Per Cubic metre	
2	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills,fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size). as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	85.72			Per Cubic metre	
3	Providing weep holes in brickstone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/inox/ vecus pipe having pressure 4kg per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	55.00			Each	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


Executive Engineer,
Tanni Devi Division
HPPWD, Tanni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 15/0 to 30/915.(SH:- C/O cement concrete causeway at RD. 20/112 to 20/114).

Estimated Cost:- Rs. 495331.00
Earnest Money:- Rs. 1000.00

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	30.24			Per Cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	72.96			Per Cubic metre	
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plas/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	15.00			Each	
Total						

Terms and Condition
1. Work shall be executed as per PWD specification.

Anil Gaba
Executive Engineer,
Tauni Devi Division,
HPPWD, Tauni Devi

Schedule of Quantity

Estimated Cost:

Rs. 497674.00
Rs. 1000.00

1. Work shall be executed as per PWD specification.

1. Work shall be executed as per PWD specification.


~~name~~: Ianni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road from km. 15/0 to 30/915.(MDR-105).(SH:- Back filling behind PCC R/Wall from RD. 20/090 to 20/101.50).

NAME OF WORK:- Restoration of rain damages on Taunil Devi Uhal Kalkhar Bajrol Jungle Beri road from km. 15/0 to 30/915.(MDR-105).(SH:- Back filling behind PCC R/Wall from RD. 20/090 to 20/101.50).							
Sr.No.	Description of Items	Qty.	Estimated Cost:-		Rs. 432894.00	Unit	Amount
			Earnest Money:-		Rs. 8700.00		
			Time:-		Two Months		
1	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 granular material as per the direction of the Engineer-in-charge including entire carriage of material within all leads and fits and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	412.28	In Fig.	In Words		Per cubic metre	
Terms and Condition						Total	

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division
 HP PWD-Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road from km. 15/0 to 30/915.(MDR-105).(SH:- Back filling behind PCC R/Wall from RD. 20/103 to 20/114).

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earnest Money:-	Rs. 8700.00		
				Time:-	Two Months		
1	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 granular material as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	412.12				Per cubic metre	
Terms and Condition						Total	


1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division
 H.P.P.W.D.: Tauni Devi

Schedule of Quantity

NAME OF WORK:- C/O link road Nanot to Bakkar Khad via Jamli km. 0/0 to 4/0.(SH:- P/L GSB at RD. 3/500 to 4/00). (Under OTMNP Head).

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:-	Rs. 347883.00		
			Time:-	Rs. 7000.00		
			In Fig.	In Words	Two Months	
			Rate			
1	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads and lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30, including entire carriage of material within all leads and lifts and other incidentals.	175.00			Per cubic metre	
Terms and Condition						
1. Work shall be executed as per PWD specification.					Total	



 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Sujapur Sandhol road (MDR-38) km. 3/00 to 20/00. (SH:- C/O wire crates near Jangal bridge approach at km. 10/135 to 10/155).

NAME OF WORK:- Restoration of rain damages on Sujapur Sandhol road (MDR-38) km. 3/00 to 20/00.(SH:- C/O wire crates near jangal bridge approach at km. 10/135 to 10/155).									
Schedule of Quantity									
Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount			
			Earnest Money:-						
			Time:-	Rate					
			In Fig.	In Words					
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and rramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and its and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	60.00			Per cubic metre				
2	Providing and laying laid in wire crates with 4mm (four millimeters) dia G.I. wire conforming to IS:280 and IS: 4826 in 100x100mm (one hundred into one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (twenty five kilogramme) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and its and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	156.25			Per cubic metre				
					Total				
Terms and Condition									

1. Work shall be executed as per PWD specification.



 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Sujapur Sandhol road (MDR-38) km. 3/00 to 20/00. (SH:- C/O wire crates near Sachuhl Junction at km. 17/960 to 17/975).

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earnest Money:-	Rs.9900.00		
				Time:-	Two Months		
				Rate	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m,(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	18.75				Per cubic metre	
2	Providing and laying laid in wire crates with 4mm (four millimeters) dia G.I. wire conforming to IS:280 and IS: 4826 in 100x100mm (one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (twenty five kilogram) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	162.19				Per cubic metre	
Terms and Condition						Total	

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Dist.

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Sujampur Sandhol road (MDR-38) km. 3/00 to 20/00.(SH:- C/O wire crates at km. 15/100 to 15/115).

Sr.No.	Description of Items	Qty.	Time:-		Two Months	
			Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m,(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	18.75			Per cubic metre	
2	Providing and laying laid in wire crates with 4mm (four millimeters) dia G.I. wire conforming to IS:280 and IS: 4826 in 100x100mm (one hundred into one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (twenty five kilogramme) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	164.06			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

Amit
Executive Engineer,
Tauni Devi Division
HPPWD: Tauni Devi

Schedule of Quantity


NAME OF WORK:- Restoration of rain damages on Uhal to Bagehra via Jandroo road km. 0/00 to 28/000. (SH:- ROFD and Improvement of curves at RD. 18/315 to 18/375).

NAME OF WORK:- Restoration of rain damages on Uhal to Bagehra via Jandroo road Km. 0/00 to 28/000.(SH:- ROFD and improvement of curves at RD. 18/315 to 18/375).									
Schedule of Quantity									
Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount		
				Earnest Money:-	Rs. 398482.00				
				Time:-	Rs. 8000.00				
				Rate	In Words	Two Months			
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical menus including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302,1603.1,1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineres materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e. 127.83/-cubic metre shall be made from the contractor @ Rs. 300/-(three hundred only per cubic metre) amounting to Rs.38,349/-only.	953.33				Per cubic metre			
Total									

Terms and Condition

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

NAME OF WORK:- Restoration of rain damages on Khanuli Kheri Bhaddamber Dudla via Maheshnagar road km. 0/00 to 9/40/SH:- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).

Schedule of Quantity

9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						
9/46/SH- C/O PCC R/Wall at RD. 1/950 to 1/959). (Deposit work).						

Terms and Condition

1. Work shall be executed as per PWD specification.

Anil Kumar
Executive Engineer,
Tauni Devi Division
HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Khanauli Kheri Bhatlamber Dudia via Maheshgual road km. 0/00 to 9/460.(SH:- C/O PCC R/Wall at RD. 1/960 to 1/969). (Deposit work).

NAME OF WORK:- Restoration of rain damages on Khannauli Kheri Bhatlamber Dudia via Mahesbqual road km. 0/00 to 9/460.(SH:- C/O PCC R/Wall at RD. 1/960 to 1/969). (Deposit work).						
Schedule of Quantity						
Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			In Fig.	In Words		
			Rate	Time:-	Two Months	
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	23.85			Per Cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one cement: four sand: eight graded stone aggregated 40mm (forty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	47.52			Per Cubic metre	
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plastifinolex/ vecus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of (V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	21.00			Each	
Terms and Condition					Total	

1. Work shall be executed as per PWD specification.

Anil Kumar
Executive Engineer,
Tauni Devi Division
HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bairol Jungle Beri road km. 0/00 to 30/915.(SH:- C/O R/Wall at RD. 5/560 to 5/570).

NAME OF WORK:- Restoration of rain damages on Taml Devl Uhal Kakkar Bajrol Jungle Bert road km. 0/00 to 30/915.(SH:- C/0 R/Wall at RD. 5/560 to 5/570).							Estimated Cost:-	Rs. 203290.00
							Earnest Money:-	Rs. 4100.00
Sr.No.	Description of Items	Qty.	Time:-		Two Months			
			In Fig.	In Words	Unit	Amount		
1	Excavation work by mechanical means (Hydraulic excavator/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	25.20			Per Cubic metre			
2	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills,fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	45.01			Per Cubic metre			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plastiflex/ vectus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1/V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.	15.00			Each			
Total								

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPWD, Tauni Devi

Schedule of Quantity
N/ME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol jungle Beri road km. 0/00 to 30/915.(SH:- C/O
R/Wall at RD. 2/110 to 2/120 and 2/130 to 2/142).

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earnest Money:-	Rs. 332496.00		
				Time:-	Rs. 6500.00		
				Rate	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and raiming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	26.42				Per Cubic metre	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillers, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	74.25				Per Cubic metre	
3	Providing weep holes in brickstone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plastiflex/ vectus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1V, 20H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- In -Charge, including entire carriage of material within all leads and lifts and other incidentals.	28.00				Each	
Terms and Condition						Total	

1. Work shall be executed as per PWD specification.

Anand Kumar
 Executive Engineer,
 Tauni Devi Division
 H.P.P.W.D.: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road Nadiana Sadiana to village Chowki Bahal km. 0/0 to 4/00 .(SH:- C/O R/Wall at RD. 2/690 to 2/705).

Schedule of Quantity						
NAME OF WORK:- Restoration of rain damages on link road Nadiana Sadiana to village Chowki Bahal km. 0/0 to 4/00 .(SH:-						
c/O R/wall at RD. 2/690 to 2/705).						
Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:-	Rs. 349082.00		
Time:-						
Two Months						
		In Fig.	Rate	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and rammings of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	37.88			Per Cubic metre	
2	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills,fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	79.61			Per Cubic metre	
4	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vecus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.	20.00			Each	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

Anand Gh
Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi


Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Hamirpur Sujampur road (MDR-86) km. 2/600 to 16/0. (SH:- C/O R/Wall at RD. 12/415 to 12/435).

Sr.No.	Description of Items	Qty.	Time:-		Unit	Amount
			Rate			
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m,(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	40.00			Per Cubic metre	
2	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills,fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	108.90			Per Cubic metre	
4	Providing weep holes in brickstone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm/ one hundred ten millimeter) dia PVC pipe De-plast/inox/ vecus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	45.00			Each	
Terms and Condition					Total	

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi


Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungel Beri road from 15/00 to 30/915. (SH:- Providing and laying wire crate at km 25/640 to 25/650 & 25/665 to 25/674)

Sr. No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:-	Time:-		
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	47.50			Per cubic metre	
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming of IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10(ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogram) each as per drawing and technical specifications Clause 130.1 as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	146.88			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Anil Kumar
 Executive Engineer,
 Tauni Devi Division
 H.P.W.D.: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Barara to Bakkar Khad via Patnuncun road km. 2/00 to 8/00. (SH:- C/O R/Wall at RD. 2/840 to 2/858).

NAME OF WORK:- Restoration of rain damages on Barara to Bakkar Khad via Patnecun road km. 2/00 to 8/00.(Sh:- C/O R/Wall at RD. 2/840 to 2/858).							Estimated Cost:- Rs. 285431.00
							Earnest Money:- Rs. 5700.00
							Time:- Two Months
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount	
			In Fig.	In Words			
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals.	39.42			Per Cubic metre		
2	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills,fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals.	62.84			Per Cubic metre		
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plas/inox/ vedus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire cartage of material within all leads and lifts and other incidentals.	23.00			Each		
Total							

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tanni Devi Division,
HPPWD: Tanni Devi