

Office of the Executive Engineer, B&R Division, HP PWD Kalpa District Kinnaur (HP)

Web:- www.hppwd.gov.in E mail:- hp-kin@nic.in

Phone No:- 01786-226027 Fax:- 01786-226027.

No:- PW/KNR-E-Tender/2022-
To

5532-34

Dated:- 11-10-2023

"

The Executive Engineer (IT Cell),
HP.PWD. Shimla-2.

Subject:-

Publication of Tender Notice (OFFLINE)

Enclosed please find herewith the Tender of works costing below 1.00 Lac as given in the Notice Inviting Tender for uploading on the departmental website as per notification vide Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B) 1/2020 dated 16-07-2021. The works mentioned in the tender notice are urgent in nature and public interest.

Encl:- NIT, Schedule of Quantity
& Certificate.


Executive Engineer,
Kalpa Division,
HP.PWD. Kalpa.

Copy forwarded for information to:-

1. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
2. Copy to Drawing Branch in this office.


Executive Engineer,
Kalpa Division,
HP. PWD, Kalpa

CERTIFICATE

Certified that the Tender for works called vide this

office Letter No. PW/KNR/E-Tender/2023-5522-31 dated 10-10-2023.

from Sr. No. 1 to 11 are of urgent nature and public interest.


Executive Engineer,
Kalpa Division,
HP.PWD. Kalpa.


HP.P.W.D. TENDER NOTICE.(offline)

Sealed item rate offline tender on form PWD-6 & 8 are hereby invited on behalf of Governor of Himachal Pradesh by the Executive Engineer, Kalpa Division, HP, PWD. Kalpa for the following works from the approved and eligible contractors enlisted in HP.PWD; so as to reach in the office of the Executive Engineer Kalpa Division HP.PWD. Kalpa on or before **26-10-2023 up to 10.30 A.M.** and shall be opened on the same day at **11:00 AM** in presence of intending contractors or their authorized representatives. The tender form documents can be had from this office (Kalpa Division, HPPWD Kalpa) against cash payment (Non-refundable) on any working day during the office hours upto **4:00 P.M.** on **26-10-2023**. No application for issue of tender forms will be received on **25-10-2023** after **4:00 PM**. If the office happens to be closed on the above mentioned dates, the tenders will be sold/ opened on the next working day at the same time and venue. The Earnest Money in the shape of National Saving Certificate, F.D.R,s any Post office/ Bank in H.P. duly pledged in the name of Executive Engineer, Kalpa Division, HP.PWD. Kalpa must accompany with each tenders. Conditional tenders and application (For purchase of tender forms) received without Earnest Money summarily be rejected. The offer of the tenders shall be kept open for 120 days. The Executive Engineer Reserves (Right to accept or to reject any) or all the tenders without assigning any reasons.

Sr. No.	Name of work	Estimated cost	Earnest Money	Time allowed	Cost of form	Eligible class of contractor
1	A/R & M/O Peo Kalpa C.P. road Km. 0/00 to 6/675 (SH:- P/L G-II, G-III and premix carpet and repair of pot holes from Km. 0/00 to 2/00)	4,99,044/-	10,000/-	Three Months	350/-	D" Class
2	S/R to District Level Conference Bhawan at Reckong Peo in District Kinnaur HP (SH:- P/L HDF flooring in conference Hall Job No.- 1)	4,99,439/-	10,000/-	One Month	350/-	D" Class
3	S/R to District Level Conference Bhawan at Reckong Peo in District Kinnaur HP (SH:- P/L HDF flooring in conference Hall Job No.- 2)	4,99,586/-	10,000/-	One Month	350/-	D" Class
4	S/R to District Level Conference Bhawan at Reckong Peo in District Kinnaur HP (SH:- P/L 19mm. ply, HDF flooring etc. in Conference Hall)	2,32,676/-	5,000/-	One Month	350/-	D" Class
5	S/R to District Level Conference Bhawan at Reckong Peo in District Kinnaur HP (SH:- P/L 19 mm. ply board in Conference Hall)	4,19,839/-	8,500/-	One Month	350/-	D" Class
6	Annual repair and maintenance of New Circuit House at Kalpa in District Kinnaur HP (SH:- Repair of furniture Job No. 1)	4,99,877/-	10,000/-	Three Months	350/-	D" Class
7	Annual repair and maintenance of New Circuit House at Kalpa in District Kinnaur HP (SH:- Repair of furniture Job No. 2)	4,99,931/-	10,000/-	Three Months	350/-	D" Class
8	C/O NGOs Mess at Police Line Reckong Peo in District Kinnaur (HP) (SH:- Making furniture in Suits No. 1 to 3)	4,99,188/-	10,000/-	One Month	350/-	D" Class
9	C/O NGOs Mess at Police Line Reckong Peo in District Kinnaur (HP) (SH:- Making furniture in Suits No. 4 to 5)	4,99,109/-	10,000/-	One Month	350/-	D" Class
10	Additional Alteration for the Rest House at Moorang in District Kinnaur (HP) (SH:- Making furniture for Suit No. 1 to 3)	4,35,140/-	9,000/-	One Month	350/-	D" Class

11	Additional Alteration for the Rest House at Moorang in District Kinnaur (HP) (SH:- Making furniture for Suit No. 3 to 6)	3,01,396/-	6,000/-	One Month	350/-	D" Class
----	--	------------	---------	-----------	-------	----------

Terms and conditions:-

Following documents should accompany the application for tenders:-

1. Copy of valid enlistment/renewal order.
2. Copy of GST Registration No.
3. Proof of Valid E.P.F accounts No allotted by the Provident Fund Commissioner Shimla and copy of PAN No.
4. Ambiguous/Telegraphic/conditional tenders or tenders by fax/E-Mail shall not been entertained/considered in any case.
5. The contractors should quote the rates of each items in words as well as figures in the Schedule of quantity.
6. The earnest money must also accompany with the application for the tender documents.
7. The tender shall be issued to those contractors who have not more than two works in hand.



Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.

Dated:- 10-10-2023

No.PW/KNR-E-Tender/NIT/2023- 5522-31

Copy forwarded for information to:-

1. 1 The Engineer-in-Chief, HP.PWD. Shimla-2.
2. The Deputy Commissioner, Kinnaur District at Reckong Peo.
3. The Sub Divisional officer (Civil) Kalpa at Reckong Peo.
4. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
5. The Block development officer, Kalpa at Reckong Peo.
6. The Chairman, Zila Parishad, Kinnaur District at Reckong Peo.
7. The Chairman, Panchayat Samiti Kalpa at Reckong Peo.
8. Drawing Branch in this office.
9. All the Contractors under this Division.
10. Notice Board.


Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,99,044/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Name of work:- A/R & M/O Peo Kalpa C.P. Road Km 0/00 to 6/675

(SH:- P/L G-II, G-III and Premix carpet and repair of pot holes fro Km 0/00 to 2/00)

	Description of items	Qty.	Rate	Unit	Amount
			In Fig.		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405. By manual means, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	33.49		Per Cubic meter	
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405. By manual means, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	33.49		Per Cubic meter	
3	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg per sqm (Zero point twenty five to zero point thirty kilogram per square metre) on the prepared granular surfaces treated with primer & cleaned with Hydraulic broom as per Technical Specification Clause 503, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	446.50		Per Square meter	

4	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70(zero point seven zero)-1.00(one point zero zero) kg/sqm(kilogram per square meter) using mechanical means as per Technical Specification Clause 502, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	446.50			Per Square meter
5	Providing laying and rolling of open graded premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm to 5.6 mm(thirteen point two millimeter) to six millimeter) aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on previously prepared base, including mixing in a suitable plant, laying and rolling with three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat either Type A as per technical Specification Clause 508. By mechanical means bitumen (S-90)/VG-10, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	446.50			Per Square meter
6	Providing and laying seal coat sealing the voids in bituminous surface laid to the specified levels, grade and cross fall using Type B as per technical specification clause 510 by mechanical means bitumen (S-90)/VG-10, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	446.50			Per Square meter
7	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimetre) thick premix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	68.75			Per Square meter
					Total:-


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- S/R to District level conference Bhawan at Reckong Peo in distt. Kinnaur (H.P)
(SH:- P/L HDF flooring in conference Hall Job No. 1).

Estimated Cost :- 4,99,439/-

Earnest Money :- 10,000/-

Time :- One month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and fixing HDF decorative laminated core board German Kerona flooring AC4 class 32.7mm (thirty two point seven millimeter) thick placed over cushion of 2mm (two millimeter) thick expanded polythene foam plus 100 (one hundred) micron thick polythene sheet, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	135.66			Per Square meter	
				Total:-		

Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.

3

SCHEDULE OF QUANTITY

Name of work:- S/R to District level conference Bhawan at Reckong Peo in distt. Kinnaur (H.P)
(SH:- P/L HDF flooring in conference Hall Job No. 2).

Estimated Cost :- 4,99,586/-
Earnest Money :- 10,000/-
Time :- One month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and fixing HDF decorative laminated core board German Kerona flooring AC4 class 32.7mm (thirty two point seven millimeter) thick placed over cushion of 2mm (two millimeter) thick expanded polythene foam plus 100 (one hundred) micron thick polythene sheet, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	135.70			Per Square meter	
				Total:-		


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- S/R to District level conference Bhawan at Reckong Peo in distt Kinnaur (H.P)
(SH:- P/L 19 mm ply, HDF flooring etc in conference Hall).

Earnest Money :- 5,000/-

Time :- One month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and fixing 19mm(nineteen millimeter) thick Commercial Board water proof shutters for cup boards including fixing with nickel plated piano hinges with screws etc complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	64.80			Per Square meter	
2	Providing and fixing HDF decorative laminated core board German Kerona flooring AC4 class 32.7mm (thirty two point seven millimeter) thick placed over cushion of 2mm (two millimeter) thick expanded polythene foam plus 100 (one hundred) micron thick polythene sheet, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	16.80			Per Square meter	
3	Polishing two or more coats with malamine polish of required shade on new wood and wood based surfaces to give an even surface including cleaning the surface of all dirt , dust and sand papered smooth and including a coat of wood filler, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	153.60			Per Square meter	
						Total:-

Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- S/R to District level conference Bhawan at Reckong Peo in distt. Kinnaur (H.P)
(SH:- P/L 19 mm ply board in conference Hall).

Estimated Cost :- 4,19,839/-

Earnest Money :- 8,500/-

Time :- One month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and fixing 19mm(nineteen millimeter) thick Commercial Board water proof shutters for cup boards including fixing with nickel plated piano hinges with screws etc complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	216.00			Per Square meter	
				Total:-		


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

⑥

Name of work:- Annual repair & Maintiance of New Circuit House at Kalpa in Distt. Kinnaur (H.P.)
(SH:- Repair of furniture Job No.-1).

Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Katpa.

Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Annual repair & Maintenance of New Circuit House at Kalpa in Distt. Kinnaur (H.P.)
(SH:- Repair of furniture Job No.-2).
 Estimated Cost :- 4,99,931/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and fixing fabric for sofa set including cutting and sewing with all necessary fitting, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	61.13			Per Square meter	
2	Providing and fixing polyurethane foam sheet of all sizes for sofa set including all fitting, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	61.13			Per Square meter	
3	Melamine polishing on wood work (one or more coat), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	82.66			Per Square meter	
4	Providing wood work in frames of sofa set, chair, tables, dining table, doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1.13			Per Cubic meter	
				Total:-		


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,99,188/-
 Earnest Money :- 10,000/-
 Time :- One month

Name of work:- C/O NGOs Mess at Police Line at Reckong Peo in distt. Kinnaur (H.P)
 (SH:- Making furniture in Suits No. 1 to 3).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and fixing 19mm(nineteen millimeter) thick Commercial Board water proof shutters for cup boards including fixing with nickel plated piano hinges with screws etc complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	56.71			Per Square meter	
2	Providing and fixing 1.00mm(one point zero millimeter) thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	30.90			Per Square meter	
3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Deodar wood, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.01			Per Cubic meter	
4	Providing and fixing Heavy duty Smooth Soft Close Hydraulic Shocker pair for Bed Box Lift Mechanism, Weight Capacity 150kg (one hundred fifty kilogram): Set of 2 pcs(two pieces), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	6.00			Per Pair	

5	Polishing two or more coats with malamine polish of required shade on new wood and wood based surfaces to give an even surface including cleaning the surface of all dirt , dust and sand papered smooth and including a coat of wood filler, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	43.81			Per Square meter	
6	Providing and fixing superior quality cloth curtain including sewing(double lining) complete:(Size not less than 1.05m x 2.05m (one point zero five into two point zero five meter), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	27.00			Each	
					Total:-	


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa

SCHEDULE OF QUANTITY

Name of work:- C/O NGOs Mess at Police Line at Reckong Peo in distt. Kinnaur (H.P)
(SH:- Making furniture in Suits No. 4 to 5).

Estimated Cost :- 4,99,109/-
Earnest Money :- 10,000/-
Time :- One month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and fixing 19mm(nineteen millimeter) thick Commercial Board water proof shutters for cup boards including fixing with nickel plated piano hinges with screws etc complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	42.82			Per Square meter	
2	Providing and fixing 1.00mm(one point zero millimeter) thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	19.16			Per Square meter	
3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Deodar wood, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1.688			Per Cubic meter	
4	Providing and fixing Heavy duty Smooth Soft Close Hydraulic Shocker pair for Bed Box Lift Mechanism, Weight Capacity 150kg (one hundred fifty kilogram): Set of 2 pcs(two pieces), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	6.00			Per Pair	

5	Polishing two or more coats with malamine polish of required shade on new wood and wood based surfaces to give an even surface including cleaning the surface of all dirt , dust and sand papered smooth and including a coat of wood filler, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	43.81			Per Square meter	
6	Providing and fixing superior quality cloth curtain including sewing(double lining) complete:(Size not less than 1.05m x 2.05m (one point zero five into two point zero five meter), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	57.00			Each	
					Total:-	


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa

10

SCHEDULE OF QUANTITY

Estimated Cost :- 4,35,140/-
 Earnest Money :- 9,000/-
 Time :- One month

Name of work:- Add. Alteration for the Rest House at Moorang in Distt. Kinnaur (H.P.)

(SH:- Making furniture for Suit No. 1 to 3).

	Description of items	Qty.	Rate	Unit	Amount
			In Fig. In Words		
1	Providing and fixing 19mm(nineteen millimeter) thick Commercial Board water proof shutters for cup boards including fixing with nickel plated piano hinges with screws etc complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	62.83		Per Square meter	
2	Providing and fixing 1.00mm(one point zero millimeter) thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	31.62		Per Square meter	
3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Deodar wood, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1.975		Per Cubic meter	
4	Providing and fixing Heavy duty Smooth Soft Close Hydraulic Shocker pair for Bed Box Lift Mechanism, Weight Capacity 150kg (one hundred fifty kilogram): Set of 2 pcs(two pieces), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	6.00		Per Pair	

5	Polishing two or more coats with malamine polish of required shade on new wood and wood based surfaces to give an even surface including cleaning the surface of all dirt , dust and sand papered smooth and including a coat of wood filler, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	43.81			Per Square meter	
					Total:-	


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa

SCHEDULE OF QUANTITY

Name of work:- Add. Alteration for the Rest House at Moorang in Distt. Kinnaur (H.P.)
 (SH:- Making furniture for Suit No. 3 to 6).

Estimated Cost :- 3,01,396/-
 Earnest Money :- 6,000/-
 Time :- One month

	Description of items	Qty.	Rate	Unit	Amount
			In Fig.		
1	Providing and fixing 19mm(nineteen millimeter) thick Commercial Board water proof shutters for cup boards including fixing with nickel plated piano hinges with screws etc complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	50.62		Per Square meter	
2	Providing and fixing 1.00mm(one point zero millimeter) thick coloured or plain lamination sheet (summica) on boards/ply wood sheets with approved adhesive and nails etc complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	27.12		Per Square meter	
3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Deodar wood, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1.158		Per Cubic meter	
4	Providing and fixing Heavy duty Smooth Soft Close Hydraulic Shocker pair for Bed Box Lift Mechanism, Weight Capacity 150kg (one hundred fifty kilogram): Set of 2 pcs(two pieces), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	6.00		Per Pair	

5	Polishing two or more coats with malamine polish of required shade on new wood and wood based surfaces to give an even surface including cleaning the surface of all dirt , dust and sand papered smooth and including a coat of wood filler, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	43.81			Per Square meter	
						Total:-


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.