

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER

Sealed **percentage rate** tender on form No. 6 and 8 are hereby invited by the Executive Engineer (NH) Division HPPWD Nahan on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD, so as to reach in this office on **30.10.2023** up to 11:00 AM and shall be opened on the same day at 11.30 AM in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to **30.10.2023 04:00 PM**


The earnest money in the shape of FDR/TDR of any Bank in H.P. duly pledged in favour of Executive Engineer NH Division HP.PWD Nahan must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.

Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form
1	Ordinary repair to Nahan Do Sarka Sarahan Kumarhatti road on NH 907A Km 0/00 to 78/00 (SH:- Repair of Pot Hole in Km 33/00 to 36/00).	4,99,010/-	10000/-	15 days	350/-
2	Ordinary repair to Nahan Do Sarka Sarahan Kumarhatti road on NH 907A Km 0/00 to 78/00 (SH:- Repair of Pot Hole in Km 36/00 to 42/00).	4,99,297/-	10000/-	15 days	350/-
3	Ordinary repair to Nahan Do Sarka Sarahan Kumarhatti road on NH 907A Km 0/00 to 78/00 (SH:- Repair of Pot Hole in Km 75/00 to 78/00).	4,99,597/-	10000/-	15 days	350/-

**CERTIFICATE:- It is certified that the tenders of above work are exigency/emergent nature and in public interest.**

**Terms & Conditions:-**

1. The Contractors/Bidders must quoted their Permanent Income Tax Account Number/ GST number on the tender alongwith copy of the same be attached with the application.
2. The Contractors/Firms should attach copy of the Registration/Renewal with the application.
3. The contractor/bidders should quote his rates Both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. before quoting the bid/tender.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firms should have to produce the details of works in hand in HP. PWD, and its position thereof alongwith application.
7. The tender documents shall be issued to only those contractors who does not have more than two works in hand in any PWD Circle/ Division worth Rs. 1.00 Crore each.
8. The Contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 75 days.
10. The provision of guidelines issued vide the Principal Secretary (PW) to the Govt. of H.P, Shimla vide notification No. PBW (B) A (3) 1/2020-I dated Shimla-2 the 22nd July, 2020 and 07.10.2021 regarding adoption of CPWD work manual 2019 & other publication of CPWD in HPPWD and others as published by the Govt. from time to time Shall also be applicable.
11. The Executive Engineer reserve the right to reject any or all the tenders without assigning any reason.

  
Executive Engineer  
NH Division HPPWD  
Nahan

For & on behalf of Governor of Himachal Pradesh

No. PW/NHD-NHN/TA-Tender Notice/ 2022-23: **3588-365** dated:- **19-10-23**


Copy along with NIT is forwarded to the following for kind information and necessary action please:-

- 1 The Engineer in Chief HPPWD Nirman Bhawan, Niagam Bihar Shimla.

Cont. p-2



- 2 The Chief Engineer (NH) HPPWD Shimla please.
- 3 The Deputy Commissioner, Sirmour at Nahan please.
- 4 The Superintending Engineer (NH) Circle HPPWD Shimla.
- 5 The Executive Engineer (IT Cell), to the Engineer-in-Chief HPPWD, Nigam Vihar, HPPWD Shimla-2 alongwith Schedule of Quantity through (email) for taking necessary action in view of Principal Secretary (PW) to the H.P. notification No. PBW (B) A (3) dated 16 July, 2021 for uploading of Notice Inviting Tender on departmental website please.
- 6 The Sub-Divisional Magistrate Nahan/ Paonta Sahib/Pachhad please.
- 7 The District Panchayat Officer, Nahan please.
- 8 The Executive Officer, Municipal Committee Nahan/ Paonta Sahib please.
- 9 All the Assistant Engineer under this division to display on their respective Notice Boards.
- 10 Notice Board of this Office.

  
Executive Engineer  
NH Division HPPWD  
Nahan



## SCHEDULE OF QUANTITY

Name of work: Ordinary repair to Nahana Do Sarika Sarahan Kumharhatti road on NH 907A Km 0/00 to 78/00 ( SH:- Repair of Pot Holes in Km 33/00 to 36/00)

		Estimated cost :-		Rs.499010.00/- only	
		Earnest Money :-		RS.10000.00/-only	
		Time Limit :-		15 Days.	
Sr.No	Description of item/Sub Head	Quantity	Unit	Estimate Rate	Total Amount
1	Providing and applying tack coat with bitumen emulsion RS-I using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge. For Patch work & Slurry Seal	824.85	Per Sqm	16.7	13775.00
2	Providing and laying slurry seal consisting of a mixture of line aggregates, Portland cement filler, bituminous emulsion and water on a road surface including cleaning of surface, mixing of slurry seal in a suitable mobile plant, laying and compacting to provide even riding surface including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	50.30	Per Sqm	83.85	4218.00
3	Providing and laying 40mm thick Bituminous Concrete Grading -II Providing and laying bituminous concrete with higher capacity batch type hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 Percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	30.98	Per Cubic metre	15526.70	481017.00
Total :-					499010.00
Quoted Rate % (Percentage) in Figures		(+) / (-)			Four lakh ninety nine thousand ten only
Quoted Rate % (Percentage) in Words					

The contractor shall procure all the materials conforming to specification MORTH at his own risk and cost. All the rates including octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the Government.

Executive Engineer  
NH Division  
HPPWD Nahana



**SCHEDULE OF QUANTITY**


**Name of work:- Ordinary repair to Nahan Do Sarka Sarahan Kumarhati road on NH 90/7A Km 0/00 to 78/00 (Sl:- Repair of Pot Holes in Km 36/00 to 42/00)**

**Estimated cost :-** Rs.499297.00/- only  
**Earnest Money :-** RS.10000.00/-only  
**Time Limit :-** 15 Days.

Sr.No	Description of item/Sub Head	Quantity	Unit	Time Limit :-		Total Amount	Total Amount in word
				Estimate Rate	Estimate		
1	Providing and applying tack coat with bitumen emulsion RS-I using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge. <b>For Patch work &amp; Slurry Seal</b>	891.5	Per Sqm	16.8		14977.00	Fourteen thousand nine hundred seventy seven only
2	Providing and laying slurry seal consisting of a mixture of line aggregates, Portland cement filler, bituminous emulsion and water on a road surface including cleaning of surface, mixing of slurry seal in a suitable mobile plant, laying and compacting to provide even riding surface including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	100.20	Per Sqm	83.15		8332.00	Eight thousand three hundred thirty two only
3	Providing and laying 40mm thick Bituminous Concrete Grading -II Providing and laying bituminous concrete with higher capacity batch type hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 Percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	31.65	Per Cubic metre	15039.10		475988.00	Four lakh seventy five thousand nine hundred eighty eight only
<b>Total :-</b>						499297.00	Four lakh ninety nine thousand two hundred ninety seven only
<b>Quoted Rate % (Percentage) in Figures</b>				(*)/(c)			
<b>Quoted Rate % (Percentage) in Words</b>							

The contractor shall procure all the materials conforming to specification MORTH at his own risk and cost. All the rates including octroi, royalty, malikana, toll tax, GST or other taxes imposed by the Government.

Executive Engineer  
 NH Division  
 HPPWD Nahan

  
 8




**SCHEDULE OF QUANTITY**

Name of work:- Ordinary repair to Nahana Do Sarika Sarahan Kumarhatti road on NH 907A Km 0/00 to 78/00 (SH:- Repair of Pot Holes in Km 75/00 to 78/00)

SCHEDULE OF QUANTITY									
Name of work:- Ordinary repair to Nahan Do Sarika Sarahan Kumarhatti road on NH 907A Km 0/00 to 78/00 (SH:- Repair of Pot Holes in Km 75/00 to 78/00)									
Sr.No	Description of Item/Sub Head	Quantity	Unit	Estimated cost :-		Estimated cost :-		Total Amount in word	
				Estimate Rate	Total Amount	Earliest Money :-	15 Days.		
1	Providing and applying tack coat with bitumen emulsion RS-I using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge. <b>For Patch work &amp; Slurry Seal</b>	876.55	Per Sqm	16.9	14814.00			Forteen thousand eight hundred fourteen only	
2	Providing and laying slurry seal consisting of a mixture of line aggregates, Portland cement filler, bituminous emulsion and water on a road surface including cleaning of surface, mixing of slurry seal in a suitable mobile plant, laying and compacting to provide even riding surface including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	100.50	Per Sqm	83.95	8437.00			Eight thousand four hundred thirty seven only	
3	Providing and laying 40mm thick Bituminous Concrete Grading -II Providing and laying bituminous concrete with higher capacity batch type hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 Percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	31.04	Per Cubic metre	15346.20	476346.00			Four lakh seventy six thousand three hundred forty six only	
Total :-					499597.00			Four lakh ninety nine thousand five hundred ninety seven only	
Quoted Rate % (Percentage) in Figures		(+) / (-)							
Quoted Rate % (Percentage) in Words									

The contractor shall procure all the materials conforming to specification MORTH at his own risk and cost. All the rates including octroi, royalty, malikana, toll tax, GST or other taxes imposed by the Government.

  
 Executive Engineer  
 NH Division  
 HPPWD Nahana

Vol No. 3