

Sealed tenders on item rates on PWD form 6 & 7 are hereby invited by the Executive Engineer, Tauni Devi Division, and HPPWD Tauni Devi for the following works. The tender shall be received in this office on or before 07.11.2023 up to 11:00 AM and the same shall be opened on the same day at 11:30AM in the presence of the contractor/first. The application for the issue of tender document shall be received on dated 04.11.2023 upto 2:30PM and the tender form will be sold on cash payment (non refundable) on dated 06.11.2023 from 11.30 AM to 4:00 PM

Sr. No.	Name of Work	Estimated Cost (Rs.)	Earnest Money	Time Limit	Cost of form
1	R/R damages on Kakkar Sachuhi road km 0/0 to 8/500 (Sh:- P/L G-III & Premix carpet in patches in km 0/00 to 1/500	493059/-	10000/-	Two Months	350.00
2	R/R damages on Kakkar Sachuhi road km 1/500 to 2/300 link road to Jamuli Mata Mandir km 0/00 to 1/870 & link road to Chamiyana-Di-Khanauli km 0/00 to 2/200 (Sh:- P/L premix carpet in patches)	486485/-	9700/-	Two Months	350.00
3	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km 15/0 to 30/915 (Sh:- P/L G-III & premix carpet in patches in km 22/00 to 28/00)	493359/-	10000/-	Two Months	350.00
4	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km 15/0 to 30/915 (Sh:- P/L G-III & premix carpet in patches in km 15/00 to 22/00)	493359/-	10000/-	Two Months	350.00
5	R/R damages on Sujanpur Sandhol road km 3/00 to 20/00 (Sh:-P/L patch work in km 10/00 to 20/00)	385649/-	7700/-	Two Months	350.00
6	R/R damages on Sujanpur Sandhol road km 3/00 to 20/00 (Sh:-P/L patch work in km 3/00 to 10/00)	439379/-	8800/-	Two Months	350.00
7	R/R damages on Hamirpur Sujanpur road (MDR)-86) (Sh:-P/Lpatch work km 10/600 to 12/00 and 13/00 to 16/00)	492867/-	9800/-	Two Months	350.00
8	R/R damages on link road Kuthera Chalokhar via Dei Ka Naun km 1/00 to 2/700 & link road to village Kakru km 0/0 to 0/500 (SH:- Providing and laying pach work)	212482/-	4300/-	Two Months	350.00
9	R/R damages on link road Pastal to Bugdhar Matroh road km 0/0 to 3/500(Sh:-Providing laying patch work)	498310/-	10000/-	Two Months	350.00
10	C/O link road from Khadoula to Darsal G.P Dera (SH:- P/L patch work in km 0/00 to 1/500) Deposit work	332695/-	6600/-	Two Months	350.00
11	R/R damages on Barin Dhawal via Siswan Ghalot road km 0/00 to 5/00 (Sh:-P/L patch work in km 1/00 to 2/00 & 3/00 to 5/00 (ii) R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km 0/00 to 7/300 (sh:- P/L Patch work in km 6/00 to 7/300)	443215/-	8800/-	Two Months	350.00
12	R/R damages on Lungwan Tauni Devi road km .3/345 to 7/305 (SH:- Providing patch work)	472492/-	9500/-	Two Months	350.00
13	Prepainted sheet Chajja in old civil Hospital building at Sujanpur Tihra (SH:- Demolition of old Chajja and providing and fixing of sheet (steel) Chajja) (Deposit work)	303340/-	6100/-	Two Months	350.00
14	Prepainted sheet Chajja in old civil Hospital building at Sujanpur Tihra (SH:- Demolition of old Chajja and providing and fixing of sheet (steel) Chajja) (Deposit work)	287499/-	5800/-	Two Months	350.00
15	Providing and fixing of shed on balconies of Ravi Hostel at Sainik School Sujnapur Thira Distt Hamirpur (HP) (P/F prepainted sheet shed) (Deposit work)	454699/-	9100/-	Two Months	350.00
16	R/R damages on Patlander Bhagolu Ree road km 0/00 to 7/120 (SH:- Installation of crash barriers valley side at RD 1/945 to 1/965 and 2/465 to 2/485 with R/wall at RD2/470 to 2/479)	215763/-	4400/-	Two Months	350.00
17	Special repair to Sanik School Rest House at Sujanpur (Providing entrance gate and providing window shutter and flush door) Deposit work	134231/-	2700/-	Two Months	350.00
18	Preparation of FCA Case under Tauni Devi Sub-Division,HP:PWD, Tauni Devi (Sh:- Data preparation of KML file digital map with coordinates and C.A map and HPS file including online submission of forest case) (i) C/O link road Krust to Dhuntar via Shamsher Singh House km .0/0 to 1/700 (MLA Priorty) (ii) Link road to Amit vKapil House Dalwana (Under OTMNP)	363000/-	7300/-	Two Months	350.00
19	Preparation of FCA case of link road from Anu to Gharan Masanda km 0/0 to 0/400 (Sh:-Data preparation of KML file digital map with coordinates and C.A map and HPS file including online submission of forest case) (Under OTMNP)	174000/-	3500/-	Two Months	350.00
20	C/O link road Kaloh to Bakkar Kahd via Bakniar km 0/0 to 0/750 (SH:- C/O C.C rigid pavement at RD 0/108 to 0/150) Deposit work	188587/-	3800/-	Two Months	350.00

21	C/O link road from Naughin to Thai km 0/0 to 0/400 (SH:- C/O R.C.C hume pipe culvert 900mm dia at RD 0/270 with wing walls) (Deposit work)	118788/-	2400/-	Two Months	350.00
22	C/O preapainted sheet shed for Dhobi Ghat at Sainik School Sujanpur Thira (SH:- Foooting plinth beam etc) (Deposit work)	239479/-	4800/-	Two Months	350.00
23	R/R damages on Behrda Bajrol via Tholu road km 0/0 to 4/00 (SH:- C/O PCC R/wall at RD 1/780 to 1/800) Deposit work	284217/-	5700/-	Two Months	350.00
24	(i) C/O link road from Khadola Kahd to Balla Rathiyan via Sabzi Mandi km 0/00 to 1/557 (ii) C/O link road to village Kangral G.P Ranger km 0/0 to 1/500 (iii) C/O link road from Chakriyana to nallahi via Gahla-jagehri including one bridge km 0/00 to 4/500) (SH:- Preapparation of DPR there of)	324710/-	6500/-	Two Months	350.00
25	C/o link road from Banalag to lower Utpur including one bridge km 0/00 to 5/00 (SH:-Preparation of DPR and Hydraulic data there of) C/O Degree college at Tauni Devi (SH:- Survy and contour site plan)	356300/-	7100/-	Two Months	350.00
26	(i) Link road from Pohanj to Lower Pohanj under NABARD (ii) C/O Science Lab at Govt.Sr.Sec School Pohanj (iii) C/O J.E Office Cum residence Building at Uhal .(iv) C/O Science Lab.at Govt.Sr.Sec School Uhal (SH:- Preparation of DPR there of)	350000/-	7000/-	Two Months	350.00
27	R/R damages on Uhal to Bagehra via Jandroo road km 0/00 to 27/00(SH:- C/O R/wall at RD 9/615 to 9/628)	393223/-	7900/-	Two Months	350.00
28	R/R damages on Phonj to Andral road km 0/00 to 3/695 (Sh:- C/O wire crate at RD 1/953 to 1/948 & 1/790 to 1/795)	479721/-	9600/-	Two Months	350.00
29	R/R damages on Kakkar Sachuhi road from km 0/00 to 8/500 (SH:- C/O wire crate R/wall at RD 5/530 to 5/543)	433620/-	8700/-	Two Months	350.00
30	R/R damages on Sujanpur to Sandhole road km 3/00 to 20/00(SH:- C/O wire crates at km 13/200 to 13/210 & 17/610 to 17/620)	428519/-	8500/-	Two Months	350.00
31	R/R damages on Tauni Devi Uhal Kakr Bajrol Jungle Beri road km .0/00 to 30/915 (MDR-105) (SH:- C/O R/wall at RD 9/020 to 9/039)	438587/-	8800/-	Two Months	350.00
32	Repair and restoration of link road Beri to Kudana km 0/00 to 3/00 (SH:- C/O B/wall at RD 2/100 to 2/115 near house of Sh. Anirudh Chauhan) Deposit work	213612/-	4300/-	Two Months	350.00
33	R/R damages on link road Beri to Kudana road km 0/0 to 3/00 (SH:- C/O R/wall in km 0/985 to 0/996, Brest wall in km 2/00 to 2/011,2/100 to 2/112.50)	369147/-	7400/-	Two Months	350.00
34	R/R damages on Kaisiri Duhak Chattruru road km 0/0 to 8/00 (SH:- C/o R/wall from RD 1/045 to 1/052.5)	279608/-	5500/-	Two Months	350.00
35	R/R damages on link road from Mehalroo to village Lohar Bali km 0/00 to 2/00 (Sh:- C/O wire crate at RD 0/600 to 0/612.50) (RHS)	488342/-	10000/-	Two Months	350.00
36	R/R damages on Uhal to Bakkar Khad via Parnali road km 0/0 to 5/700 (SH:- C/O wire crate wall at RD 2/030 to 2/048.60)	488702/-	9700/-	Two Months	350.00
37	R/R damages on Utpur to Bakkar Khad via Kuthar road km .0/0 to 4/0 (SH:- C/O wire crate at RD .1/660 to 1/675 and 2/975 to 2/980	476784/-	9500/-	Two Months	350.00
38	R/R damages on Utpur to Bakkar Khad via Kuthar road km .0/0 to 4/0 (SH:- C/O wire crate at RD .2/550 to 2/568)	469684/-	9400/-	Two Months	350.00
39	C/O Assistant Engineer office cum Residence at Kakkar ,Tehsil Tauni Devi Distt Hamirpur (HP) (Sh:- Site Development)	491000/-	10000/-	Two Months	350.00
40	C/O link road from Mehroo to village Lohar Bali km 0/0 to 2/00 (SH:- P/L WBM G-III & 2cm thick premix carpet with seal coat at RD 0/585 to 0/885) Under OTMNP	473878/-	9500/-	Two Months	350.00
41	C/O link road from Rain shelter to Bhalana via Chuhak Sawahal bifurcated from Hamirpur Sujanpur road km 9/750 (SH:- C/O C.C causeway toe wall and drain in C.C 1:3:6 in km 0/740 to 1/200) (Under OTMNP)	499613/-	10000/-	Two Months	350.00
42	C/O Uhal to Bakkar Khad via Parnali road km 0/0 to 6/0 (SH:- protection wall to 40.00mtr .span Jamli side abutment 5/700 and 82.50 mtr Span protection Jamli side at RD 5/758 and C/O wire crate at RD 4/810 to 4/833) (Under Bridge head)	415299/-	8300/-	Two Months	350.00
43	R/R damages on Nanot to Bakkar Khad via Jamli road km 0/0 to 4/0(SH:- C/O wire crate at RD 2/120 to 2/138.50)	486351/-	9700/-	Two Months	350.00
44	R/R damages on Nanot to Bakkar Khad via Jamli road km 0/0 to 4/0(SH:- C/O wire crate at RD 2/750 to 2/768.60)	486351/-	9700/-	Two Months	350.00
45	R/R damages on Darkoti Mohin road km 0/0 to 3/0 and Kotlu to Naugin road km 0/0 to 2/405 (SH:- C/O unlined surface drain and dressing berms)	412090/-	8200/-	Two Months	350.00
46	R/R damages on various road under Chouri Section Sujanpur Sub-Division (SH:-Hiring of JCB/front end Loader for removal of slips/clearing of drain due to heavy rains) (Balance work)	429000/-	8600/-	Two Months	350.00

TERMS AND CONDITIONS:-

The tender documents shall be issued only to those contractors/firms who fulfill the following criteria and submit documents with the application. The valid enlistment/registration of contractor in appropriate class. Permanent Account Number (PAN). Earnest money in the shape of National saving certificate/Time deposit Account in any of the Post office in H.P./F.D.R from any Nationalized Bank (i/c Kangra Central Cooperative Bank) duly pledged in favour of the Executive Engineer. Other speical terms and condition can be seen/obtain in this office on any working day. Any ambiguous/telegraphic conditional tenders by fax shall not be

Excutive Engineer
TauniDevDivision,
HPPWDTauniDevi.

No. PW/TDD/GA/N.I.T./2023-24

12/21- 12/71

Dated:- 27-10-2027


Copy forwarded for infromation & necessary action.

- 1 The Engineer-in-Chief, HP:PWD , Shimla.
- 2 The Chief Engineer (HZ), HP:PWD, Hamirpur.
- 3 The Superintending Engineer, 8th Circle, HP:PWD Hamirpur.
- 4 All the Superintending Engineers/Executive Engineers in HP:PWD.
- 5 The Deputy Commissioner, Hamirpur(HP)
- 6 ✓ The Director, Information and Public Relations, Suchna Avam Jan Sampark Bhawan, HP Shimla-2 .
- 7 The Tehsildar, Tauni Devi.
- 8 The B.D.O Tauni Devi.
- 9 The Municipal Committee, Hamirpur(HP)
- 10 All the Assistant Engineers working under this Division.
- 11 Account Branch/Drawing Branch/Notice Board.
- 12 Lok Mitra, Tauni Devi.
- 13 Various Contractors/ Firms.

Excutive Engineer
TauniDevDivision,
HPPWDTauniDevi.

CERTIFICATE

Certified that the tender for job No. 1 to 46 are called vide this office letter No. PW/TDD/GA/2023-24-12121-71 dated 27.10.2023 are an urgent nature and in public interest.



Executive Engineer,
Tauni Devi Division,
HP: PWD., Tauni Devi.

Schedule of Quantity


NAME OF WORK:- Restoration of rain damages on Kakkar Sachuhi road km. 0/0 to 8/500.(SH:- P/L G-III & premix carpet in patches in km. 0/00 to 1/500).

Estimated Cost:- Rs. 493059.00
Earnest Money:- Rs. 10000.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and laying spreading and compacting stone aggregate of specific sizes 50mm to 25mm (fifty millimetre into twenty five millimetre) to water bound macadam specification including spreading in uniform thickness hand packing rolling with three wheel 80-100 KN static roller in stages to proper grade with camber applying and brooming stone screening/binding materials to fill-up the interstices of coarse aggregate watering and compacting to the required density Grading -III as per technical specification clause 405 by manual means and as per entire satisfaction and direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.50			Per cubic metre	
2	Repair to patch/pot holes (any depth) in connection with repairing including sweeping free from dust and mud, scoring sunkeda in road, patches etc. cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion bitumen @ 0.300kg/sqm. (zero point three zero zero kilogramme per square metre) and then providing 20mm (twenty millimeter) thick premix carpet using VG-10 bitumen @ 1.46kg/sqm (one point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @ 0.68kg/sqm (zero point six eight kilogramme per square metre) as per technical specification clause 1904.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	1397.20			Per Square metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.
2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.


 Executive Engineer,
 Tauni Devi Division,
 H.P.PWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Kakkar Sachuhi road km. 1/500 to 2/300, Link road to Jamuli Mata Mandir km. 0/00 to 1/870 & Link road road to Chamiyania-Di-Khanauli km.0/00 to 2/200 (SH:- P/L premix carpet in patches).

Estimated Cost:- Rs. 486485.00
Earnest Money:- Rs. 9700.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to patch/pot holes (any depth) in connection with repairing including sweeping free from dust and mud, scoring sunkeda in road, patches etc. cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion bitumen @ 0.300kg/sqm. (zero point three zero zero kilogramme per square metre) and then providing 20mm (twenty millimeter) thick premix carpet using VG-10 bitumen @ 1.46kg/sqm (one point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @ 0.68kg/sqm (zero point six eight kilogramme per square metre) as per technical specification clause 1904.2.503 and 503.2 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	1410.10			Per Square metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.
2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

Anil Kumar
Executive Engineer,
Tanni Devi Division,
HPPWD: Tanni Devi.

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 15/0 to 30/915.(SH:- P/L G-III & premix carpet in patches in km. 22/00 to 28/00).

Estimated Cost:- Rs. 493359.00
Earnest Money:- Rs. 10000.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and laying spreading and compacting stone aggregate of specific sizes 50mm to 25mm (fifty millimetre into twenty five millimetre) to water bound macadam specification including spreading in uniform thickness hand packing rolling with three wheel 80-100 KN static roller in stages to proper grade with camber applying and brooming stone screening/binding materials to fill-up the interstices of coarse aggregate watering and compacting to the required density Grading -III as per technical specification clause 405 by manual means and as per entire satisfaction and direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.50			Per cubic metre	
2	Repair to patch/pot holes (any depth) in connection with repairing including sweeping free from dust and mud, scoring sunkeda in road, patches etc. cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion bitumen @ 0.300kg/sqm. (zero point three zero zero kilogramme per square metre) and then providing 20mm (twenty millimeter) thick premix carpet using VG-10 bitumen @ 1.46kg/sqm (one point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @ 0.68kg/sqm (zero point six eight kilogramme per square metre) as per technical specification clause 1904.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	1398.07			Per Square metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.
2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

Amo Ose
Executive Engineer,
Tauni Devi Division,
H.P. WD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Bert road km. 15/0 to 30/915.(SH:- P/L-G-III & premix carpet in patches in km. 15/00 to 22/00).

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			In Fig.	In Words		
1	Providing and laying spreading and compacting stone aggregate of specific sizes 50mm to 25mm (fifty millimetre into twenty five millimetre) to water bound macadam specification including spreading in uniform thickness hand packing rolling with three wheel 80-100 KN static roller in stages to proper grade with camber applying and brooming stone screening/binding materials to fill-up the interstices of coarse aggregate watering and compacting to the required density Grading -III as per technical specification clause 405 by manual means and as per entire satisfaction and direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.50			Per cubic metre	
2	Repair to patch/pot holes (any depth) in connection with repairing including sweeping free from dust and mud, scoring sunkeda in road, patches etc. cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion bitumen @ 0.300kg/sqm. (zero point three zero zero kilogramme per square metre) and then providing 20mm (twenty millimeter) thick premix carpet using VG-10 bitumen @ 1.46kg/sqm (one point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @ 0.68kg/sqm (zero point six eight kilogramme per square metre) as per technical specification clause 1904.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	1398.07			Per Square metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.
2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

Executive Engineer,
Tauni Devi Division,
HP/PWD: Tauni Devi.


Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Sujapur Sandhol road km. 3/00 to 20/00.(SH:- Providing and laying patch work in km. 10/00 to 20/00).

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earnest Money:-	Time:-		
				Rate	In Words		
1	Providing and laying spreading and compacting stone aggregate of specific sizes 50mm to 25mm (fifty millimetre into twenty five millimetre) to water bound macadam specification including spreading in uniform thickness hand packing rolling with three wheel 80-100 KN static roller in stages to proper grade with camber applying and brooming stone screening/binding materials to fill-up the interstices of coarse aggregate watering and compacting to the required density Grading -III as per technical specification clause 405 by manual means and as per entire satisfaction and direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.08				Per cubic metre	
2	Repair to patch/pot holes (any depth) in connection with repairing including sweeping free from dust and mud, scoring sunken in road, patches etc. cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion bitumen @ 0.300kg/sqm. (zero point three zero zero kilogramme per square metre) and then providing 20mm (twenty millimeter) thick premix carpet using VG-10 bitumen @ 1.46kg/sqm (one point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @ 0.68kg/sqm (zero point six eight kilogramme per square metre) as per technical specification clause 1904.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	1060.85				Per Square metre	
Total			3				

Terms and Condition

1. Work shall be executed as per PWD specification.
2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.


 Executive Engineer,
 Tauni Devi Division,
 H.P.PWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Sujapur Sandhol road km. 3/00 to 10/00.(SH:- Providing and laying patch work in km. 3/00 to 10/00).

Estimated Cost:- Rs. 439379.00
Earnest Money:- Rs. 8800.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and laying spreading and compacting stone aggregate of specific sizes 50mm to 25mm (fifty millimetre into twenty five millimetre) to water bound macadam specification including spreading in uniform thickness hand packing rolling with three wheel 80-100 KN static roller in stages to proper grade with camber applying and brooming stone screening/binding materials to fill-up the interstices of coarse aggregate watering and compacting to the required density Grading -III as per technical specification clause 405 by manual means and as per entire satisfaction and direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	6.87			Per cubic metre	
2	Repair to patch/pot holes (any depth) in connection with repairing including sweeping free from dust and mud, scoring sunkeda in road, patches etc. cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion bitumen @ 0.300kg/sqm. (zero point three zero zero kilogramme per square metre) and then providing 20mm (twenty millimeter) thick premix carpet using VG-10 bitumen @ 1.46kg/sqm (one point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @ 0.68kg/sqm (zero point six eight kilogramme per square metre) as per technical specification clause 1904.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	1234.73			Per Square metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.
2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

Anand Kumar
Executive Engineer,
Tauni Devi Division,
HPPWD, Tauni Devi


Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Hamirpur Sujampur road (MDR-86)(SH:- Providing and laying patch
work km 10/600 to 12/00 and 13/00 to 16/00)

Sr. No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:-	Time:-		
			In Fig.	In Words		
1.00	Repairs to pot holes(any depth) in connection with repainting including sweeping free from dust and mud, scoring sunken surfaces in road path etc, cutting around edges to atleast 25mm (twenty five millimetre) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion @0.25 to 0.30 Kg/Sqm(zero point twenty five to zero point thirty kilogram per square metre) and then providing 20mm(twenty millimetre) thick premix carpet using VG-10 bitumen@ 1.46 Kg/Sqm(one point forty six kilogram per square metre) and seal coat type B with bitument VG-10 @ 0.68 Kg/Sqm(zero point sixty eight kilogram per square metre) as per technical specification clause 1904.2.503 and 508.1 including entire carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge at site.	1428.60				
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 T40ni Devi Division,
 HPPWD: Tauni Dept.


Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road Kuthera Chalokhar via Dei Ka Naun Km 1/00 to 2/700 & link road to Village Kakru Km 0/0 to 0/500). (SH:- Providing and laying patch work)

Sr. No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earnest Money:-	Rs.212482.00		
				Time:-	Two Months		
				Rate	In Words		
1.00	Repairs to pot holes(any depth) in connection with repainting including sweeping free from dust and mud, scoring sunken surfaces in road path etc, cutting around edges to atleast 25mm (twenty five millimetre) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion @0.25 to 0.30 Kg/Sqm(zero point twenty five to zero point thirty killogram per square metre) and then providing 20mm(twenty millimetre) thick premix carpet using VG-10 bitumen@ 1.46 Kg/Sqm(one point forty six killogram per square metre) and seal coat type B with bitument VG-10 @ 0.68 Kg/Sqm(zero point sixty eight killogram per square metre) as per technical specification clause 1904.2.503 and 508.1 including entire carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge at site.	600.45				Per square metre	
2.00	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm(fifty three millimetre) to 0.075 mm(zero point seven five millimetre) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8(eight) to 10(ten) tonne capacity to achieve the desired density, complete as per technical specification clause 302.3 direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	2.50				Per cubic metre	
Total							

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division
 HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road Pastal to Bugdhar Matroh road Km 0/00 to 3/500.(SH:-
Providing and laying patch work)

Sr. No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			In Fig.	In Words		
1.00	Repairs to pot holes(any depth) in connection with repainting including sweeping free from dust and mud, scoring sunkeda surfaces in road path etc, cutting around edges to atleast 25mm (twenty five millimetre) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion @0.25 to 0.30 Kg/Sqm(zero point twenty five to zero point thirty kilogram per square metre) and then providing 20mm(twenty millimetre) thick premix carpet using VG-10 bitumen@ 1.46 Kg/Sqm(one point forty six kilogram per square metre) and seal coat type B with bitument VG-10 @ 0.68 Kg/Sqm(zero point sixty eight kilogram per square metre) as per technical specification clause 1904.2.503 and 508.1 including entire carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge at site.	1425.85			Per square metre	
2.00	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm(fifty three millimetre) to 0.075 mm(zero point seven five millimetre) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8(eight) to 10(ten) tonne capacity to achieve the desired density, complete as per technical specification clause 302.3 direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	3.00			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

And
Executive Engineer,
Tauni Devi Division,
HPBWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Construction of link road from Khadoula to Darsal G.P. Dera. (SH:- Providing and laying patch work in KM 0/00 to 1/500) (Deposit Work)


Estimated Cost:- Rs.332695.00
Earnest Money:- Rs.6600.00

Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) premix carpet and seal coat type-B specification clause 1904.2.503 and 508.1 and as per the direction of Engineer-In-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	962.66			Per Square metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPWD: Tauni Devi

Schedule of Quantity


NAME OF WORK:- (i) Restoration of rain damages of Barin Dhawal via Siswan Ghalot road Km 0/00 to 5/00. (SH:- Providing and laying Patch work in Km 1/00 to 2/00 & 3/00 to 5/00. (ii) Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road Km 0/00 to 7/300. (SH:- Providing and laying Patch work in Km 6/00 to 7/300)

Estimated Cost:- Rs.443215.00
Earnest Money:- Rs.8800.00
Time:- Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
2.00	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm(fifty three millimetre) to 0.075 mm(zero point zero seven five millimetre) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8(eight) to 10(ten) tonne capacity to achieve the desired density, complete as per technical specification clause 302.3 direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, roll tax, GST or other taxes imposed by the Government.	9.28			Per cubic metre	
1.00	Repairs to pot holes(any depth) in connection with repainting including sweeping free from dust and mud, scoring sunkeda surfaces in road path etc, cutting around edges to atleast 25mm (twenty five millimetre) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion @0.25 to 0.30 Kg/Sqm(zero point twenty five to zero point thirty killogram per square metre) and then providing 20mm(twenty millimetre) thick premix carpet using VG-10 bitumen@ 1.46 Kg/Sqm(one point forty six killogram per square metre) and seal coat type B with bitument VG-10 @ 0.68 Kg/Sqm(zero point sixty eight killogram per square metre) as per technical specification clause 1904.2.503 and 508.1 including entire carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge at site.	1284.68			Per square metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Schedule of Quantity


NAME OF WORK:- Restoration of rain damages on Lungwan Tauni Devi road km. 3/345 to 7/305.(SH:- Providing patch work).

Estimated Cost:- Rs. 472492.00
Earnest Money:- Rs. 9500.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm)(fifty three millimeter to zero point seven five millimeter) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge, including entire carriage of material within all leads and lifts and other incidentals.	16.78			Per cubic metre	
2	Repair to patch/pot holes (any depth) in connection with repairing including sweeping free from dust and mud, scoring sunken in road, patches etc. cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion bitumen @ 0.300kg/sqm. (zero point three zero zero kilogramme per square metre) and then providing 20mm (twenty millimeter) thick premix carpet using VG-10 bitumen @ 1.46kg/sqm (one point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @ 0.68kg/sqm (zero point six eight kilogramme per square metre) as per technical specification clause 1904.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	1265.91			Per Square metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.
2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Dev

Schedule of Quantity


NAME OF WORK:- Pre-painted sheet Chajja in old civil Hospital building at Sujapur Thirra. (SH-Demolition of old Chajja and providing and fixing of sheet (steel) Chajja) (Deposit Work)

Estimated Cost:- Rs.303340.00
Earnest Money:- Rs.6100.00
Time:- Two Months

Sr. No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In Words			
1.00	Demolishing R.C.C. work by mechanical means and stockpiling at designated locations and disposal of dismantled materials up to a lead of 1(one) kilometre, stacking serviceable and unserviceable material separately including cutting enforcement bars as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.25				Per cubic metre	
2.00	Providing and fixing 0.60mm (zero point sixty nine millimetre) thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular odified polyester (RNP) organic coating of 20(twenty) microns over 5(five) microns over primer coating to back coat of polyester of 5(five) microns over 5(five) microns primer coating including fixing with pre-painted iron J or L hooks, bolts and nuts 6mm (six millimetre) dia metre with pre-painted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	55.68				Per Square metre	
3.00	Providing and fixing M.S BP sheet 1.66mm (one point sixty six millimetre) to 2mm(two millimetre) thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer in charge (base members of steel work shall be measured & paid separately) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	65.12				Per square metre	
	Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Prepainted sheet Chajja in old civil Hospital building at Sujampur Tihra. (SH:-Providing and fixing of sheet (steel) Chajja) (Deposit Work)

Estimated Cost:- Rs.287499.00
Earnest Money:- Rs.8500.00
Time:- Two Months

Sr. No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In Words			
1.00	Structural steel work in single section, fixed with or without connecting plate,including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2540.13				Per kilogram	
2.00	15 mm(fifteen millimetre) cement plaster on rough side of single or half brick wall of mix 1:6 (one cement: six coarse sand)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	108.40				Per square metre	
3.00	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm (zero point niney litre per ten square metre) over an under coat of primer applied @ 0.80 ltr/10 sqm(zero point eighty litre per ten square metre) of approved brand and manufacture as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.	81.92				Per square metre	
4.00	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.60 mm(zero point six zero millimetre) (+ 0.05 %) (Plus zero point zero five percent) total coated thickness with zinc coating 120 grams(one hundred twenty grams) per square metre as per IS: 277, in 240 (two hundred forty) mpa steel grade, 5-7(five to seven) microns epoxy primer on both side of the sheet and polyester top coat 15-18(fifteen to eighteen) microns. Sheet should have protective guard film of 25(twenty five) microns minimum to avoid scratches during transportation and should be supplied in single length upto 12(twelve) metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm)(five point five into fifty five millimetre) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	140.80				Per square metre	
Total							

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Providing and fixing of shed on balconies of Ravi Hostel at Sainik School Sujapur Tihra Dist Hamirpur (HP) (SH:-Providing and fixing preprinted sheet shed)(Deposit Work)

Estimated Cost:- Rs.454699.00
Earnest Money:- Rs.9100.00
Time:- Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete in trusses and trussed purlins in building as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1735.00			Per Kilogram	
2.00	Providing and fixing 0.60mm(zero point sixty millimetre) thick preprinted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20(twenty) microns over 5(five) microns primer coating to back coat of polyester of 5(five) microns over 5(five) microns primer coating including fixing with preprinted iron j or L hooks, bolts and nuts 6mm(six millimetre) dia metre with preprinted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	158.00			Per square metre	
3.00	Providing and fixing M.S. BP Sheet 1.66mm to 2mm thick in eaves board / fascia / soffits / ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete (Base members of steel work shall be measured & paid separately as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	32.49			Per square metre	
4.00	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm(zero point ninety litre per ten square metre) over an under coat of primer applied @ 0.80 ltr/ 10 sqm(zero point eighty litre per ten square metre) of approved brand and manufacture as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	122.48			Per square metre	

5.00	Providing and fixing pre-coated galvanised steel (Tata/Sail) sheet roofing accessories 0.50 mm (zero point five zero) (+0.05 %)(plus zero point five percent) total coated thickness, Zinc coating 120(one hundred twenty) grams per sqm as per IS: 277, in 240(two hundred forty) mpa steel grade, 5-7 (Five to seven)microns epoxy primer on both side of the sheet and polyester top coat 15-18(fifteen to eighteen) microns using self drilling/ self tapping screws complete Flashings/ Aprons. (Upto 380 mm)(three hundred eighty millimetre) as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	68.30					Per running metre	
Terms and Condition							Total	

1. Work shall be executed as per PWD specification.


Anand Arora
Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Patlander Bhogolu Ree road Km 0/00 to 7/120. (SH:- Installation of crash barriers valley side at RD 1/945 to 1/965 and 2/465 to 2/485 with R/Wall at RD 2/470 to 2/479)

Schedule of Quantity									
NAME OF WORK:- Restoration of rain damages on Patander Bhagoli Ree road Km 0/00 to 7/120. (SH:- Installation of crash barriers valley side at RD 1/945 to 1/965 and 2/465 to 2/485 with R/Wall at RD 2/470 to 2/479)									
Sr. No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount			
			Earnest Money:-						
			Time:-	Rate					
			In Fig.	In Words					
1.00	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre) on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m(one point five metre). Including getting out the excavated soil and disposal of surplus excavated soils as directed, within all leads (Ordinary rock)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	6.84			Per cubic metre				
5.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (one cement : two coarse sand) : four graded stone aggregate 20 mm(twenty millimetre) nominal size) as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	2.16			Per cubic metre				
3.00	Providing and erecting "W" metal beam crash barrier comprising of 3mm (three millimetres) thick corrugated sheet metal beam rail 70cm(seventy centimeters) above road/ground level, fixed on ISMC section vertical post 150x75x75 mm (one hundred fifty into seventy five into seventy five millimetre) spaced 2.00m (two point zero zero metre) centre to centre 1.80m (one point eighty metre) high & 1.10m (one point ten metre) below ground/road level all steel parts and fittings to be galvanized by hot process all fittings to confirm to IS:1367 & IS:1364 metal beam rail to be fixed on the vertical post with a spacer or channel section 150x75x5 mm (one hundred fifty into seventy five into five millimetre) long completed as per clause 810 as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	40.00			per running metre				
4.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	10.94			Per cubic metre				
5.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimetre) dia PVC pipe De plast /finolex/vectus having pressure 4kg per sqmt (four kilogram) per square meter extending through the full width of the structures with slopes of (1V): 20(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	6.00			Each.				
					Total				

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tami Devi Division,
 HPMD: Tami De

Schedule of Quantity

NAME OF WORK:- Special Repair to Sainik Rest House at Sujianpur. (SH:-Providing entrance gate and providing window shutter and flush door)(Deposit Work)

Estimated Cost:- Rs.134231.00
Earnest Money:- Rs.2700.00
Time:- Two Months

Sr. No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In Words			
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.65				Per cubic metre	
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand : six graded stone aggregate 20 mm (twenty millimetre) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.65				Per cubic metre	
3.00	Steel (Tata/Sail) work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	231.04				Per Kilogram	
4.00	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm(zero point ninety litre per ten square metre) over an under coat of primer applied @ 0.80 ltr/ 10 sqm(zero point eighty litre per ten square metre) of approved brand and manufacture as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30.00				Per square metre	
5.00	Stainless Steel (SS-304) with adjustable double nylon roller (weight bearing capacity to be 120kg (One hundred twenty kilogram) for uPVC sliding door / window as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.00				Each	

6.00	Providing and fixing 300x16 mm(three hundred into sixteen millimetre) ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.00			Each	
7.00	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately) Second class teak wood as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.05			Per cubic metre	
8.00	Providing and fixing glazed shutters for doors, windows and clerestory windows using 4 mm(four millimetre) thick float glass panes, including ISI marked M.S. ressed butt hinges bright finished of required size with necessary screws Second class teak wood 35 mm(thirty five millimetre) thick as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.18			Per square metre	
9.00	Providing and fixing 35 mm(thirty five millimetre) thick ISI marked Flush Door Shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3(three) ply veneering with vertical grains or cross bands and face veneers on both faces of shutters including ISI marked stainless steel butt hinges with necessary screws as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	2.46			Per square metre	
10.00	Providing and fixing 250x16mm (two hundred fifty into sixteen millimetre) aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	1.00			Each	
11.00	Providing and fixing 250x10mm (two hundred fifty into ten millimetre) aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	8.00			Each	

12.00	Providing and fixing 125 mm(one hundred twenty five millimetre) aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.00					Each	
13.00	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm(Rupees fifty into fifty millimetre) including strengthening with 2 mm(two millimetre) dia wire or nuts, bolts and washers as required complete Made of G.I. wire of dia 4 mm(four millimetre) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	100.00					Per square metre	
Terms and Condition							Total	

1. Work shall be executed as per PWD specification.

Amid Ar
 Executive Engineer,
 Tauni Deyl Division,
 HPPWD: Tauni Deyl
A

Schedule of Quantity

NAME OF WORK:- Preparation of FCA case under Tauni Devi Sub-Division, HP:PWD, Tauni Devi (SH:- Data preparation of KML file digital map with coordinates and C.A. map and HPS file including online submission of forest case.), (i) C/O link road Krust to Dhuntar via Shamsher Singh House km. 0/0 to 1/700. (MLA Priority) (ii) link road to Amit Kapil house Dalwana (Under OTMNP)

Estimated Cost:- Rs. 363000.00
Earnest Money:- Rs. 7300.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Preparation of Geo reference Topo sheet map layout map and collection of data for proposed site including field visits, preparation of KML file along with marking of habitation to be benefited by construction of road as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.300			Per Km	
2	Processing the case for preparation of forest diversion under F.C.A. 1980 including the collection of field data and all relevant documents/formats mandatory required to be attached with the case as per latest requirement of Ministry Environment and forest conservation, Govt of India Dehradun after getting the joint inspection of site including computer typing of (two) copies in each case, binding complete and getting it resubmit the same by neatly and accurately filling in all formats/documents for submission, rectifying any observations and receiving approval in all respect as per direction and complete satisfaction of user agency and forest department including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.00			Each	
Terms and Condition					Total	

1. Work shall be executed as per PWD specification.

Anil Kumar
Executive Engineer,
Tauni Devi Division,
HP:PWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Preparation of FCA case of link road from Anu to Charan Masanda km. 0/0 to 0/400. (SH:- Data preparation of KML file digital map with coordinates and C.A. map and HPS file including online submission of forest case-). (Under OTMNP)

Estimated Cost:- Rs. 174000.00
Earnest Money:- Rs. 3500.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Preparation of Geo reference Topo sheet map layout map and collection of data for proposed site including field visits, preparation of KML file along with marking of habitation to be benefited by construction of road as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.400			Per Km	
2	Processing the case for preparation of forest diversion under F.C.A. 1980 including the collection of field data and all relevant documents/formats mandatory required to be attached with the case as per latest requirement of Ministry Environment and forest conservation, Govt of India Dehradun after getting the joint inspection of site including computer typing of (two) copies in each case, binding complete and getting it through from DFO, R.O. including all the observation if raised at any time by any office and to pursue and resubmit the same by neatly and accurately filling in all formats/documents for submission, rectifying any observations and receiving approval in all respect as per direction and complete satisfaction of user agency and forest department including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.00			Each	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

A. Singh
Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- C/O link road Kaloh to Bakkar Khad via Bakmiar km. 0/0 to 0/750.(SH:- C/O C.C. rigid pavement at RD. 0/108 to 0/150). (Deposit work).

Estimated Cost:- Rs. 188587.00


Earnest Money:- Rs. 3800.00

Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	50.83			Per Cubic metre	
2	Stone soiling properly handpacked filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD., specification 100mm (one hundred millimeter) spread thickness finished work including materials and labour as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.	21.78			Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	14.52			Per Cubic metre	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm nominal size) (twenty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	14.52			Per Cubic metre	
	Total					

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi


Schedule of Quantity

NAME OF WORK:- C/O link road from Naughia to Thai km. 0/0 to 0/400.(SH:- C/O R.C.C. hume pipe culvert 900mm dia at RD. 0/270 with wing walls). (Deposit Work).

NAME OF WORK:- C/O link road from Naughia to Thak km. 0/0 to 0/400.(SH:- C/O R.C.C. hume pipe culvert 900mm dia at RD. 0/270 with wing walls). (Deposit Work).							Estimated Cost:-	Rs. 118788.00
							Earnest Money:-	Rs. 2400.00
							Time:-	Two Months
Sr.No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount	
				In Words				
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m,(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	12.15				Per Cubic metre		
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one cement: four sand: eight graded stone aggregated 40mm (forty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	1.89				Per Cubic metre		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	16.83				Per Cubic metre		
4	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (one cement : two fine sand) including testing of joints etc. complete 900mm (nine hundred millimeters) dia RCC pipe as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	7.00				Per Rmt.		
Total								

Terms and Condition

1. Work shall be executed as per PWD specification.



 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Construction of pre-painted sheet shed for Dhobi Ghat at Sainik School Sujapur Thhra. (SH:-
Footings and plinth beam etc)(Deposit Work)

NAME OF WORK:- Construction of preapainted sheet shed for Dhobi Ghat at Sainik School Supanpur Tihra. (SH:-									
Footing and plinth beam etc)(Deposit Work)									
Sr. No.	Description of Items	Qty.	Estimated Cost:-		Earnest Money:-		Two Months		
			Time:-		Rate		Unit		
			In Fig.	In Words				Amount	
1.00	Steel reinforcement (Tata Tiscon/sail make) for Reinforced cement concrete work including straightening, cutting, bending, placing in position and binding all complete above plinth level Mild steel and Medium Tensile steel bars as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	1620.10					Per kilogram		
2.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in superstructure above plinth level up to floor all level in all shapes and sizes in Cement mortar 1:4 (one cement : four coarse sand) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	7.24					Per cubic metre		
3.00	Centering and shuttering including strutting, propping etc. and removal of form work Foundations, footings, bases for columns etc for mass concrete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	77.49					Per square metre		
Terms and Condition							Total		

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi.

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Behrda Bajrol via Tholu road km. 0/0 to 4/00. (SH:- C/O PCC R/Wall at RD. 1/780 to 1/800). (Deposit Work).

1/780 to 1/800), (Deposit Work).							Estimated Cost:-	Rs. 284217.00
							Earnest Money:-	Rs. 5700.00
							Time:-	Two Months
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount		
			In Fig.	In Words				
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm) ten square metre on plan,including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m,(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	32.70			Per Cubic metre			
2	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills,fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	65.99			Per Cubic metre			
3	Providing weep holes in brickstone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm/ one hundred ten millimeter) dia PVC pipe De-plast/irolex/ vecus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	15.00			Each			
Totals and Condition						Total		

Terms and Condition
1. Work shall be executed as per PWD specification.

Executive Engineer,
Tamil Devl Division,
HPWD: Tamil Devl

Schedule of Quantity

NAME OF WORK:- (i) C/O link road from Khadola Khad to Baila Rathiyana via Sabzi Mandi km. 0/00 to 1/557, (ii) C/O link road to village Kangral G.P. Rangar km. 0/0 to 1/500, (iii) C/O link road from Chakriyana to Natahi via Gahla-Jagehri including one bridge km. 0/00 to 4/500. (SH:- Preparation of DPR thereof).

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Rate	Time:-		
			In Fig.	In Words		
1	Preparation of detailed project report and drawing complete including consultancy service for survey investigation etc. in manuscript form and submission of the same in higher office for approval. If any correction/amendment required by the higher office the same may be corrected to the satisfaction of Engineer-in-Charge complete in all projects. After approval of the same should be submitted in five copies in fair manner completed in all respect as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.557			Per Km	
2	Preparation of Hydraulic data report and drawing complete including consultancy service for topographical survey etc. in manuscript form and submission of the same in higher office for approval. If any correction/amendment required by the higher office the same may be corrected to the satisfaction of Engineer-in-charge complete in all projects. After approval of the same from S.E. office should be submitted in three copies in fair manner complete in all respect as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.000			Per Bridge	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

Anil Kumar
Executive Engineer,
Tadun Devi Division,
HPPWD, Tauni Devi


Schedule of Quantity

NAME OF WORK:-C/O link road from Banalag to Lower Uapur including one bridge km. 0/00 to 5/000 (SH:- Preparation of DPR and Hydraulic data thereof) & C/O Degree College at Tauni Devi. (SH:- Survey and contour site plan).

NAME OF WORK:-C/O link road from Banalag to Lower Udupur including one bridge km. 0/00 to 5/000 (SH:- Preparation of DPR and Hydraulic data thereof) & C/O Degreee College at Tauni Devi. (SH:- Survey and contour site plan).						
Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:-	Time:-		
			In Fig.	In Words		
1	Preparation of detailed project report and drawing complete including consultancy service for survey investigation etc. in manuscript form and submission of the same in higher office for approval. If any correction/amendment required by the higher office the same may be corrected to the satisfaction of Engineer-in-Charge complete in all project. After approval of the same should be submitted in five copies in fair manner completed in all respect as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	5.000			Per Km	
2	Preparation of Hydraulic data report and drawing complete including consultancy service for topographical survey etc. in manuscript form and submission of the same in higher office for approval. If any correction/amendment required by the higher office the same may be corrected to the satisfaction of Engineer-in-charge complete in all projects. After approval of the same from S.E. office should be submitted in three copies in fair manner complete in all respect as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	1.000			Per Bridge	
3	Site survey using Total station/DGPS and preparation of survey and contour plan at desired intervals. The survey will be carried out to show all boundary points compound walls, roads, trees, buildings, structures stream electric poles, telephone poles, and any other man-made structures within survey permanent structures including supply of 3(three) sets of drawings along with a soft copy of entire survey work and approval of contour plan from higher authority as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	2.850			Per hectare	
					Total	

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 H.P.W.D. Tauni Devi


Schedule of Quantity

NAME OF WORK:- (i) Link road from Pohanj to Lower Pohanj under NABARD (ii) C/O Science Lab at Govt. Sr. Secondary School Pohanj. (iii) C/O J.E. Office Cum residence Building at Uhal. (iv) C/O Science Lab. at Govt. Sr. Secondary School Uhal. (SH:- Preparation of DPR thereof).

NAME OF WORK:- (i) Link road from Pohanj to Lower Pohanj under NABARD (ii) C/O Science Lab at Govt. Sr. Secondary School Pohanj. (iii) C/O J.E. Office Cum residence Building at Uhal. (iv) C/O Science Lab. at Govt. Sr. Secondary School Uhal. (SH:- Preparation of DPR thereof).							Estimated Cost:-	Rs. 350000.00
							Earnest Money:-	Rs. 7000.00
							Time:-	Two Months
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount		
			In Fig.	In Words				
1	Preparation of detailed project report for the work (i) Link road from Pohanj to Lower Pohanj under NABARD (ii) C/O Science Lab at Govt. Sr. Secondary School Pohanj. (iii) C/O J.E. Office Cum residence Building at Uhal. (iv) C/O Science Lab. at Govt. Sr. Secondary School Uhal on analyzed/market rate and approval of the same from the competent authority and if any amendment/correction at desired by the competent authority, the same may be corrected. After the approval of the estimate should be submitted in five copies as per the condition of TOR. After the approval of the estimate the DNT and justification if required be prepared in fair manner and approved of the same from competent authority as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	1.00			Per Job			
					Total			

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Taqni Devi Division,
 HPPWD, Tauni Devi

Schedule of Quantity

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Taani Devi Division,
HPWD: Taani Devi

Schedule of Quantity


NAME OF WORK:- Restoration of rain damages on Polhaji to Andral road km. 0/00 to 3/695.(SH:-C/O wire crate at RD. 1/953 to 1/948 & 1/790 to 1/795).

Estimated Cost:- Rs. 479721.00
Earnest Money:- Rs. 9600.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	61.89			Per cubic metre	
2	Providing and laying laid in wire crates with 4mm (four millimeters) dia G.I. wire conforming to IS:280 and IS: 4826 in 100x100mm (one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (twenty five kilogramme) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	156.53			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


Executive Engineer,
Tauni Devl Division,
HPPWD: Tauni Devl

Draft Schedule of Quantity

N.A.M.E. OF WORK:- Restoration of rain damages on: Kakkar Sachuhi road from km. 0/00 to 8/530 (SH:- C/O wire crate R/Wall at RD. 5/530 to 5/543).

Draft Schedule of Quantity									
NAME OF WORK:- Restoration of rain damages on Kakkar Sachhi road from km. 0/00 to 8/530.(SH:- C/O wire crate R/Wall at RD.5/530 to 5/543).									
Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount		
				Rate	Estimate Money:-				
				In Words	Two Months				
1	Excavation work by mechanical means (Hydraulic excavator/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and its and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	48.80	290.15	Two hundred ninety and paise fifteen only	Per cubic metre	14159.00			
2	Providing and laying laid in wire crates with 4mm (four millimeters) dia G.I. wire conforming to IS:280 and IS: 4826 in 100x100mm (one hundred into one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (twenty five kilogramme) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and its and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	142.19	2950.00	Rupees two thousand nine hundred fifty only	Per cubic metre	419461.00			
Total						433620.00			

DNIT No. 161 for the year 2023-24 duly approved for Rs. 4,33,620/- (Four lac. Thirty three thousand six hundred twenty) Only.

Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Terms and Condition
 1. Work shall be executed as per PWD specification.

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Sujapur to Sandhole road KM 3/00 to 20/00. (SH:- Construction of wire crates at Km 13/200 to 13/210 & 17/610 to 17/620)

Sr. No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:-	Time:-		
			Rate			
			In Fig.	In Words		
1.00	Earth work in excavation for all types of road structures such as retaining walls, breast walls, Culverts, drains and parapets etcetera in all types of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting in prohibited) as per drawing and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and black filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an strutting and pumping and balling out water(surface and sub soil water) up to any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	18.00			Per cubic metre	
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming of IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10(ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogram) each as per drawing and technical specifications Clause 1301as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	140.63			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

Anand Chavhan
Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bairol Jungle Beri road km. 0/00 to 30/915. (M.D.R. 105) (SH:- C/O R/Wall at RD. 9/020 to 9/039).

Estimated Cost:- Rs. 438587.00

Earnest Money:- Rs. 8800.00

Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and running of bottom, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m,(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	46.51			Per Cubic metre	
2	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills,fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	100.52			Per Cubic metre	
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plas/finolex/ vecus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1/V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	18.00			Each	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Repair and restoration of link road Bert to Kudana km. 0/00 to 3/00.(Sh:- C/O B/Wall at RD. 2/100 to 2/115 near the house of Sh. Anirudh Chauhan). (Deposit Work).

NAME OF WORK:- Repair and restoration of link road Beri to Kudana km. 0/00 to 3/00.(SH:- C/O B/Wall at RD. 2/100 to 2/115 near the house of Sh. Anirudh Chauhan). (Deposit Work).									
Schedule of Quantity									
Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount			
			Earnest Money:-						
			Time:-	Two Months					
			In Fig.	In Words					
1	Excavation work by mechanical means (Hydraulic excavator/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	18.90			Per Cubic metre				
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one cement: four sand: eight graded stone aggregated 40mm (forty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	42.75			Per Cubic metre				
3	Providing weep holes in brickstone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/Inolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1/V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204,3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	14.00			Each				
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	1.91			Per Cubic metre				
Terms and Condition					Total				

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division
 HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road Beri to Kudana road Km 0/00 to 3/00. (SH:- ~~Existing~~ *46*)
~~and Retaining~~ Retaining Wall in Km 0/985 to 0/996, Breast Wall in Km 2/00 to 2/011, 2/100 to 2/112.50)

Estimated Cost:- Rs.369147.00
 Earnest Money:- Rs.7400.00
 Time:- Two Months

Sr. No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In Words			
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government	46.42				Per cubic metre	
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size(as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government	82.94				Per cubic metre	
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimeter) dia PVC pipe De plast /finolex/vecus having pressure 4kg per sqmt (four kilogram) per square meter extending through the full width of the structures with slopes of 1(V): 20(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government	31.00				Each.	
Total							

Terms and Condition

1. Work shall be executed as per PWD specification.

Anil Kumar
 Executive Engineer,
 Tauni Devi Division
 HPPWD: Tauni Devi


Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Kaisiri Duhak Chattruru road Km 0/00 to 8/00. (SH:- Construction of retaining wall from RD 1/045 to 1/052.5)

NAME OF WORK:- Restoration of rain damages on Kaisiri Duhak Chattru road Km 0/00 to 8/00. (SH:- Construction of retaining wall from RD 1/045 to 1/052.5)									
		Estimated Cost:-		Rs.279608.00					
		Earnest Money:-		Rs.5500.00					
		Time:-		Two Months					
Sr. No.	Description of Items	Qty.	Rate		Unit	Amount			
			In Fig.	In Words					
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	27.00			Per cubic metre				
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	58.99			Per cubic metre				
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimeter) dia PVC pipe De plast /finolex/vectus having pressure 4kg per sqmt (four kilogram) per square meter extending through the full width of the structures with slopes of 1(V): 20(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	30.00			Each.				
4.00	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600mm(six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	17.55			Per cubic metre				
					Total				

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tajani Devi Division,
 KPPWB: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link from Melahroo to village Lohar Ball km. 0/00 to 2/00.(SH:- C/O wire crate at RD. 0/600 to 0/612.50 (RHS).

Schedule of Quantity									
NAME OF WORK:- Restoration of rain damages on link from Mehatroo to village Lohar Bail km. 0/00 to 2/00.(SH:-C/O wire crate at RD. 0/600 to 0/612.50 (RHS).									
Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount			
			Earnest Money:-						
			Time:-	Two Months					
			In Fig.	In Words					
1	Excavation work by mechanical means (Hydraulic excavator/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other Incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	28.13			Per cubic metre				
2	Providing and laying laid in wire crates with 4mm (four millimeters) dia G.I. wire conforming to IS:280 and IS: 4826 in 100x100mm (one hundred into one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (Twenty five kilogramme) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other Incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	156.25			Per cubic metre				
Terms and Condition					Total				

1. Work shall be executed as per PWD specification.

Anil Kumar
Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi


Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Uhal to Bakkar Khad via Parnali road Km 0/0 to 5/700. (SH:- Construction of wire crate wall at RD 2/030 to 2/048.60)

NAME OF WORK:- Restoration of rain damages on Uhal to Bakkar Khad via Parnali road Km 0/0 to 5/700. (SH:- Construction of wire crate wall at RD 2/030 to 2/048.60)						Estimated Cost:-	Rs 488702.00
						Earnest Money:-	Rs 9700.00
						Time:-	Two Months
Sr. No.	Description of Items	Qty.	Rate		Unit	Amount	
			In Fig.	In Words			
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	76.98			Per cubic metre		
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming ot IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10(ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogram) each as per drawing and technical specifications Clause 1301as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	158.09			Per cubic metre		
Total							

Terms and Condition

1. Work shall be executed as per PWD specification.


 Anand Kumar
 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Utpur to Bakkar Khad via kuthar road km. 0/0 to 4/0.(SH:- C/O wire crate at RD. 1/660 to 1/675 and 2/975 to 2/980).

NAME OF WORK:- Restoration of rain damages on Utpur to Bakkar Khad via Kuthar road km. 0/0 to 4/0.(SH:- C/O wire crate at RD. 1/660 to 1/675 and 2/975 to 2/980).						
Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:-			
			Time:-			
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	51.87			Per cubic metre	
2	Providing and laying laid in wire crates with 4mm (four millimeters) dia G.I. wire conforming to IS:280 and IS: 4826 in 100x100mm (one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (twenty five kilogramme) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	156.52			Per cubic metre	
					Total	

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tauni Devi Division
HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Upur to Bakkar Khad via kuthar road km. 0/0 to 4/0.(SH:- C/O wire crate at RD. 2/550 to 2/568).

Estimated Cost:- Rs. 469684.00
Earnest Money:- Rs. 9400.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and its and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	62.88			Per cubic metre	
2	Providing and laying laid in wire crates with 4mm (four millimeters) dia G.I. wire conforming to IS:280 and IS: 4826 in 100x100mm (one hundred into one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (twenty five kilogramme) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and its and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	153.03			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

Amrinder
Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

NAME OF WORK:- C/O Assistant Engineer Office Cum Residence at Kakkar, Tehsil Tauni Devi Distt. Hamirpur. (HP). (SH- Site development).

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tami Devi Division,
HPWD: Tauni Devi

NAME OF WORK:- C/O link road from Mehroo to village Lohar Ball Km. 0/0 to 2/00, (SH:- P/L WBM G-II, & 2cm thick premix carpet with seal coat at RD. 0/585 to 0/885), (Under OTMNP)

Schedule of Quantity

Sr. No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earnest Money:-	Time:-		
				In Words	Two Months		
1	Providing and laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) 75mm (seventy five millimetre) consolidated thick to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100KN (eight to hundred) static roller in stages to proper grade and camber applying and booning, stone screening of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density of grading-II as per technical specification and clause 405 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	68.63				Per cubic metre	
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer @ 0.70-1.0 kilogram (zero point seven zero to one point zero kilogram per square metre) using mechanical means as per technical specification clause -502 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	915.00				Per Square metre	
3	Providing and applying tack coat with bitumen emulsion using emulsion (FS-1) distributor at the rate of 0.25 to 0.30 kg. (zero point two five to zero point three zero kilogram) per sqm on the prepared bitumen surfaces cleaned with hydraulic broom as per technical specification clause 503 as per the direction of the Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	915.00				Per Square metre	
4	2 cm (two centimetre) premix carpet surfacing with 1.8 cum/one point eight cubic metre) and 0.30 cum (zero point three zero cubic metre) of stone chippings of 13.2 mm (thirteen point two millimetre) size and 11.2 mm (eleven point two millimetre) size respectively per 100 sqm (one hundred square metre) and 52 kg (fifty two kilogram) and 56 kg (fifty six kilogram) of hot bitumen per cum of stone chippings of 13.2 mm (thirteen point two millimetre) and 11.2 mm (eleven point two millimetre) size respectively, including a tack coat with hot straight run bitumen, including consolidation with road roller of 6 to 9 tonne capacity etc. complete (tack coat to be paid for separately). With paving Asphalt grade VG - 30 heated and then mixed with solvent at the rate of 70 grams per kg of asphalt as per direction of Engineer-in-Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	915.00				Per Square metre	
5	Providing and laying seal coat of premixed fine aggregate (passing 2.36 mm and retained on 180 micron sieve) with bitumen using 128 kg (one hundred twenty eight kilogram) of bitumen of grade VS - 30 bitumen per cum of fine aggregate and 0.60 cum (zero point six zero only) of fine aggregate per 100 sqm of road surface, including rolling and finishing with road roller all complete, as per direction of Engineer-in-Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	915.00				Per Square metre	
Terms and Condition						Total	

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tajani Devi Division
HPPWD, Tauni Dev.

Schedule of Quantity

NAME OF WORK:- C/O link road from Rain Shelter to Bhalana via Chubhak Sawhal bifurcated from Hamirpur Sujapur road km.9/750.(SH:- C/O cement concrete causeway, toe wall and drain in C.C. 1:3:6 in km. 0/740 to 1/200).(Under OTMNP)

Estimated Cost:- Rs. 499613.00
Earnest Money:- Rs. 10000.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqmt ten square metre on plan).including dressing of sides and ramming of bottoms, lift upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	34.50			Per cubic metre	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plan window sills, fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing. 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12.75			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one cement: four sand: eight graded stone aggregated 40mm (forty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.96			Per cubic metre	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	79.57			Per cubic metre	
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm(twenty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.96			Per cubic metre	
6	Providing weep holes in brickstone masonry/ plan/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plastifinex/ vecus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in - Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.00			Each	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


Arunil Dhar
Executive Engineer,
Tamsi Devi Division,
HPWD, Tauni Devi

Schedule of Quantity

Schedule of Quantity									
NAME OF WORK:- C/O Uhal to Bakkar Khad via Parnali road km. 0/0 to 6/0.(SH:- C/O protection wall to 40.00mtr. Span Jamli side abutment 5/700 and 82.50 mtr. Span protection Jamli side at RD. 5/758 and C/O wire crate at RD. 4/810 to 4/833).(Under Bridge Head).								Estimated Cost:-	
Sr.No.								Earnest Money:-	
Description of Items								Time:-	
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and raiming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	72.28	In Fig.	Rate		Unit	Amount		
				In Words					
						Per cubic metre			
2	Providing and laying laid in wire crates with 4mm (four millimeters) dia G.I. wire conforming to IS:280 and IS: 4826 in 100x100mm (one hundred into one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (twenty five kilogramme) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	133.67				Per cubic metre			
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement three sand, six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	12.09				Per cubic metre			
Total									

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

NAME OF WORK:- Restoration of rain damages on Nanot to Bakkar Khad via Jamli road km. 0/0 to 4/0.(SH:- C/O wire crate at RD. 2/120 to 2/138.50).

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Nanot to Bakkar Khad via Jamli road km. 0/0 to 4/0. (Sh:- C/O wire crate at RD. 2/120 to 2/138.50).									
				Estimated Cost:-		Rs. 486351.00			
				Earnest Money:-		Rs. 9700.00			
				Time:-		Two Months			
Sr.No.		Description of Items		Qty.		In Fig.		In Words	
						Rate		Unit	
								Amount	
1		Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.		74.58				Per cubic metre	
2		Providing and laying laid in wire crates with 4mm (four millimeters) dia G.I. wire conforming to IS:280 and IS: 4826 in 100x100mm (one hundred into one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (twenty five kilogramme) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.		157.23				Per cubic metre	
Terms and Condition								Total	
Work shall be executed as per PWD specification.									

Anand Desai
Executive Engineer,
Tamil Devl Division,
HPPWD: Tamil Devl


Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Nanot to Bakkar Khad via Jamli road km. 0/0 to 4/0.(SH:- C/O wire crate at RD. 2/750 to 2/768.60).

Sr.No.	Description of Items	Qty.	Time:-		Two Months	Amount
			Rate	In Words	Unit	
					In Fig.	
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire cartage of material within all leads and its and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	68.98			Per cubic metre	
2	Providing and laying laid in wire crates with 4mm (four millimeters) dia G.I. wire conforming to IS.280 and IS. 4826 in 100x100mm (one hundred into one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (twenty five kilogramme) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire cartage of material within all leads and its and other incidentals.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	158.08			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Darkoti Mohin road km. 0/0 to 3/0 and Kodlu to Naugin road km. 0/0 to 2/405.(SH:- C/O Un-lined surface drain and dressing of berms).

Estimated Cost:- Rs. 412090.00
Earnest Money:- Rs. 8200.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Clearing jungle including uprooting of rank vegetation, grass brush wood, trees and saplings of girth upto 30 cm. (thirty centimetre) measured at a height of 1m (one metre) above ground level and removal of rubbish upto a distance of 50m (fifty metre) outside the periphery of the area cleared as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	11080.50			Per Square metre	
2	Maintenance of earthen shoulder (filling with fresh selected soil). Making up loss of material/irregularities on shoulders to the design level by adding fresh approves selected soil and compacting it with appropriate equipment at OMC upto all leads and lifts as per technical specification clause 1903, as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6270.00			Per Square metre	
	Total					

Terms and Condition

1. Work shall be executed as per PWD specification.

Asid GR
Executive Engineer,
Tamil Dev Division,
HPPWD, Tamil Dev

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on various road under Chouri Section Sujapur Sub-Division. (SH:- Hiring of JCB/front end Loader for removal of slips/clearing of drain due to heavy rains). (Balance work).

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			In Fig.	In Words		
1	Hiring of J.C.B. (front end loader 1 cum capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kinds of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8.00 hours from 9.00AM to 5.00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified by the Engineer-in-charge.	330.00			Per hour	
Total						

Terms and Condition

- 1 The contractor shall be responsible for any kind of breakage in the meachinery and accident happens during working hours.
- 2 Nothing shall be paid for idle hours
- 3 All bear and tear and POL charges are to be born by the contractor.

Executive Engineer,
Tauni Devi Division,
HPPWB: Tauni Devi.