

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Short terms tenders on form 6&8 are hereby invited by the Executive Engineer Bangana Division HP.PWD Bangana on behalf of the Governor of H.P. for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach and open in his office as per time schedule given below The offer of the tender will be kept open for 45 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of applications for the tender
Form a/w requisite documents: - 01.11.2023 upto 5.00 PM.
2. Date of issue /sale of tender forms against
Cash payment (Non-refundable):- 02.11.2023 upto 2:00 to 5.00 PM.
3. Date of receipt of tenders: - 03.11.2023 upto 10.30 A.M.
4. Date of opening of tenders: - 03.11.2023 at 11.00 A.M.

Sr. No.	Name of Work	Estimated Cost	EMD	Time Limit	Cost of Tender	Eligible class of Contractor
1	Restoration of Rain Damages on Tutru Kitpal Bhiambi road (SH:- Improvement of Geometrics from RD. 0/000 to 2/705)	499805	10000	Two Month	350	Class D
2	Restoration of Rain Damages on Tutru Kitpal Bhiambi road (SH:- Improvement of Geometrics from RD. 2/870 to 4/000)	482383	9700	Two Month	350	Class-D
3	A/R & M/O various road under Bangana Sub-Division (SH:- Providing and Fixing of dual directional delinator, retro reflective plastic and rod stud / cat eyes)	397600	8000	Two Month	350	Class-D
4	Repair and maintenance of Bridge over Madanpur Lamlehri road (SH:0 P/L 25 mm thick Mastic Asphalt over 2.00 No's Bridges at RD 7/925, 8/790 & 7/719.25 to 7/737.50)	498438	10000	Two Month	350	Class-D
5	Repair and maintenance of Bridge over Madanpur Lamlehri road (SH:0 P/L 25 mm thick Mastic Asphalt over 3.00 No's Bridges at RD 9/650, 7/480, 7/705)	491815	9900	Two Month	350	Class-D

The Earnest money in the shape of National Saving certificate/Time deposit/Saving account of any post office or FDR of Nationalised Bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No., Income Tax PAN No & EPF No. must be attached with application.

SPECIAL CONDITION:-

1. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their applications.(The proof of ownership of machinery/legal tie up arrangement).
2. The tender form will not be issued to those contractors who have already two works in hand.The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.
3. The conditional/ambiguous/telegraphic tenders or tender by fax shall not entertained/considered in any case.

No.PW/BGN/CB/T-1/2023-24-

Copy forwarded to the following for information and necessary action:-

1. The Engineer-in-Chief HPPWD, Nirman Bhawan Shimla.
2. All the Chief Engineer in HPPWD.
3. The Superintending Engineer, 15th Circle, HPPWD, Una.
4. All the Assistant Engineer, working under this Division.
5. Various Contractors working under this Division.
6. Notice Board.

Executive Engineer
Bangana Division
HPPWD Bangana.
Dated

Executive Engineer,
Bangana Division,
HPPWD Bangana

Certificate

Certified that the tenders called vide this office letter No. PW/BGN/CB/T-1/2023-24- 6027-57 dated 23/10/2023 is emergent nature and in public interest.



Executive Engineer,
Bangana Division,
HPPWD Bangana.



Schedule of Quantity

Name of Work:- Restoration of Rain Damages on Tutru Kitpal Bhiambi road (SH:- Improvement of Geometrics from RD. 0/000 to 2/705)

Estimated Cost: 499805.00
Earnest Money: 10000.00
Time Limit: Two months


Sr. No.	Description of work	No. or Qty.	Unit	RATE in Figures and words		AMOUNT Rs.
				Figures	Words	
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts on acquired width of road and transportation for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to required width of the road or to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tool and labour if required. Any loss to the public private property during the course to execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all the cases as per the direction of engineer-in-charge including carriage of material with in all leads and lifts. All useful material such as stone, shingle, sand and slates etcetra shall be sorted out. A recovery of 51.47 cum (fifty one point four seven) stone to be obtained from excavation cutting at the rate of Rs. 300/- (Rupees three hundred only) per cubic metre shall be effected on prorata bases in each running bill for this item. including carriage of material with in all leads and lifts and other incidentals. The rate includes octori, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	1257.91	Per Cubic metre			
Total in Figures						



Executive Engineer
Bangana Division
H.P.T.W.D. Bangar

Schedule of Quantity

Name of Work:- Restoration of Rain Damages on Tutru Kitpal Bhiambi road (SH:- Improvement of Geometrics from RD. 2/870 to 4/000)					Estimated Cost: 482363.00	
					Earnest Money: 9700.00	Two month
					Time Limit:	
Sr. No.	Description of work	No. or Qty.	Unit	RATE in Figures and words		AMOUNT Rs.
				Figures	Words	
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiselling, wedging out of rock(when blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts on acquired width of road and transportation for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to required width of the road or to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tool and labour if required. Any loss to the public private property during the course to execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all the cases as per the direction of engineer-in-charge including carriage of material with in all leads and lifts. All useful material such as stone, shingle, sand and slates etcetra shall be sorted out. A recovery of 47.40 cum (forty point four zero) stone to be obtained from excavation cutting at the rate of Rs. 300/- (Rupees three hundred only) per cubic metre shall be effected on prorata bases in each running bill for this item, including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	874.88	Per Cubic metre			
Total in Figures						


 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangar

Schedule of Quantity

Name of Work:-A/R & M/O Various road under Bangana Sub Division (SH:- Providing and Fixing of dual directional delinator , retro reflective plastic and rod stud/ cat eyes)						Estimated Cost:-	
						Earnest Money:-	8000.00
						Time Limit:-	Two mont
Sr. No.	Description of work	No.or Qty.	Unit	RATE in Figures and words		AMOUN Rs.	
				Figures	Words		
1	Providing and fixing dual directional retro reflective plastic road studs/cat-eyes stud Art No. C-12110 with dimentions 100 mm 100mm and 20 mm thickness in yellow, white and red colours (Two war acrylic presmectic reflectoer). as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	300.00	Each				
2	Providing and fixing of dual directional delinator made of dia is guage MS reatapular pipe of sotze 25 x 6 mm and of length 600 mm pipe stove enameled and baket to 120 C/power coated. Head made of ABS plastic rectangular moulded with flat face provided with high tensity presmatic reflactor of colour (white/yellow) of size 100 X 125 mm with additional to reflective strips of 25 mm wide made greens/ lite. as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	200.00	Each				
Total in Figures							


 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana

Schedule of Quantity

Name of Work:- Repair and maintenance of Bridge over Madanpur Lamlehri road (SH:- P/L 25mm thick Mastic Asphalt over 2.00 No.s Bridges at RD. 7/925,8/790 & 7/719.25 to

7/737.50)

Sr. No.	Description of work	No. or Qty.	Unit	RATE in Figures and words		AMOUNT Rs.
				Figures	Words	
1	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kg.per sqm (Zero point two hundred seventy five kilogram) per square metre on the prepared granular surfaces treated with primer and cleaned with Hydraulic broom as per technical specification .clause 503 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	368.70	Per Square metre			
2	Providing and laying 25 mm thick mastic asphalt wearing course with paving grade bitumen meeting the requirements given in table 500-29, prepared by using mastic cooker and laid to required level and slope after cleaning the surface, including providing antiskid surface with bitumen precoated finegrained hard stone chipping of 13.2 mm nominal size at the rate of 0.005cum per 10 sqm and at an approximate spacing of 10 cm center to center in both directions, pressed into surface when the temperature of surfaces is not less than 1000C, protruding 1 mm to 4 mm over mastic surface, all complete as per clause 515.as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by	368.70	Per Square metre			
3	Providing and fixing Dual Direction Reflective Cat Eye with Double Barriar Sanks of Impact resistant ABS PLASTIC STUD 100X90X16MM Ultra Violet , resistant Yellow/ Red Colour having micro prismatic / Cube corner reflectors suitable for fixing with epoxy / Bitumen adseive make acolite Twin moulded shank / Green Light including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	340.00	Each			
Total in Figures						


Executive Engineer
Bangana Division
H.P.W.D. Bangar

Schedule of Quantity

Name of Work:- Repair and maintenance of Bridge over Madanpur Lamlehri road (SH:- P/L 25mm thick Mastic Asphalt over 3.00 Nos.Bridges at RD. 9/650, 7/480, 7/705)

Estimated Cost: 491815.00
Earnest Money: 9900.00
Time Limit: Two months

Sr. No.	Description of work	No.or Qty.	Unit	RATE in Figures and words		AMOUNT Rs.
				Figures	Words	
1	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kg.per sqm (Zero point two hundred seventy five kilogram) per square metre, on the prepared granular surfaces treated with primer and cleaned with Hydraulic broom as per technical specification, clause 503 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	415.88	Per Square metre			
2	Providing and laying 25 mm thick mastic asphalt wearing course with paving grade bitumen meeting the requirements given in table 500-29, prepared by using mastic cooker and laid to required level and slope after cleaning the surface, including providing antiskid surface with bitumen precasted finegrained hard stone chipping of 13.2 mm nominal size at the rate of 0.005cum per 10 sqm and at an approximate spacing of 10 cm center to center in both directions, pressed into surface when the temperature of surfaces is not less than 1000C, protruding 1 mm to 4 mm over mastic surface, all complete as per clause 515 as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkhana, toll tax, sale tax or other taxes imposed by the Government.	415.88	Per Square metre			
3	Providing and fixing Dual Direction Reflective Cat Eye with Double Barriar Sanks of Impact resistant ABS PLASTIC STUD 100X90X16MM Ultea Voilet, resistant Yellow/ Red Colour having micro prismatic / Cube corner reflectors suitable for fixing with epoxy / Bitumen adseive make acolite Twin moulded shank / Green Light including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkhana, toll tax, sale tax or other taxes imposed by the Government.	160.00	Each			
Total in Figures						

Executive Engineer
Bangana Division
H.P.P.W.D. Bangana