



Office of Executive Engineer, Banjar Division,
Himachal Pradesh Public Works Department Banjar 175123
Phone No.01903-221031 Fax: 01903-221031

No:-PW/Banjar/CB/Tender/2023- 11960-12019

Dated:- 11/10/2023

To


The Executive Engineer (I.T. Cell),
o/o Engineer-in-Chief,
HPPWD. Nigam Bihar Shimla -171002.

Subject :-

Publishing of Notice Inviting Tenders Advertisement.


Enclosed please find herewith Copies of Notice Inviting Tender for the up-loading on department website on or upto 20.10.2023 as per notification issued by Secretary (PW) to the Govt. of HP Shimla vide letter No.PBW(S) A(3)1/2020 dated-16.07.2021, as the works mentioned in the Notice is urgent nature of work in the public interest.

Encl:- Notice


Executive Engineer,
Banjar Division,
H.P.P.W.D. Banjar.

Copy forwarded to followings for information and necessary action.

The Engineer- in- Chief, HPPWD Shimla-171002.
The Chief Engineer (M Z) HPPWD Mandi.
The Superintending Engineer 6th circle HPPWD Kullu.
All the Contractors enlisted in HPPWD.
The Superintendent, DAO ,HDM of this Office.
Notice Board


Executive Engineer,
Banjar Division,
H.P.P.W.D. Banjar

Himachal Pradesh
Public works Department
Notice Inviting Tender

Sealed item rate tender on from No. 6 & 8 are hereby invited by the Executive Engineer Banjar Division, HP,PWD, Banjar on behalf of Governor of H.P. from the eligible contractors enlisted in HP,PWD for the following works, so as to reach in this office on or before 25.10.2023 up to 11.00 AM and the tender will be opened on the same day at 11.30AM in the presence of intending contractors or their authorized representatives. The tender forms can be had from this office against cash payment (non-refundable) up to 23.10.2023 at 4.00 PM. The application for issue of tender forms shall be received upto 2.00 PM on 23.10.2023.

The Earnest money in the shape of National Certificate/Time deposit/Saving Account in any of the post office/Saving Bank Account of Nationalized Bank in H.P. duly pledged in favour of Executive Engineer Banjar Division HP, PWD, Banjar must be accompany each tender. Conditional tender and the tender received without earnest money will summarily be rejected. The offer of tender shall remain open for 75 days from the date of opening. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

All the contractors will have to bring with them attested copy of enlistment/ renewal/ exemption in earnest money. Contractor will be issued the tender forms only when they fulfill the terms and condition of form No. 6 & 8. Contractors should be registered under HP, Sales Tax Act. 1968/GST.

Job No.	Name of Work	Estimated cost	Earnest Money	Time	Cost of form
1	RRD on Hurla Thars Suchani road Km. 0/0 to 12/500. (SH:- C/O R/R masonry, R/Wall at RD- 4/240 to 4/255)	309765	6500	Three months	350/-
2	RRD on Khundhan Shatyaugi road Km. 0/00 to 6/00. (SH:- C/O Sub-Structrue 3.00 mtr RCC slab culvert at RD. 0/800). (Job NO. 2)	493561	10000	Three Months	350/-
3	Restoration of rain damages on Bhuin Diyar road Km. 0/0 to 12/500. (SH:- Construction of Breast wall in PCC 1:3:6 at RD. 3/100 to 3/115).	473872	10000	Three Months	350/-
4	Extension of Luhri Aut Manikaran road Km. 6/00 to 11/00. (SH:- Construction of R/wall at RD. 8/640 to 8/660).	416572	8500	Three Months	350/-
5	Restoration of rain Damages on Bhunter to Garsa road Km. 4/700 to 14/00. (SH:- Construction of wire crated R/Wall at RD. 11/120 to 11/132.50).	272291	6000	Three Months	350/-
6	Restoration of rain damages on Bhunter to Garsa road Km. 4/700 to 14/00. (SH:- Construction of wire crated R/wall at RD. 11/132.50 to 11/145).	272291	6000	Three Months	350/-
7	Restoration of rain damages on Bhunter to Garsa road Km. 4/700 to 14/00. (SH:- Construction of R/wall at RD. 10/230 to 10/235).	309465	6500	Three Months	350/-
8	Restoration of rain damages on Bhunter to Garsa road Km. 4/700 to 14/00. (SH:- Construction of R/wall at RD. 10/235 to 10/240).	309465	6500	Three Months	350/-
9	Restoration of rain damages on Bhunter to Garsa road Km. 4/700 to 14/00. (SH:- Construction of wire crated R/wall at RD. 11/182.50 to 11/195).	276183	6000	Three Months	350/-
10	C/O Dalasani to Mahi road Km. 0/00 to 2/010). (SH:- C/O Retaining wall at RD. 1/650 to 665).(under NABARD)	498464	10000	Three Months	350/-
11	Restoration of rain damages on kakroo Nalla Shogi road Km. 0/00 to 10/920. (SH:- Construction of Retaining wall at RD. 1/535 to 1/543.35)	366231	7500	Three months	350/-
12	RRD on Kakroo Nalla to Shoghi road Km. 0/00 to 10/920. (SH:- Construction of retaining wall at RD. 1/543.35 to 1/551.70).	366231	7500	Three Month	350/-
13	Restoration of rain damages on Garsa to Khora Aage road Km. 0/00 to 6/00. (SH:- Construction of Retaining wall at RD. 5/260 to 5/265).	265471	5500	Three Months	350/-
14	Restoration of rain damages on Garsa to Khora Aage road Km. 0/00 to 6/00. (SH:- Construction of Retaining wall at RD. 5/265 to 5/270).	265471	5500	Three Months	350/-


15	Construction of Dalashani to Mahi road Km. 0/00 to 2/010. (SH:- C/O wire crated R/wall at RD. 0/390 to 0/410 & C/O wire crated B/wall at RD- 1/250 to 1/290).(under NABARD).	418252	8500	Three Months	350/-
16	Restoration of rain damages on Suchain to Shanghar road Km. 0/00 to 8/00. (SH:- Construction of Wire crated B/wall at RD- 7/630 to 7/650).	359972	7500	Three Months	350/-
17	Restoration of rain damages on Suchain to Shanghar road Km. 0/00 to 8/00. (SH:- Construction of Retaining wall at RD. 7/700 to 7/710).	430784	9000	Three months	350/-
18	Restoration of rain damages on Jibhi Bahu Gadagushani road Km. 0/00 to 20/00. (SH:- Construction of PCC Toe wall along with C/O R/wall at RD. 5/360 to 5/373.50).	480455	9800	Three Months	350/-
19	Restoration of rain damages on Dhoru Plach road Km. 0/00 to 5/00. (SH:- C/O P.C.C. Toe wall & Breast wall at RD. 2/902 to 2/912).	380050	8000	Three Months	350/-
20	Restoration of rain damages on Bajaura to Kandi road Km. 3/700 to 12/500. (SH:- Construction of R/Wall at RD. 8/060 to 8/070)	205698	4500	Three Months	350/-
21	C/O Pnau Nalla to Dhara road Km. 0/00 to 2/300. (SH:- Formation Cutting RD. 1/120 to 1/405). (Deposit)	483457	9800	Two Months	350/-
22	C/O Pnau Nalla to Dhara road km. 0/00 to 2/300. (SH:- Formation cutting RD. 1/405 to 1/600). (Deposit)	495808	10000	Two Months	350/-
23	RRD on Bahu Bachoot up to Teel road Km. 0/00 to 3/500. (SH:- C/O wire crated B/Wall at RD. 0/475 to 0/495).	297117	6000	Three Month	350/-
24	Construction of Damothi Barthidhar road Km. 0/0 to 14/200. (SH:- Construction of wire crated Retaining wall at RD. 2/470 to 2/500).	494943	10000	Three Months	350/-
25	RRD on Larji Sainj road Km. 0/00 to 14/00.(Hiring of Tipper for carriage of Muck/debries of slips at various RDs reaches).	123120	2500	One Months	350/-
26	Restoration of rain damages on Banjar to Bathad road Km. 0/00 to 20/00. (SH:- Construction of Retaining wall at RD. 11/480 to 11/493).	453944	9500	Three Months	350/-
27.	Restoration of rain damages on Larji Sainj road Km. 0/00 to 11/300. SH:- Removal of slips at various reches).	452598	9200	15 days	350/-
28	Restoration of Rain damages on Lagani to chhawara road Km. 0/00 to 5/520 . (SH:- construction of Breast wall at RD. 4/875 to 4/890).	328210	7000	Three Months	350/-
29	Restoration of Rain damages on Lagani to Chhawara road Km. 0/00 to 5/520j. (SH:- Construction of Breast wall at RD. 4/860 to 4/875).	328210	7000	Three Months	350/-
30	Restoration of rain Damages on Garsa to Hawaii Gharat road Km. 0/00 to 7/290. (Construction of R/wall at RD. 4/190 to 4/196.70)	465227	9500	Three Months	350/-
31	Restoration of rain damages on Sidhwan Godigad Thanicher road Km. 0/00 to 7/200. (SH:- Construction of wire crated B/wall & Wire crated R/wall at RD. 0/160 to 0/172 & 0/750 to 0/762).	223193	4800	Three Months	350/-
32	Restoration of rain damages on Chanon Layida road Km. 0/00 to 1/900.(SH:- Construction of wire crated R/wall at RD. 0/700 to 0/720).	497634	10000	Three Months	350/-
33	Restoration of rain damages on Garsa to Hawaii Gharat road Km. 0/00 to 7/290. (SH:- Construction of R/Wall at RD. 4/203.40 to 4/210).	459797	9500	Three Months	350/-
34	Restoration of rain damages on Hurla Tharas to Suchaini road Km. 0/00to 12/500. (SH:- Construction of Breast wall at RD. 10/080 to 10/090 with PCC toe wall for protection of GPS Suchaini.)	474334	9500	Three Months	350/-
35	Restoration of rain damages on Hurla Tharas to Suchaini road Km. 0/00 to 12/500. (SH:- Construction of Breast wall at RD. 10/090 to 10/100 with PCC toe wall for protection of GPS Suchaini.)	474334	9500	Three Months	350/-

36	Restoration of rain damages on Bhuin Diyar road km. 0/00 to 12/500. (SH:- Construction of wire crated R/wall at RD. 3/112.50 to 119.50).	495353	10000	Three Months	350/-
37	Restoration of rain damages on Sidhwan Godigad Thanicher road km. 0/00 to 8/105. (SH:- Construction of 3.00 meter PCC Slab Culvert at RD. 0/130). <i>Job No. 1</i>	468584	9500	Three Months	350/-
38	Restoration of rain damaged on Sidhwan Godigad Thanicher road km. 0/00 to 8/105. (SH:- Construction of 3.00 meter PCC Slab Culvert at RD. 0/130). <i>Job No. 2</i>	468584	9500	Three Months	350/-
39	Restoration of rain damages on Kkroo Nala to Shoghi road k. 0/00 to 10/20. (SH:- Construction of Retaining wall at RD. 1/551.70 to 1/560).	366231	7500	Three Months	350/-
40	Restoration of rain damages on Sainj Neuli Kartah road km. 2/660 to 10/00. (SH:- Removal of slips at various reaches).	499575	10000	15Days	350/-
41	Restoration of rain damages on Sainj Neuli Kartah road km. 2/660 to 10/00. (SH:- Removal of slips at various reaches). <i>Job-2</i>	498576	10000	15 Days	350/-
42	Restoration of Rain damages on Siund Neuli road km. 2/660 to 10/00. (SH:- Construction of wire crated R/Wall at RD. 8/115 to 8/128.75).	486657	9900	Three Months	350/-
43	Restoration of rain damages on Siund Neuli road km. 2/660 to 10/00. (SH:- Construction of wire Crated Retaining wall at RD. 8/128.75 to 8/147.50).	486392	9900	Three Months	350/-
44	Restoration of rain damages on Naglari to Sarchi road km. 0/00 to 16/500. (SH:- Construction of wire Crated R/Wall at RD. 3/330 to 3/345).	246630	5200	Three Months	350/-
45	Restoration of rain damages on Sainj Kartah Neuli road km. 0/00 to 10/00. (SH:- Construction of wire rated R/Wall at RD. 0/630 to 0/641.50).	459251	9500	Three Months	350/-
46.	Restoration of rain damages on Suchain Shangar road 0/00 to 8/00 (SH:- Removal of slips at various RSs)	497772	10000	15 Days	350/-

TERMS AND CONDITIONS :-

The contractors /Bidders must quote their PAN/Income Tax Number/GST No. on the tender along with the copy of the same be attached with the application. The contractor/Firms should attach copy of registration/Renewal with the application, Contractor/Bidder are advised to visit and examine the site where the work are to be carrying out and its surrounding. The contractors/Bidders should quote his rates Both in figure and words. Where there is any discrepancy between the rates in figure and in words. The rates in words will be governed. Contractors/Bidders must inspect the site to ascertain/familiar the site condition accessibility etc. before quoting the bid/tender. Conditional and telegraphic tenders shall not be accepted and rejected straightway. Tenders received after due date and time will be rejected. Executive Engineer reserves the right to reject or all tenders without assigning any reason.

Certificate :- It is certified that the above works are required to be carried out immediately being emergent nature of work in the public interest.


Executive Engineer
Banjar Division,
HP,PWD, Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Hurla Thrass Suchani road Km. 0/00 to 12/500.
(SH :-Construction of R/R Masonry ,R/wall at RD.4/240 to 4/255).

Estimated Cost:- Rs. 309765/- only.
Earnest Money :-Rs. 6500/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	2			5	6	7	8.00
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidents to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, egg, and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	35.25	Cubic Metre.			Per cubic metre.	8.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D. specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	6.45	Cubic Metre.			Per cubic metre.	
3	Providing and laying cement concrete in open foundation 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 25mm (twenty five millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and H.P.W.D. specification/MORD technical specification section and clause 800,1202 and 1203 and curing complete including the cost of form work and hauling / carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	2.70	Cubic Metre.			Per cubic metre.	
4	Random rubble stone masonry in cement mortar 1:6 (one cement : six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	22.65	Cubic Metre.			Per cubic metre.	
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	34.20	Cubic Metre.			Per cubic metre.	
6	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	10.50	Cubic Metre.			Per cubic metre.	
						Total:-	

Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Khundhan Shatyaugi road Km. 0/00 to 6/00.
(SH :- Construction of Sub-Structure 3.00 mtr RCC Slab culvert at RD. 0/000). (Job No.2).

Estimated Cost:- Rs. 493561/- only.
Earnest Money :-Rs. 10000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding Figures	Words	Unit	Amount
		3	4				
1	2	113.00	Cubic Metre.	5	6	7	8.00
	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.					Per cubic metre.	
						Total:-	

Executive Engineer
Banjar Division
HPPWD Banjar

2

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Bhui Diyar road Km. 0/00 to 12/500.
(SH :- Construction of Breast wall in PCC 1:3:6 at RD.3/100 to 3/115).

Estimated Cost:- Rs. 473872/- only.
Earnest Money :-Rs. 10000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	2 Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	89.92	Cubic Metre.			Per cubic metre.	8.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	12.75	Cubic Metre.			Per cubic metre.	
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803, 1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 20mm (twenty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	71.20	Cubic Metre.			Per cubic metre.	
4	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1:20 (H) towards draining face complete as per drawing and technical specifications clause 614.709, 1206.6 including hauling/ carryage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	57.00	Each			Per cubic metre.	
						Total:-	

3

Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Extension of Luhri Aut Manikarn road Km. 6/00 to 11/00.
(SH :-Construction of R/wall at RD.8/640 to 8/660).

Estimated Cost:- Rs. 416572/- only.
Earnest Money :-Rs. 8500/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, egg, and states shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	43.70	Cubic Metre.	5	6	7	8.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D. specification & MORD technical specification and curing complete including the cost of form work and hauling/carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	8.60	Cubic Metre.			Per cubic metre.	
3	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 25mm (twenty five millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and HP.PWD. specification/MORD technical specification section and clause 800.1202 and 1203 and curing complete including the cost of form work and hauling / carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	3.60	Cubic Metre.			Per cubic metre.	
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	30.20	Cubic Metre.			Per cubic metre.	
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	45.60	Cubic Metre.			Per cubic metre.	
6	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	17.10	Cubic Metre.			Per cubic metre.	
						Total:-	

4

Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain Damages on Barvita to Garsa road Km. 4/700 to 1400..
(SH :-Construction of wire crated Rdwall at RD. 11/120 to 11/132.50).

Estimated Cost:- Rs. 272291/- only.
Earnest Money :-Rs. 6000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	2	36.00	Cubic Metre.		6	7 Per cubic metre.	8.00
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.						
2	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	97.65	Cubic Metre.			Per cubic metre.	
3	Construction of the Embankment with approved material of obtained from borrows pits with a lift up to 1.50 m transporting to site spreading grading a required slope and compacting to meet requirement of table 300.1 and 300.2 with a lead upto 1000 m as per technical specification clause 301.5 with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	30.34	Cubic Metre.			Per cubic metre.	
						Total:-	


 Executive Engineer
 Banjar Division
 HPPWD Banjar

5

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain Damages on Bhunka to Garsa road Km. 4/700 to 14/00..

(SH :-Construction of wire crated RWall at RD. 11/132.50 to 11/145) .

Estimated Cost:- Rs. 272291/- only.

Earnest Money :-Rs. 6000/- only.

Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	2	36.00	Cubic Metre.		6	7 Per cubic metre.	8.00
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg. and states shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.						
2	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	97.65	Cubic Metre.			Per cubic metre.	
3	Construction of the Embankment with approved material of obtained from borrows pits with a lift up to 1.50 m transporting to site spreading grading a requird slope and compacting to meet requirement of table 300.1 and 300.2 with a lead upto 1000 m as per technical specification clause 301.5 with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	30.34	Cubic Metre.			Per cubic metre.	
						Total:-	

(Handwritten signature)

Executive Engineer
Banjar Division
HPPWD Banjar

6

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain Damages on Burkha to Garsa roadKm. 4700 to 14/00.
(SH :-Construction of R/wall at RD. 10/230 to 10/235).

Estimated Cost:- Rs. 309465/- only.
Earnest Money :-Rs. 6500/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, egg, and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	28.60	Cubic Metre.	5	6	7	8.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D specification) & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	3.60	Cubic Metre.			Per cubic metre.	
3	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 25mm (twenty five millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, breast walls and parapets etc. complete as per drawings and HP.PWD. specification MORD technical specification section and clause 800, 1202 and 1203 and curing complete including the cost of form work and hauling / carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	2.15	Cubic Metre.			Per cubic metre.	
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702, 704, 1202 and 1204 including carryage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	14.32	Cubic Metre.			Per cubic metre.	
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carryage of all labour equipment and materials to various location through all modes of transportation, with in all leads and lift of materials and as per direction of Engineer-in-charge.	16.79	Cubic Metre.			Per cubic metre.	
6	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	10.12	Cubic Metre.			Per cubic metre.	
7	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 20mm (twenty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	20.55	Cubic Metre.			Per cubic metre.	
						Total:-	

Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain Damages on Shunt to Garsa road Km. 4700 to 1400.
(SH :-Construction of R/wall at RD. 10/235 to 10/240).

Estimated Cost:- Rs. 309465/- only.
Earnest Money :-Rs. 6500/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, levelling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, egg, and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and unserviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	28.60	Cubic Metre.	5	6	7 Per cubic metre.	8.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D. specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	3.60	Cubic Metre.			Per cubic metre.	
3	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 25mm (twenty five millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and H.P.W.D. specification/MORD technical specification section and clause 800, 1202 and 1203 and curing complete including the cost of form work and hauling / carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	2.15	Cubic Metre.			Per cubic metre.	
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702, 704, 1202 and 1204 including carryage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	14.32	Cubic Metre.			Per cubic metre.	
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carryage of all labour equipment and materials to various location through all modes of transportation with in all leads and lift of materials and as per direction of Engineer-in-charge.	16.79	Cubic Metre.			Per cubic metre.	
6	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	10.12	Cubic Metre.			Per cubic metre.	
7	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 20mm (twenty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	20.55	Cubic Metre.			Per cubic metre.	
						Total:-	


 Executive Engineer
 Banjar Division
 HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain Damages on *Bhundi* to Garsa road Km. 4700 to 1400..
(SH :-Construction of wire crated R/wall at RD. 11/182.50 to 11/195).

Estimated Cost:- Rs. 276183/- only.
Earnest Money :-Rs. 6000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		Figures	Words	Figures	Words		
1	2	3	4	5	6	7	8.00
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	34.31	Cubic Metre.			Per cubic metre.	
2	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4825 in 100mm x 100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighing not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carrriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	97.65	Cubic Metre.			Per cubic metre.	
3	Construction of the Embankment with approved material of obtained from borrows pits with a lift up to 1.50 m transporting to site spreading grading a requird slope and compacting to meet requirement of table 300.1 and 300.2 with a lead upto 1000 m as per technical specification clause 301.5 with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	67.43	Cubic Metre.			Per cubic metre.	
						Total:-	

A
Executive Engineer
Banjar Division
HPPWD Banjar

9

SCHEDULE OF QUANTITY

Name of Work:- Construction of Dalashani to Mahi road Km. 0/00 to 2/010).

(SH :- Construction of Retaining wall at RD. 1/650 to 1/665).

4 d c 2 N A B A R D

Estimated Cost:- Rs. 498464/- only.

Earnest Money :-Rs. 10000/- only.

Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	2			5	6	7	
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	31.73	Cubic Metre.			Per cubic metre.	8.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D specification & MORD technical specification and curing complete including the cost of form work and hauling/carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	6.45	Cubic Metre.			Per cubic metre.	
3	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 25mm (twenty five millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and HP.PWD. specification MORD technical specification section and clause 800, 1202 and 1203 and curing complete including the cost of form work and hauling / carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	2.70	Cubic Metre.			Per cubic metre.	
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702, 704, 1202 and 1204 including carrriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	22.65	Cubic Metre.			Per cubic metre.	
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carrriage of all labour equipment and materials to various location through all modes of transportation, with in all leads and lift of materials and as per direction of Engineer-in-charge.	34.20	Cubic Metre.			Per cubic metre.	
6	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	16.65	Cubic Metre.			Per cubic metre.	
7	Providing concrete for plain 1:3:6 (one cement: three sand: six aggregate 40mm nominal size) concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202 and 1203 P.C.C. with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	30.00	Cubic Metre.			Per cubic metre.	
						Total:-	


 Executive Engineer
 Banjar Division
 RPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Kakroo Nala to Shoghi road Km. 0/00 to 10/920.
(SH :-Construction of Retaining wall at RD. 1/535 to 1/543.35).

Estimated Cost:- Rs.366231/- only.
Earnest Money :-Rs. 7500/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		Figures	Words	5	6		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	3	Cubic Metre.	36.54	Per cubic metre.	7	8.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D. specification & MORD technical specification and curing complete including the cost of form work and hauling/carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	6.65	Cubic Metre.		Per cubic metre.		
3	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 25mm (twenty five millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and HP.PWD. specification/MORD technical specification section and clause 800.1202 and 1203 and curing complete including the cost of form work and hauling / carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	3.91	Cubic Metre.		Per cubic metre.		
4	Random rubble stone masonry in cement mortar 1:6 (one cement six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702.704, 1202 and 1204 including carrriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	28.56	Cubic Metre.		Per cubic metre.		
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carrriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	38.25	Cubic Metre.		Per cubic metre.		
6	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	14.87	Cubic Metre.		Per cubic metre.		
						Total:-	

Dr. J. S. Chakrabarti (Rural Development)
CPD Officer

11

Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Kakroo Nala to Shoghi road Km. 0/00 to 10/920.
(SH :-Construction of Retaining wall at RD. 1/543.35 to 1/551.70).

Estimated Cost:- Rs.366231/- only.
Earnest Money :-Rs. 7500/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		Figures	Words	5	6		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	3	4	5	6	7	8.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:5:12 (One cement : Six sand :twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and hauling/carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	36.54	Cubic Metre.			Per cubic metre.	
3	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand :eight graded crushed stone aggregate 25mm (twenty five millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and HP.PWD. specification/MORD technical specification section and clause 800,1202 and 1203 and curing complete including the cost of form work and hauling / carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	5.55	Cubic Metre.			Per cubic metre.	
4	Random rubble stone masonry in cement mortar 1:5 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carrriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	3.91	Cubic Metre.			Per cubic metre.	
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.5 and 1302.5 including hauling/ carrriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	28.55	Cubic Metre.			Per cubic metre.	
6	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	38.25	Cubic Metre.			Per cubic metre.	
		14.87	Cubic Metre.			Per cubic metre.	
						Total:-	

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Garsa to Khora Aage road Km. 0/00 to 6/00.

(SH :-Construction of Retaining wall at RD.5/260 to' 5/265).

Estimated Cost:- Rs.265471/- only.

Earnest Money :-Rs. 5500/- only.

Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	2	41.42	Cubic Metre.	5	6	7	8.00
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and unserviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.						
2	Providing and laying cement concrete for plain reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	3.99	Cubic Metre.			Per cubic metre.	
3	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 25mm (twenty five millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and HP.PWD. specification MORD technical specification section and clause 800, 1202 and 1203 and curing complete including the cost of form work and hauling / carryage of all labour equipments and materials to various localions through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	2.35	Cubic Metre.			Per cubic metre.	
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702, 704, 1202 and 1204 including carryage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	17.14	Cubic Metre.			Per cubic metre.	
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carryage of all labour equipment and materials to various location through all modes of transportation, with in all leads and lift of materials and as per direction of Engineer-in-charge.	22.95	Cubic Metre.			Per cubic metre.	
6	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1205.3 and 1604.7 including haulage/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	6.57	Cubic Metre.			Per cubic metre.	
7	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	15.62	Cubic Metre.			Per cubic metre.	
						Total:-	

13


 Executive Engineer
 Banjar Division
 HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Garsa to Khora Aage road Km. 0/00 to 6/00.
(SH :-Construction of Retaining wall at RD.5/265 to 5/270).

Estimated Cost:- Rs.265471/- only.
Earnest Money :-Rs. 5500/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	2	41.42	Cubic Metre.	5	6	7	8.00
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. It water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transporting of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and unserviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.						
2	Providing and laying cement concrete for plain/reinforcement concrete 1:5:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	3.99	Cubic Metre.			Per cubic metre.	
3	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 25mm (twenty five millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and H.P.P.W.D. specification MORD technical specification section and clause 800, 1202 and 1203 and curing complete including the cost of form work and hauling / carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	2.35	Cubic Metre.			Per cubic metre.	
4	Random rubble stone masonry in cement mortar 1:5 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carryage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	17.14	Cubic Metre.			Per cubic metre.	
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revatment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carryage of all labour equipment and materials to various location through all modes of transportation, with in all leads and lift of materials and as per direction of Engineer-in-charge.	22.95	Cubic Metre.			Per cubic metre.	
6	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1504.7 including haulage/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	6.57	Cubic Metre.			Per cubic metre.	
7	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighing not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	15.62	Cubic Metre.			Per cubic metre.	
						Total:-	

14

Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:-Construction of Dalashani to Mahi road Km. 0/00 to 2/010.

(SH :-Construction of wire crated Rdwall at RD. 0/390 to 0/410 & C/O wire crated B/wall at RD. 1/250 to 1/290).(Under NABARD).

Estimated Cost:- Rs. 418252/- only.

Earnest Money :-Rs. 8500/- only.

Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		Figures	Words	Figures	Words		
1	2	3	4	5	6	7	8.00
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	45.00	Cubic Metre.			Per cubic metre.	
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, levelling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	19.00	Cubic Metre.			Per cubic metre.	
3	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	156.25	Cubic Metre.			Per cubic metre.	
						Total:-	

Executive Engineer
Banjar Division
HPPWD Banjar

15

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Suchain to Shanghar road Km. 0/00 to 8/00.
(SH :- Construction of wire crated B/wall at RD. 7/630 to 7/650).

Estimated Cost:- Rs. 359972/- only.
Earnest Money :-Rs. 7500/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		Figures	Words	Figures	Words		
1	2	3	4	5	6	7	8.00
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	189.60	Cubic Metre.			Per cubic metre.	
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, aggs and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	15.00	Cubic Metre.			Per cubic metre.	
3	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	125.00	Cubic Metre.			Per cubic metre.	
						Total:-	


 Executive Engineer
 Banjar Division
 BPPWD Banjar

16

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Suchain to Shanghar road Km. 0/00 to 8/00.
(SH :- Construction of Retaining wall at RD.7700 to 7710).

Estimated Cost:- Rs. 430784/- only.
Earnest Money :-Rs. 9000/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds settling out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	33.30	Cubic Metre.	5	6	7 Per cubic metre.	8.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D specification & MORD technical specification and curing complete including the cost of form work and hauling/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	7.98	Cubic Metre.			Per cubic metre.	
3	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand eight graded crushed stone aggregate 25mm (twenty five millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and H.P.W.D. specification/MORD technical specification section and clause 800,1202 and 1203 and curing complete including the cost of form work and hauling / carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	4.70	Cubic Metre.			Per cubic metre.	
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	34.28	Cubic Metre.			Per cubic metre.	
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	45.90	Cubic Metre.			Per cubic metre.	
6	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	15.65	Cubic Metre.			Per cubic metre.	
	Total:-						


 Executive Engineer
 Banjar Division
 HPPWD Banjar

17

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Jibhi Bahu Gadagushani road Km. 0/00 to 20/00.

(SH :- Construction of PCC Toe wall along with C/o R/wall at RD. 5/360 to 5/373.50).

Estimated Cost:- Rs. 480455/- only.

Earnest Money :-Rs. 9800/- only.

Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		Figures	Words	Figures	Words		
1	2	3	4	5	6	7	8.00
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, egg, and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	39.15	Cubic Metre.			Per cubic metre.	
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D. specification & MORD technical specification and curing complete including the cost of form work and hauling/carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	3.78	Cubic Metre.			Per cubic metre.	
3	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 25mm (twenty five millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and HP PWD. specification/MORD technical specification section and clause 800, 1202 and 1203 and curing complete including the cost of form work and hauling / carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	81.40	Cubic Metre.			Per cubic metre.	
4	Providing weep holes in brick masonry /stone masonry plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1 in 20 (H) towards draining face complete as per drawing and technical specifications clause 614, 709, 1206.6 including hauling/ carrriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	18.00	Each			Each	
5	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	12.15	Cubic Metre.			Per cubic metre.	
						Total:-	


 Executive Engineer
 Bajjar Division
 HPPWD Banjar

18

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Dhoru Plach road Km. 0/00 to 5/00.
(SH :- Construction of P.C.C Toe wall & Breast wall at RD.2/902 to 2/912).

Estimated Cost:- Rs. 380050/- only.
Earnest Money :-Rs. 8000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding		Unit	Amount
		3	4	Figures	Words		
1	2	60.95	Cubic Metre.	5	6	7	8.00
1	Excavation soil in hilly area by mechanical means including cutting and trimming at side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.					Per cubic metre.	
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds settling out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	6.30	Cubic Metre.			Per cubic metre.	
3	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 25mm (twenty five millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and HP.PWD. specification/MORD technical specification section and clause 800,1202 and 1203 and curing complete including the cost of form work and hauling / carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	21.00	Cubic Metre.			Per cubic metre.	
4	Random rubble stone masonry in cement mortar 1:5 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	28.82	Cubic Metre.			Per cubic metre.	
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	34.55	Cubic Metre.			Per cubic metre.	
						Total:-	

19

Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain Damages on Bajaura to Kandi road Km. 3/700 to 12/500.
(SH :-Construction of Rwall at RD. 8/60 to 8/070).

Estimated Cost:- Rs. 205698/- only.
Earnest Money :-Rs. 4500/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	2	24.40	Cubic Metre.	5	6	7	8.00
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and unserviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.					Per cubic metre.	
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D. specification & MORD technical specification and curing complete including the cost of form work and hauling/carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	4.30	Cubic Metre.			Per cubic metre.	
3	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 25mm (twenty five millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and HP PWD, specification/MORD technical specification section and clause 800.1202 and 1203 and curing complete including the cost of form work and hauling / carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	1.80	Cubic Metre.			Per cubic metre.	
4	Random rubble stone masonry in cement mortar 1:5 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702.704.1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	15.10	Cubic Metre.			Per cubic metre.	
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revatment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation, with in all leads and lift of materials and as per direction of Engineer-in-charge.	22.80	Cubic Metre.			Per cubic metre.	
6	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	8.25	Cubic Metre.			Per cubic metre.	
						Total:-	

20
Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work :- Construction of Pnau Nalla to Dhara road Km. 0/00 to 2/300.
(SH :- Formation cutting RD. 1/120 to 1/405 (Deposit).

Estimated Cost:- Rs.483457/-only.
Earnest Money :-Rs. 9800/- only.
Time :- Two Month.

Sr. No	Description of Items	Quantity	Rate with all taxes in		Unit	Amount
			Figures	Words		
1	2	3	4	5	6	7
1	Cutting in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock(where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings and sorting out useful/unasetaf materials and stacking the same in all leads and lift and transportation of the un- useful materialsand then disposing of surplus excavated earth through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful stone of 238.07Cum@ 300/per cum amounting to Rs. 71421 /- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1958.98	Cubic Metre.		Per cubic metre.	
					Total:-	


Executive Engineer
Banjar Division
HPPWD Banjar.

21

SCHEDULE OF QUANTITY

Name of Work :- Construction of Pnau Nalla to Dhara road Km. 0/00 to 2/300.
(SH :- Formation cutting RD.1/405 to 600).(Deposit).

Estimated Cost:- Rs.495808/-only.
Earnest Money :-Rs. 10000/- only.
Time :- Two Month.

Sr. No	Description of items	Quantity	Rate with all taxes in		Unit	Amount
			Figures	Words		
1	2	3	4	5	6	7
1	Cutting in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock(where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings and sorting out useful/unaseful materials and stacking the same in all leads and lift and transportation of the un-usful materialsand then disposing of surplus excavated earth through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machinerries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful stone of 295.93Cum@ 300/per cum amounting to Rs. 88779 /- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1785.86			Per cubic metre.	
					Total:-	

22

 Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Bahu Bachoot up to Teel road Km. 0/00 to 3/500.
[SH :- Construction of wire crated B/ wall at RD. 0/475 to 0/495].

Estimated Cost:- Rs. 297117/- only.
Earnest Money :-Rs. 6000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		Figures	Words	Figures	Words		
1	2 Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock/hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	3 82.80	4 Cubic Metre.	5	6	7 Per cubic metre.	8.00
3	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge	108.00	Cubic Metre.			Per cubic metre.	
						Total:-	


Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Construction of Damothi Bartidhar road Km. 0/00 to 14/200.
(SH :- Construction of wire crated Retaining wall at RD.2/470 to 2/500).

Estimated Cost:- Rs. 494943/- only.
Earnest Money :-Rs. 10000/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	2 Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock-hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	75.60	Cubic Metre.			Per cubic metre.	8.00
2	Providing and laying of boulder upron laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	162.00	Cubic Metre.			Per cubic metre.	
3	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	25.20	Cubic Metre.			Per cubic metre.	
						Total:-	


 Executive Engineer
 Banjar Division
 SHPPWD Banjar

24

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Larji Sainj road Km. 0/00 to 14/00.
(SH :-Hiring of Tipper for carriage of Muck/debrides of slips at various RDs reaches).

Estimated Cost:- Rs. 123120 only.
Earnest Money :-Rs. 2500/- only.
Time :- One Month.

Sr. No	Description of items	Quantity	Rate with all taxes including GST		Unit	Amount
			Figures	Words		
1	Hiring of Tipper for carriage of muck /debrides of slip on various RDs. including POL charges and other incidentals i.e operator and cleaner and other staff charges complete and stacking the servicable material and disposal of non-servicable material. with in all leads and lifts of material as per direction and entire satisfaction of Engineer-in-charge the capacity of tipper not less than 5.50 Cum/10 tonne.	30.00			Per Day	
					TOTAL:-	

Executive Engineer
Banjar Division
BPPWD Banjar

25

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Banjar to Bathad road Km. 0/00 to 20/00.
(SH :- Construction of Retaining wall at RD.11/480 to 11/493).

Estimated Cost:- Rs. 453944/- only.
Earnest Money :-Rs. 9500/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		Figures	Words	Figures	Words		
1	2	3	4	5	6	7	8.00
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	74.23	Cubic Metre.			Per cubic metre.	
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	9.36	Cubic Metre.			Per cubic metre.	
3	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 25mm (twenty five millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and HP.PWD. specification/MORD technical specification section and clause 800,1202 and 1203 and curing complete including the cost of form work and hauling / carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	5.59	Cubic Metre.			Per cubic metre.	
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	35.70	Cubic Metre.			Per cubic metre.	
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation, with in all leads and lift of materials and as per direction of Engineer-in-charge.	44.20	Cubic Metre.			Per cubic metre.	
6	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	8.58	Cubic Metre.			Per cubic metre.	
						Total:-	

26

Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Larji Sainj road Km. 0/00 to 11/300,
(SH:- Removal of slips at various reaches).

Estimated Cost:- Rs. 452598/- only.
Earnest Money :-Rs. 9200/- only.
Time :- 15 Days.

Sr. No	Description of Items	Quantity		Rate with all taxes including GST		Unit	Amount
		3	4	Figures	Words		
1	2 Removal of land slide in hilly are in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification clause 302.3.5 and 1611.with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	3217.90	Cubic Metre.	5	6	7 Per cubic metre.	8.00
						Total:-	


Executive Engineer
Banjar Division
HPPWD Banjar

27

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on Lagani to Chhawara road Km. 0/00 to 5/520.
(SH :- Construction of Breast wall at RD. 4/875 to 4/890).

Estimated Cost:- Rs. 328210/- only.
Earnest Money :-Rs. 7000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	2			5	6	7	8.00
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	138.15	Cubic Metre.			Per cubic metre.	
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	32.70	Cubic Metre.			Per cubic metre.	
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	61.50	Cubic Metre.			Per cubic metre.	
4	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation, with in all leads and lift of materials and as per direction of Engineer-in-charge.	5.39	Cubic Metre.			Per cubic metre.	
						Total:-	

28

Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain damages on Lagani to Chhawara road Km. 0/00 to 5/520.
(SH :- Construction of Breast wall at RD. 4/860 to 4/875).

Estimated Cost:- Rs. 328210/- only.
Earnest Money :-Rs. 7000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	2	138.15	Cubic Metre.			7	8.00
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.					Per cubic metre.	
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	32.70	Cubic Metre.			Per cubic metre.	
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702.704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	61.50	Cubic Metre.			Per cubic metre.	
4	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	5.39	Cubic Metre.			Per cubic metre.	
						Total:-	

29

A

Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain Damages on Garsa to Hawal Gharat road Km. 0/00 to 7/290.
(SH :-Construction of R/wall at RD. 4/190 to 4/196.7).

Estimated Cost:- Rs. 465227/- only.
Earnest Money :-Rs. 9500/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		Figures	Words	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (Blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and unserviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	3	30.28	4	Cubic Metre.	7	8.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand twelve graded stone aggregate 40mm (four millimetre nominal size) mechanically mixed in open foundations and pinthills complete as per drawings and H.P.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	5.35				Per cubic metre.	
3	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand eight graded crushed stone aggregate 25mm (twenty five millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and HP.PWD. specification/MORD technical specification section and clause 800.1202 and 1203 and curing complete including the cost of form work and hauling / carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	3.15				Per cubic metre.	
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702.704, 1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	24.13				Per cubic metre.	
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	29.60				Per cubic metre.	
6	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	14.54				Per cubic metre.	
7	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803, 1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 20mm (twenty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	27.53				Per cubic metre.	
						Total:-	

39

Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Sidhwan Godigad Thanicher road Km. 0/00 to 7/200.
(SH :- Construction of wire crated B/ wall & Wire crated R/wall at RD.0/160 to 0/172 & 0/750 to 0/762).

Estimated Cost:- Rs. 223193/- only.
Earnest Money :-Rs. 4800/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	109.20	Cubic Metre.			Per cubic metre.	8.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock/hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	10.80	Cubic Metre.			Per cubic metre.	
3	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-1 wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge	77.76	Cubic Metre.			Per cubic metre.	
						Total:-	

21

Executive Engineer
Banjar Division
UPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Chanon Layida road Km. 0/00 to 1/900.
 (SH :- Construction of wire crated R/ wall at RD.0/700 to 0/720).

Estimated Cost:- Rs. 497634/- only.
 Earnest Money :-Rs. 10000/- only.
 Time :- Three Month.

Sr.No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	103.20	Cubic Metre.			Per cubic metre.	8.00
2	Providing and laying of boulder upron laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	165.60	Cubic Metre.			Per cubic metre.	
3	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	13.20	Cubic Metre.			Per cubic metre.	
						Total:-	


 Executive Engineer
 Banjar Division
 HMD D. D. D.

22

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain Damages on Garsa to Hawai Gharat road Km. 0/00 to 7/290.
(SH :-Construction of R/wall at RD. 4/203.40 to 4/210).

Estimated Cost:- Rs. 459797/- only.
Earnest Money :-Rs. 9500/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock (Blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, levelling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and unserviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	36.63	Cubic Metre.	5	6	7	8.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	5.27	Cubic Metre.			Per cubic metre.	
3	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 25mm (twenty five millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and H.P.P.W.D. specification/MORD technical specification section and clause 800,1202 and 1203 and curing complete including the cost of form work and hauling / carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	3.10	Cubic Metre.			Per cubic metre.	
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	23.93	Cubic Metre.			Per cubic metre.	
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revealment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation, with in all leads and lift of materials and as per direction of Engineer-in-charge.	28.99	Cubic Metre.			Per cubic metre.	
6	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	13.13	Cubic Metre.			Per cubic metre.	
7	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 20mm (twenty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	27.13	Cubic Metre.			Per cubic metre.	
						Total:-	

33

Executive Engineer
Banjar Division
APPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Hurla Tharass to Suchaini road Km. 0/00 to 12/500.
(SH :- Construction of Breast wall at RD. 10/080 to 10/090 with PCC toe wall for Protection of GPS Suchaini.

Estimated Cost:- Rs.474334/- only.
Earnest Money :-Rs. 9500/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	2	36.35	Cubic Metre.	5	6	7	8.00
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.					Per cubic metre.	
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	9.00	Cubic Metre.			Per cubic metre.	
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	28.82	Cubic Metre.			Per cubic metre.	
4	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	34.66	Cubic Metre.			Per cubic metre.	
5	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 20mm (twenty millimetre nominal size) including the cost of form work and curing complete and hauling/carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	34.00	Cubic Metre.			Per cubic metre.	
						Total:-	

34
Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Hurla Tharass to Suchaini road Km. 0/00 to 12/500.
(SH :- Construction of Breast wall at RD. 10/090 to 10/100 with PCC toe wall for Protection of GPS Suchaini.

Estimated Cost:- Rs.474334/- only.
Earnest Money :-Rs. 9500/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
				5	6		
1	2	36.35	Cubic Metre.			7	8.00
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.					Per cubic metre.	
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock-hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	9.00	Cubic Metre.			Per cubic metre.	
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	28.82	Cubic Metre.			Per cubic metre.	
4	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	34.66	Cubic Metre.			Per cubic metre.	
5	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 20mm (twenty millimetre nominal size) including the cost of form work and curing complete and hauling/carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	34.00	Cubic Metre.			Per cubic metre.	
						Total:-	

35
Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Bhuin Diyar road Km. 0/00 to 12/500.
(SH :- Construction of wire crated R/wall at RD. 3/112.5 & 119.50).

Estimated Cost:- Rs. 495353/- only.
Earnest Money :-Rs. 10000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding Words	Unit	Amount
		Figures	Words			
1	2	3	4	5	6	7
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost , including dressing of slopes and beds setting out conforming to required lines, grades , side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	61.46	Cubic Metre.		Per cubic metre.	8.00
2	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	155.90	Cubic Metre.		Per cubic metre.	
4	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	39.00	Cubic Metre.		Per cubic metre.	
					Total:-	

Executive Engineer
Banjar Division
P.W.D Banjar

36

SCHEDULE OF QUANTITY

Name of work: Restoration of rain damaged on Sidhwan Godigad Thanicher road km 0/00 to 8/05
(SH:- Construction of 3.00 metre P.C.C Slab culvert at RD. 0/130)

Job No.1
Estimated Cost:- Rs. 468584/- only.
Earnest Money :-Rs. 9500/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	2	3	4	5	6	7
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	118.15 Cubic Metre.			Per cubic metre.	
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	48.51 Cubic Metre.			Per cubic metre.	
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202 and 1203 P.C.C. Grade m-10 nominal size 1:3:6 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	13.75 Cubic Metre.			Per cubic metre.	
4	Providing and laying concrete for plain/reinforced concrete 1:6:12 (One cement : six sand : twelve graded stone aggregate 40mm nominal size) in open foundations complete as per drawing and technical specification clause 802, 803, 1202 and 1203 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	3.25 Cubic Metre.			Per cubic metre.	

27

5	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	75.00	Cubic Metre.		Per cubic metre.	
Total						

57

Executive Engineer
Banjar Division
UPPWD Banjar

SCHEDULE OF QUANTITY

Job No.2

Name of work: Restoration of rain damaged on Sidhwan Godigad Thanicher road km 0/00 to 8/105

(SH:- Construction of 3.00 metre P.C.C Slab culvert at RD. 0/130

Estimated Cost:- Rs. 468584/- only.

Earnest Money :-Rs. 9500/- only.

Time :- Three Month.

Sr. No	Description of Items	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	2	3	4	5	6	7
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	118.15	Cubic Metre.		Per cubic metre.	
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	48.51	Cubic Metre.		Per cubic metre.	
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 PCC. Grade m-10 nominal size 1:3:6 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	13.75	Cubic Metre.		Per cubic metre.	
4	Providing and laying concrete for plain/reinforced concrete 1:6:12 (One cement : six sand : twelve graded stone aggregate 40mm nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	3.25	Cubic Metre.		Per cubic metre.	

5	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	75.00	Cubic Metre.			Per cubic metre.	
Total							

Executive Engineer
Banjar Division
HPPWD Banjar

78

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Kakroo Nala to Shoghi road Km. 0/00 to 10/920.
(SH :-Construction of Retaining wall at RD. 1/551.70 to 1/560).

Estimated Cost:- Rs.366231/- only.
Earnest Money :-Rs. 7500/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	2	36.54	Cubic Metre.	5	6	7	8.00
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.						
2	Providing and laying cement concrete for plain/reinforcement concrete 1:5:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D. specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	6.65	Cubic Metre.			Per cubic metre.	
3	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 25mm (twenty five millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and HP.PWD. specification/MORD technical specification section and clause 800, 1202 and 1203 and curing complete including the cost of form work and hauling / carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	3.91	Cubic Metre.			Per cubic metre.	
4	Random rubble stone masonry in cement mortar 1:5 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702, 704, 1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	28.56	Cubic Metre.			Per cubic metre.	
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	38.25	Cubic Metre.			Per cubic metre.	
6	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	14.87	Cubic Metre.			Per cubic metre.	
						Total:-	


 Executive Engineer
 Banjar Division
 HPPWD Banjar

Neeli Kastah SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Saini Kastah Memli road Km. 2/660 to 10/00.
(SH :- Removal of slips at various reaches).

Estimated Cost:- Rs. 499575/- only.
Earnest Money :-Rs. 10000/- only.
Time :- 15 Days.

Sr. No	Description of Items	Quantity		Rate with all taxes including GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	2	3529.85	Cubic Metre.			7	8.00
1	Removal of land slide in hilly are in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification clause 302.3.5 and 1611.with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.					Per cubic metre.	
						Total:-	

Executive Engineer
Banjar Division
HPPWD Banjar

30

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Sainj ~~Kartah Nauli~~ road Km. 2/660 to 10/00.
(SH :- Removal of slips at various reaches).

Estimated Cost:- Rs. 498576/- only.
Earnest Money :-Rs. 10000/- only.
Time :- 15 Days.

Sr. No	Description of Items	Quantity		Rate with all taxes including GST		Unit	Amount
		3	4	Figures	Words		
1	2	3544.80	Cubic Metre.	5	6	7	8.00
1	Removal of land slide in hilly are in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification clause 302.3.5 and 1611.with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.					Per cubic metre.	
						Total:-	

Executive Engineer
Banjar Division
HPPWD Banjar

(4)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Sind Neuli road Km.2/660 to 10/00.
(SH :- Construction of wire Crated R/wall at RD. 8/115 to 8/128.75).

Estimated Cost:- Rs. 486657/- only.
Earnest Money :-Rs. 9900/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		Figures	Words	5	6		
1	2	3	4	5	6	7	8.00
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	30.66	Cubic Metre.			Per cubic metre.	
2	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	165.00	Cubic Metre.			Per cubic metre.	
3	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	18.00	Cubic Metre.			Per cubic metre.	
4	Construction of the Embankment with approved material of obtained from borrows pits with a lift up to 1.50 m transporting to site spreading grading a required slope and compacting to meet requirement of table 300.1 and 300.2 with a lead upto 1000 m as per technical specification clause 301.5. with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	140.00	Cubic Metre.			Per cubic metre.	
						Total:-	

Executive Engineer
Banjar Division
HPPWD Banjar

42

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Siund Neuli road Km.2/660 to 10/00.
(SH :- Construction of wire Crated R/wall at RD. 8/128.75 to 8/147.50).

Estimated Cost:- Rs. 486392/- only.
Earnest Money :-Rs. 9900/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	41.90	Cubic Metre.	5	6	7	8.00
2	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire confirming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighing not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1201 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	168.75	Cubic Metre.			Per cubic metre.	
3	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1604.7 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	8.00	Cubic Metre.			Per cubic metre.	
4	Construction of the Embankment with approved material of obtained from borrows pits with a lift up to 1.50 m transporting to site spreading grading a required slope and compacting to meet requirement of table 300.1 and 300.2 with a lead upto 1000 m as per technical specification clause 301.5 with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	150.00	Cubic Metre.			Per cubic metre.	
						Total:-	


Executive Engineer
Banjar Division
HPPWD Banjar

15

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on Naglari to Sarchi road Km. 0/00 to 16/500.
(SH :- Construction of wire Crated R/wall at RD. 3/330 to 3/345).

Estimated Cost:- Rs. 246630/- only.
Earnest Money :-Rs. 5200/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	2	39.15	Cubic Metre.	5	6	7	8.00
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.					Per cubic metre.	
2	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	81.00	Cubic Metre.			Per cubic metre.	
3	Back filling with granular materials behind abutment, wing walls and return walls complete as per drawing and technical specification clause 1206.3 and 1504.7 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	11.70	Cubic Metre.			Per cubic metre.	
						Total:-	

Executive Engineer
Banjar Division
HPPWD Banjar

(54)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Sainj Kartah Neuli road Km. 0/00 to 10/00.
(SH :- Construction of wire Crated R/wall at RD.0/630 TO 0/641.50).

Estimated Cost:- Rs. 459251- only.
Earnest Money :-Rs. 9500/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		Figures	Words	Figures	Words		
1	2	3	4	5	6	7	8.00
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock-hard rock (Requiring blasting). hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	35.32	Cubic Metre.	5		Per cubic metre.	
2	Providing and laying of boulder upron laid in wire crates with 4mm (four millimetre) dia G I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	164.06	Cubic Metre.			Per cubic metre.	
3	Construction of the Embankment with approved material of obtained from borows pits with a lift up to 1.50 m transporting to site spreading grading a required slope and compacting to meet requirement of table 300.1 and 300.2 with a lead upto 1000 m as per technical specification clause 301.5. with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	161.10	Cubic Metre.			Per cubic metre.	
						Total:-	


 Executive Engineer
 Banjar Division
 H.P.PWD. Banjar

45

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Suchain Shangar road 0/00 to 8/00
(SH:- Removal of slips at various RDs)

Estimated Cost:- Rs 497772 only.
Earnest Money :-Rs. 10000/- only.
Time :- 15 days

Sr. No	Description of items	Quantity	Rate with all taxes		Unit	Amount
			In Figures	In Words		
1	2	3	4	5	6	7
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in a left up to 1.5 metre and land upto 1000 metre as per technical specification 302.5.5 and 1611. with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	3539.08 Cubic metre			Cubic metre	
					Total:-	

yb


 Executive Engineer,
 Banjar Division
 HPPWD, Banjar