



E-Mail id – ee-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

“NOTICE INVITING TENDERS”

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 30/10/2023 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 27/10/2023 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

Sr. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1	Restoration of Rain damages on CMM road NH-205 in Km. 86/0 to 127/0 (SH:- C/o B/wall at RD, 114/250 to 114/270)	Rs. 2,17,483/-	Rs. 4,400/-	Rs. 350/-	Three Month
2	Restoration of rain damages on Sh. Naina Devi Ji Bhakra road Km. 0/0 to 37/300 (SH:- C/o wire crate as B/wall at RD 16/180 to 16/205)	Rs. 4,73,463/-	Rs. 9,500/-	Rs. 350/-	Three Month
3	Restoration of Rain damages on link road Harizen Basti Tiun Khas Km. 0/0 to 3/15 (SH:- C/o wire carte as a R/wall at RD 0/970 to 0/984)	Rs. 2,63,692/-	Rs. 5,300/-	Rs. 350/-	Three Month
4	Construction of Health Sub Center at Dabat Tehsil Sh. Naina Devi Ji Distt. Bilaspur (HP) (SH:- C/o Boundary wall and Gate) Deposit work	Rs. 1,67,900/-	Rs. 3,400/-	Rs. 350/-	Three Month
5	Construction of P.H.C. Building at Toba Tehsil Sh. Naina Devi Ji Distt. Bilaspur (HP) (SH:- C/o R/wall and Boundary wall) Deposit work	Rs. 4,17,064/-	Rs. 8,400/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

Sd/
Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

Dated:- 21-10-2023

No.PW/NBT/CB/Tender-State/EA-1/2023-

8658-67

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & ee-pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

LD
Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

SCHEDULE OF QUANTITY.				Estimated cost:- Rs.2,17,483/-Only.			
				Earnest Money :- Rs.4,400/-			
				Time:- Three Months.			
NAME OF WORK:- Restoration of Rain Damages on CMM road NH-205 in km 86/00 to 127/00 (SH:- C/o B/wall at RD 114/250 to 114/270)							
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount	
			Figure.	Words.			
1	2	3	4	5	6	7	
1	Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00	cubic metre		Per cubic metre		
2	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m (Twenty meter) as per Technical Specification Clause 1603.1 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.80	Cubic metre.		Per Cubic Metre		
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.00	Cubic metre		Per Cubic metre		
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.00	Nos.		Each		
Total:-							

Executive Engineer,
Bilaspur Division No.2,
Jharkhand PWD, Bilaspur (Jharkhand).

SCHEDULE OF QUANTITY.			Estimated cost:- Rs.4,73,963/-Only.			
			Earnest Money :- Rs.9,500/-			
			Time:- Three Months.			
NAME OF WORK:- Restoration of Rain Damages on Sh. Naina Devi ji Bakhra road km 0/00 to 37/300 (SH:- C/O wire crate as a Bi/wall at RD 16/180 to 16/205)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-Charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 54.75	cubic metre	4 5	6 Per cubic metre	7
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-Charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.75	cubic metre		Per cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	52.50	Cubic metre		Per Cubic metre	
4	Providing and laying of boulder apron laid in wire crates with 4mm (Four Millimeter) dia GI wire conforming to IS:280 and IS:4826 in 100mmx100mm mesh(Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301. including cost of form work and curing complete including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	78.12	Cubic metre		Per Cubic metre	
5	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess ,royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Nos.		Each	
Total:-						

Executive Engineer,
Bilaspur Division No. 2
H.P.W.D., Bilaspur

SCHEDULE OF QUANTITY.						Estimated cost:- Rs.2,63,692/-Only.
						Earnest Money :- Rs.5,300/-
						Time:- Three Months.
NAME OF WORK:- Restoration of Rain Damages on link road Harizan Basti Tiun Khas km 0/00 to 3/135 (SH:- C/o wire crate as a R/wall at RD 0/970 to 0/984)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	25.48			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four Millimeter) dia GI wire confirming to IS:280 and IS:4826 in 100mm (One hundred Millimeter) x100mm (One hundred Millimeter) mesh (Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301, including cost of form work and curing complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	96.00			Per Cubic metre	
Total:-						


 Executive Engineer,
 Alappur Division No. 2,
 P. S. RD, Alappur (P. S.)

SCHEDULE OF QUANTITY.		Estimated cost:- Rs.1,67,900/-Only.					
		Earnest Money :- Rs.3,400/-					
		Time:- Three Months.					
NAME OF WORK:- Construction of Health sub Centre at Dabat Teh. Sh. Naina Devi ji Distt. Bilaspur (HP) (SH:- C/o Boundary wall and Gate) (Deposit Work)							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3	4	5	6	7	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge, ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.57	cubic metre		Per cubic metre		
2	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (one cement :Six coarse sand : Twelve graded stone aggregate 20 mm(Twenty millimeter) nominal size) upto plinth level with cement mortar 1:6 (one cement : Six coarse sand) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.92	cubic metre		Per cubic metre		
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:4:8 (one Cement : Four coarse sand : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess ,royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.34	Cubic Metre		Per Cubic Metre		
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:2:4 (one Cement : Two coarse sand : Four graded stone aggregate) 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.640	Cubic metre.		Per Cubic Metre		

	providing Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and including all complete in all height / depth with Mild steel and Medium Tensile steel bars including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	196.80	Kilogram		Per Kilogram	
6	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in foundation and plinth in Cement mortar 1:6 (one cement : six coarse sand) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.68	Cubic Metre		Per Cubic Metre	
7	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in foundation and plinth in Cement mortar 1:4 (one cement : Four coarse sand) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	32.41	Square metre.		Per Square metre.	
8	15mm (fifteen millimetre) cement plaster in single coat on Fair side of brick/concrete/stone masonry for interior plastering including arries internal rounded angles, chamfers, and/ or rounded angles not exceeding 80mm (Eighty millimetre) in girth and finished even and smooth: cement mortar 1:6 (One cement Six sand) including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	51.82	Square metre.		Per Square metre.	
9	15 mm (fifteen millimeter) cement plaster on rough side of single or half brick wall of mix 1:6 (one cement: Six fine sand) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	51.82	Square Meter		Per Square Meter	
10	Finishing walls with water proofing cement paint of required shade New work (Two or more coats applied @ 3.84 kg/10 sqm) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	103.64	Square Meter		Per Square Meter	

	structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, joining, fixing in position and applying a priming coat of approved steel primer all complete. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	94.50	Kilogram			Per kilogram	
12	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.70	Square Meter			Per Square Meter	
Total:-							

Executive Engineer,
Nasipur Division No. 2
J.P.W.D., Bhalspur (H.P.)

SCHEDULE OF QUANTITY.						Estimated cost:- Rs.4,17,064/-Only.	
						Earnest Money :- Rs.8,400/-	
						Time:- Three Months.	
NAME OF WORK:- Construction of P.H.C Building at Toba Teh. Sh. Naina Devi Ji Distt. Bilaspur (HP) (SH:- C/o R/wall and Boundary wall) (Deposit Work)							
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount	
			Figure.	Words.			
1	2	3	4	5	6	7	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.40	cubic metre		Per cubic metre		
2	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (one cement :Six coarse sand : Twelve graded stone aggregate 20 mm(Twenty millimeter) nominal size) upto plinth level with cement mortar 1:6 (one cement : Six coarse sand) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.79	cubic metre		Per cubic metre		
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.27	Cubic metre		Per Cubic metre		
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:4:8 (one Cement : Four coarse sand : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess ,royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.49	Cubic Metre		Per Cubic Metre		

	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:2.4 (one Cement : Two coarse sand : Four graded stone aggregate) 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.700	Cubic metre.			Per Cubic Metre	
6	Providing Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete in all height / depth with Mild steel and Medium Tensile steel bars including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, Malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	324.00	Kilogram			Per Kilogram	
7	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, Malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.88	Cubic metre.			Per Cubic Metre	
8	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.00	Nos.			Each	
9	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in foundation and plinth in Cement mortar 1:6 (one cement : six coarse sand) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, Malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.13	Cubic Metre			Per Cubic Metre	
10	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in foundation and plinth in Cement mortar 1:4 (one cement : Four coarse sand) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, Malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	57.39	Cubic Metre			Per Cubic Metre	

	15mm (fifteen millimetre) cement plaster in single coat on fair side of brick/concrete/stone masonry for interior plastering including arrises internal rounded angles, chamfers, and/ or rounded angles not exceeding 80mm (Eighty millimetre) in girth and finished even and smooth: cement mortar 1:6 (One cement Six sand) including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	76.94	Square metre.			Per Square metre.
12	15 mm (fifteen millimeter) cement plaster on rough side of single or half brick wall of mix 1:6 (one cement: Six fine sand) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	76.94	Square Meter			Per Square Meter
13	Finishing walls with water proofing cement paint of required shade New work (Two or more coats applied @ 3.84 kg/10 sqm) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	153.88	Square Meter			Per Square Meter
14	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. Including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	189.00	Kilogram			Per kilogram
15	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.40	Square Meter			Per Square Meter
	Total:-					

Executive Engineer,
Narasapur Division No. 2,
Hq. PWD., BHASAPUR (P.)