



E- Mail id – ee-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

“NOTICE INVITING TENDERS”

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 18/10/2023 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 17/10/2023 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be outrightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

Sr. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1	Restoration of Rain damages on Navgaon Beri road Km. 4/350 to 23/700 (SH:- Repair of Pot holes in Km. 5/550 to 7/0) Deposit work	Rs. 4,89,083/-	Rs. 9,800/-	Rs. 350/-	Three Month
2	Restoration of Rain damages on Thatch Sikroha Neri Jukhala road Km. 0/0 to 18/690 (SH:- Repair of Pot Holes in Km. 14/0 to 16/0) Deposit work	Rs. 4,92,482/-	Rs. 10,000/-	Rs. 350/-	Three Month
3	Restoration of Rain damages on Rajpura Chilla Charnmore Km. 0/0 to 4/405 (SH:- Supplying of mixed material at HMP in Km. 0/0 to 2/0) Deposit work	Rs. 4,88,580/-	Rs. 9,800/-	Rs. 350/-	One Month
4	Restoration of Rain damages on Navgaon Beri road Km. 4/350 to 23/700 (SH:- Repair of Pot holes in Km. 4/350 to 5/550) Deposit work	Rs. 4,84,986/-	Rs. 9,700/-	Rs. 350/-	Three Month
5	Restoration of Rain damages on Sh. Naina Devi Ji Toba road Km. 0/0 to 9/225 (SH:- Repair of Pot holes in Km. 1/0 to 4/0) Deposit work	Rs. 4,45,669/-	Rs. 9,000/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

Dated:- 12-10-2023

No.PW/NBT/CB/Tender-State/EA-1/2023- 8077-86

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

SCHEDULE OF QUANTITY.									
								Estimated cost:- Rs.4,89,083/-Only.	
								Earnest Money :- Rs.9,800/-	
Time:- Three Months.									
NAME OF WORK:- Restoration of Rain Damages on Navgaon Beri road Km. 4/350 to 23/700 (SH:- Repair to Pot Holes in km 5/550 to 7/000) (Deposit work)									
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount			
			Figure.	Words.					
1	Providing and applying tack coat with bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.20 to 0.25 Kg. (Zero point two zero to Zero point two five)Kilogram per square metre on the prepared granular surface treated with primer and cleaned with Hydraulic broom as per Technical Specification Clause-503 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rates includes octroi,royalty ,Malkana toll tax ,goods and service ,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by * this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1316.25	Square metre.		Per Square metre.				
2	Providing and laying bituminous concrete 30 (Thirty) millimeter thick with 100-120 TPH batch type hot mix plant producing an average output of 75(Seventy five) tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4(Five point four) to 5.6(Five point six) percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respectsincluding carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess ,royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	39.49	Cubic metre.		Per Cubic metre				
Total									

Executive Engineer,
Bilaspur Division No. 2,
P.W.D., Bilaspur (H.P.).

SCHEDULE OF QUANTITY.							Estimated cost:- Rs.4,92,482/-Only.
							Earnest Money :- Rs.10,000/-
							Time:- Three Months.
NAME OF WORK:- Restoration of Rain Damages on Thatch Sikroha Neri Jukhala road Km. 0/00 to 18/690 (SH:- Repair to Pot Holes in km 14/00 to 16/00) (Deposit work)							
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount	
			Figure.	Words.			
1	Providing and applying tack coat with bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.20 to 0.25 Kg. (Zero point two zero to Zero point two five)Kilogram per square metre on the prepared granular surface treated with primer and cleaned with Hydraulic broom as per Technical Specification Clause-503 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge..The rates includes octroi,royalty ,Malkana toll tax ,goods and service ,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1350.80	Square metre.		Per Square metre.		
2	Providing and laying bituminous concrete 30 (Thirty) millimeter thick with 100-120 TPH batch type hot mix plant producing an average output of 75(Seventy five) tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4(Five point four) to 5.6(Five point six) percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respectsincluding carriage of material within all leads and lifts and other incidental.The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess ,royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.52	Cubic metre.		Per Cubic metre		
Total							

Executive Engineer,
Buzsaur Division No. 2,
DA PWD., Buzsaur (H.P.)

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.						Estimated Cost:- Rs.=4,88,580/-Only.
						Earnest Money:- Rs. =9,800/- only
						Time:- One Month.
Name of work :- Restoration of Rain Damages on Rajpura Chilla Charnmore km 0/00 to 4/405 (SH:- Supplying of mixed material at HMP in Km 0/00 to 2/00)						
(Deposit Work)						
Sr.No	Sub-head and item of work.	Quantity	Figure	Rate words.	Unit	Amount
1	Providing Mixed material for bitumenious concrete with 100-120 TPH batch type nearest Hot Mix plant producing an average output of 75 Tonnes per hour using crushed aggregates of specified grading ,premixed with bitumenious binder@ 5.4 to 5.6 percent of mix as per Morth specification clause No.503 complete in all respects The bitumenious, aggregate,sand and filler will be arranged by the supplier in all leads and lifts including loading of mixed material at Hot Mix plant . The mixed material will be carried by departmental tipper and work will be executed as per direction and entire satisfaction of Engineer in charge.	60.00			per cubic metre	
						Total Rs.

Executive Engineer
Bharatpur Division
H.P. PWD., Bharatpur (H.P.)

SCHEDULE OF QUANTITY.			Estimated cost:- Rs.4,84,986/-Only.			
			Earnest Money :- Rs.9,700/-			
			Time:- Three Months.			
NAME OF WORK:- Restoration of Rain Damages on Navgaon Beri road Km. 4/350 to 23/700 (SH:- Repair to Pot Holes in km 4/350 to 5/550) (Deposit work)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	Providing and applying tack coat with bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.20 to 0.25 Kg. (Zero point two zero to Zero point two five)Kilogram per square metre on the prepared granular surface treated with primer and cleaned with Hydraulic broom as per Technical Specification Clause-503 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rates includes octroi, royalty, Malkana toll tax, goods and service, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1305.25	Square metre.		Per Square metre.	
2	Providing and laying bituminous concrete 30 (Thirty) millimeter thick with 100-120 TPH batch type hot mix plant producing an average output of 75(Seventy five) tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4(Five point four) to 5.6(Five point six) percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respects including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	39.16	Cubic metre.		Per Cubic metre	
Total						

Executive Engineer,
Bilaspur Division No. 2,
H.O. PWD., Bilaspur (H.P.).

SCHEDULE OF QUANTITY.				Estimated cost:- Rs.4,45,669/-Only.		
				Earnest Money :- Rs.9,000/-		
				Time:- Three Months.		
NAME OF WORK:- Restoration of Rain Damages on Sh. Naina Devi Ji Toba Road km 0/00 to 9/225 (SH:- Repair to Pot Holes in km 1/00 to 4/00) (Deposit work)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	Providing and applying tack coat with bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.20 to 0.25 Kg. (Zero point two zero to Zero point two five)Kilogram per square metre on the prepared granular surface treated with primer and cleaned with Hydraulic broom as per Technical Specification Clause-503 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge..The rates includes octroi,royalty ,Malkana toll tax ,goods and service ,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1233.08	Square metre.		Per Square metre.	
2	Providing and laying bituminous concrete 30 (Thirty) millimeter thick with 100-120 TPH batch type hot mix plant producing an average output of 75(Seventy five) tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4(Five point four) to 5.6(Five point six) percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respectsincluding carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess ,royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	36.99	Cubic metre.		Per Cubic metre	
Total						

Executive Engineer,
Bilaspur Division No. 4
H.P. PWD., Bilaspur (Jharkhand)