



Tel.01899-299219.

cepwd-chowari@hp.gov.in

No. PWD-CHW/Tender /2023-24-

To

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

6577-79

Dated:- 30/09/2023

The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.

~~Executive Engineer,~~
Chowari Division,
HPPWD, Chowari.

Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

Executive Engineer,
Chowari Division,
HPPWD, Chowari.

Certificate

Certified that the tenders called vide this office letter No. PWD-
CHW/Tender /2023-24-6577-78...dated, 30/9/23 is emergent nature and in Public interest.

Executive Engineer,
Chowari Division,
HPPWD Chowari.



Tel.01899-299219.
cepwd-chowari@hp.gov.in

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed percentage/item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Chowari Division, HPPWD, Chowari on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

- 1 Date of receipt of application for the tender
Form a/w requisite documents: -
- 2 Date of issued/sale of tender form against
Cash payment (non refundable).

09/10/2023

10/10/2023

The tender shall be received upto 11.00 AM on **11/10/2023** and will be opened on the same day at 12.00 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on **11/10/2023**

The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Chowari Division, HPPWD, Chowari must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1	Restoration of rain damage on Kakira to Chalama Road km 0/0 to 4/300 (SH:- Construction of R/ wall at RD 0/185 to 0/197)	4,98,697.00	10000/-	Rs. 350/-	Three Month	Class-D & C
2	Restoration of rain damage on Shahpur Sihunta Chowari Jot Chamba Bharmour Road km 40/0 to 76/0 (SH:- Hiring of Tipper and Excavator cum Loader for removal of slips in km 54/200 to 65/500)	4,94,441.00	10000/-	Rs. 350/-	Three Month	Class-D & C
3	Restoration of rain damage on Shahpur Sihunta Chowari Jot Chamba Bharmour Road km 40/0 to 76/0 (SH:- Hiring of Poclain for removal of slips in km 66/0 to 76/0)	4,98,825.00	10000/-	Rs. 350/-	Three Month	Class-D & C
4	Restoration of rain damage on Patka Dalhousie Road km 45/0 to 66/0(SH:- Construction of R/ wall at RD 45/985 to 45/996)	4,32,500.00	8650/-	Rs. 350/-	Three Month	Class-D & C
5	Restoration of rain damage on Hunera to Kahri Kothi Road km 0/0 to 2/240 (SH:- Hiring of Tipper & Excavator cum Loader for removal of slips km 0/500 to 1/600)	4,96,150.00	10000/-	Rs. 350/-	Three Month	Class-D & C

6	Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti Road km 15/390 to 25/00 (SH:- Hiring of Poclain for removal of slips in km 22/0 to 25/0)	4,98,825.00	10000/-	Rs. 350/-	Three Month	Class-D & C
7	Restoration of rain damage on Shahpur Sihunta Chowari Jot Chamba Road km 40/0 to 76/0 (SH:- Hiring of Excavator cum Loader for removal of slips km 47/0 to 53/0)	4,99,800.00	10000/-	Rs. 350/-	Three Month	Class-D & C
8	Restoration of rain damage on Patka Dalhousie Road km 32/0 to 45/0 (SH:- Hiring of Excavator cum Loader for removal of slips km 32/0 to 45/0)	4,98,750.00	10000/-	Rs. 350/-	Three Month	Class-D & C
9	Restoration of rain damage on Ghatasani Pul to Bhalog Road km 0/0 to 7/360 (SH:- Hiring of Excavator cum Loader for removal of slips km 0/0 to 3/00)	4,93,500.00	10000/-	Rs. 350/-	Three Month	Class-D & C
10	Restoration of rain damage on various road under Chowari Sub-Division (SH:- Hiring of Tipper for shifting of muck/ debries on various road under Chowari Sub-Division)	1,64,160.00	3300/-	Rs. 350/-	Three Month	Class-D & C
11	Restoration of rain damage on various road under Chowari Sub-Division (SH:- Hiring of Tipper for shifting of muck/ debries on various road under Chowari Sub-Division)	4,05,270.00	9100/-	Rs. 350/-	Three Month	Class-D & C
12	Restoration of rain damage on Chowari to Kainthly Road km 0/0 to 12/570 (SH:- Hiring of Tipper and Excavator cum Loader for removal of slips in km 1/500 to 5/500)	1,97,160.00	4000/-	Rs. 350/-	Three Month	Class-D & C
13	Restoration of rain damage on Chowari Mandhiar Gaghar Baloh Fagot Road km 0/0 to 13/330 (SH:- Pusta in R/wall & wire crate at RD 10/985 to 11/0)	4,96,413.00	10000/-	Rs. 350/-	Three Month	Class-D & C
14	Restoration of rain damage on Chowari Mandhiar Gaghar Baloh Fagot Road km 0/0 to 13/330 (SH:- Pusta in R/wall & wire crate at RD 11/050 to 11/065)	4,11,420.00	9500/-	Rs. 350/-	Three Month	Class-D & C
15	Restoration of rain damage on Shahpur Sihunta Chowari Jot Chamba Road km 40/0 to 76/0 (SH:- C/o HP culvert at RD 50/005 & wing wall at RD 50/011.30 to 50/013.80 & 50/016.20 to 50/018.70)	4,90,414.00	10000/-	Rs. 350/-	Three Month	Class-D & C
16	Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti Road km 15/390 to 25/0 (SH:- C/o R/wall at RD 16/645 to 16/654)	4,81,268.00	9800/-	Rs. 350/-	Three Month	Class-D & C
17	Restoration of rain damage on various road under Sihunta Sub-Division (SH:- Hiring of Excavator cum Loader for removal of slips under Sihunta section)	1,60,338.00	3300/-	Rs. 350/-	Three Month	Class-D & C
18	Restoration of rain damage on Jolna to Baded Road km 0/0 to 3/810(SH:- Removal of slips in km 3/0 to 3/700)	4,97,080.00	10000/-	Rs. 350/-	Three Month	Class-D & C
19	Restoration of rain damage on Chowari Mandhiar Gaghar Road km 0/0 to 8/700 (SH :- C/o R/wall at RD 2/030 to 2/043)	4,95,935.00	10000/-	Rs. 350/-	Three Month	Class-D & C
20	Restoration of rain damage on Link Road to village Aghar km 0/0 to 1/00 (SH:- C/o R/wall at RD 0/450 to 0/462.50)	4,85,247.00	9800/-	Rs. 350/-	Three Month	Class-D & C

21	Restoration of rain damage on Hunera to Kahri Kothi Road km 0/0 to 2/420 (SH:- C/o R/wall at RD 1/010 to 1/022.50)	4,74,735.00	9500/-	Rs. 350/-	Three Month	Class-D & C
22	Restoration of rain damage on various road under Chowari Sub-Division (SH:- Hiring of Excavator cum Loader for removal of slips)	4,91,400.00	9800/-	Rs. 350/-	Three Month	Class-D & C
23	Restoration of rain damage on various road under Sihunta Sub-Division (SH:- Hiring of Excavator cum Loader for removal of slips)	4,87,500.00	9800/-	Rs. 350/-	Three Month	Class-D & C

- 1 The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
- 2 The Contractor should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.
- 3 GST No/Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
- 4 application without all documents will not be entertained.
- 5 Proxy application will not be entertained.

Executive Engineer,
Chowari Division,
HPPWD, Chowari.

No. PWD-CHW/Tender /2023-24-

6580-6630

Dated:-

30-9-2023

Copy forwarded to the following for information and necessary action please:-

- 1 Engineer-in-Chief, HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 The BDO Bhattiyat.
- 7 Sub Divisional Magistrate/B.D.O/Tehsildar Chowari.
- 8 Notice Board of this office.


Executive Engineer,
Chowari Division,
HPPWD, Chowari.

Schedule of Quantity

Name of work:- Restoration of rain damage on Kakira to Chalama Road km 0/0 to 4/300 (SH:- C/o R/ wall at RD 0/185 to 0/197)

Estimated Cost	Rs 498697/-
Earnest Money	Rs 10000/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	43.56			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	93.84			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V) : 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	27.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	16.20			Per cubic metre	
Total						


Executive Engineer
 Chowari Division
 Hppwd Chowari

Schedule of Quantity

Estimated Cost	Rs. 494444/-
Earnest Money	Rs. 100000/-
Time Limit	One month

Name of work:- Restoration of rain damages on Shahpur Sihunta Chowari Road km 40/0 to 76/0 (SH:- Hiring of Tipper & Hydraulic Excavator cum Loader for removal of slips)

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	270.00			Per hour	
2	Hiring of Tipper having capacity 5.5 (five decimal five zero) cubic meter for cartage of all type of material upto any leads and lifts as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also are borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	412.00			Per hour	
Total						

Executive Engineer
 Chowari Division
 Hingyad Chowari

Schedule of Quantity

Name of work :- Restoration of rain damages on Shahpur Sihunta Chowari Road km 40/0 to 76/0 (Sub head:- Hiring of Poclain for removal of Slip/Debris/Boulder etc)

Estimated Cost . Rs. 498825/-
Earnest Money Rs. 10000/-
Time Limit One month

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of Poclain ofr removal of lips /Debris/Boulder in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be lave to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	135.00			Per Hours	
Total						

Executive Engineer
Chowari Division
Hdpwd Chowari

Schedule of Quantity

Estimated Cost	Rs 432500/-
Earnest Money	Rs 9800/-
Time Limit	Three months

Name of work:- Restoration of rain damage on Patka Dalhousie Road km 45/0 to 66/0 (SH:- C/o R/ wall at RD 45/985 to 45/996)

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	38.50			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	80.30			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (IV); 20 (11) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204, 3.7 as per the directions of the Engineer-in-charge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	28.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	13.86			Per cubic metre	
Total						


 Executive Engineer
 Chowari Division
 Appwd Chowari

(5)

Schedule of Quantity

Name of work:- Restoration of rain damages on Hunnera to Kahri Kothi Road km 0/0 to 2/240 (SH:- Hiring of Tipper & Hydraulic Excavator cum Loader for removal of slips in km 0/500 to 1/600)	Estimated Cost Rs. 496150/-
	Earnest Money Rs. 100000/-
	Time Limit One month

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	375.00			Per hour	
2	Hiring of Tipper having capacity 5.5 (five decimal five zero) cubic meter for carriage of all type of material upto any leads and lifts as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also are borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	200.00			Per hour	
Total						

Executive Engineer
 Chowari Division
 Hppwd Chowari

63

Schedule of Quantity

Name of work :- Restoration of rain damages on Nurpur Sanjhi Nallah Lahru Tunuhatti Road km 15/390 to 25/00 (Sub head:- Hiring of Poclain for removal of Slip/Debris/boulder in km 22/0 to 25/0)

		Estimated Cost		Rs. 498825/-	
		Earnest Money		Rs. 10000/-	
		Time Limit		One month	
S.No.	Description	Quantity	Rate	Unit	Amount
		Fig.	Word		
1	Hiring of Poclain for removal of slips /Debris/Boulder in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be laved to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	135.00		Per Hours	
Total					

Executive Engineer
Chowari Division
Hidwad Chowari


(2)

Schedule of Quantity

Estimated Cost	Rs. 499800/-
Earnest Money	Rs. 10000/-
Time Limit	One month

Name of work:- Restoration of rain damage on Shahpur Sihunta Chowari Jot Road km 40/0 to 76/0 (SH:- Hiring of Hydraulic Excavator cum Loader for removal of slips)

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be laive to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge .The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	476.00			Per hour	
Total						


Executive Engineer
Chowari Division
Hppwd Chowari

8

Schedule of Quantity

Estimated Cost	Rs. 498750/-
Earnest Money	Rs. 100000/-
Time Limit	One month

Name of work:- Restoration of rain damage on Patka to Dalhousie Road km 32/0 to 45/0(SH:- Hiring of Hydraulic Excavator cum Loader for removal of slips)

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge .The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	475.00			Per hour	
Total						

Executive Engineer
Chowari Division
Hppwd Chowari

Schedule of Quantity

Name of work:- Restoration of rain damage on Chatasani Pul to Bhalog Road km 0/00 to 7/360(SH:- Hiring of Hydraulic Excavator cum Loader for removal of slips km 0/0 to 3/0)

Estimated Cost	Rs. 493500/-
Earnest Money	Rs. 10000/-
Time Limit	One month

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be lave to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge .The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	470.00			Per hour	
Total						

Executive Engineer
 Chowari Division
 Hppwd Chowari

Schedule of Quantity

Name of work:- Restoration of rain damages on various Road under Chowari Sub-Division(SH:- Hiring of Tipper for shifting of muck/debrics on various roads under Chowari Sub-Division)

		Estimated Cost		Rs. 164160-	
		Earnest Money		Rs.3300/-	
		Time Limit		One month	

Name of work:- Restoration of rain damages on various Road under Chowari Sub-Division(SH:- Hiring of Tipper for shifting of muck/debris on various roads under Chowari Sub-Division)						
S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of Tipper having capacity 5.5 (five decimal five zero) cubic meter for carriage of all type of material upto any leads and lifts as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be lave to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also are borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	375.00			Per hour	

Executive Engineer
Chowari Division
Hppwd Chowari

Schedule of Quantity

Name of work:- Restoration of rain damages on various Road under Chowari Sub-Division (SH:- Hiring of Tipper for shifting of muck/debris on various roads under Chowari Sub-Division)

		Estimated Cost		Rs. 405270/-	
		Earnest Money		Rs.8300/-	
		Time Limit		One month	

Name of work:- Restoration of rain damages on various Road under Chowari Sub-Division(SH:- Hiring of Tipper for shifting of muck/debris on various roads under Chowari Sub-Division)					
<u>Schedule of Quantity</u>					
S.No.	Description	Quantity	Rate	Unit	Amount
			in Fig.	in Word	
1	Hiring of Tipper having capacity 5.5 (five decimal five zero) cubic meter for cartage of all type of material upto any leads and lifts as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be lave to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also are borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	790.00			Per hour


Executive Engineer
 Chowari Division
 HPQWD Chowari

Schedule of Quantity

Name of work:- Restoration of rain damages on Chowari to Kainthly Road km 0/00 to 12/570 (SH:- Hiring of Tipper and Hydraulic Excavator cum loader vfor removal of slips in k 1/500 to 5/00)

Estimated Cost	Rs. 197160/-
Earnest Money	Rs. 4000/-
Time Limit	One month

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge .The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	100.00			Per hour	
2	Hiring of Tipper having capacity 5.5 (five decimal five zero) cubic meter for carriage of all type of material upto any leads and lifts as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also are borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	180.00			Per hour	

Executive Engineer
 Chowari Division
 Appvd Chowari

(13)

Schedule of Quantity

Name of work:- Restoration of rain damage on Chowari Mandhhar Baloh Fagot Road km 0/00 to 13/330 (SH:- C/o CC Pusta in R/wall and wire crate at RD 10/985 to 10/ 11/00)

		Estimated Cost		Rs 496413/-		
		Earnest Money		Rs 10000/-		
		Time Limit		Three months		
Name of work:- Restoration of rain damage on Chowari Mandhilar Baloh Fagot Road km 0/00 to 13/330 (SH:- C/o CC Pusta in R/wall and wire crate at RD 10/985 to 10/ 11/00)						
S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	36.30			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimeter) mesh (woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 40kg (Forty Kilogram) each as per drawing and technical specifications Clause 1301 and as per directions of including the octroi, royalty Malkana, toll tax sales taxes GST or any taxes imposed by the Government.	70.31			Per cubic metre	
3	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	54.00			Per cubic metre	
Total						


 Executive Engineer
 Chowari Division
 H.P.O. Chowari

Schedule of Quantity

Name of work:- Restoration of rain damage on Chowari Mandhiar Baloh Fagot Road km 0/00 to 13/330 (SH:- C/o CC Pusta in R/wall and wire crate at RD 11/050 to 11/065)

Estimated Cost	Rs 411420/-
Earnest Money	Rs 8300/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	31.80			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia G1 wire conforming to IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimeter) mesh (woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 40kg (Forty Kilogram) each as per drawing and technical specifications Clause 1301 and as per directions of including the octroi, royalty Malkana, toll tax sales taxes GST or any taxes imposed by the Government.	93.75			Per cubic metre	
3	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	21.60			Per cubic metre	
Total						

Executive Engineer
Chowari Division
Hppwd Chowari

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Shahpur Sihunta Chowari Jot Chamba Road km 40/0 to 76/0 (Sub Head:- C/O H.P. culverts at RD 50/05 and along with wing walls at RD 50/011.30 to 50/013.80 & 50/016 to 50/016.20)

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1.	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other detriorous material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts as per the direction of the Engineer in Charge. The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt	60.37			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:3:6) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt	2.20			Per cubic metre	
3	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2:5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt	1.28			Per cubic metre	
4	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2:4) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt	0.37			Per cubic metre	
5	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2:5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt	28.15			Per cubic metre	
6	Providing and laying (to level or slope) 900mm dia (Nine thousand millimeters) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete or first class bedding and masonry work in head walls and parapets as per drawing and MORD technical specifications section 11080, including hauling of materials in all leads and lifts and other incidental. The rate including Octroi, Royalty, Malkana, Toll Tax, Sale Tax, GST or other taxes imposed by the Government	7.50			Per running metre	
7	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt	43.7			Per cubic metre	

125

8	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V); 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614,709,1204.3.7 as per the directions of the Engineer-in-charge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	16					Each	
9	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	8.08					Per cubic metre	

Executive Engineer,
 Chowari Division,
 P.W.D. Chowari

Schedule of Quantity

Name of work:- Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti Road km 15/390 to 25/00 (SH:- C/o R/ wall at RD 16/645 to 16/654)

		Estimated Cost	
		Earnest Money	Rs 481268/-
		Time Limit	Rs 9800/- Three months

Name of work:-Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti Road km 15/390 to 25/00 (Sft:- C/o R/ wall at RD 16/645 to 16/654)						
S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead , dressing of sides and bottom and backfilling in trenches with excavated suitable material . as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt	37.53			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	93.60			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (IV); 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	28.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	18.32			Per cubic metre	
Total						

Executive Engineer
Chowari Division
H.P.W.D Chowari

(12)

Schedule of Quantity

Name of work:- Restoration of rain damages on various roads under Sihunta Sub-Division (SH:- Hiring of Tipper and Hydraulic Excavator cum loader for removal of slips under Sihunta section)

Estimated Cost	Rs. 160338/-
Earnest Money	Rs. 3200/-
Time Limit	One month

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge .The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	85.00			Per hour	
2	Hiring of Tipper having capacity 5.5 (five decimal five zero) cubic meter for carriage of all type of material upto any leads and lifts as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also are borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	151.00			Per hour	

Executive Engineer
 Chowari Division
 Hppwd Chowari

18

Schedule of Quantity

Name of work:- Restoration of rain damages on Jolna to Bhaded Road km 0/0 to 3/810 (SH:- Removal of slips in km 3/0 to 3/700)

Estimate Cost :- Rs.	497080/-
Earnest Money	10000/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			m.Figs	In Word		
	Removal of landslides/ slip clearance in hilly area in all kinds of soil not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any leads and lifts as per technical specifications. The rate including octroi, royalty, Malkana Toll tax sale tax, GST or other taxes imposed by the Govt.	3974.415			Per cubic metre	
Total						

Executive Engineer
Chowari Division
Hppwd Chowari

Schedule of Quantity

Name of work:- Restoration of rain damage on Chowari to Mandhilar Gagahar Road km 0/0 to 8/700 (SH:- C/o R/ wall at RD 2/030 to 2/043)

				Estimated Cost	Rs 495935/-
				Earnest Money	Rs 10000/-
				Time Limit	Three months
S.No.	Description	Quantity	Rate	Unit	Amount
			in Fig.	in Word	
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	44.79		Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	94.38		Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V): 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	33.00		Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	16.97		Per cubic metre	
Total					


 Executive Engineer
 Chowari Division
 Hppwd Chowari

Schedule of Quantity

Estimated Cost	Rs 485247/-
Earnest Money	Rs 100000/-
Time Limit	Three months

Name of work:- Restoration of rain damage on Link Road to village Aggarh km 0/0 to 1/00 (Sl:- C/o R/ wall at RD 0/450 to 0/462.50)

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidentals. The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	51.19			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	90.75			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V) : 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204, 3.7 as per the directions of the Engineer-in-charge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	31.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	24.19			Per cubic metre	
Total						


 Executive Engineer
 Chowari Division
 Hppwd Chowari

Schedule of Quantity

Name of work:- Restoration of rain damage on Hunnara to Kahri Kohli Road km 0/0 to 2/420 (Sl:- C/o R/ wall at RD 1/010 to 1/022.50)

Estimated Cost	Rs 474735/-
Earnest Money	Rs 10000/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidentals The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	37.56			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Normal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	90.75			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V), 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	31.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	19.50			Per cubic metre	
Total						


Executive Engineer
 Chowari Division
 Hppwd Chowari

22

Schedule of Quantity

Name of work:- Restoration of rain damage on various roads under Chowari Sub-Division (SH:- Hiring of Hydraulic Excavator cum Loader for removal of slips)

Estimated Cost	Rs. 491400/-
Earnest Money	Rs. 10000/-
Time Limit	One month

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge . The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	468.00			Per hour	
Total						


Executive Engineer
 Chowari Division
 HRPWD Chowari

Schedule of Quantity

Estimated Cost	Rs. 487500/-
Earnest Money	Rs. 10000/-
Time Limit	One month

Name of work:- Restoration of rain damage on various roads under Sihunta Sub-Division (SH:- Hiring of Hydraulic Excavator cum Loader for removal of slips)

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge .The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	500.00			Per hour	
Total						

Executive Engineer
 Chowari Division
 Hppwd Chowari