

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/DPD/CB-Tender/2023- 4475-76
To

Dated:- 26-10-2023

The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - Publishing of tender Notice.
Sir,

Enclosed please find herewith tender notice of work as given in the Notice inviting Tender along with Draft Bill of Quantities for uploading on department website as per Notification No. Pr. Secy. (PW) to the Govt. of HP letter No. PBW (B) A(3) 1/2020 dated Shimla-2, the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ As above.


Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur chowk.

Copy forwarded to the Superintending Engineer, 15th Circle, HPPWD
Una for information please.


Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur chowk.

CERTIFICATE

Certified that tenders for the works called vide this office letter No. PWD/DPD/CB-Tender/2023-4468-74 dated 26-10-23 are required to be carried out immediately being emergent nature of work in the public interest.


Executive Engineer,
Daulatpur chowk Division,
HPPWD Daulatpur Chowk.

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER.

Sealed Percentage rates tenders on form 6 & 7 are hereby invited by the Executive Engineer Daulatpur Chowk Division, HPPWD, Daulatpur Chowk on behalf of Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office and opened as per time schedule given below. The offer of the tender will be kept open for 75 days from the date of opening of the tenders.

Date and time of receipt of applications for the tender form : 04.11.2023 up to 05.00 PM
Date and time of issue/sale of tender forms against cash payment : 06.11.2023 from 02.00 PM to 5.00 PM
Date and time of receipt of tenders : 07.11.2023 up to 10.30 AM
Date and time of opening of tenders : 07.11.2023 at 11.30 AM

The tender forms will be issued against cash payment (non-refundable). The earnest money in the shape of NSC/Time Deposit/FDR of nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

Sr. No.	Name of Work	Estimated Cost	Earnest money	Time Limit	Cost of Form
1	A/R & M/O HPPWD Non-Residential building under HPPWD Sub-Division Daulatpur Chowk (SH: Providing and installation of computer system with UPS, Printers, Intercom system and Computer table)	154460.00	3800.00	One Month	350-
2	C/O link road from Kuneran bridge to Billu Di Talai via Mohalla Chumukhdu in G.P Nakroh Km. 0/0 to 2/200, (SH: Providing services outsource basis of 1 No. Junior Draftsman for period 15/11/2023 to 15/05/2024)	110983.00	2200.00	One Month	350-
3	A/R & M/O HPPWD Non-Residential building under HPPWD Sub-Division Daulatpur Chowk, (SH:-Providing and fixing aluminium Shutter in wall almirah)	98381.00	2000.00	One Month	350-
4	Restoration of Rain Damages on Link Road Gondpur Banehra to Billu Di Talai in G.P Upper Banehra KM. 0/0 to 2/360, (SH:- C/O U-shape Drain in Km 0/685 to 0/835 LHS)	499748.00	10000.00	Two Month	350-
5	Restoration of Rain Damages on Link Road Bhadarkali to Bajigar Mohalla Km. 0/0 to 1/800, Link Road Harijan Basti Bhanjal Km 0/0 to 4/000 and Link Road to Village Abheypur Km 0/0 to 1/300, (SH: Repair of pot holes at various RD,s)	498159.00	10000.00	Two Month	350-
6	Restoration of Rain Damages on Link Road to Changa Basti Ghanari Km. 0/0 to 1/800 and Link Road Mawa Kohalan Nangal Jarialan Km 0/0 to 6/120, (SH: Repair of pot holes at various RD,s)	487579.00	9800.00	One Month	350-

TERMS AND CONDITIONS: -

1. The contractor should produce a copy of enlistment/renewal letter at the time of application.
2. The contractor/firm shall have his registration and GST No. and copy of the same be attached with the application.
3. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Daulatpur chowk division, HPPWD Daulatpur chowk and cost of the tender form should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
4. The contractor/firms are required to insert the rate in words as well as in figures failing which Executive Engineer reserves the right to accept/rejects any or all tenders.
5. If any of the date mentioned above happens to be Local/Gazetted Holidays the same shall be process on next date.
6. Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.


 Executive Engineer,
 Daulatpur Chowk Division
 HP.PWD Daulatpur Chowk.

No. PWD/DPD/CB-Tender/2023- 4468-74

Dated: - 26-10-2023

Copy forwarded to the following for information and necessary action: -

1. The Engineer-in-Chief, HPPWD Nirman Bhawan Shimla.
2. The Chief Engineer (HZ) HPPWD Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD Una.
4. All the Assistant Engineers working under this division.
5. Drawing Branch in this office.
6. Notice Board


 Executive Engineer
 Daulatpur Chowk Division
 HPPWD

BILL OF QUANTITY

Job - I

Estimate Cost :- Rs.154460/-
Earnest Money :-Rs.3800/-
Time Limit :- One Month.

Name of work:- A/R & M/O HPPWD Non-Residential building at HPPWD Sub-Division Daultapur Chowk (SH: Providing and installation of computer system with UPS, Printers, Intercom system and Computer table)

Sr. No.	Description of Item	Quantity		Rate in		Unit	Amount
				Figures	Words		
1	Providing and installation of Computer system of HP make with intel (R) Core™ I-5- 4590 T CPU @ or higher @ 2.00 GHz, 2 MD L2 Cache, 800 MHzFSB/intel Q G31/033 or higher chipset/integrated GB LAN card/8 GB Dual channel DDR 3 Ram/1 TB HDD/DVD-RW driver (dual layer) 19.5" TTTT Analog color Monitor/USB Key board/USB optical mouse/ PL-windows 7 ultimate/ PL-antivirus 60 days updating (6 years comprehensive on site warranty) complete. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2.00	Number	47870.00	Rupees Forty Seven Thousand Eight Hundred Seventy Only	Each	95740.00
2	Providing and installation of Elhova: 650 VA offline UPS system (12Vx7AHx2 No.) with 25-30 Min battery backup 3 years warranty on UPS & 18 month on batteries from date of delivery. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2.00	Number	3200.00	Rupees Three Thousand Two Hundred Only	Each	6400.00
3	Providing and installation of HP Laserjet Pro M126a Monochrome printer with Print, scan and copy facility (A4 size): Prints upto 18ppm, 64MB RAM, 150 pages input & 75 sheets output tray, high speed USB Port, Wi-Fi with one year warranty. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2.00	Number	23360.00	Rupees Twenty Three Thousand Three Hundred Sixty Only	Each	46720.00
4	Supplying Computer table size 1.5'x3' and as per direction of engineer in charge. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2.00	Number	2800.00	Rupees Two Thousand Eight Hundred Only	Each	5600.00
	TOTAL						154460.00
	Quoted Rate in Figure						
	Quoted Rate in Words						
					% above/below		

Executive Engineer,
HPPWD Division,
Daultapur Chowk.

JOB-2

DRAFT BILL OF QUANTITY

Estimated Cost: Rs.110983/-
Earnest Money: Rs.2200/-
Time Limit : One Month

Name of Work:-C/o link road from Kuneran bridge to Billu Di Talai via Mohalla Chumukhdu in G.P Nakroh Km. 0/0 to 2/200, (SH: Providing services outsource basis of 1 No. Junior Draftsman for period 15/11/2023 to 15/05/2024)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Providing services on temporary basis of Junior Draftsman for attending the office during working days and hours 10:00 AM to 5:00 PM as well required by this office by the officer in charge. The rate inclusive of all Taxes imposed by the Government time to time.	184.00 Days	603.17	Rupees Six Hundred Three And Paise Seventeen Only	Per Day	110983.00
	TOTAL					110983.00
	Quoted Rate in Figure		% above/below			
	Quoted Rate in Words					


Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

DRAFT BILL OF QUANTITY

Job-3

Estimated Cost: Rs. 98381/-
Earnest Money: Rs. 2000/-
Time Limit : One Months

Name of Work:- A/R & M/O HPPWD Non-Residential building under HPPWD Sub-Division Daulatpur Chowk, (SH:-Providing and fixing aluminium Shutter in wall almirah)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions make of Hindco Co., Jindal India Aluminium Co. with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge for fixed portion (Powder coated aluminium (minimum thickness of powder coating 50 micron) (Glazing, paneling and dash fasteners to be paid for separately) as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	110.00 Kilogram	400.00	Rupees Four Hundred Only	Per kilogram	44000.00
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions ake of Hindco Co., Jindal India Aluminium Co. with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete for shutters of doors, windows and ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately Powder coated aluminium (minimum thickness of powder coating 50 micron) as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	63.25 Kilogram	425.00	Rupees Four Hundred Twenty Five Only	Per kilogram	26881.00
3	Providing and fixing backlight sheet in 2mm (two millimeter) thickness in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge (Cost of aluminium snap beading shall be paid in basic item).	24.78 Square metre	935.00	Rupees Nine Hundred Thirty Five	Per square metre	23169.00
4	Providing and fixing aluminium tower bolts (berrel type) anodized trans parent or dyed to required shade and colour with screws etc. complete	20.00 Each	50.00	Rupees Fifty Only	Each	1000.00
5	Providing and fixing aluminium handles anodized transparent or dyed to required colour & shade with necessary screws etc. complete.	20.00 Each	60.00	Rupees Sixty Only	Each	1200.00
6	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of approved steel primer using structure steel etcetera as required lead paint in gratings framed guard bars, ladders, railing, brackets and similar works complete upto all heights/all floor level as per CPWD specifications 2019 complete and direction by the Engineer in charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government	25.00 Kg	85.25	Rupees Eighty Five And Paise Twenty Five Only	Per Kg	2131.00
	TOTAL					
	Quoted Rate in Figure		% above/below			98381.00
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division

56B-4

DRAFT BILL OF QUANTITY

Estimated Cost: Rs.499748/-
Earnest Money: Rs.10000/-
Time Limit : Two Month

Name of Work:- Restoration of Rain Damages on Link Road Gondpur Banehra to Billu Di Talai in G.P Upper Banehra KM. 0/0 to 2/360, (SH:- C/O U-shape Drain in Km 0/685 to 0/835 LHS)

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	173.25	Cubic metre	185.00	Rupees One Hundred Eighty Five Only	Per cubic metre	32051.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, M-10 Grade (M-Ten) Nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (Twenty millimeter) nominal size) in or under water in open foundations and the like for all types of structures, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, including cost of form work and curing complete as per drawing and MORTH technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	129.75	Cubic metre	3604.60	Rupees Three Thousand Six Hundred Four And Paise Sixty Only	Per cubic metre	467697.00
	TOTAL						499748.00
	Quoted Rate in Figure			% above/below			
	Quoted Rate in Words						


Executive Engineer,
HPPWD Division,
Daulatpur Chowk.


Job-5

BILL OF QUANTITY

Estimate Cost :- Rs. 498159/-
Earnest Money :-Rs.10000/-
Time Limit :- Two Month

Name of work: Restoration of Rain Damages on Link Road Bhadarkali to Bajigar Mohalla Km. 0/0 to 1/800, Link Road Harijan Basti Bhanjal Km 0/0 to 4/000 and Link Road to Village Awaypur Km 0/0 to 1/300, (SH: Repair of pot holes at various RD,s)

Sr. No.	Description of Item	Quantity		Rate in		Unit	Amount
				Figures	Words		
1	Providing, laying, spreading and compacting graded stone aggregate size range 53 mm to 0.075 mm (Fifty three millimetre to zero point zero seven five millimetre) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers with mechanical/manual mean in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 (eight) to 10 (ten) tonne capacity to achieve the desired density, complete as per MORTH technical specification section 400 and as per the directions of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	25.510	Cubic meter	1500.00	Rupees One Thousand Five Hundred Only	Per Cubic meter	38265.00
2	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface with hydraulic brooms and spraying primer with bitumen emulsion pressure distributor at the rate of 0.85 kg (zero point eight five kilogram) per square metre of road surface as per MORTH technical specifications section 500 and as per the directions of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	620.000	Square metre	52.50	Rupees Fifty Two And Paise Fifty Only	Per Square meter	32550.00
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1, and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	1478.700	Square metre	289.00	Rupees Two Hundred Eighty Nine Only	Per Square meter	427344.00
	TOTAL						498159.00
	Quoted Rate in Figure			% above/below			
	Quoted Rate in Words						


Executive Engineer,
HPPWD Division,
Daultpur Chowk

Job-6

BILL OF QUANTITY

Estimate Cost :- Rs. 487579/-
Earnest Money :-Rs.9800/-
Time Limit :- Two Month

Name of work: Restoration of Rain Damages on Link Road to Changa Basti Ghanari Km. 0/0 to 1/800 and Link Road Mawa Kohalan Nangal Jarialan Km 0/0 to 6/120, (SH: Repair of pot holes at various RD,s)

Sr. No.	Description of Item	Quantity		Rate in		Unit	Amount
		Figures	Words	Figures	Words		
1	Providing, laying, spreading and compacting graded stone aggregate size range 53 mm to 0.075 mm (Fifty three millimetre to zero point zero seven five millimetre) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers with mechanical/manual mean in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 (eight) to 10 (ten) tonne capacity to achieve the desired density, complete as per MORTH technical specification section 400 and as per the directions of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	41.750	Cubic meter	1500.00	Rupees One Thousand Five Hundred Only	Per Cubic meter	62625.00
2	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface with hydraulic brooms and spraying primer with bitumen emulsion pressure distributor at the rate of 0.85 kg (zero point eight five kilogram) per square metre of road surface as per MORTH technical specifications section 500 and as per the directions of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	620.000	Square metre	52.50	Rupees Fifty Two And Paise Fifty Only	Per Square meter	32550.00
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1. and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	1357.800	Square metre	289.00	Rupees Two Hundred Eighty Nine Only	Per Square meter	392404.00
	TOTAL						487579.00
	Quoted Rate in Figure			% above/below			
	Quoted Rate in Words						


Executive Engineer,
HPPWD Division,
Daulatpur Chowk.