



OFFICE OF

Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030
Email ee-jaipwd-hp@gov.in

"CERTIFICATE"

Certified that the tenders for the works as called vide this office letter No. PWD/JSD/TA/NIT/ 2023-24- 9286-9320 dated 06-10-2023 are of urgent nature and in public interest.

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur.



"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **13.10.2023** up to **11:00 A.M.** and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **12.10.2023** up to **4:00 PM** and the application for issue of tender form shall be received on **12.10.2023** up to **11:00 AM**. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office/ Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days:-

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time Limit
1	C/O Combined office building at Jaisinghpur Distt. Kangra HP (SH:- C/O Sugam Centre Aluminium partition frame door Tehsildar court room attach toilet at Ground floor Hall) (Deposit)	497275.00	10000.00	Two month
2	C/O Combined office building at Jaisinghpur Distt. Kangra HP (SH:- C/O Sugam Centre Aluminium partition frame door MDF board table and Tehsildar court room attach toilet at Ground floor Hall) (Deposit)	374856.00	7500.00	Two month
3	Restoration of rain damages to Mungal Rananagar Danpathar road Km 0/00 to 5/750 (SH:- C/O damaged road portion between Km 5/360 to 5/440 and 5/460 to 5/575)	484285.00	9700.00	Two month
4	Restoration of rain damages to Mungal Rananagar Danpathar road Km 0/00 to 5/750 (SH:- C/O damaged road portion between Km 5/575 to 5/660)	485343.00	9800.00	Two month
5	Restoration of rain damages to Mungal Rananagar Danpathar road Km 0/00 to 5/750 (SH:- C/O earth filling portion between Km 5/440 to 5/460)	144540.00	2900.00	Two month
6	Restoration of rain damages on Bhawarna Jhunga Devi Road Km 15/400 to 26/250 (SH:- Hiring of JCB and Tipper for rainy season 2023 in Lambagaon Section) SDRF	399800.00	8000.00	One month
7	Restoration of rain damages on various road Under Balakrupi Sub Division (SH:- Hiring of JCB for rainy season 2023 in Gander Section)	330000.00	6600.00	One month
8	Restoration of Rain Damages on Khera Bhulla to Praga da Gallu road Km 0/00 to 16/330 (SH:- Hiring of JCB for rainy season 2023 in Gander Section) SDRF	400400.00	8000.00	One month
9	Restoration of rain damages to various roads under Sub-Division Jaisinghpur (SH:- Hiring of Excavator cum Pock lane (Tata Hitachi) & Tipper for removal of slips of various roads Under Alampur Section)	450800.00	9100.00	One month
10	Restoration of rain damages on various road under Sub-Division Jaisinghpur (SH:- Hiring of JCB and Tipper for rainy season 2023 in Lambagaon Section)	283375.00	5700.00	One month

11	Restoration of rain damages on various road under Sub-Division Jaisinghpur (SH:- Hiring of JCB for rainy season 2023 in Lambagaon Section)	196020.00	40000.00	One month
12	Restoration of rain damages on Ropri to Umber road Km 0/00 to 6/360 (SH:- C/O B/wall at RD 4/615 to 4/635)	339026.00	6800.00	Two month
13	Restoration of rain damages on Panchrukhi Lambagoan road Km22/00 to 28/00 (SH:- C/O B/wall at RD 24/300 to 24/318)	485426.00	9800.00	Two month

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal ellisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK.



Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur
(On behalf of Governor of Himachal Pradesh)

Pradesh)


No. PW/JSD/TA/Tender/NIT/2023-24-

9286-9320

Dated:- 06-10-2023.

Copy to the following for information and necessary action:-

1. The Principal Secy. (PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief HPPWD, Shimla.
3. The Chief Engineer (K.Z.) HPPWD Dharamshala.
4. The Director, Information & Publications Department, H.P. Shimla.
5. The Executive Engineer (IT) Nigam Vihar Shimla-2 for information. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. All the S.E.s / E.E.s under Kangra Zone.
9. The Sub Divisional Officer (C) Jaisinghpur
10. The Block Development office Lambagaon
11. All the Assistant Engineer under this Division.
12. The Drawing /Accounts Branch in this office.
13. The Contractors concerned.
14. Notice Board.



Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :- C/O Combined office building at Jaisinghpur Distt. Kangra HP (SH:- C/O sugam Centre Aluminium) partition frame door MDF board table and Tehsildar court room attach toilet at Ground floor Hall)					Estimated cost Rs.	497275.00
(Deposit)					Earnest Money Rs.	10000.00
S. N.					Time Limits	Two month
	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions. i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately Powder coated aluminium (minimum thickness of powder coating 50 micron) The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1182.72	420.45	Rupees Four Hundred Twenty And Paise Forty Five Only	Per Kilogram	497275.00
		Total				497275.00
	Quoted Rate (in Figures) Percentagee	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division
 HP.PWD Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :- C/O Combined office building at Jaisinghpur Distt. Kangra HP (SH:- C/O sugam Centre Aluminium partition frame door MDF board table and Tehsildar court room attach toilet at Ground floor Hall) (Deposit)					Estimated cost Rs.		374856.00
					Earnest Money Rs.		7500.00
					Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains etc. in all kind of soil (not exceeding 1.5 m (one point five Metre) in width or 10 Per Square Metre (ten square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto any height, including getting out the excavated soil and disposal of surplus excavated soil asdirected, within a lead from the edge of excavation . All kind of soil complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	2.70	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	608.00	
2	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishing and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty millimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	0.54	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per Cubic Metre	3321.00	
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetra as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	2.16	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	10692.00	

4	Providing and laying mechanically mixed and vibrated plain cement concrete 1:4:8 (one cement is to four sand is to eight graded crushed stone aggregate 40 mm (forty millimeter) nominal size) and curing complete excluding the cost of form work in foundation and plinth as per specifications approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	0.68	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	2890.00
5	Providing form work with steel plates 3.15 mm (three point fifteen millimeter) thick welded with angle iron frame 30 X 30 X 5 mm (thirty into thirty into five millimeter) so as to give a fair finish including centering, shuttering, strutting and propping etcetera with wooden battens and ballies, in all heights of propping and centering below supporting floor to ceiling and removal of the same for insitu-reinforced concrete and plain concrete work in Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. etcetera and mass concrete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	14.40	360.00	Rupees Three Hundred Sixty Only	Per Square Metre	5184.00
6	Providing and Laying damp-proof course 40mm (forty millimetre) thick with cement concrete 1:2:4 (one cement : two sand : four graded stone aggregate 12.5mm (twelve point five millimetre) nominal size) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.50	284.20	Rupees Two Hundred Eighty Four And Paise Twenty Only	Per Square Metre	426.00
7	Providing plinth protection 50mm thick cement concrete 1:3:6 (one isto three sand isto six aggregate) 20mm (twenty millimetre) nominal size) including finishing the top surfaces of concrete smooth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	5.04	650.00	Rupees Six Hundred Fifty Only	Per Square Metre	3276.00

8	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° (Fifteen Degree) landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (One cement : one point five coarse sand : Three graded stone aggregate 20 mm (Twenty Millimetre) nominal size) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.30	7200.00	Rupees Seven Thousand Two Hundred Only	Per Cubic Metre	9360.00
9	Providing form work with steel plates 3.15 mm (three point fifteen millimeter) thick welded with angle iron frame 30 X 30 X 5 mm (thirty into thirty into five millimeter) so as to give a fair finish including centering, shuttering, strutting and propping etcetera with wooden battens and ballies, in all heights of propping and centring below supporting floor to ceiling and removal of the same for insitu-reinforced concrete and plain concrete work in Beams, cantilever, girders and lintels. Sides and soffits of beams, beam haunchings, cantilevers, bressumers and lintels upto all depth and in all heights including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	9.40	380.00	Rupees Three Hundred Eighty Only	Per Square Metre	3572.00
10	Steel reinforcement TATA TISCO/SAIL for reinforced cement concrete work including strengthening, cutting, bending, binding and placing in position complete and binding all complete above plinth level TMT bar grade Fe-500 including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	195.00	95.00	Rupees Ninety Five Only	Per Kilogram	18525.00

11	Providing and fixing Pre-laminated medium density fibre board IS: 4587:1998 marked, with one side decorative lamination other side balancing lamination Grade-I(exterior grade) in shelves with screws and fittings wherever required, edges to be sealed with PVC edge bending tape 2.00 mm thick of approved brand (fittings to be paid separately).Pre-laminated with decorative lamination one side and other side balancing lamination exterior Grade - I MDF Board 18 mm thick conforming to IS:14587 and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	71.19	1325.00	Rupees One Thousand Three Hundred Twenty Five Only	Per Square Metre	94327.00
12	Providing and fixing 18 mm thick skirting with Pre-laminated medium density fibre board exterior grade (Grade-I) conforming to IS: 14587:1998 marked, with (one side decorative and other side balancing lamination and edges to be sealed with PVC edge bending tape 2.00 mm thick of approved brand with necessary fixing arrangements and screws, including drilling necessary holes for rawl plugs etc. all complete and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	25.63	1745.35	Rupees One Thousand Seven Hundred Forty Five And Paise Thirty Five Only	Per Square Metre	44733.00
13	Making the opening in brick masonry including dismantling in floor or walls by cutting masonry and making good the damages to walls, flooring and jambs complete, to match existing surface i/c disposal of mulba/ rubbish to the nearest municipal dumping ground, all complete as per direction of Engineer-in-Charge For door/ window/ clerestory window The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	2.20	554.65	Rupees Five Hundred Fifty Four And Paise Sixty Five Only	Per Square Metre	1220.00
14	Distemping with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade Old work (one or more coats) and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	4.40	45.00	Rupees Forty Five Only	Per square metre	198.00
15	Repair to plaster of thickness 12mm (twelve millimetre) to 20 mm (twenty millimetre) in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer-In-Charge. as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	18.00	264.35	Rupees Two Hundred Sixty Four And Paise Thirty Five Only	Per square metre	4758.00

16	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :Cement mortar 1:6 (1 cement : 6 coarse sand) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	4.58	8500.00	Rupees Eight Thousand Five Hundred Only	Per Cubic Metre	38930.00
17	Providing and fixing angle iron frames for doors, windows and ventilators of mild steel Angle sections of size 35x35x5 mm (Thirty five into thirty five into five), joints mitered and welded by angle iron 35x35x5 (Thirty five into thirty five into five) mm or 35x 5 mm (Thirty five into five) flat pieces to the existing T iron frame or to the wall with dash fastener, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer, all complete as per the direction of Engineer-In-charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	150.00	95.00	Rupees Ninety Five Only	Per Kilogram	14250.00
18	Providing and fixing aluminum sliding door bolts, ISI marked anodized (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete :250x16 mm (Two hundred fifty into sixteen millimetre) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	12.00	214.20	Rupees Two Hundred Fourteen And Paise Twenty Only	Each	2570.00
19	Providing and fixing aluminum tower bolts, ISI marked, anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :250x16 mm (Two hundred fifty into sixteen millimetre) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	24.00	85.60	Rupees Eighty Five And Paise Sixty Only	Each	2054.00

20	Providing and fixing 125mm (one hundred twenty five millimetre) aluminium handles, ISI marked, anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	24.00	57.55	Rupees Fifty Seven And Paise Fifty Five Only	Each	1381.00
21	Providing and fixing bright finished brass 100 mm mortice latch and lock, ISI marked, with six levers and a pair of anodised (anodic coating not less than grade AC 10 as per IS : 1868) aluminium lever handles of approved quality with necessary screws etc. complete. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	12.00	689.05	Rupees Six Hundred Eighty Nine And Paise Five Only	Each	8269.00
22	Providing and fixing exhaust fan of approve quality as per direction of Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	2.00	2000.00	Rupees Two Thousand Only	Each	4000.00
23	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	16.80	95.00	Rupees Ninety Five Only	Per Square Metre	1596.00
24	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	16.80	70.00	Rupees Seventy Only	Per Square Metre	1176.00
25	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade One or more coats on old work and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government	6.72	58.00	Rupees Fifty Eight Only	Per Square Metre	390.00

26	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade old work (two or more coats) over and including water thinnable priming coat with cement primer including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	10.08	45.00	Rupees Forty Five Only	Per Square Metre	454.00
27	Providing and fixing 150 mm bright finished floor brass door stopper with rubber cushion, necessary brass screws etc. to suit shutter thickness complete The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the	3.00	230.05	Rupees Two Hundred Thirty And Paise Five Only	Each	690.00
28	Removing and refixing the various electric appliances boards switches etc including rewiring and fixing new awitches if required of superior quality and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	10.00	2000.00	Rupees Two Thousand Only	Each	20000.00
29	Providing and fixing 18 mm thick, 150 mm wide pelmet of flat pressed 3 layer or graded wood particle board medium density grade 1, IS : 3087 marked, including top cover of 6 mm commercial ply wood conforming to IS: 303 BWR grade, nickel plated M.S. pipe 20 mm dia (heavy type) curtain rod with nickel plated brackets, including fixing with 25x3 mm M.S. flat 10 cm long fixed to pelmet with hollock wood cleats of size 100 mm x 40 mm x 40 mm on both inner side of pelmet and rawl plugs 75 mm long etc. all complete and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	20.00	450.00	Rupees Four Hundred Fifty Only	Per running metre	9000.00
30	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete Plantks of size 0.45 x 1.20 mtr. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	2.25	1850.00	Rupees One Thousand Eight Hundred Fifty Only	Per Square Metre	4163.00

31	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete size of tile 600x600 mm. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	12.00	1850.00	Rupees One Thousand Eight Hundred Fifty Only	Per Square Metre	22200.00
32	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws, the rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.58	1850.00	Rupees One Thousand Eight Hundred Fifty Only	Per Square Metre	2923.00
33	Providing and fixing wash basin star white/snow white shade of Cera / Hindware/Jaquar with C.I. brackets, 15 mm (fifteen millimetre) C.P. brass pillar taps, 32 mm (thirty two millimetre) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm (six hundred thirty into four hundred fifty millimetre) with a single 15 mm (fifteen millimetre) C.P. brass pillar tap including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	4.00	3500.00	Rupees Three Thousand Five Hundred Only	Each	14000.00
34	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete Single rubber stopper and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	2.00	35.00	Rupees Thirty Five Only	Each	70.00

35	Providing and fixing 600x450 mm (six hundred into four hundred fifty millimetre) beveled edge mirror superior glass of Atul/Modi Gaurd (of approved quality) complete with 6 mm (six millimetre) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.00	1050.00	Rupees One Thousand Fifty Only	Each	1050.00
36	Providing and fixing 600x120x5 mm (six hundred into one hundred twenty into five millimetre) glass shelf with edges round off, supported on anodized aluminum angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm (forty millimetre) long screws, rawl plugs etc..complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	6.00	650.00	Rupees Six Hundred Fifty Only	Each	3900.00
37	Providing and fixing soil, waste and vent pipes Sand cast iron S&S pipe as per IS: 1729 and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	6.00	850.00	Rupees Eight Hundred Fifty Only	Per running metre	5100.00
38	Providing and fixing 15 mm (fifteen millimetre) dia G.I. pipes complete with G.I. Fittings and clamps including cutting and making good the walla etc. Internal work including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	6.00	225.00	Rupees Two Hundred Twenty Five Only	Per Running Metre	1350.00
39	Providing and fixing 15 mm (fifteen millimetre) dia G.I. pipes complete with G.I. Fittings including trenching and refilling etc. including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	6.00	200.00	Rupees Two Hundred Only	Per Running Metre	1200.00
40	Providing and fixing CP brass long nose 15mm diameters C.P. brass bib tap bib cock of approved quality confirming to IS standard and weighting not less than 810 grams 15 mm nominal bore of Jaguwar or contra with capstan head including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.00	650.00	Rupees Six Hundred Fifty Only	Each	650.00

41	Providing and fixing 15 mm nominal bore ball valve (brass) of approved quality, High or low pressure, with plastic floats complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	4.00	350.00	Rupees Three Hundred Fifty Only	Each	1400.00
42	Providing and fixing 15 mm CP brass angle valve for basin mixer and geyser points Jal Jaguar or equivalent as per approved drawing and design directed of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.0000	1800.00	Rupees One Thousand Eight Hundred Only	Each	1800.00
43	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.00	6500.00	Rupees Six Thousand Five Hundred Only	Each	6500.00
44	Providing and fixing PVC floor trap of Supreme/ prince/ Finolex ISI marked of self cleaning design including fixing with approved adhesive cost of cutting and making good the wall and floor etc. Complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	2.00	350.00	Rupees Three Hundred Fifty Only	Each	700.00
	Total					374856.00
	Quoted Rate (in Figures) Percentagee	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Sum
 Executive Engineer,
 Jaisinghpur Division
 HP.PWD Jaisinghpur.

SCHEDULE OF QUANTITY

Qing

Executive Engineer,
Jaisinghpur Division
HP.PWD Jaisinghpur.

④

Curva

Executive Engineer,
Jaisinghpur Division
HP.PWD Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages to Mungal Rananagar Danpathar road Km 0/00 to 5/750 (SH:- C/O earth filling portion between Km 5/440 to 5/460)

Estimated cost Rs.
Earnest Money Rs.
Time Limits

Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	525.60	275.00	Rupees Two Hundred Seventy Five Only	Per cubic metre	144540.00
	Total					144540.00
	Quoted Rate (in Figures) Percentagee	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Card

Executive Engineer,
Jaisinghpur Division
HP.PWD Jaisinghpur.

(2)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Bhawaria Jhunga Devi Road Km 15/400 to 26/250 (SH:- Hiring of JCB and Tipper for rainy season 2023 in Lambagaon Section)		Estimated Cost - Rs. 399800.00	
SDRF		Earnest Money - Rs. 8000.00	
		Time - One Month	
So.No.	Description of Item	Rate in	
		In Figures	In Word
Quantity		Unit	Amount
240.00	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per hour basis	1100.00 Rupees One Thousand One Hundred Only	Per Hour 264000.00
38.80	Hiring of carriage Tipper for carriage of material such as Crusher and Sand labour and T & P stricals and other essential material from PWD store Jaisinghpur/quarry site to various roads Under Jaisinghpur Sub Division in HP.PWD. Jaisinghpur as directed by the Engineer-In-Charge. Any loss to the public private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for carriage vehicle also be borne by the contractor owner. The daily 70 Km per day running charges will be assuming and log book will also be maintained at site which should be verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per day basis	3500.00 Rupees Three Thousand Five Hundred Only	Per Day 135800.00
Total			399800.00
Quoted Rate (in Figures) Percentagee		Excess (+)	%
		Less (-)	%
G.Total in Figures			
G.Total in Words			



Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various road Under Balakrupi Sub Division (SH:- Hiring of JCB for rainy season 2023 in Gander Section Section)

Estimated Cost - Rs.330000.00
Earnest Money - Rs. 6600.00

Time - One Month


So.No.	Description of Item	Quantity	Rate in		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	300.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	330000.00
	Total					330000.00
	Quoted Rate (in Figures) Percentagee	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Chand

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

DRAFT SCHEDULE OF QUANTITY

Name of work :-Restoration of Rain Damages on Khera Bhulla to Praga da Gallu road		Estimated Cost - Rs. 400400.00				
Km 0/00 to 16/330 (SH:- Hiring of JCB for rainy season 2023 in Gander Section) SDRF		Earnest Money - Rs. 8000.00				
		Time - One Month				
So. No.	Description of Item	Quantity	Rate in		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	364.00	1100.00	Ruppes One Thousand One Hundred Only	Per Hour	400400.00
	Total					400400.00
	Quoted Rate (in Figures) Percentagee	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages to various roads under Sub-Division Jaisinghpur (SH:- Hiring of Excavator cum Pock lane (Tata Hitachi) & Tipper for removal of slips of various roads Under Alampur Section)		Estimated Cost - Rs. 450800.00				
		Earnest Money - Rs. 9100.00				
		Time - One Month				
So.No.	Description of Item	Quantity	Rate in		Unit	Amount
			In Figures	In Word		
1	Hiring of JCB/ Excavator cum Pock lane (Tata Hitachi) for removal of slips, debris and boulders clear from road surface upto any height and depth in all in all kind and classification of soil including rocky portion and saturated soil and then disposal of all un-serviceable materials from the road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-Charge. The JCB/Excavator Cum Rock lane (Tata Hitachi) should minimum 8.00 hours from 9.00 to 5.00 PM daily and excavate at least 100 cum quantity of earth/slips per hour. Any loss to the public/private property or any accident etc, happened during the course of hiring period/execution shall be the absolute responsibility of the Excavator Cum Pock lane (Tata Hitachi) owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per hour basis	86.00	2800.00	Rupees Two Thousand Eight Hundred Only	Per Hour	240800.00
2	Hiring of carriage Tipper for carriage of material such as Crusher and Sand labour and T & P stricals and other essential material from PWD store Jaisinghpur/quarry site to various roads Under Jaisinghpur Sub Division in HP.PWD. Jaisinghpur as directed by the Engineer-In-Charge. Any loss to the public private property or any accidnetetc, happened during the course of hiring period shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and opertaional staff for carriage vehicle also be born by the contractor owner. The daily 70 Km per day running charges will be assuming and log book will also be maintained at site which should be verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per day basis	60.00	3500.00	Rupees Three Thousand Five Hundred Only	Per Day	210000.00
Total						450800.00
Quoted Rate (in Figures) Percentagee		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						

Sum

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

DRAFT SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on various road under Sub-Division Jaisinghpur (SH:- Hiring of JCB and Tipper for rainy season 2023 in Lambagaon Section)		Estimated Cost - Rs. 283375.00	
		Earnest Money - Rs. 5700.00	
		Time - One Month	
So.No.	Description of Item	Rate in	
		In Figures	In Word
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	1100.00	Rupees One Thousand One Hundred Only
2	Hiring of carriage Tipper for carriage of material such as Crusher and Sand labour and T & P stricals and other essential material from PWD store Jaisinghpur/quarry site to various roads Under Jaisinghpur Sub Division in HP.PWD. Jaisinghpur as directed by the Engineer-In-Charge. Any loss to the public private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for carriage vehicle also be born by the contractor owner. The daily 70 Km per day running charges will be assuming and log book will also be maintained at site which should be verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per day basis	3500.00	Rupees Three Thousand Five Hundred Only
	Total		
	Quoted Rate (in Figures) Percentage	Excess (+)	%
		Less (-)	%
	G.Total in Figures		
	G.Total in Words		
			283375.00


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

DRAFT SCHEDULE OF QUANTITY						
		Name of work :-Restoration of rain damages on various road under Sub-Division Jaisthingpur (SH:- Hiring of JCB for rainy season 2023 in Lambagaon Section)	Estimated Cost - Rs. 196020.00			
			Earnest Money - Rs. 4000.00			
			Time - One Month			
So.No.	Description of Item	Quantity	Rate in		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	178.20	1100.00	Rupees One Thousand One Hundred Only	Per Hour	196020.00
	Total					196020.00
	Quoted Rate (in Figures) Percentagee	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Garud


Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

(12)

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Ropri to Umber road Km 0/00 to 6/360 (SH:- C/O B/wall at RD 4/615 to 4/635)						Estimated cost Rs.	339026.00
						Earnest Money Rs.	6800.00
						Time Limits	Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual/mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of an useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	66.42	195.00	Rupees One Hundred Ninety Five Only	Per cubic metre	12952.00	
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	18.66	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	4199.00	

3	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	82.50	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	309375.00
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	50.00	250.00	Rupees Two Hundred Fifty Only	Each	12500.00
	Total					339026.00
	Quoted Rate (in Figures) Percentagee	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

13

SCHEDULE OF QUANTITY						
Name of work :- Restoration of rain damages on Panchrukhi Lambagoan road Km22/00 to 28/00 (SH; - C/O B/wall at RD 24/300 to 24/318)				Estimated cost Rs.		485426.00
				Earnest Money Rs.		9800.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual/mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of an useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	47.13	195.00	Rupees One Hundred Ninety Five Only	Per cubic metre	9190.00
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	37.38	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	8411.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete 1:4:8 (one cement is to four sand is to eight graded crushed stone aggregate 40 mm (forty millimeter) nominal size) and curing complete excluding the cost of form work in foundation and plinth as per specifications approved drawing , design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	106.90	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	454325.00

4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D. technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	54.00	250.00	Rupees Two Hundred Fifty Only	Each	13500.00
	Total					485426.00
	Quoted Rate (in Figures) Percentagee	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

(Signature)

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur