




Office of

Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030 Email ee-jaipwd-hp@gov.in

"CERTIFICATE"

Certified that the tenders for the works as called vide this office
letter No. PWD/JSD/TA/NIT/ 2023-24- 9441-80 dated 07-10-2023 are of
urgent nature and in public interest.

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur.



"NOTICE INVITING TENDERS"

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer. HP.PWD Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **17.10.2023** up to **11:30 A.M.** and the same shall be opened on the same day at 04:00 P.M. in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **16.10.2023** up to **4:00 PM** and the application for issue of tender from shall be received on **16.10.2023** up to **11:30 AM**. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office/ Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days:-

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time Limit
1	A/R & M/O Various road in Balakrupi section under HP.PWD Sub Division Balakrupi (SH:- Repair of Pot Hole / patch work in various road (1) Oach Phri road Between Km 0/00 to 1/00 (2) Lahru to Dole road Between Km 0/0 to 2/00 (3) Dhar Lahar Langha Dhab road between Km 0/0 to 5/00 (4) Balakrupi Duhak Dhaniara road Between Km 0/00 to 1/400)	496902.00	10000.00	One month
2	A/R & M/O Various road in Alampur and Gander section under HP.PWD Sub Division Balakrupi (SH:- Repair of Pot Hole / patch work in various road (1) Bhawarna Jhunga Devi road Between Km 12/200 to 13/00 & 14/00 to 15/500 (2) Khera Bhula Praga da Gallu road at various Rds (3) Gander Siyara Kudana road at Various RDs	496212.00	10000.00	One month
3	A/R & M/O Various road in Gander section under HP.PWD Sub Division Balakrupi (SH:- Repair of Pot Hole / patch work in various road (1) Tikker Sakoh Jean road at various RDs (2) Gander Bardam road various Rds (3) Hamirpur sujanpur Thural Maranda road at various Rds (4) Gander Siyara Kudana road at Various RDs)	497593.00	10000.00	One month
4	A/R & M/O Various road in Panchrukhi section under HP.PWD Sub Division Panchrukhi (SH:- Repair of Pot Hole / patch work in various road (1) Banuri Saliana road Between Km 2500 to 4/500 (2) Saliana Chathmi road Between Km 0/00 to 2/200 (3) Approach road to Rest House Ashapuri	497928.00	10000.00	One month
5	A/R & M/O Various road in Jalag section under HP.PWD Sub Division Panchrukhi (SH:- Repair of Pot Hole / patch work in various road (1) Panchrukhi Lambagoan road Between Km 10/0 to 22/00 (2) Draman Jalag road road Between Km 0/00 to 2/500 (3) Shanti Nagar Syhoti baba Jakh road Between km 0/00 to 3/700)	498618.00	10000.00	One month
6	A/R & M/O Various road in Sari section under HP.PWD Sub Division Jaisinghpur (SH:- Repair of Pot Hole / patch work in various road (1) Chadhiar Mungal Haler road Between Km 6/00 to 10/030 (2) Haler to Guhan Ram Nagar Ropa Dalu Chatter road road Between Km 0/00 to 3/00 (3) Link road to village Rananagar Between km 2/00 to 5/00)	497237.00	10000.00	One month

7	A/R & M/O Various road in Lambagoan section under HP.PWD Sub Division Jaisinghpur (SH:- Repair of Pot Hole / patch work in various road (1) Bhawarna Jhunga Devi road Between Km 20/0 to 26/150 (2) Ppper Lambagoan to saralpatt road road Between Km 0/00 to 2/500	497761.00	10000.00	One month
8	A/R & M/O Various road in Jaisinghpur section under HP.PWD Sub Division Jaisinghpur (SH:- Repair of Pot Hole / patch work in various road (1) Tinbar to Jaisinghpur road Between Km 2/00 to 8/00 (2) Tinbar to Lugat road Between Km 0/00 to 2/000 (3) Bhati Guler Tarahla road Between Km 0/00 to 3/825)	498129.00	10000.00	One month

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal ellisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK.

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur.

(On behalf of Governor of Himachal Pradesh)

No. PW/JSD/TA/Tender/NIT/2023-24- 9441-80

Dated:- 07/10/2023

Copy to the following for information and necessary action:-

1. The Principal Secy. (PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief HP.PWD., Shimla.
3. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
4. The Director, Information & Publications Department, H.P. Shimla.
5. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Nigam Vihar Shimla-2 for information. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. All the S.E.s / E.E.s-under Kangra Zone.
9. The Sub Divisional Officer (C) Jaisinghpur
10. The Block Development office Lambagoan
11. All the Assistant Engineer under this Division.
12. The Drawing /Accounts Branch in this office.
13. Notice Board.


Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Various road in Balakrupi section under HP.PWD Sub Division Balakrupi (SH:- Repair of Pot Hole / patch work in various road (1) Oach Phri road Between Km 0/00 to 1/00 (2) Lahru to Dole road Between Km 0/0 to 2/00 (3) Dhar Lahar Langha Dhaba road between Km 0/0 to 5/00 (4) Balakrupi Duhak Dhaniara road Between Km 0/00 to 1/400)

Estimated cost Rs. 496902.00
Earnest Money Rs. 10000.00
Time Limits One month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Repairing of pot holes and removal of loose material trimming of sides by providing with Bitumen Vg-10(ten) tack coat at the rate of 0.30 kg. (zero point thirty kilograms) per Square metre, Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen VG-10(ten) @ 14.60 kg (fourteen point sixty kilogram) per ten square of road surface required line grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	1450.00	335.00	Rupees Three Hundred Thirty Five Only	Per Square metre	485750.00
	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	5.44	2050.00	Rupees Two Thousand Fifty Only	Per cubic metre	11152.00
	Total					496902.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

(2)

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Various road in Alampur and Gander section under HP.PWD Sub Division Balakrupi (SH):- Repair of Pot Hole / patch work in various road (1) Bhawarna Jhunga Devi road Between Km 12/200 to 13/00 & 14/00 to 15/500 (2) Khara Bhula Praga da Gallu road at various Rds (3) Gander Siyara Kudana road at Various RDs

Balakrupi (SH):- Repair of Pot Hole / patch work in various road (1) Bhawarna Jhunga Devi road Between Km 12/200 to 13/00 & 14/00 to 15/500 (2) Khera Bhula Praga da Gallu road at various Rds (3) Gander Siyara Kudana road at Various RDs							Estimated cost Rs.	496212.00
							Earnest Money Rs.	10000.00
							Time Limits	One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount		
			In Figures	In Word				
1	Reparing of pot holes and removal of loose material trimming of sides by providing with Bitumen Vg-10(ten) tack coat at the rate of 0.30 kg. (zero point thirty kilograms) per Square metre,Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen VG-10(ten) @ 14.60 kg (fourteen point sixty kilogram) per ten square of road surface required line grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D. technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect	1448.00	335.00	Rupees Three Hundred Thirty Five Only	Per Square metre	485080.00		
2	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand picking, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required densities per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	5.43	2050.00	Rupees Two Thousand Fifty Only	Per cubic metre	11132.00		
	Total							
	Quoted Rate (in Figures) Percentage	Excess (+)				496212.00		
		Less (-)			%			
	G.Total in Figures				%			
	G.Total in Words							




Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

3

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Various road in Gander section under HP.PWD Sub Division Balakrupi (SH:- Repair of Pot Hole / patch work in various road (1) Tikker Sakoh Jean road at various RDs (2) Gander Bardam road various RDs (3) Hamirpur sujanpur Thural Maranda road at various RDs (4) Gander Siyara Kudana road at Various RDs)

S. N.		Description of Item	Quantity	Rate		Unit	Amount
				In Figures	In Word		
1		Reparing of pot holes and removal of loose material trimming of sides by providing with Bitumen Vg-10(ten) tack coat at the rate of 0.30 kg. (zero point thirty kilograms) per Square metre, Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen VG-10(ten) @ 14.60 kg (fourteen point six kilogram) per ten square of road surface required level grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D. technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect	1452.00	335.00	Rupees Three Hundred Thirty Five Only	Per Square metre	486420.00
		Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	5.45	2050.00	Rupees Two Thousand Fifty Only	Per cubic metre	11173.00
		Total					
		Quoted Rate (in Figures) Percentagee		Excess (+)			497593.00
				Less (-)		%	
		G.Total in Figures				%	
		G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur


SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Various road in Panchrukhi section under HP.PWD Sub Division Panchrukhi (SH:- Repair of Pot Hole / patch work in various road (1) Banuri Saliana road Between Km 2/500 to 4/500 (2) Saliana Chatham road Between Km 0/00 to 2/200 (3) Approach road to Rest House Ashapuri)

Estimated cost Rs.
Earnest Money Rs.
Time Limits

497928.00
10000.00
One month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Repairing of pot holes and removal of loose material trimming of sides by providing with Bitumen Vg-10(ten) tack coat at the rate of 0.30 kg. (zero point thirty kilograms) per Square metre. Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen VG-10(ten) @ 14.60 kg (fourteen point sixty kilogram) per ten square of road surface required line grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D. technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect	1453.00	335.00	Rupees Three Hundred Thirty Five Only	Per Square metre	486755.00
2	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge . The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	5.45	2050.00	Rupees Two Thousand Fifty Only	Per cubic metre	11173.00
	Total					
	Quoted Rate (in Figures) Percentagee		Excess (+)			497928.00
			Less (-)		%	
	G.Total in Figures				%	
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP PWD Jaisinghpur


SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Various road in Jalag section under HP.PWD Sub Division Panchrukhi (SH:- Repair of Pot Hole / patch work in various road (1) Panchrukhi Lambagoan road Between Km 10/0 to 22/00 (2) Draman Jalag road road Between Km 0/00 to 2/500 (3) Shanti Nagar Syhoti baba Jakh road Between km 0/00 to 3/700)

Estimated cost Rs.
Earnest Money Rs.
Time Limits

498618.00
10000.00
One month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Reparing of pot holes and removal of loose material trimming of sides by providing with Bitumen Vg-10(ten) tack coat at the rate of 0.30 kg. (zero point thirty kilograms) per Square metre, Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen VG-10(ten) @ 14.60 kg (fourteen point sixty kilogram) per ten square of road surface required line grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D. technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect	1455.00	335.00	Rupees Three Hundred Thirty Five Only	Per Square metre	487425.00
	Providing laying spreading and compacting by manual means of stone aggregate of size 6.3mm to 45mm (sixty three millimeter to forty five millimeter) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K. N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimeter) nominal size at the rate of 0.20 cum (zero point two cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge . The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	5.46	2050.00	Rupees Two Thousand Fifty Only	Per cubic metre	11193.00
	Total					
	Quoted Rate (in Figures) Percentage					
		Excess (+)			%	498618.00
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Various road in Sari section under HP.PWD Sub Division Jaisinghpur (SH:- Repair of Pot Hole / patch work in various road (1) Chadhar Mungal Haler road Between Km 6/00 to 10/030 (2) Haler to Guhan Ram Nagar Ropa Dalu Chatter road Between Km 0/00 to 3/00 (3) Link road to village Rananagar Between km 2/00 to 5/00)

Estimated cost Rs. 497237.00
Earnest Money Rs. 10000.00
Time Limits One month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Repairing of pot holes and removal of loose material trimming of sides by providing with Bitumen Vg-10(10) tack coat at the rate of 0.30 kg. (zero point thirty kilograms) per Square metre. Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen VG-10(10) @ 14.60 kg (fourteen point sixty kilogram) per ten square of road surface required line grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D. technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	1451.00	335.00	Rupees Three Hundred Thirty Five Only	Per Square metre	486085.00
2	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimeter to forty five millimeter) Grading-II to water bound Macadam specification (including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K. N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimeter) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	5.44	2050.00	Rupees Two Thousand Fifty Only	Per cubic metre	11152.00
	Total					
	Quoted Rate (in Figures) Percentage	Excess (+)				497237.00
		Less (-)			%	
	G.Total in Figures				%	
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Various road in Lambagoan section under HP.PWD Sub Division Jaisinghpur (SH:- Repair of Pot Hole / patch work in various road (1) Bhawarna Jhunga Devi road Between Km 20/0 to 26/150 (2) Ppper Lambagoan to saralpatt road Between Km 0/00 to 2/500)

Estimated cost Rs. 497761.00
Earnest Money Rs. 10000.00
Time Limits One month


S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Repairing of pot holes and removal of loose material trimming of sides by providing with Bitumen Vg-10(ten) tack coat at the rate of 0.30 kg. (zero point thirty kilograms) per Square metre, Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen VG-10(ten) @ 14.60 kg (fourteen point sixty kilogram) per ten square of road surface required line grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	1452.50	335.00	Rupees Three Hundred Thirty Five Only	Per Square metre	486588.00
2	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification (including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K. N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	5.45	2050.00	Rupees Two Thousand Fifty Only	Per cubic metre	11173.00
	Total					
	Quoted Rate (in Figures) Percentagee	Excess (+)			%	497761.00
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Various road in Jaisinghpur section under HP.PWD Sub Division Jaisinghpur (SH:- Repair of Pot Hole / patch work in various road (1) Tinbar to Jaisinghpur road Between Km 2/00 to 8/00 (2) Tinbar to Lugat road Between Km 0/00 to 2/000 (3) Bhati Guler Tarahla road Between Km 0/00 to 3/825)

				Estimated cost Rs.	
				Earnest Money Rs.	
				Time Limits	
				One month	
S. N.	Description of Item	Quantity	Rate		Amount
			In Figures	In Word	
1	Repairing of pot holes and removal of loose material trimming of sides by providing with Bitumen Vg-10 (ten) tack coat at the rate of 0.30 kg. (zero point thirty kilograms) per Square metre. Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen VG-10 (ten) @ 14.60 kg (fourteen point sixty kilogram) per ten square of road surface required line grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D. technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect	1453.60	335.00	Rupees Three Hundred Thirty Five Only	486956.00
2	Providing laying spreading and compacting by manual means of stone aggregate of size 6.3mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	5.45	2050.00	Rupees Two Thousand Fifty Only	11173.00
	Total				498129.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%
		Less (-)			%
	G.Total in Figures				
	G.Total in Words				


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur