



Office of

Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030 Email ee-
jaipwd-hp@gov.in

"CERTIFICATE"

Certified that the tenders for the works as called vide this office
letter No. PWD/JSD/TA/NIT/ 2023-24- 9704-43 dated 12-10-2023
are of urgent nature and in public interest.

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur.



"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer. HP.PWD Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **21.10.2023** up to **11:30 A.M.** and the same shall be opened on the same day at 04:00 P.M. in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **20.10.2023** up to **4:00 PM** and the application for issue of tender form shall be received on **19.10.2023** up to **11:30 AM**. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office/Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD Division Jaisinghpur.


The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days:-

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time Limit
1	Improvement, widening and strengthening of Panchrukhi Lambagaon road KM 22/000 to 28/800 (Sub Head:- Providing and laying of hot applied thermoplastic compound (painting line) in KM 25/500 to 28/000)	355000/-	7100/-	Two month
2	Improvement, widening and strengthening of Panchrukhi Lambagaon road KM 22/000 to 28/800 (Sub Head:- Providing and laying of hot applied thermoplastic compound (painting line) in KM 22/000 to 25/000)	497000/-	10000/-	Two month
3	Improvement, widening and strengthening of Jhamon to Jaisinghpur road KM 8/0 to 18/300 (SH:- P/L interlocking paver block at RD 9/309.80 to 9/360)	428165/-	8600/-	Two month
4	Improvement, widening and strengthening of Jhamon to Jaisinghpur road KM 8/0 to 18/300 (SH:- P/L interlocking paver block at RD 15/567.50 to 15/576 and 10/390 to 10/420)	203244/-	4100/-	Two month
5	Improvement of black spot on Paplah Bandahu Odri road KM 0/0 to 7/465 (SH:- C/O R/Wall with W-Metal Beam crash barrier at RD 4/550 to 4/564) (Black Spot)	479368/-	9600/-	Two month
6	Restoration of rain damages on HSTM portion KM 24/135 to 30/000 (SH:- C/O Edge walll at RD 24/515 to 24/645)	491400/-	9900/-	Two month

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal ellisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK.



Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur
(On behalf of Governor of Himachal Pradesh)

No. PW/JSD/TA/Tender/NIT/2023-24- 9704-43

Dated:- 12-10-2023

Copy to the following for information and necessary action:-


1. The Principal Secy. (PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief HP.PWD., Shimla.
3. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
4. The Director, Information & Publications Department, H.P. Shimla.
5. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Nigam Vihar Shimla-2 for information. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. All the S.E.s / E.E.s under Kangra Zone.
9. The Sub Divisional Officer (C) Jaisinghpur
10. The Block Development office Lambagaon
11. All the Assistant Engineer under this Division.
12. The Drawing /Accounts Branch in this office.
13. Notice Board.


Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur.

①

SCHEDULE OF QUANTITY

Name of work :-Improvement, widening and strengthening of Panchrukhi Lambagaon road Km. 22/0 to 28/800 (SH:-Providing and laying of hot applied thermoplastic compound (painting line) in Km 25/500 to 28/00)									
S. N.	Description of Item	Quantity	Rate		Unit	Time Limits		Estimated cost Rs.	
			In Figures	In Word				Earnest Money Rs.	
								Two month	Amount
1	Providing and laying of hot applied thermoplastic compound 2.5 mm (two point five millimetres) thick including reflectorising glass beads @ 250 gms (two hundred fifty grams) per square area, thickness of 2.5 mm (two point five millimetres) is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes as per MORTH Technical specification clause 803 and as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	500.00	710.00	Rupees Seven Hundred Ten Only	Per square Metre			355000.00	7100.00
		Total						355000.00	
	Quoted Rate (in Figures) Percentage	Excess (+)						%	
		Less (-)						%	
	G.Total in Figures								
	G.Total in Words								



 Executive Engineer,
 Jaisinghpur Division,
 JHP PWD Jaisinghpur

Executive Engineer,
Jaisinghpur Division,
A.P. PWD Jaisinghpur

(3)

SCHEDULE OF QUANTITY

Name of work :-Improvement,Widening & Strengthening of Jhamon to Jaisinghpur road Km.8/0 to 18/300 (SH:-P/L Interlocking paver block at RD 9/309.80 to 9/360)						Estimated cost Rs.	428165.00
						Earnest Money Rs.	8600.00
						Time Limits	Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Providing and laying mechanically mixed and vibrated plain cement concrete 1:4:8 (one cement is to four sand is to eight graded crushed stone aggregate 40 mm (forty millimeter) nominal size) and curing complete excluding the cost of form work in foundation and plinth as per specifications approved drawing , design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	18.83	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	80028.00	
2	Providing and laying 80 mm thick Interlocking M-40 grade Concrete paver block pavement conforming to ISI 15658:2006 having thickness 80mm (eighty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shell be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	251.00	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per square metre	338850.00	
3	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishing and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty millimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.51	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per Cubic Metre	9287.00	
	Total						428165.00
	Quoted Rate (in Figures) Percentagee	Excess (+)			%		
		Less (-)			%		
	G.Total in Figures						
	G.Total in Words						


 Executive Engineer,
 Jaisinghpur Division,
 PWD Jaisinghpur

⑤

Estimated cost Rs.	203244.00
Earnest Money Rs.	4100.00


Executive Engineer,
Jaisinghpur Division,
H.P.W.D Jaisinghpur

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Improvement of black spot on Paplah Bandahu Odri road Km 0/0 to 7/465(SH:-C/O R/wall with W-Metal Beam Crash Barrier at RD 4/550 to 4/564) (Black spot)						
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
			Estimated cost Rs.		479368.00	
			Earnest Money Rs.		9600.00	
			Two month			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	50.75	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	11419.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	105.00	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	393750.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	11.13	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre.	10574.00

4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	62.00	250.00	Rupees Two Hundred Fifty Only	Each	15500.00
5	Providing and erecting of "W" metal beam crash barrier comprising of 3mm (three millimetre) thick corrugated sheet metal beam rail, 70 cm (seventy centimetre) above road/ground level, fixed on ISMC series channel vertical post. 150x75x5 mm (one hundred fifty into seventy five into five millimetre) spaced 2 mtr.(two metre) center to center, 108 Mtr.(one hundred eight metre) high, 1.10Mtr.(one point ten metre) below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fitting confirm to IS: 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5 mm (one hundred fifty into seventy five into five millimetre) long complete clause 810 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12.50	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per running metre	48125.00
	Total					479368.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur



SCHEDULE OF QUANTITY

Item of work :- Restoration of rain damages on HSTM Portion km 24/135 to 30/0
(SH:- C/O Edge wall at RD 24/515 to to 24/645)

N.	Description of Item	Quantity	Rate		Unit	Estimated cost Rs.	
			In Figures	In Word		Earnest Money Rs.	Time Limits
							Two Month Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	36.40	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre		8190.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement: four sand : eight graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) and curing complete in Retaining walls, Breast walls, etcetera on ground or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200, 1600 and as per the direction of Engineer-in-Charge. including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	101.40	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre		430950.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	20.80	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre.		19760.00
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	130.00	250.00	Rupees Two Hundred Fifty Only	Each		32500.00
Total							491400.00
Quoted Rate(in Figures) Percentage		Excess (+)				%	
		Less (-)				%	
G.Total in Figures							
G.Total in Words							

Executive Engineer,
Jaisinghpur Division,