



E-Mail ID - ecpwd-jha-bll@hp.gov.in

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed item^{percentage} tender(s) on PWD form No 6 & 7/8 are hereby invited by the Executive Engineer Jhandutta HPPWD Jhandutta on behalf of the Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

Date of application 20/10/2023
Date of sale of Tender forms 21/10/2023
Date of opening of tender 23/10/2023

The tender shall be received up to 11:00A.M. on 23/10/2023 and will be opened on the same day at 11:30 A.M in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non-refundable) during the working hours on 21/10/2023.

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ in any of the Post-Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Jhandutta Division, HP-PWD, Jhandutta must accompany with each application. Conditional tenders and the tenders received without earnest money will simultaneously be rejected.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of form	Time limit	Class
1.	C/o circular road at Jhandutta Km. 0/00 to 4/904 (SH: P/L GSB, 1:3:6, 1:2:4, interlocking concrete pavement block at RD 1/420 to 1/475 near temple BDO office).	4,36,369/-	8,700/-	350/-	Three Month	D
2.	C/o circular road at Jhandutta Km. 0/00 to 4/904 (SH: P/L GSB, 1:3:6, 1:2:4, interlocking concrete pavement block at RD 1/730 to 1/785 near Police Thana office).	4,36,369/-	8,700/-	350/-	Three Month	D
3.	Construction of link road from Khalsai to Basandwari-Nakhlehra Km. 0/00 to 2/125 (SH: R.O.F.D. in Km. 1/525 to 1/705).	3,48,333/-	7,000/-	350/-	One Month	D
4.	Construction of link road from Khalsai to Basandwari-Nakhlehra Km. 0/00 to 2/00 (SH: C/o 900mm Dia Hume Pipe Culvert at RD 0/435 with both side wing wall).	1,68,039/-	3,400/-	350/-	Three Month	D
5.	Construction & M/T on Barsand Talab to Jungle Jungle Jamothi Serwa via Kutla Basti Km. 0/00 to 1/600 (SH: P/L C.C. Pavement at RD 0/00 to 0/180).	4,54,166/-	9,100/-	350/-	Three Month	D
6.	C/o link road at PHC Kalol Tehsil Jhandutta District Bilaspur (HP) (SH: C/o edging, P/L GSB, 900mm dia HPC for PHC Kalol approach from BJSJ road).	4,98,442/-	10,000/-	350/-	Three Month	D
7.	C/o link road to Village Jejwin (Unconnected Gram Panchayat) Km. 0/00 to 1/210 (SH: C/o Formation Cutting at Km. 0/300 to 0/600).	3,81,700/-	7,600/-	350/-	One Month	D

8.	Construction of link road from Khalsai to Basandwari - Nakhlehra Km. 0/0 to 2/125 (SH: ROFD in Km. 1/195 to 1/500).	4,99,470/-	10,000/-	350/-	One Month	D
9.	Repair of Building under Swaran Jayanti Utkrist Vidyalaya Yojna 2022-23 of Government Senior Secondary School Kosharian (SH: Repair of Plaster, Painting and Distemping) Deposit Work.	4,21,585/-	8,400/-	350/-	Three Month	D
10.	Construction of link road from Twali to Village Chhuman Km. 0/0 to 1/0 (SH: R.O.F.D. at Km. 0/0 to 0/600).	3,77,444/-	7,600/-	350/-	Two Month	D

Certified that tender of above works are being called of emergent nature in exigency of public interest.

Terms and conditions:

1. The tender forms will not be issued to those contractors whose performance is not found Satisfactory.
2. The contractors should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within last five years.
3. GST, EPF No, Earnest Money, Tender form cost, copy of Enlistment should be accompanied with application.
4. Application without all documents will not be entertained.
5. Proxy Application will not be entertained.
6. Payment for the works under N.I.T shall be made as & when sufficient funds are available with the Department.
7. Tender form shall not be issued to those contractors who have two or more work in hand.

Executive Engineer,
Jhandutta Division,
HPPWD., Jhandutta.

No-PW-JDT-CB-Tender NIT/2023-24:-

5977 -86

Dated:-

10/10/23

Copy forwarded to the following for information and necessary action Please:-

- The Engineer -in-Chief HPPWD Nirman Bhawan Shimla.
- The Chief Engineer (HZ) HPPWD Hamirpur.
- The Superintending Engineer 10th Circle HP PWD Bilaspur.
- The Executive Engineer(IT) O/o the Engineer-in-Chief HPPWD., Shimla.
- All the Assistant Engineers Working under this Division.
- The B.D.O. Jhandutta.
- A/B & D/B in this office.
- Various Contractors working under this Division.
- Notice Board.

Executive Engineer,
Jhandutta Division,
HPPWD., Jhandutta

[Signature]

SCHEDULE OF QUANTITY

Name of Work :- C/O of circular Road at Jhandutta Km 0/0 to 4/904 (SH:- P/L GSB, 1:3:6, 1:2:4, Interlocking concrete Pavement Block at RD 1/420 to 1/475 Near temple BDO office)

Estimated cost:- ₹ 436369.00 Only
 Earnest Money:- ₹ 8700.00 Only
 Time allowed:- Three Month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	35.06			Per Cubic Meter	
2	Providing and laying concrete for plain/reinforced cement concrete 1:3:6 (One cement is to Three sand is to six graded stone aggregate 20 mm.(twenty millimetre nominal size) in open foundation and curing complete including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.53			Per cubic metre	
3	Providing & laying of Interlocking concrete block pavement having thickness 80 mm (eighty millimetre) as per drawing and technical specification clause 1504, including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax; levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	217.25			Per Square metre	

4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete 1:2:4 (one cement : two sand : four graded/crushed stone aggregate 20 mm (twenty millimetre) nominal mix. including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royally or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.04			Per cubic metre	
Total:-						

Estimate No.
 DNIT No.
 Head of Account .
 Available Fund:-/-only


 Executive Engineer,
 Jhanduta Division
 H.P.W.D. Jhanduta

SCHEDULE OF QUANTITY

Name of Work :- C/O of circular Road at Jhandutta Km 0/0 to 4/904 (SH:- P/L GSB, 1:3:6, 1:2:4, Interlocking concrete Pavement Block at RD 1/730 to 1/785) Near Police thana)

Sr.No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
Estimated cost:- ₹ 436369.00 Only Earnest Money:- ₹ 8700.00 Only Time allowed:- Three Month						
1	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	35.06			Per Cubic Meter	
2	Providing and laying concrete for plain/reinforced cement concrete 1:3:6 (One cement is to Three sand is to six graded stone aggregate 20 mm.(twenty millimetre nominal size) in open foundation and curing complete including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.53			Per cubic metre	
3	Providing & laying of Interlocking concrete block pavement having thickness 80 mm (eighty millimeter) as per drawing and technical specification clause 1504. including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	217.25			Per Square metre	

4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete 1:2:4 (one cement : two sand : four graded/crushed stone aggregate 20 mm (twenty millimetre) nominal mix. including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.04			Per cubic metre	
Total:-						


 Executive Engineer,
 Jhanda Dutta Division
 H.P.W.D. Jhanduita

3

SCHEDULE OF QUANTITY

Name of Work :- Construction of link road From Khalsai to Basandwari-
Naklehra km 0/0 to 2/125 (SH-ROFD in km 1/525 to 1/705)

Estimated cost:- ₹ 348333.00
Earnest Money:- ₹ 7000.00
Time allowed:- One Month

Only
Only

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil, setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification 2014 Clause 302,1603.1,1603.2, and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation of useful material for filling in road ways, camber ,embankments for grade improvements and disposal of all surplus materials to the approved dumping sites, which shall be managed by the contractor / firm at their own, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials, tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. A recovery of useful stones for 117.68 Cubic metre @ Rs.300/- per cubic metre shall be done on pro-rata basis from each running bill for this item.	1176.8			Per Cubic Meter	
Total:-						

(Signature)
EXECUTIVE ENGINEER,
Jhاندura Division
HPPWD, Jhاندura


SCHEDULE OF QUANTITY

④

Name of Work :- C/O Link road From Khalsai to Basandwari Nahkichehra road Km 0/0 to 2/00. (SI:- C/O 900 mm dia Hume pipe culvert at RD 0/435 With both side Wing wall).

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
Estimated cost:- ₹ 168039.00 Only Earnest Money:- ₹ 3400.00 Only Time allowed:- Three Month						
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 (fifty) mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	33.25			Per Cubic Meter	
2	Providing and laying cement concrete 1:4:8 (One cement into four sand into eight graded stone aggregate 40mm.(forty millimeter) nominal size) and curing complete including cost of form work in retaining walls/breast walls, as per H.P.V.D. specification including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.14			Per cubic metre	
3	Plain Cement Concrete M10 (1:3:6 nominal mix) and curing complete including cost of form work in retaining levelling course below open Foundation of Head walls as per drawings & Technical Specification Clause 1109, including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.70			Per Cubic Meter	

4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 in 900 mm (nine hundred millimeter) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.25				Per Running Meter	
5	Providing and laying cement concrete 1.5:10 (one cement : five sand: ten graded stone agg. 40 mm (forty millimeter) nominal size) and curing complete work in foundation and plinth including the cost of centring & shuttering in foundation and plinth including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.85				Per Cubic Meter	
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material. including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.68				Per Cubic Meter	
7	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe extending through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.00				Each	
Total:-							


 Executive Engineer,
 Jharkhand Division
 HPPWD, Shandurda

SCHEDULE OF QUANTITY

Name of Work :- Construction & M/T on Barsand Talab to jungle Jamothi Serwa Via kutia Basi km 0/00 to 1/600 (SH:-P/L CC pavement at RD 0/00 to 0/180)

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
Estimated cost:- ₹ 454166.00 Only Earnest Money:- ₹ 9100.00 Only Time allowed:- Three Month						
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1/ie setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto all a lead and heights dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royally or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.52			Per Cubic Meter	
2	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comb including spreading watering and rolling of binding materials moonum or earth etc. complete as per HP PWD specification. 100 mm spread thickness (Finished work including materials and labour) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royally or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.09			Per Cubic Meter	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering -1:3:6 (one Cement into three coarse sand) into six graded stone aggregate 20 mm (twenty Millimeter) nominal size) All work up to plinth level including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royally or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.51			Per cubic metre	
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement. All work up to plinth level :4:1.5:3 (one cement into one part five coarse sand) into three graded stone aggregate 20 mm (twenty Millimeter) nominal size including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royally or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	34.91			Per cubic metre	
Total:-						


 EXECUTIVE ENGINEER,
 Jhpadurta Division
 Bapatwadi, Jhpadurta

SCHEDULE OF QUANTITY

6

Name of Work :- C/O link road at PHC Kalol Teh, Jhandutta Distt, Bilaspur HP (SH:- C/O edging, P.L GSB, 900 mm dia HPC for PHC Kalol approach from BJSM road)

Estimated cost:- ₹ 498442.00 Only

Earnest Money:- ₹ 100000.00 Only


Time allowed:- Three Month

Sl. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out of 50 (th) mts dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	16.23			Per Cubic Meter	
2	Providing and laying reinforced concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 in 900 mm The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	5.00			Per Running Meter	
3	Plain Cement Concrete M10 (1:3:6 nominal mix) in levelling course below open undation of Head walls as per drawings & Technical Specification Clause 1109. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	42.73			Per Cubic Meter	
4	Banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks, and guide banks etc., lead upto 50 All kinds of soil The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	200.10			Per Cubic Meter	
5	Providing weep holes in brick masonry /stone masonry, plain reinforced concrete abutment wing wall return wall with 100 mm dia PVC pipe entering through full of width of the structure with slope of (V) 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	48.00			Each	

Construction of granular sub-base by providing closegraded Material conforming to specifications, mixing in pneumatic mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octy, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.

Total:-

	58.80	✓			Per Cubic Meter	✓
--	-------	---	--	--	-----------------	---


 Executive Engineer,
 Jharpdutta Division,
 H.P.P.W.D. Jhandutta


SCHEDULE OF QUANTITY

(7)

Name of Work :- Construction of link road to village Jejiwin (Unconnected Gram Panchayat) at RD 0/0 to 1/210 (SH:- Formation Cutting at Km 0/300 to 0/600).

Estimated cost:- ₹ 381700.00	Only
Earnest Money:- ₹ 7600.00	Only
Time allowed:- One Month	

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil, setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification 2014 Clause 302,1603.1,1603.2, and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to the approved dumping sites, which shall be managed by the contractor / firm at their own, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials, tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. A recovery of useful stones for 122.60 Cubic metre @ Rs. 300/- per cubic metre shall be done on pro-rata basis from each running bill for this item.	1225.95			Per Cubic Meter	
Total:-						


 Executive Engineer,
 Jhagadutta Division
 H.P. WD, Jhandauda

SCHEDULE OF QUANTITY

Name of Work :- Construction of link road From Khalsai to Basandwari-Nakhehra km 0/0 to 2/125 (SH-ROFD in km 1/195 to 1/500) Under OTMNP.

Estimated cost:- ₹ 499470.00 (Only)
 Earnest Money:- ₹ 10000.00 (Only)
 Time allowed:- One Month

Sr. No.	Description of Items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil, setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the N.C.R.D Technical Specification 2014 Clause 302, 1603.1, 1603.2, and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to the approved dumping sites, which shall be managed by the contractor / firm at their own, through all modes of transportation including head load or animals transport or mechanical means, alongwith its leveling, line dressing and carriage of machineries, materials, tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. Any loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. A recovery of useful stones for 168.74 Cubic metre @ Rs. 300/- per cubic metre shall be done on pro-rata basis from each running bill for this item.	1687.40			Per Cubic Meter	
Total:-						

Estimate No.
 DNIT No.
 Head of Account.


 Executive Engineer,
 Jhanduta Division
 H.P.O., Jhanduta

9

SCHEDULE OF QUANTITY

Name of Work :- Repair of building under Swaran Jayanti Ukrist Vidyalaya
Yojna 2022-23 of Government Senior Secondary School Kosriyan (SH.-Repair of
plaster, Painting and Distempering). Deposit Work

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Repairs to plaster of thickness 12 mm to 20 mm (twelve to Twenty millimeter) in patches of area 2.5 sq. (two point Five square) meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (one cement into four coarse sand) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royally or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.38			Per square Meter	
2	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royally or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	242.87			Per square Meter	
3	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royally or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1232.68			Per square Meter	

4	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm) (three point eight four Kilogram per ten Square meter) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1232.68			Per square Meter	
5	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (zero point Nine zero liter per ten square meter) over an under coat of primer applied @ 0.75 ltr/10 sqm (zero point seven five liter per ten square meter) of approved brand and manufacture including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	388.58			Per square Meter	
6	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm (zero point Nine zero liter per ten square meter) over an under coat of primer applied @ 0.80 ltr/10 sqm (zero point seven five liter per ten square meter) of approved brand and manufacture including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	350.62			Per square Meter	
7	Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701 Hindi (Matras commas and the like not to be measured and paid for. Half letters shall be counted as half only) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30000			Per cm heigh per letter	

8	Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701 English and Roman Hyphens, commas and the like not to be measured and paid for. Including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30000			Per cm height per letter	
Total:-						


 Executive Engineer,
 Jhagdura Division
 H.P.W.D. Jhagdura


SCHEDULE OF QUANTITY

16

Name of Work :- Construction of link road From Twali to Village Chhuman Km o/o to 1/0 (SH- R.O.F.D at Km 0/0 to 0/600)

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil, setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification 2014 Clause 302.1603.1,1603.2, and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation of useful material for filling in road ways, camber ,embankments for grade improvements and disposal of all surplus materials to the approved dumping sites, which shall be managed by the contractor / firm at their own, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials, tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octy, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. A recovery of useful stones for 127.52 Cubic metre @ Rs.300/- per cubic metre shall be done on pro-rata basis from each running bill for this item.	1275.15			Per Cubic Meter	
Total:-						

Estimated cost:- ₹	377444.00	Only
Earnest Money:- ₹	7600.00	Only
Time allowed:-	Two Month	


 Executive Engineer,
 Jhandutta Division
 HPWD, Jhandutta