



Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 04-11-2023 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 03-11-2023 up to 10.00 A.M. to 12:30 P.M. and tender form can be had from this office on 03-11-2023 from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Restoration of Damages due to Laying of OFC on Baijnath Lad Bharol Kandapatan road km. 0/00 to 46/00 (SH:- Improvement of Sharp Curve between km. 41/680 to 41/840)	Rs. 4,28,138/-	Rs. 8,600/-	Rs. 350/-	Class "D"	Three months
2	Restoration of Damages due to Laying of OFC on Baijnath Lad Bharol Kandapatan road km. 0/00 to 46/00 (SH:- Improvement of Sharp Curve between km. 39/780 to 40/590)	Rs. 4,02,576/-	Rs. 8,100/-	Rs.350/-	Class "D"	Three months
3	Restoration of rain damages on link road Suja to Keyor km. 0/00 to 1/00 (SH:- Providing and laying Renewal/Taring in Bituminous Concrete at km. 0/200 to 0/600).	Rs.4,74,860/-	Rs.9,500/-	Rs. 350/-	Class "D"	Three Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

- The contractor should produce a copy of enlistment / renewal letter at time of application.
- Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
- The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
- The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
- No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
- The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
- The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2023-24-

21557-21606

Dated:-

18-10-2023

- Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-Chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- All the Contractor working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder

SCHEDULE OF QUANTITY

Name of Work: Restoration of Damages due to Laying of OFC on Baijnath Lad Bharol Kandapattan Road km 0/00 to 46/00 (SH: Improvement of Sharp Curve between km 39/780 to 40/590)				Estimate Cost: Earnest Money: Time Limit :		4,02,576.00 8,100.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 247.59 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	1494.62	Per cubic metre				
Total							

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work: Restoration of Damages due to Laying of OFC on Baijnath Lad Bharol Kandapattan Road km 0/00 to 46/00 (SH: Improvement of Sharp Curve between km 41/680 to 41/840)

Name of Work: Restoration of Damages due to Laying of OFC on Baijnath Lad Bharol Kandapattan Road km 0/00 to 46/00 (SH: Improvement of Sharp Curve between km 41/680 to 41/840)			Estimate Cost: 4,28,138.00 Earnest Money: 8,600.00 Time Limit : Three Months		
			Rate	AMOUNT	
Sr. No.	Description of work	No. or Qty.	Unit	Figures	Words
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 250.33 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	1672.22	Per cubic metre		
Total					


Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on link road Suja to keyor km 0/00 to 1/00 (S.H. : Providing and laying Renewal/Tarring in Bitumenious Concrete at km 0/200 to 0/600)					Estimate Cost: Earnest Money: Time Limit :		4,74,860.00 9,500.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate	Words		AMOUNT	
					Figures		Rs.	P
1	Providing and applying primer/tack with bituminous primer (VG-10) at the rate of 1.00 (one point zero zero) kilogram per square metre on existing WBM (Water bound macadam) surface cleaned with mechanical brooms as per HP.PWD./MORD specification complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	1155.00	Per square metre					
2	Providing and Laying bituminous concrete 30mm (thirty millimetre) compacted thickness with bitumen of grade VG-30 (Thirty) @ 5.50% (at the rate of five point five per cent) (percentage by weight of total mix) and lime filler @ 3% (three percentage) (percentage by weight of aggregate) prepared in Batch Type Hot Mix Plant of 100-120 (Hundred - one hundred twenty) TPH capacity by using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site by tippers, laying with paver finisher equipped with electronic sensor to the required garde, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction and density as per specification, complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	33.00	Per Cubic metre					
Total								


 Engineer
 B & R Division HP.PWD.
 Joginder Nagar