



OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030
Email ce-jaipwd-hp@gov.in

"CERTIFICATE"

Certified that the tenders for the works as called vide this office
letter No. PWD/JSD/TA/NIT/ 2023-24- 9350-9a dated 06-10-2023 are of urgent
nature and in public interest.

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur.



"NOTICE INVITING TENDERS"

Sealed percentage rates tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **16.10.2023** up to **11:00 A.M.**, and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **13.10.2023** up to **4:00 PM** and the application for issue of tender form shall be received on **12.10.2023** up to **3:00 PM**. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office/ Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days:-


Sr. No.	Name of work	Estimated Cost	Earnest Money	Time Limit
1	C/O Bhuana Ashapuri road Km 0/00 to 12/135 (SH:- C/O 900 mm dia RCC hume pipe culvert at RD 1/392)SCDP	218023/-	4400/-	Two month
2	Restoration of rain damages to Jaisinghpur to Vijapur Netru road Km 0/00 to 2/700 (SH:- C/O U-shape drain & Edge wall with at RD 1/800 to 1/850)	218347/-	4400/-	Two month
3	Renovation of Volleyball ground at Govt. Sr. Secondary School Jalag (SH:- Repair of Volleyball Ground and thick synthetic flooring) (Deposit)	299030/-	6000/-	Two month
4	C/O Bhuana Ashapuri road Km 0/00 to 12/135 (SH:- Providing and fixing crash barrier ends of existing crash barrier at various RDs / locations) (SCDP)	488635/-	9800/-	Two month
5	Restoration of rain Damages on Dalu Chatter Guhan Ropa road Km 0/0 to 4/0 (SH:- C/O crate wall at RD 1/290 to 1/305)	432693/-	8700/-	Two month
6	Restoration of rain damages on Chadhar Mungal Haler Road Km 2/600 to 10/030 (SH:- C/O R/wall at RD 7/130 to 7/145 and 8/850 to 8/860)	462799/-	9300/-	Two month
7	C/O Link road from main road Jangal to Via Rajput, Pandit Mohalla Paraga Da Gallu Km 0/00 to 1/00 (SH:- C/O Edge wall at RD 0/413 to 0/458) MNP	146853/-	3000/-	Two month
8	Restoration of rain damages on Tinbar to Jaisinghpur road Km 0/00 to 18/300 (SH:- C/O R/ wall at RD 6/100 to 6/120 and U-shape drain RD 6/135 to 6/165)	392756/-	7900/-	Two month
9	C/O Bhuana Ashapuri road Km 0/00 to 12/135 (SH:- Providing and Fixing Crash Barrier for Improvement of black spot at Km 8/340 to 8/425) (SCDP)	495659/-	10000/-	Two month
10	C/O Ambulance road from house of Sh. Bikram Singh to House of Sh. Jagdish Chand WN-4 GP Lower Thedu (SH:- C/O B/Wall at RD 0/117 to 0/137 and CC pavement at RD 0/115 to 0/140) Deposit	244498/-	4900/-	Two month
11	C/O Draman Amb Mali road Km 0/00 to 2/060 (SH:- C/O R/wall at RD 1/300 to 1/307 and 1/615 to 1/624) MNP	430107/-	8600/-	Two month
12	Restoration of rain damages on Bhuana Ashapuri road KM 0/0 to 12/135 (SH:- C/O R/Wall at RD 1/380 to 1/390)SDRF	399976/-	8600/-	Two month

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal ellisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.

4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK.




Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur.
(On behalf of Government of Himachal Pradesh)

No. PW/JSD/TA/Tender/NIT/2023-24- 9350-90

Dated:- 06-10-2023.

Copy to the following for information and necessary action:-

1. The Principal Secy. (PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief HPPWD, Shimla.
3. The Chief Engineer (K.Z.) HPPWD Dharamshala.
4. The Director, Information & Publications Department, H.P. Shimla.
5. The Executive Engineer (IT) Nigam Vihar Shimla-2 for information. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. All the S.E.s / E.E.s under Kangra Zone.
9. The Sub Divisional Officer (C) Jaisinghpur
10. The Block Development office Lambagaon
11. All the Assistant Engineer under this Division.
12. The Drawing /Accounts Branch in this office.
13. The Contractors concerned.
14. Notice Board.



Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur.

(1)

SCHEDULE OF QUANTITY

Name of work :-C/O Bhuana Ashapuri road Km 0/00 to 12/135

(SH:- C/O 900mm dia hume pipe culvert at RD 1/392)SCDP

S.N.	Description of Item	Quantity	Rate		Unit	Estimated cost Rs.	
			In Figures	In Word		Earnest Money Rs.	Two Month
						Amount	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	50.52	225,00	Rupees Two Hundred Twenty Five Only	Per cubic metre	2,18,023.00	4,400.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, M-10 Grade (M-Ten) Nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate (40mm) forty millimeters nominal size) on ground or under water in open foundations for all types of structures, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete as per drawing and MORD technical specification section 800,900, 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	1.85	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	9158.00	

S.N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in sub structure for all types of structure complete for (PCC) plain cement concrete grade M-15 (M Fifteen) grade design mix with minimum cement contents of 275 kg(two hundred seventy five kilogram) per cubic metre leveling course below approach slab completed including curing complete including pumping or bailing out water ,dewatering and removal of slush as required at site which may arise at the time of laying concrete for all heights/depths including cost of form work in complete in levelling course as per drawings and M.O.R.D. technical specification section 800,900 and 1100 as directed by the Engineer-in-Charge including carriage of material within all leads ,lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	29.16	5450.00	Rupees Five Thousand Four Hundred Fifty Only	Per cubic metre	158922.00
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete M-15 (M- fifteen) nominal mix 1:2½:5 (one cement is to two and half sand is to five graded crushed stone aggregate 40mm (forty millimetre) nominal size) on ground or under water and curing complete for 14 (fourteen) days . in cradle bedding for hume pipe including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying concrete complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification section 800,900 and 1100 as directed by the Engineer-in-Charge including carriage of material within all leads ,lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	1.78	5450.00	Rupees Five Thousand Four Hundred Fifty Only	Per cubic metre	9701.00
4	Providing and laying (to level or slope) 900mm dia (nine hundred millimetre) diameter reinforced cement concrete heavy duty non pressure pipes (S Class NP-2 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work, in head walls and parapets as per drawing and M.O.R.D. technical specifications section 1100 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	7.50	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per running metre	28875.00
Total						218023.00
			Excess (+)		%	
			Less (-)		%	
		G.Total in Figures				
		G.Total in Words		<i>Amf</i>		


Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of Rain Damages on Jasinghpur to Vijapur Netru Road Km 0/0 to 2/700
(SH:- C/O U-Shape drain & Edge wall at RD 1/800 to 1/850).

S.N.	Description of Item	Quantity	Rate		Unit	Estimated cost Rs.
			In Figures	In Word		
						2,18,347.00
						4,400.00
						Two Month
						Amount
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures all useful material such as stone single aggregate and slates etcetera shall be shorted out and stacked in proper stack. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	48.75	185.00	Rupees One Hundred Eighty Five Only	Per cubic metre	9019.00
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	51.00	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	11475.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	37.95	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	187853.00

S.N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	40.00	250.00	Rupees Two Hundred Fifty Only	Each	10000.00
	Total					218347.00
	Quoted Rate(in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Renovation of volleyball ground at GOVT Sr. Sec. School Jalag
(SH:- Repair of Volleyball Ground and Thick Syenthic Flooring)

S.N.	Description of Item	Quantity	Rate		Unit	Estimated cost Rs.	
			In Figures	In Word		Earnest Money Rs.	Two Month Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MQRD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	37.80	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	2,99,930.00	8505.00
2	Supplying and filling in plinth with sand under floors,including watering, ramming, consolidating and dressing complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	37.80	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre	35910.00	
3	Providing and laying cement concrete 1:6:12 (One cement: six sand: twelve graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size and curing complete. excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	18.90	3450.00	Rupees Three Thousand Four Hundred fifty Only	Per cubic metre	65205.00	
4	Providing and Laying 40mm thick Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete.40 mm(forty millimetre) thick with 20 mm (twenty millimetre) nominal size stone aggregate as per direction of Engineer-In-Charge.Bars upto 12 mm (twelve millimetre) diameter.The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	252.00	340.00	Rupees Three Hundred Forty Only	Per square metre	85680.00	

S.N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
5	Providing and Fixing 10mm (ten millimetre) thick Artificial volleyball court turf (flooring) made superior quality material with seamless finish in volleyball court & needs to maintain some specific measurements knowing each of them and the best synthetic flooring of volleyball court alongwith standard specification. The line works defining the back and front court and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	162.00	615.00	Rupees Six Hundred Fifteen Only	Per square metre	99630.00
6	Providing and fixing 100mm Dia (hundred millimetre) paint coated Miled Steel volleyball poll made specific measurements knowing each of them Complete as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.00	2500.00	Rupees Two Thousand Five Hundred Only	Each	5000.00
	Total					299930.00
	Quoted Rate(in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Chnd

Executive Engineer,
Jaisingpur Division,
HP.PWD Jaisingpur

SCHEDULE OF QUANTITY

Name of work :- C/O Bhuana Ashapuri road Km 0/00 to 12/135

(SH:- Providing and fixing Crash Barrier Ends of Existing Crash Barrier at Various Rds /Location)

S.N.	Description of item	Quantity	Rate		Unit	Estimated cost Rs.	Earnest Money Rs.
			In Figures	In Word			
			Time Limits				
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.32	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	4,88,635.00	9,800.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in Sub Structure using grade M-20 (M twenty) design mix with cement contents not less than 330 kg (three hundred thirty kilogram) per cubic metre with 40mm (forty millimetre) nominal size graded crushed stone aggregate as per drawing and M.O.R.D. technical specification section 800,900,1200 including the cost of form work and curing complete in aboutment etcetera and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.25	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	63038.00	
3	Providing and erecting a "W" metal beam crash barrier comprising of 3mm (Three millimetre) thick corrugated sheet metal beam rail, 70cm (Seventy centimetre) above road/ground level, fixed on ISMC series channel vertical post, 150x75x5mm (One hundred fifty into seventy five into five millimetre) spaced 2 m (Two metre) centre to centre, 1.8 m (One decimal eight mtr) high, 1.1 m (One decimal one metre) below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5 mm (One hundred fifty into seventy five into five millimetre), 330 mm (Three hundred thirty millimetre) long complete as per MORTH technical Specification section 800. as direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	110.00	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per running metre	423500.00	
Total							488635.00
Quoted Rate(in Figures) Percentage		Excess (+)			%		
G. Total in Figures		Less (-)			%		
G. Total in Words							

[Signature]


Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

5

SCHEDULE OF QUANTITY

Name of work :- Restoration of Rain damages on Dalu Chatter Guhan Ropa road Km 0/0 to 4/0
(SH:- C/O Crate Wall at at RD 1/290 to 1/305)

S.N.	Description of Item	Quantity	Rate		Unit	Estimated cost Rs.	
			In Figures	In Word		Earnest Money Rs.	Two Month
						Time Limits	Amount
1	Earth work in excavation for all types of road structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, comprising of ordinary mix soil, ordinary rock, hard rock, chiselling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown in the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification section 300 & 1600 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	41.63	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre		4,32,693.00
2	Providing and laying of boulder apron or gabion walls laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	140.64	2950.00	Rupees Two Thousand Nine Hundred Fifty Only	Per cubic metre		414888.00
3	Earth filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	56.25	150.00	Rupees One Hundred Fifty Only	Per cubic metre		8438.00
		Total					432693.00
			Excess (+)		%		
			Less (-)		%		
		G. Total in Figures					
		G. Total in Words					



Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

6

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Chadhar Mungal Haler road Km 2/600 to 10/030
(SH:- C/O R/wall at RD 7/130 to 7/145 and 8/850 to 8/860)

S.N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
						Estimated cost Rs. 4,62,799.00
						Earnest Money Rs. 9,300.00
						Time Limits Two Month
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	34.88	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	7848.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	109.63	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	411113.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	38.25	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre.	36338.00
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	30.00	250.00	Rupees Two Hundred Fifty Only	Each	7500.00
	Total					462799.00
	Quoted Rate(in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Amo

Executive Engineer,
Jaisinghpur Division,
HP.P.W.D Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- C/O Link road from main road Jangal to Via Rajput, Pandit Mohalla Paraga da Galu Km 0/0 to 1/0
(SH:- C/O Edge wall at RD 0/413 TO 0/458).

S.N.	Description of Item	Quantity	Rate		Unit	Estimated cost Rs.	Earnest Money Rs.
			In Figures	In Word			
							Two Month Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.10	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	1,46,853.00	3,000.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	21.60	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	106920.00	
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	28.80	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre	27360.00	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	43.00	250.00	Rupees Two Hundred Fifty Only	Each	10750.00	
Total							146853.00
Quoted Rate(in Figures) Percentage						Excess (+)	%
						Less (-)	%
G.Total in Figures							
G.Total in Words							

June

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of Rain Damages on Tinbar to Jasinghpur Road Km 0/0 to 18/300 (SH:- C/O R/Wall at RD 6/100 To 6/120 and U-Shape drain at RD 6/135 to 6/165).		Estimated cost Rs.		3,92,756.00		
		Earnest Money Rs.		7,900.00		
		Time Limits		Two Month		
S.N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil), comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	65.80	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	14805.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	53.45	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per cubic metre	200438.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	16.60	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre	15770.00
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	50.00	250.00	Rupees Two Hundred Fifty Only	Each	12500.00

SCHEDULE OF QUANTITY

Name of work :-C/O Bhuana Ashapuri road Km 0/00 to 12/135

(SH:- Providing and fixing Crash Barrier for improvement of Black Spot at Km 8/340 to 8/425)SCDP

S.N.	Description of Item	Quantity	Rate		Unit	Estimated cost Rs.		
			In Figures	In Word				
			Earnest Money Rs.					
						Time Limits	Two Month	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	22.81	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	4,95,659.00	10,000.00	5132.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in Sub Structure using grade M-20 (M -twenty) design mix with cement contents not less than 330 kg (three hundred thirty kilogram) per cubic metre with 40mm (forty millimetre) nominal size graded crushed stone aggregate as per drawing and M.O.R.D. technical specification section 800,900,1200 including the cost of form work and curing complete in aboutment etcetera and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.58	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	58917.00		
3	Providing and erecting a "W" metal beam crash barrier comprising of 3mm (Three millimetre) thick corrugated sheet metal beam rail, 70cm (Seventy centimetre) above road/ground level, fixed on ISMC series channel vertical post, 150x75x5mm (One hundred fifty into seventy five into five millimetre) spaced 2 m (Two metre) centre to centre, 1.8 m (One decimal eight metre) high, 1.1 m (One decimal one metre) below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5 mm (One hundred fifty into seventy five into five millimetre), 330 mm (Three hundred thirty millimetre) long complete as per MORTH technical Specification section 800. as direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	85.00	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Running Metre	327250.00		
4	Providing and laying cement concrete 1.5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	26.20	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per cubic metre	98250.00		

(9)

SCHEDULE OF QUANTITY

Name of work :- C/O Ambulance road from House of Sh. Bikram Singh to House of Sh. Jagdish Chand WN-4 GP Lower Thedu.
 (SH:- C/O B/Wall at RD 0/117 To 0/137 and C.C. Pavement at RD 0/115 to 0/140). Deposit

S.N.	Description of Item	Quantity	Rate		Unit	Estimated cost Rs.
			In Figures	In Word		
			Time Limits			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and purapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	26.60	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	5985.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	49.78	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per cubic metre	186675.00
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	19.00	250.00	Rupees Two Hundred Fifty Only	Each	4750.00
4	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	8.64	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per cubic metre	11664.00
						2,44,498.00
						4,900.00
						Two Month

SCHEDULE OF QUANTITY

Name of work :- C/O Draman Amb Malli Road Km 0/00 to 2/060
(SH:- C/O R/wall at RD 1/300 to 1/3071 & 1/615 to 1/624)

S.N.	Description of Item	Quantity	Rate		Unit	Estimated cost Rs.	
			In Figures	In Word		Estimated cost Rs.	Earnest Money Rs.
						Time Limits	Two Month
						Amount	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	63.36	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	14256.00	
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	100.95	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	378563.00	
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	26.88	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre.	25536.00	
4	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	17.28	275.00	Rupees Two Hundred Seventy Five Only	Per cubic metre.	4752.00	
5	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	28.00	250.00	Rupees Two Hundred Fifty Only	Each	7000.00	
Total						430107.00	
Quoted Rate(in Figures) Percentage							
						Excess (+)	
						Less (-)	
G.Total in Figures							
G.Total in Words							


[Signature]

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

12

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Bhuana Ashapuri road Km 0/00 to 12/135
(SH:- C/O R/wall at RD 1/380 to 1/390)

S.N.	Description of Item	Quantity	Rate		Unit	Estimated cost Rs.	
			In Figures	In Word		Earnest Money Rs.	Two Month
							Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	51.30	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	3,99,976.00	8,000.00
2	Providing and laying cement concrete 1:3:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	96.90	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	363375.00	
3	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	15.85	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre.	15058.00	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	40.00	250.00	Rupees Two Hundred Fifty Only	Each	10000.00	
Total							399976.00
		Excess (+)			%		
		Less (-)			%		
		G.Total in Figures					
		G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD, Jaisinghpur