

**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**

PH: 01907-222229 Fax: 222229 , e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2023- **6797**
To

Dated:- **06.10.23**

✓ The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.

Subject :- Regarding publication of Tender on departmental site.

Enclosed please find herewith the copies of Notice Inviting Tender for the loading on departmental web-site before 10.10.2023 as per notification issued by the Pr. Secy.(PW) to the Govt. of HP vide letter No. PBW(B)A(3)1/2020 dated 16th July, 2021. It is further intimated that all the works mentioned are of urgent nature.

Encl:- As above.


**Executive Engineer,
B&R Division,
HP PWD Karsog**



**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division, HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **19.10.2023 upto 11.00 AM** and shall be opened on the same day at **12:00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 17.10.2023** for which the application should reach in this office **upto 1.00 PM 17.10.2023**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Mamail Mehandi road Km. 0/00 to 19/00 (SH:- Removal of slips in km. 0/00 to 10/00)	3,14,169/-	6,300/-	One month	350/-
2	R/R damages on Kelodhar to Sainj road km. 0/00 to 19/00 and Seri to Mahawan road Km. 0/00 to 7/00 (SH:- Removal of slips on various RDs)	4,73,877/-	9,500/-	One month	350/-
3	C/o Bag Shalana Nind Dogri road Km. 0/00 to 2/450 (SH:- C/o 900mm dia RCC hume Pipe Culvert & Wing wall at RD 0/900) under SCDP	2,38,038/-	4,800/-	One month	350/-
4	C/o Khenol to Sidh Chowasi Km. 0/00 to 6/00 (SH:- ROFD in Km. 0/015 to 0/30) SCDP	3,63,869/-	7,300/-	One month	350/-
5	R/R damages on Kotlu Katanda road km. 0/00 to 19/00 (SH:- C/o R/wall at RD 16/130 to 16/140) Kotlu Side)	2,23,764/-	4,500/-	One month	350/-
6	R/R damages on Lotla Nalla to Sidh road km. 0/00 to 4/00 (SH:- Removal of slips at various RDs)	2,68,868/-	5,400/-	One month	350/-
7	R/R damages on Karsog Parlog road km. 0/00 to 19/00 (SH:- Widening of road in km. 15/085 to	3,16,461/-	6,400/-	One month	350/-


	15/125 and slips at various RDs in Km. 10/00 to 17/00)				
8	R/R damages on Seri Bagoond road km. 0/00 to 7/00 (SH:- C/o R/wall at RD 4/660 to 4/675)	4,03,798/-	8,100/-	One month	350/-
9	R/R damages on Seri Bagoond road km. 0/00 to 7/00 (SH:- C/o R/wall at RD 2/920 to 2/932)	2,75,938/-	5,600/-	One month	350/-
10	R/R damages on Seri Bagoond road km. 0/00 to 7/00 (SH:- C/o R/wall at RD 2/945 to 2/960)	2,50,865/-	5,100/-	One month	350/-
11	R/R damages on Seri Bagoond road km. 0/00 to 7/00 (SH:- C/o R/wall at RD 3/280 to 3/288)	2,33,023/-	4,700/-	One month	350/-
12	R/R damages on Seri Bagoond road km. 0/00 to 7/00 (SH:- C/o R/wall at RD 6/435 to 6/446)	4,09,554/-	9,200/-	One month	350/-
13	R/R damages on Rashog Deyom road Km. 0/0 to 9/00 (SH:- C/o R/wall at RD 3/745 to 3/758)	4,26,131/-	8,600/-	One month	350/-
14	R/R damages on Mahog Gawala road km. 10/500 to 19/00 (SH:- Removal of slips at various RDs)	4,25,112/-	8,600/-	One month	350/-
15	R/R damages on Kotlu Katanda road km. 0/00 to 19/00 (SH:- C/o R/wall at RD 14/780 to 14/792) Kotlu side	2,51,142	5,100/-	One month	350/-
16	R/R damages on various road under Karsog Sub-Division (SH:- hiring of Tipper for disposal/Carriage of material)	1,86,200/-	3,800/-	49 days	350/-
17	R/R damages on various road in Kelodhar Section under Karsog Sub-Division (SH:- Removal of slips on various RDs)	4,76,797/-	9,600/-	One month	350/-
18	R/R damages on Chauridhar Kotlu road Km. 0/00 to 8/00 (SH:- Hiring of Tipper for disposal/carriage of material)	98,800/-	2,000/-	26 days	350/-
19	R/R damages on Thakurthana Delag road km. 0/00 to 7/100 (SH:- C/o R/wall at RD 0/900 to 0/915)	2,98,813/-	6,000/-	One month	350/-
20	R/R damages on Thakurthana Delag road km. 0/00 to 7/100 (SH:- C/o R/wall at RD 1/915 to 1/930)	3,88,409/-	7,800/-	One month	350/-
21	R/R damages on Sorta to Badar road Km. 0/00 to 2/700 (SH:- Removal of slips at various RDs)	88,094/-	1,800/-	One month	350/-
22	R/R damages on Jharandi Sandhol Thandapani road km. 0/00 to 2/600 (SH:- Removal of land slips at various reaches in Km. 0/00 to 2/600)	1,00,981/-	2,100/-	One month	350/-
23	Repair of link road Shill to village Khanaloo Km. 0/00 to 3/00 (SH:- C/o unlined surface drain and maintenance of earthen shoulders and removal of slips at various RDs) in Km. 0/00 to 0/255) SDF2022/589	1,50,607/-	3,100/-	One month	350/-
24	R/R damages on Kelodhar Sainj road km. 0/00 to 19/00 (SH:- hiring of Tipper for disposal/carriage of material)	98,800/-	2,000/-	26 days	350/-
25	R/R damages on Thakurtthana to Delag road Km. 0/00 to 7/100 (SH:- C/o R/wall at Rd 3/245 to 3/265)	4,99,568/-	10,000/-	One month	350/-

26	R/R damages on Ralla to Saryogi road km. 0/00 to 2/500(Removal of slips at various RDs)	98,289/-	2,000/-	One month	350/-
27	C/o link road from Karsog to Dachhain road km. 0/00 to 2/030 (SH:- C/o R/wall at RD 0/710 to 0/718) Deposit	4,23,529/-	8,500/-	One month	350/-
28	R/R damages on Seri Shout road KM. 0/00 to 19/00 (SH:- hiring of Air Compressor for ROFD, Black Spots etc.	98,952/-	2,000/-	One month	350/-
29	R/R damages on Chhitadhartu to Nag Sunani Mandir road km. 0/00 to 1/500 (SH:- C/o B/wall at RD 1/150 to 1/174) MMGSY Deposit	4,85,077/-	9,800/-	One month	350/-
30	R/R damages on Chhitadhartu to Nag Sunani Mandir road km. 0/00 to 1/500 (SH:- C/o B/wall at RD 1/235 to 1/258) MMGSY Deposit	4,64,753/-	9,300/-	One month	350/-
31	R/R damages on Chhitadhartu to Nag Sunani Mandir road km. 0/00 to 1/500 (SH:- C/o R/wall at RD 1/450 to 1/468) MMGSY Deposit	4,81,966	9,700/-	One month	350/-
32	R/R damages on Chhitadhartu to Nag Sunani Mandir road km. 0/00 to 1/500(C/o B/wall at RD 1/280 to 1/300) MMGSY Deposit	4,04,584/-	8,100/-	One month	350/-
33	R/R damages on Katanda Pokhi road Km. 0/00 to 10/00(C/o R/wall at RD 9/510 to 9/521) MMGSY Deposit	2,48,246/-	5,000/-	One month	350/-
34	R/R damages on Kelodhar to Sainj road km. 0/00 to 19/00 (SH:- C/o B/wall at RD 15/030 to 15/038)	1,36,288/-	2,800/-	One month	350/-
35	R/R damages on Sanarli to Karsog road Km. 0/0 to 1/330 (SH:- C/o unlined surface drain, maintenance of earthen shoulders in km. 0/00 to 3/330)	4,71,708/-	9,400/-	One month	350/-
36	C/o Punni to Naswar road km. 0/00 to 3/00 (SH:- C/o R/wall at RD 0/175 to 0/185)	3,28,768/-	6,600/-	One month	350/-
37	C/o Punni to Naswar road km. 0/00 to 3/00 (SH:- C/o R/wall at RD 0/165 to 0/175)	3,30,287/-	6,700/-	One month	350/-
38	R/R damages on various road under Kotlu Section in Karsog Sub-Division (SH:- Removal of slips at various RDs)	3,07,005/-	6,200/-	One month	350/-
39	R/R damages on Narenabali to Balna road Km. 0/00 to 3/00 (SH:- Removal of slips at various RD)	98,788/-	2,000/-	One month	350/-
40	R/R damages on Tangla to Kot road Km. 0/00 to 4/00 (SH:- Removal of slips at various RD)	95,085/-	2,000/-	One month	350/-
41	R/R damages on Chindi Pangna road km. 0/00 to 12/480(SH:- removal of slips at various RDs)	2,15,983/-	4,400/-	One month	350/-
42	R/R damages on Chindi Pangna road Km. 0/00 to 12/480(SH:- C/o R/wall at RD 5/780 to 5/791))	4,98,302/-	10,000/-	One month	350/-
43	R/R damages on various road under Pangna Sub-Division (SH:- Hiring of Tipper for	98,800/-	2,000/-	26 days	350/-

	disposal/carriage of material)				
44	R/R damages on various road under Karsog Sub-Division (SH:- Hiring of Tipper for disposal/carriage of material)	98,800/-	2,000/-	26 days	350/-
45	R/R damages on various road under Karsog Sub-Division (SH:- Hiring of Tipper for disposal/carriage of material)	98,800/-	2,000/-	26 days	350/-
46	R/R damages on various road under Karsog Sub-Division (SH:- Hiring of Tipper for disposal/carriage of material)	98,800/-	2,000/-	26 days	350/-
47	R/R damages on various road under Karsog Sub-Division (SH:- Hiring of Tipper for disposal/carriage of material)	98,800/-	2,000/-	26 days	350/-
48	R/R damages on Bhanthal Punni road Km. 0/00 to 4/00 (SH:- C/o B/wall at RD 0/900 to 0/915)	2,54,000/-	5,100/-	One month	350/-
49	R/R damages on Tattapani to Shakra road km. 0/00 to 10/00 and Shakra Parlog upto village Bindla Km. 0/00 to 6/250 (SH:- Removal of land slide slip at various RDs).	4,89,955/-	9,800/-	One month	350/-
50	C/o Ropa to Phegla road Km. 0/00 to 1/600 (SH:- ROFD Ropa to Phegla in Km. 0/495 to 1/150)	4,15,120/-	8,400/-	One month	350/-
51	R/R damages on Jachh to Sarhi road km. 0/00 to 5/00 (SH:- C/o PCC R/wall at RD 0/955 to 0/968.50).	4,80,756/-	9,700/-	One month	350/-
52	R/R damages on Karsog to Kanda road km. 0/00 to 8/500 (SH:- C/o R/wall at RD 3/534 to 3/550)	4,05,022/-	8,200/-	One month	350/-
53	R/R damages on Kumru to Khadain road km. 0/00 to 5/00 (SH:- C/o R/wall at RD 0/235 to 0/245)	4,98,503/-	10,000/-	One month	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-38095 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.


Executive Engineer
B&R Division
HPPWD Karsog,
Distt. Mandi (HP)

No. PW-E-Tender-NIT/23-

6790 - 96

Dated:-

16.10.23

1. Copy to the Director , Information & Publications Department, HP Shimla for favour of publication in one Regional Newspaper and one National Newspaper.
2. Copy to the Superintending Engineer, 1st Circle, HP, PWD, Mandi for information please.
3. The Sub-Divisional Officer (Civil) Karsog, Tehsil Karsog Distt. Mandi HP.
4. The Block Development Officer Karsog , Tehsil Karsog Distt. Mandi HP.
5. All the Assistant Engineers, working under this Division.
6. Copy to Drawing & Account Branch.
7. Notice board of this office.


**Executive Engineer,
B&R Division,
HP PWD Karsog**

Scheduled Quantity

Estimated Cost
Earnest Money
Time

314169
6300
One Month

Name of work : - R/R Damages on Mamall Mehandi road km 0/00 to 19/00 (SH :- Removal of slips in km 0/00 to 10/00).

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			In Figure	In words		
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	2286.53			Per Cubic Meter	
Total Amount						


 Executive Engineer,
 Karsog Division,
 HPPMD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 473877
Earnest Money 9500
Time One Month

Name of Work:- R/R Damages on Kelodhar to Sainj road km. 0/00 to 19/00 and Seri to Mahavan road Km. 0/00 to 7/00 (SH:- Removal of slips on various RD)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	3749.03	Per Cubic Meter	126.40	473877.00	Rupees Four Lakhs Seventy Three Thousand Eight Hundred Seventy Seven and Paise Zero Only
Total in Figures					473877.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 238038
Earnest Money 4800
Time One Month

Sub-Head and Items of works.

Name of Work:- C/O Bag Salana Nind Dogri road Km. 0/00 to 2/450 (SH:- C/O 900mm dia RCC Hume Pipe culvert & Wing wall at RD 0/900) under SCDP						
Sr.No.		No. Or Qty.	Unit	Estimated Rate (Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Excavation in soil in hilly area by mechanical mean including cutting and trimming of side slope and disposing of excavated earth with any lift and any lead as per technical specification clause 1603.1 as per direction of engineer in charge with in all lead and lift As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	47.72	Per Cubic Meter	204.30	9749.00	Rupees Nine Thousand Seven Hundred Forty Nine and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Noimimal mix 1:6:12 (one cement: six sand: twelve graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	2.02	Per Cubic Meter	4765.50	9626.00	Rupees Nine Thousand Six Hundred Twenty Six and Paise Zero Only
3	Providing and laying concrete for plain/reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802.803, 1202 and 1203 as per direction of Engineer-in- Charge including carriage of material within all leads and lifts and other incidentals.	32.10	Per Cubic Meter	5140.40	165007.00	Rupees One Lakh Sixty Five Thousand Seven and Paise Zero Only
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in double row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets as per clause 1106as per direction of Engineer-in- Charge with in all leads and lifts and other incidentals.	7.50	Per Running Meter	5435.10	40763.00	Rupees Forty Thousand Seven Hundred Sixty Three and Paise Zero Only
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in- Charge including carriage of material within all leads and lifts and other incidentals.	6.60	Per Cubic Meter	1277.55	8432.00	Rupees Eight Thousand Four Hundred Thirty Two and Paise Zero Only
6	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614.709, 1204.3.7 As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	12.00	Each	371.75	4461.00	Rupees Four Thousand Four Hundred Sixty One and Paise Zero Only
Total in Figures					238038.00	
Quoted Rate in Figures		Select			0.00	
Quoted Rate in Words		Zero and Paise Zero Only				


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 363869.00
Earnest Money 7300
Time One Month

Name of Work:- Construction of road Khaneol to Sidh Chowsi Km. 0/00 to 6/00 (SH:-ROFD in Km. 0/015 to 0/030) SCDP

Sub-Head and items of works.

Sr.No.		No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 245.70 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 73710/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	737.10	Per Cubic Meter	493.65	363869.00	Rupees Three Lakhs Sixty Three Thousand Eight Hundred Sixty Nine and Paise Zero Only
Total In Figures					363869.00	
Quoted Rate In Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 223764
Earnest Money 4500
Time One Month

Name of Work:- R/R Damages on Kotlu to Katanda road Km. 0/00 to 19/00 (SH:- C/O R/Wall at RD 16/130 to 16/140) Kotlu Side)

Sub-Head and items of works.

Sr.No.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	24.00	Per Cubic Meter	379.90	9118.00	Rupees Nine Thousand One Hundred Eighteen and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	36.98	Per Cubic Meter	5140.40	190092.00	Rupees One Lakh Ninety Thousand Ninety Two and Paise Zero Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	13.40	Per Cubic Meter	1277.55	17119.00	Rupees Seventeen Thousand One Hundred Nineteen and Paise Zero Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	20.00	Each	371.75	7435.00	Rupees Seven Thousand Four Hundred Thirty Five and Paise Zero Only
Total in Figures					223764.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words		Zero and Paise Zero Only				


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Schedule of Quantity

Estimated Cost
Earnest Money
Time

268868
5400
One Month

Name of work : - R/R Damages on Lotla Nalla to Sidh road Km. 0/00 to 4/00 (SH :- Removal of slips at various RDS)

Sr.No.	Sub-Head and Items of works.	Qty.	Rate		Unit.	Amount.
			In Figure	In words		
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1956.83			Per Cubic Meter	
Total Amount						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 316461.00
Earnest Money 6400
Time One Month

Name of Work:- R/R Damges on Karsog to parlog road km. 0/00 to 19/00 (SH:- Widening of road n Km. 15/085 to 15/125 and slips at various RDs in Km. 10/00 to 17/00)

Sr.No.		Sub-Head and Items of works.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1		Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 114.69 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 34406/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.		452.72	Per Cubic Meter	335.81	152028.00	Rupees One Lakh Fifty Two Thousand Twenty Eight and Paise Zero Only
2		Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.		1196.75	Per Cubic Meter	137.40	164433.00	Rupees One Lakh Sixty Four Thousand Four Hundred Thirty Three and Paise Zero Only
Total in Figures							316461.00	
Quoted Rate in Figures					Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only				


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 403798
Earnest Money 8100
Time One Month

Name of Work:- R/R Damages on Serit to Bagoond road Km 0/00 to 7/00(SH:- C/O R/Wall at RD 4/660 to 4/675)

Sub-Head and items of works.

Sr.No.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	55.50	Per Cubic Meter	379.90	21084.00	Rupees Twenty One Thousand Eighty Four and Paise Zero Only
2	71.04	Per Cubic Meter	5140.40	365174.00	Rupees Three Lakhs Sixty Five Thousand One Hundred Seventy Four and Paise Zero Only
3	26.00	Each	371.75	9666.00	Rupees Nine Thousand Six Hundred Sixty Six and Paise Zero Only
4	5.70	Per Cubic Meter	1381.34	7874.00	Rupees Seven Thousand Eight Hundred Seventy Four and Paise Zero Only
Total in Figures				403798.00	
Quoted Rate in Figures			Select	0.00	
Quoted Rate in Words			Zero and Paise Zero Only		


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 275938
Earnest Money 5600
Time One Month

Name of Work:- R/R Damages on Seri Bagoond road Km. 0/00 to 7/00 (SH:- C/O RWall at RD 2/920 to 2/932)
Sr.No.

Sub-Head and Items of works.

UNIT PRICE AND DETAILS OF WORKS.						
		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	33.36	Per Cubic Meter	379.90	12673.00	Rupees Twelve Thousand Six Hundred Seventy Three and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10, (one cement, five sand, ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	47.35	Per Cubic Meter	5140.40	243398.00	Rupees Two Lakhs Forty Three Thousand Three Hundred Ninety Eight and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment/wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	20.00	Each	371.75	7435.00	Rupees Seven Thousand Four Hundred Thirty Five and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204,3.8 or as per direction of engineer in charge including carriage of materials within in all lead and lifts and other incidentals.	9.00	Per Cubic Meter	1381.34	12432.00	Rupees Twelve Thousand Four Hundred Thirty Two and Paise Zero Only
Total In Figures					275938.00	
Quoted Rate In Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 250865
Earnest Money 5100
Time One Month

Name of Work:- R/R Damages on Seri Bagoond road Km. 0/00 to 7/00 (SH:- C/O R/Wall at RD 2/945 to 2/960)

Sub-Head and items of works.

Sr.No.		No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	19.50	Per Cubic Meter	379.90	7408.00	Rupees Seven Thousand Four Hundred Eight and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Noimimal mix 1:5:10. (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	42.74	Per Cubic Meter	5140.40	219701.00	Rupees Two Lakhs Nineteen Thousand Seven Hundred One and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	26.00	Each	371.75	9666.00	Rupees Nine Thousand Six Hundred Sixty Six and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	10.20	Per Cubic Meter	1381.34	14090.00	Rupees Fourteen Thousand Ninety and Paise Zero Only
Total in Figures					250865.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 233023
Earnest Money 4700
Time One Month

Name of Work:- R/R Damages on Seri Bagoond road Km. 0/00 to 7/00 (SH:- C/O R/Wall at RD 3/280 to 3/289)

Sr.No.		Sub-Head and items of works.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1		Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.		28.96	Per Cubic Meter	379.90	11002.00	Rupees Eleven Thousand Two and Paise Zero Only
2		Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Noimimal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.		38.28	Per Cubic Meter	5140.40	196775.00	Rupees One Lakh Ninety Six Thousand Seven Hundred Seventy Five and Paise Zero Only
3		Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.		15.00	Each	371.75	5576.00	Rupees Five Thousand Five Hundred Seventy Six and Paise Zero Only
4		Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.		14.24	Per Cubic Meter	1381.34	19670.00	Rupees Nineteen Thousand Six Hundred Seventy and Paise Zero Only
Total in Figures							233023.00	
Quoted Rate in Figures					Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only				


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

409554
9200
One Month

Name of Work:- R/R Damages on Seri to Bagoond road Km 0/00 to 7/00(SH:- C/O R/Wall at RD 6/435 to 6/446)						
Sub-Head and Items of works.						
Sr.No.		No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	44.99	Per Cubic Meter	379.90	17092.00	Rupees Seventeen Thousand Ninety Two and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Noimnal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	71.47	Per Cubic Meter	5140.40	367384.00	Rupees Three Lakhs Sixty Seven Thousand Three Hundred Eighty Four and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment/wing wall/return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(v):20 (1h) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	18.00	Each	371.75	6692.00	Rupees Six Thousand Six Hundred Ninety Two and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	13.31	Per Cubic Meter	1381.34	18386.00	Rupees Eighteen Thousand Three Hundred Eighty Six and Paise Zero Only
Total in Figures					409554.00	
Quoted Rate in Figures				Select	0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Scheduled Quantity

Estimated Cost 426131
Earnest Money 8600
Time One Month

Name of Work:- R/R Damages on Rashog Deyom road 0/0 to 9/00 (SH:- C/O R/Wall at RD 3/745 to 3/758)

Sr.No.	Sub-Head and Items of works.	Qty.	Rate		Unit.	Amount.
			In Figure	In Words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	29.4			Per Cubic meter	
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	70.85			Per Cubic meter	
3	Providing weep holes in brick masonry/stone. masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	22			Each	
4	Back filling behind abutment wing wall, retaining wall , Breast Wall & Return Wall complete as per drawing & technical clause 1204.3.8 Granular materials. As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	10.92			Per Cubic Meter	
Total :-						

Executive Engineer,
Karsog Division,
HPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 425112
Earnest Money 8600
Time One Month

Name of Work:-R/R Damges on Mahog to Gawala road Km. 10/500 to 19/00(SH:- Removal of slips at various RDs)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	3363.23	Per Cubic Meter	126.40	425112.00	Rupees Four Lakhs Twenty Five Thousand One Hundred Twelve and Paise Zero Only
Total in Figures					425112.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 251142
Earnest Money 5100
Time One Month

Name of Work:- R/R Damages on Kotlu to Katanda road Km. 0/00 to 19/00 (SH:- C/O R/Wall at RD 14/780 to 14/792) Kotlu Side

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	28.80	Per Cubic Meter	379.90	10941.00	Rupees Ten Thousand Nine Hundred Forty One and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 Nominal mix 1:5:10, (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	42.18	Per Cubic Meter	5140.40	216822.00	Rupees Two Lakhs Sixteen Thousand Eight Hundred Twenty Two and Paise Zero Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204,3,8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	12.48	Per Cubic Meter	1277.55	15944.00	Rupees Fifteen Thousand Nine Hundred Forty Four and Paise Zero Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	20.00	Each	371.75	7435.00	Rupees Seven Thousand Four Hundred Thirty Five and Paise Zero Only
Total in Figures					251142.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 186200
Earnest Money 3800
Time 49 Days

Name of Work:- R/R Damages on various road under Karsog Sub Division (SH:- Hiring of Tipper for disposal/Carriage of Material)						
Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes including
1	Hiring of Tipper on daily wages basis for carriage of material i.e aggregate, stone, mud etc. upto any leads and lifts and as per direction of Engineer-in-charge to Tipper should work 8 hours daily. Any loss of public property and accident etc. The contractor is fully responsible during the execution of work the fuel and operation staff for the tipper will be provided by the owner. The repair charges of machinery during the execution of work will be by the owner. The useful material shall be stacked along the road side and as per direction of Engineer-in-charge with in all lead and lifts and other incidentals.	49.00	Per Day	3800.00	186200.00	Rupees One Lakh Eighty Six Thousand Two Hundred and Paise Zero Only
Total in Figures					186200.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 476797
Earnest Money 9600
Time One Month

Name of Work:- R/R Damages on various road in Kelodhar Section under Karsog Sub Division (SH:- Removal of slips on various RD)						
Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	3772.13	Per Cubic Meter	126.40	476797.00	Rupees Four Lakhs Seventy Six Thousand Seven Hundred Ninety Seven and Paise Zero Only
Total in Figures					476797.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

D.N.I.T / SCHEDULE OF QUANTITY

Estimated Cost Rs :-98800/-
Earnest money:-2000/-
Time :- 26 Days

Name of Work :- R.R. Damages on Chauridhar Kotlu road Km 00/0 to 8/0 (SH.:- Hiring of Tipper for disposal/carriage of Material)

S.No.	Description of Item.	Qty.	Rate.		Unit.	Amount
			In figure	In Words		
1.	Hiring of Tipper on daily wages basis for carriage of materials le. Aggregate, stone, mud etc. up to any leads and lifts and as per direction of Engineer-in-Charge to Tipper should work 8 Hours daily. Any loss of public property and accident etc. The contractor is fully responsible during the execution of work the fuel and operation staff for the Tipper will be provided by the owner. The repair charges of machinery during the execution of work will be Borne by the owner. The useful material shall be stacked along the road side and as per the direction of Engineer-in-Charge.	26 Days			Per day.	
	Total					


Executive Engineer
 Karsog Division
 HPPWD Karsog

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

298813
6000
One Month

Sub-Head and items of works.

Sr.No.		No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	31.50	Per Cubic Meter	379.90	11967.00	Rupees Eleven Thousand Nine Hundred Sixty Seven and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	52.39	Per Cubic Meter	5140.40	269306.00	Rupees Two Lakhs Sixty Nine Thousand Three Hundred Six and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	26.00	Each	371.75	9666.00	Rupees Nine Thousand Six Hundred Sixty Six and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals.	5.70	Per Cubic Meter	1381.34	7874.00	Rupees Seven Thousand Eight Hundred Seventy Four and Paise Zero Only
Total in Figures					298813.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

388409
7800
One Month

Name of Work:- R/R Damages on Thakurthana to Delag road Km. 0/00 to 7/100 (SH:- C/O RWall at RD 1/915 to 1/930)

Sub-Head and Items of works.

Sr.No.		No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	59.40	Per Cubic Meter	379.90	22566.00	Rupees Twenty Two Thousand Five Hundred Sixty Six and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	68.00	Per Cubic Meter	5140.40	349547.00	Rupees Three Lakhs Forty Nine Thousand Five Hundred Forty Seven and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	26.00	Each	371.75	9666.00	Rupees Nine Thousand Six Hundred Sixty Six and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials within in all lead and lifts and other incidentals.	4.80	Per Cubic Meter	1381.34	6630.00	Rupees Six Thousand Six Hundred Thirty and Paise Zero Only
Total in Figures					388409.00	
Quoted Rate In Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 88094
Earnest Money 1800
Time One Month

Name of Work:- R/R Damages on Sorta to Badar road Km. 0/00 to 27/00 (SH:- Removal of land slips at various RDs)						
Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	696.95	Per Cubic Meter	126.40	88094.00	Rupees Eighty Eight Thousand Ninety Four and Paise Zero Only
Total in Figures					88094.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 100981
Earnest Money 2100
Time One Month

Name of Work:- R/R Damages on ~~asat~~ Sandhol Thandapani road km. 0/00 to 2/600 (SH:- Removal of land slips at various reaches in Km. 0/00 to 2/600)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	798.90	Per Cubic Meter	126.40	100981.00	Rupees One Lakh Nine Hundred Eighty One and Paise Zero Only
Total in Figures					100981.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words		Zero and Paise Zero Only				


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

SCHEDULE OF QUANTITY

Estimated Cost
Earnest Money
Time

150607
3100
One Month

Name of work : - Repair of Link road Shill to village Khanaloo Km 0/00 to 3/00 (SH :- C/O unlined surface drain and maintenance of earthen shoulders a & removal of slips at various RD'S)in Km 0/00 to 0/255).SDF2022/589

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified time grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	735.00			Per Running Meter	
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1797.00			Per Square Meter	
3	Removal of land slide slip clearance.-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	742.80			Per Cubic Meter	
	Total Amount					

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

D.N.I.T / SCHEDULE OF QUANTITY

Name of Work :- R.R. Damages on Kelodhar Saini road Km 00/0 to 19/0 (SH.:- Hiring of Tipper for disposal/ carriage of Material)
S.No. Description of Item.

Estimated Cost Rs :-98800/-
Earnest money:-2000/-
Time :- 26 Days

S.No.	Description of Item.	Qty.	Rate.		Unit.	Amount
			In figure	In Words		
1.	Hiring of Tipper on daily wages basis for carriage of materials le. Aggregate, stone, mud etc. up to any leads and lifts and as per direction of Engineer-in-Charge to Tipper should work 8 Hours daily. Any loss of public property and accident etc. The contractor is fully responsible during the execution of work the fuel and operation staff for the Tipper will be provided by the owner. The repair charges of machinery during the execution of work will be Borne by the owner. The useful material shall be stacked along the road side and as per the direction of Engineer-in-Charge.	26 Days			Per day.	
Total						


Executive Engineer
Karsog Division
HPPWD Karsog

Percentage Schedule Of Quantity

Estimated Cost 499568
Earnest Money 10000
Time One Month

Name of Work:- R/R Damages on Thakurharna to Delag road Km. 0/00 to 7/100 (SH:- C/O R/Wall at RD 3/220 to 3/240) 3/245 to 3/265

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	74.00	Per Cubic Meter	379.90	28113.00	Rupees Twenty Eight Thousand One Hundred Thirteen and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	89.98	Per Cubic Meter	5140.40	462533.00	Rupees Four Lakhs Sixty Two Thousand Five Hundred Thirty Three and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	24.00	Each	371.75	8922.00	Rupees Eight Thousand Nine Hundred Twenty Two and Paise Zero Only
Total in Figures					499568.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 98289
Earnest Money 2000
Time One Month

Name of Work:-R/R Damges on Ralla to Saryogl road Km. 0/00 to 2/500(SH):- Removal of slips at various RDs)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	715.35	Per Cubic Meter	137.40	98289.00	Rupees Ninety Eight Thousand Two Hundred Eighty Nine and Paise Zero Only
Total In Figures					98289.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

SCHEDULE OF QUANTITY

Estimated Cost 423529
Earnest Money 8500
Time One Month

Name of Work:- C/O Link road from Karsog to Dachhain road Km. 0/00 to 2/030 (SH:- C/O R/Wall at RD 0/710 to 0/718)

Sr. No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			In Figure	in words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	36.00			Per Cubic Meter	
2	Providing and laying concrete for pain/reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	73.94			Per Cubic Meter	
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	16.32			Per Cubic Meter	
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1 (v):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	24.00			Each	
	Total Amount					


Executive Engineer,
Karsog Division,
APPWD, Karsog.

D.N.I.T / SCHEDULE OF QUANTITY

Name of Work :- R.R. Damages on Seri Shout Road Km 0/00 to 19/00 (SH.- Hiring of air Compressor for ROFD, Black spots etc.)

Estimated Cost Rs :- 98952/-
Earnest money:- 2000/-
Time :- 21 days

S.No.	Sub- Head and items of work.	Qty.	Rate		Unit.	Amount.
			In Figure	In Words.		
1.	Hiring of air compressor with tractor and jack hammer for hole cutting in all kind of soil fuel ,oil lubricants and wages of operating staff, any repair during operation and shifting of machinery from on place to other, required location will be carried out by the owner on this own risk and cost .Actually working hours will be deployed at any location as desired by the Engineer-in charge.	21 Days			Per Days	
	Total :-					


Executive Engineer
Karsog Division
H.P.P.W.D Karsog

Schedule of Quantity

Estimated Cost 485077
 Earnest Money 9800
 Time One month

NAME OF WORK :- R/R Damages of Chhitadharthu to Nag Sunani Mandir road Km. 0/00 to 1/500 (SH:- C/O B/Wall at RD 1/150 to 1/174)					
Sr.No.	Sub-Head and Items of works.	Qty.	Rate		Unit.
			In Figure	In words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	74.26			Per Cubic Meter
2	Providing and Laying cement concrete 1:5:10 (one Cement : five Sand : ten graded stone aggregate 40mm nominal size) and curing complete including cost of form work in retaining walls/ breast walls the size of plumb shall be 150mm to 300mm as per HPPWD specification as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	85.84			Per Cubic meter
3	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall, return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	42.00			Each
Total :-					


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Schedule of Quantity

Carthage

Estimated Cost
Earnest Money

464753
9300

Time

One month

NAME OF WORK :- ~~R/R Damages on~~ Chithadharthu to Nag Sunani Mandir road Km. 0/00 to 1/500 (SH:- C/O B/Wall at RD 1/235 to 1/258)

R/R Damages on

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	71.16			Per Cubic Meter	
2	Providing and Laying cement concrete 1:5:10 (one Cement : five Sand : ten graded stone aggregate 40mm nominal size) and curing complete including cost of form work in retaining walls/ breast walls the size of plumb shall be 150mm to 300mm as per HPPWD specification as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	82.26			Per Cubic meter	
3	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall, return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	40.00			Each	
Total :-						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.



Schedule of Quantity

Substructure

Estimated Cost
Earnest Money

481966
9700

Three Months one month

NAME OF WORK :- R/B Damages on Chhithadharthu to Nag Sunani Mandir road Km. 0/00 to 1/500 (SH:- C/O R/Wall at RD 1/450 to 1/468)

R/B Damages on

Sub-Head and items of works.

Sr.No.		Qty.	Rate		Unit.	Amount
			In Figure	in words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	39.69			Per Cubic Meter	
2	Providing and Laying cement concrete 1:5:10 (one Cement : five Sand : ten graded stone aggregate 40mm nominal size) and curing complete including cost of form work in retaining walls/ breast walls the size of plum shall be 150mm to 300mm as per HPPWD specification as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	84.77			Per Cubic Meter	
3	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall, return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	42.00			Each	
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	12.15			Per Cubic Meter	
Total :-						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Schedule of Quantity

Name of Work: R/R Damages of Chithadharthu to Nag Sunani Mandir road Km. 0/0 to 1/500 (SH: C/O B/Wall at RD 1/280 to 1/300)

Estimated Cost
Earnest Money
Time
Mmasy Deposait

404584
8100
One month

Sr.No.	Sub-Head and Items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	61.88			Per Cubic Meter	
2	Providing and Laying cement concrete 1:5:10 (one Cement : five Sand : ten graded stone aggregate 40mm nominal size) and curing complete including cost of form work in retaining walls/ breast walls the size of plum shall be 150mm to 300mm as per HPPWD specification as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	71.53			Per Cubic meter	
3	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall, return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614.709.1204.3.7 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	36.00			Each	
Total :-						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Scheduled Quantity

Estimated Cost 248246
 Earnest Money 5000
 Time One Month

Name of Work:- R/R Damages on Katanda to Pokhi Road km 0/0 to 10/00 (SH:- C/O R/Wall at RD 9/510 to 9/521)

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	15.29			Per Cubic meter	
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Noimnal mix 1:5:10. (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	41.78			Per Cubic meter	
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	18.00			Each	
4	Back filling behind abutment wing wall, retaining wall , Breast Wall & Return Wall complete as per drawing & technical clause 1204.3.8 Granular materials. As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	11.44			Per Cubic Meter	
Total :-						


Executive Engineer,
 Karsog Division,
 APPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

136288
2800
One Month

Name of Work:- R/R Damages on Kelodhar to Saini road Km. 0/00 to 19/00 (SH:- C/O B/Wall at RD 15/030 to 15/038)

Sub-Head and Items of works.

Sr.No.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Earth work in excavation by mechanical means(hydraulic excavator)/manual means in foundation trenches of drain (not exceeding 1.5 meter in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, upto any lift and lead, including gating out the excavated soil and disposal of surplus excavated soil as directed, as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	6.48	Per Cubic Meter	204.30	1324.00	Rupees One Thousand Three Hundred Twenty Four and Paise Zero Only
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	7.98	Per Cubic Meter	379.90	3032.00	Rupees Three Thousand Thirty Two and Paise Zero Only
3	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10. (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	25.20	Per Cubic Meter	5140.40	129538.00	Rupees One Lakh Twenty Nine Thousand Five Hundred Thirty Eight and Paise Zero Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment/wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1 (v):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	10.00	Each	371.75	3718.00	Rupees Three Thousand Seven Hundred Eighteen and Paise Zero Only
Total in Figures					136288.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


Executive Engineer,
Karsog Division,
HPMD, Karsog.

Schedule of quantity

Estimated Cost
Earnest Money
Time

471708
9400
One Month

Name of work : - R/R Damages on Sanarli to Karsog road Km. 0/00 3/330 (SH :- C/O unlined surface drain, maintenance of earthen shoulders in Km. 0/00 to 3/330)

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	3310.00			Per Running Meter	
2	Stripping excess soil from the shoulder surface to achive the approved level and compacting with plate compactor at OMC as per drawing and technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	4965.00			Per Square Meter	
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	4303.00			Per Square Meter	
	Total Amount					


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- Construction of Punni to Nawswar road Km. 0/00 to 3/00 (SH:- C/O R/Wall at RD 0/175 to 0/185)
Sub-Head and items of works.

Estimated Cost 328768
Earnest Money 6600
Time One Month

Sr.No.	Description	No. Or Qty.	Unit	Estimated Rate (Rs.)	Total Amount including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	11.30	Per Cubic Meter	379.90	4293.00	Rupees Four Thousand Two Hundred Ninety Three and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10. (one cement: five sand: ten graded stone aggregate and lifts and other incidentals as per direction of Engineer-in-Charge including carriage of materials within all lead lifts and other incidentals.	51.50	Per Cubic Meter	5140.40	264731.00	Rupees Two Lakhs Sixty Four Thousand Seven Hundred Thirty One and Paise Zero Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204,3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	42.40	Per Cubic Meter	1277.55	54168.00	Rupees Fifty Four Thousand One Hundred Sixty Eight and Paise Zero Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	15.00	Each	371.75	5576.00	Thousand Five Hundred Seventy Six and Paise Zero Only
Total in Figures					328768.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


Executive Engineer,
Karsog Division,
HPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- Construction of Punni to Nawswar road Km. 0/00 to 3/00 (SH:- C/O R/Wall at RD 0/165 to 0/175)

Sub-Head and items of works.

Estimated Cost 330287
Earnest Money 6700
Time One Month

Sr.No.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	15.30	Per Cubic Meter	379.90	5812.00	Rupees Five Thousand Eight Hundred Twelve and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	51.50	Per Cubic Meter	5140.40	264731.00	Rupees Two Lakhs Sixty Four Thousand Seven Hundred Thirty One and Paise Zero Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	42.40	Per Cubic Meter	1277.55	54168.00	Rupees Fifty Four Thousand One Hundred Sixty Eight
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	15.00	Each	371.75	5576.00	Rupees Five Thousand Five Hundred Seventy Six and Paise Zero Only
Total in Figures					330287.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


Executive Engineer,
Karsog Division,
HFPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 307005
Earnest Money 6200
Time One Month

Name of Work:- R/R Damages on various road under Kottu Section in Karsog Sub Division (SH:- Removal of slips at various RDs)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	2234.39	Per Cubic Meter	137.40	307005.00	Rupees Three Lakhs Seven Thousand Five and Paise Zero Only
Total in Figures					307005.00	
Quoted Rate In Figures			Select		0.00	
Quoted Rate In Words		Zero and Paise Zero Only				


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 98788
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Narenabail to Balna road Km. 0/00 to 3/00 (SH:- Removal of slips on various RD)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	781.55	Per Cubic Meter	126.40	98788.00	Rupees Ninety Eight Thousand Seven Hundred Eighty Eight and Paise Zero Only
Total in Figures					98788.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words			Select	Zero and Paise Zero Only		


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 95085
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Tangle to Kot road Km. 0/00 to 4/00 (SH:- Removal of slips on various RD)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other Incidentals.	692.03	Per Cubic Meter	137.40	95085.00	Rupees Ninety Five Thousand Eighty Five and Paise Zero Only
Total in Figures					95085.00	
Quoted Rate In Figures			Select		0.00	
Quoted Rate In Words			Zero and Paise Zero Only			


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Scheduled Quantity

Estimated Cost
Earnest Money
Time

215983
4400
One Month

Name of work : - R/R Damages on Chindi Pangna road km 0/00 to 12/480 (SH :- Removal of slips at various RD's).

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			In Figure	In words		
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1708.73			Per Cubic Meter	
	Total Amount					


 Executive Engineer,
 Karsog Division,
 HPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost Rs. 498302
Earnest Money cost Rs. 10000
Time One Month

Name of Work:- R/R Damges on Chindi to pangna road Km. 0/00 to 12/480 (SH :- C/O R/Wall at RD 5/780 to 5/791)

Sr.No.	Description Work	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes Including
1	Earth work in excavation by mechanical means(hydraulic excavator)/manual means in foundation trenches of drain (not exceeding 1.5 meter in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, life upto 1.5 m, including gaiting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	16.56	Per Cubic Meter	207.20	3431	Rupees Three Thousand Four Hundred Thirty One and Paise Twenty Three Only
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	26.29	Per Cubic Meter	208.15	5472	Rupees Five Thousand Four Hundred Seventy Two and Paise Twenty Six Only
3	Providing and laying concrete for pain/reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	89.49	Per Cubic Meter	5140.40	460014	Rupees Four Lakhs Sixty Thousand Fourteen and Paise Thirty Nine Only
4	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	21.00	Each	371.75	7807	Rupees Seven Thousand Eight Hundred Six and Paise Seventy Five Only
5	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	16.89	Per Cubic Meter	1277.55	21578	Rupees Twenty One Thousand Five Hundred Seventy Seven and Paise Eighty One Only
Total Amount In Figure					498302	
Quoted Rate in Figures			Select			0.00
Quoted Rate in Words			Zero and Paise Zero Only			


 Executive Engineer,
 Karsog Division,
 JKPMD, Karsog.

D.N.I.T / SCHEDULE OF QUANTITY

Name of Work :- R.R. Damages on Various Road under Pangna Sub Division (SH:- Hiring of Tipper for disposal/carriage of Material)

Estimated Cost Rs :-98800/-
 Earnest money:-2000/-
 Time :- 26 Days

S.No.	Description of Item.	Qty.	Rate.		Unit.	Amount
			In figure	In Words		
1.	Hiring of Tipper on daily wages basis for carriage of materials I.e. Aggregate, stone, mud etc. up to any leads and lifts and as per direction of Engineer-in-Charge to Tipper should work 8 Hours daily. Any loss of public property and accident etc. The contractor is fully responsible during the execution of work the fuel and operation staff for the Tipper will be provided by the owner. The repair charges of machinery during the execution of work will be Borne by the owner. The useful material shall be stacked along the road side and as per the direction of Engineer-in-Charge.	26 Days			Per day.	
Total						


 Executive Engineer
 Range Division (B & P)
 R.R. & P.D. K. S. K. S.

D.N.I.T / SCHEDULE OF QUANTITY

Name of Work :- R.R. Damages on Various Road under Karsog Sub Division (SH.:- Hiring of Tipper for disposal/carriage of Material)
Section Kotlu

Estimated Cost Rs :-98800/-
 Earnest money:-2000/-
 Time :- 26 Days

S.No.	Description of Item.	Qty.	Rate.		Unit.	Amount
			In figure	In Words		
1.	Hiring of Tipper on daily wages basis for carriage of materials Le. Aggregate, stone, mud etc. up to any leads and lifts and as per direction of Engineer-in-Charge to Tipper should work 8 Hours daily. Any loss of public property and accident etc. The contractor is fully responsible during the execution of work the fuel and operation staff for the Tipper will be provided by the owner. The repair charges of machinery during the execution of work will be Borne by the owner. The useful material shall be stacked along the road side and as per the direction of Engineer-in-Charge.	26 Days			Per day.	
Total						


 Executive Engineer
 Karsog Sub Division
 APT

D.N.I.T / SCHEDULE OF QUANTITY

Estimated Cost Rs :-98800/-
 Earnest money:-2000/-
 Time :- 26 Days

Name of Work :- R.R. Damages on Various Road under Karsog Sub Division (SH.:- Hiring of Tipper for disposal/carriage of Material)
Section Kotlu

S.No.	Description of Item.	Qty.	Rate.		Unit.	Amount
			In figure	In Words		
1.	Hiring of Tipper on daily wages basis for carriage of materials Le. Aggregate, stone, mud etc. up to any leads and lifts and as per direction of Engineer-in-Charge to Tipper should work 8 Hours daily. Any loss of public property and accident etc. The contractor is fully responsible during the execution of work the fuel and operation staff for the Tipper will be provided by the owner. The repair charges of machinery during the execution of work will be Borne by the owner. The useful material shall be stacked along the road side and as per the direction of Engineer-in-Charge.	26 Days			Per day.	
Total						


Executive Engineer,
 Karsog Division
 H.P.W.D. Karsog

D.N.I.T / SCHEDULE OF QUANTITY

Name of Work :- R.R. Damages on Various Road under Karsog Sub Division (Sh.:- Hiring of Tipper for disposal/ carriage of Material)
Section Kotlu

Estimated Cost Rs :-98800/-
 Earnest money:-2000/-
 Time :- 26 Days

S.No.	Description of Item.	Qty.	Rate.		Unit.	Amount
			In figure	In Words		
1.	Hiring of Tipper on daily wages basis for carriage of materials le. Aggregate, stone, mud etc. up to any leads and lifts and as per direction of Engineer-in-Charge to Tipper should work 8 Hours daily. Any loss of public property and accident etc. The contractor is fully responsible during the execution of work the fuel and operation staff for the Tipper will be provided by the owner. The repair charges of machinery during the execution of work will be Borne by the owner. The useful material shall be stacked along the road side and as per the direction of Engineer-in-Charge.	26 Days			Per day.	
	Total					


Executive Engineer
 Karsog Division
 R.P.W.D. Karsog

D.N.I.T / SCHEDULE OF QUANTITY

Name of Work :- R.R. Damages on Various Road under Karsog Sub Division (SH.:- Hiring of Tipper for disposal/carriage of Material)
Section Kotlu

Estimated Cost Rs :-98800/-
Earnest money:-2000/-
Time :- 26 Days

S.No.	Description of Item.	Qty.	Rate.		Unit.	Amount
			In figure	In Words		
1.	Hiring of Tipper on daily wages basis for carriage of materials Le. Aggregate, stone, mud etc. up to any leads and lifts and as per direction of Engineer-in-Charge to Tipper should work 8 Hours daily. Any loss of public property and accident etc. The contractor is fully responsible during the execution of work the fuel and operation staff for the Tipper will be provided by the owner. The repair charges of machinery during the execution of work will be Borne by the owner. The useful material shall be stacked along the road side and as per the direction of Engineer-in-Charge.	26 Days			Per day.	
Total						


Executive Engineer
Karsog Division
R.P.W.D.

D.N.I.T.

Estimated Cost Rs.	254000
Earnest Money	5100
Time:-	One Month

Name of Work :- R/R Damages on Bhanthal Punni road Km. 0/00 to 4/00(Sub Head:- C/O B/wall at RD. 0/900 to 0/915)

Sr. No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount
			In Fig	In Words		
1	Excavation in soil in hilly area by mechanical mean including cutting and trimming of side slope and disposing of excavated earth with all lift upto any mtrs and any lead upto any mtrs as per technical specification clause 1603.1 or as per direction of engineer in charge including carriage of materials with in all leads, lifts and other incidentals.or as per direction of engineer in charge including carriage of materials with in all leads, lifts and other incidentals.	31.95	199.80	Ruppes One Hundred Ninety Nine and Paise Eighty Only	Per Cubic Meter	6384.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 Metre dressing of side and bottom and backfilling in trenches with excavated suitable materials. As per direction of Engineer-in Charge including carriage of material within all leads and lifts and other incidentals.	10.50	454.50	Ruppes Four Hundred Fifty Four and Paise Fifty Only	Per Cubic Meter	4772.00
3	Providing and laying concrete for pain/reinforced concert in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 nominal mix 1:6:12 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	4.75	4525.50	Ruppes Four Thousand Five Hundred Twenty Five and Paise Fifty Only	Per Cubic Meter	21496.00
4	Stone masonry in cement mortar for sub structure complete as per drawing and technical specifications clause 702, 704, 1202 1204 & in cement mortar 1:6 (1 cement: 6 sand) R/R masonry within all leads and lifts and other incidentals.	31.73	4619.60	Ruppes Four Thousand Six Hundred Nineteen and Paise Sixty Only	Per Cubic Meter	146580.00
5	Construction of dry Rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704 704.6& 1302.5 within all leads and lifts and other incidentals	23.24	3217.20	Ruppes Three Thousand Two Hundred Seventeen and Paise Twenty Only	Per Cubic Meter	74768.00
	Total:-					254000.00

DNIT checked and approved for Rs. 254000 /-only
S.No. 325 For the year 2022-23

Executive Engineer,
Karsog Division,
HBW/D, Karsog

Percentage Schedule Of Quantity

Name of Work:- R/R damages on Tattapani to Shakra road km 0/00 to 10/00 and Shakra Parlog upto village Bindla km 0/00 to 6/250 (SH:- Removal of land slide slip at various RD's)

Estimated Cost 489955
Earnest Money 9800
Time One Month

Sr.No	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST in Rs. p	Toatal Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 161 1 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	3876.23	Per Cubic Meter	126.40	489955	Rupees Four Lakhs Eighty Nine Thousand Nine Hundred Fifty Five and Paise Forty Seven Only
Total in Figures					489955	
Quoted Rate in Figures			Select		0.05	
Quoted Rate in Words			Zero and Paise Zero Only			


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Schedule Quantity

Name of Work:- C/O Ropa to Phegla road km 0/00 to 1/600 (SH:- ROFD Ropa to Phegla in Km 0/ 495 to 1/150).

Estimated Cost 415120
Earnest Money 8400
Time One Month

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 167.83 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 50350/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1198.80			Per Cubic Meter	
Total Amount						0


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Bill Of Quantity

Name of Work:- R/R Damages on Jach To Sarhi Road 0/00 to 5/00 (SH :- C/O P.C.C R/Wall at Rd 0/955 to 0/968.50)

Estimated Cost Rs. 480756
Earnest Money cost Rs. 9700
Time One Month

Sr.No.	Description Work	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Excavation in soil in hilly area by mechanical mean including cutting and trimming of side slope and disposing of excavated earth with lift upto 1.50 mtr and a lead upto 20 mtr as per technical specification clause 1603.1 as per direction of engineer in charge with in all lead and lift As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	14.17	Per Cubic Meter	207.20	2936	Rupees Two Thousand Nine Hundred Thirty Six and Paise Two Only
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	25.24	Per Cubic Meter	208.15	5254	Rupees Five Thousand Two Hundred Fifty Three and Paise Seventy Only
3	Providing and laying concrete for pain/reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	88.15	Per Cubic Meter	5140.40	453126	Rupees Four Lakhs Fifty Three Thousand One Hundred Twenty Six and Paise Twenty Six Only
4	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	21.00	Each	371.75	7807	Rupees Seven Thousand Eight Hundred Six and Paise Seventy Five Only
5	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	9.11	Per Cubic Meter	1277.00	11633	Rupees Eleven Thousand Six Hundred Thirty Three and Paise Forty Seven Only
	Total Amount In Figure				480756	
	Quoted Rate In Figure					
	Quoted Rate In Words					


Executive Engineer,
Karsog Division,
M.P.W.D., Karsog.

Scheduled Quantity

Estimated Cost
Earnest Money
Time

405022
8200
One Month

Name of Work:- R/R Damages on Karsog to Kanda road Km. 0/00 to 8/500 (SH:- C/O R/Wall at RD 3/534 to 3/550)

Sr. No.	Sub-Head and Items of works.	Qty.	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mts depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	30.16			Per Cubic Meter	
2	Providing and laying concrete for plain/reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	3.60			Per Cubic Meter	
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clause 702, 704, 1202 and 1204 in cement mortar 1:6 (one cement : six sand) R/R masonry with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	65.88			Per Cubic Meter	
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204, 3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	20.16			Per Cubic Meter	
5	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	20.00			Per Cubic Meter	
	Total Amount					


 Executive Engineer,
 Karsog Division,
 HPWD, Karsog.

Scheduled Quantity

Name of Work:- R/R Damages on Kumru to Khadainn road Km. 0/00 to 5/00 (SH:- C/O R/Wall at RD 0/235 to 0/245)

Estimated Cost 498503
Earnest Money 10000
Time One Month

Sr. No.	Sub-Head and items of works.	Qty.	Rate		Unit	Amount
			in Figure	in words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	32.250			Per Cubic Meter	
2	Providing and laying concrete for pain/reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	86.50			Per Cubic Meter	
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	48.00			Each	
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	18.60			Per Cubic Meter	
Total Amount						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.