



OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2023- 6134
To


Dated:- 28 ⁰⁹/₂₃

✓ The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.

Subject :- Regarding publication of Tender on departmental site.

Enclosed please find herewith the copies of Notice Inviting Tender for the loading on departmental web-site before 30.09.2023 as per notification issued by the Pr. Secy.(PW) to the Govt. of HP vide letter No. PBW(B)A(3)1/2020 dated 16th July, 2021. It is further intimated that all the works mentioned are of urgent nature.

Encl:- As above.


**Executive Engineer,
B&R Division,
HP PWD Karsog**



**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division, HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **09.10.2023 upto 11.00 AM** and shall be opened on the same day at **12:00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 07.10.2023** for which the application should reach in this office **upto 1.00 PM 07.10.2023**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Kotlu to Katanda road km. 0/00 to 19/00 (SH:- C/o R/wall at RD 14/898 to 14/925) Kotlu Side	4,28,247/-	8,600/-	One month	350/-
2	R/R damages on Chouridhar Kotlu road km. 0/00 to 7/00 (SH:- C/o R/wall at RD 0/960 to 0/967)	3,69,303/-	7,400/-	One month	350/-
3	R/ R damages on Shakelar to Tuman road Km. 0/00 to 2/700 (SH:- Removal of slips at various RDs)	4,72,068/-	9,500/-	One month	350/-
4	R/R damages on various road under Kotlu Section in Karsog Sub-Division (SH:- Removal of slips at various RDs)	2,88,541/-	5,800/-	One month	350/-
5	R/ R damages on Nehal to Cheveri road Km. 0/00 to 2/700 (SH:- Removal of slips at various RDs)	1,41,360/-	2,900/-	One month	350/-
6	R/R damages on Chauridhar Kotlu road Km. 0/00 to 7/00 (SH:- C/o R/wall at RD 0/967 to 0/974)	3,72,813/-	7,500/-	One month	350/-
7	R/R damages on Chauridhar Kotlu road Km. 0/00 to 7/00 (SH:- C/o R/wall at RD 3/425 to 3/435)	3,70,155/-	7,500/-	One month	350/-
8	R/R damages on Chauridhar Kotlu road Km. 0/00 to 7/00 (SH:- C/o R/wall at RD 3/390 to 3/400)	2,84,975/-	5,700/-	One month	350/-

9	R/R damages on Kelodhar Sainj road Km. 0/00 to 19/00 (SH:- C/o R/wall at RD 12/090 to 12/098)	3,54,085/-	7,100/-	One month	350/-
10	R/R damages on Kenchimod to Mashog road Km. 0/00 to 5/500, Jachh Sarahi road Km. 0/00 to 5/00 and Pangna Majhangan road Km. 0/00 to 8/00 (SH:- Removal of land slides slips) Under Pangna Section	4,75,923/-	9,600/-	One month	350/-
11	R/R damages on Pangna Majhangan road Km. 0/00 to 8/00 (SH:- C/o PCC R/wall at RD 6/445 to 6/660)	3,78,383/-	7,600/-	One month	350/-
12	R/R damages on Kenchimod to Mashog road Km. 0/00 to 3/500, (SH:- C/o PCC R/wall at RD 0/605 to 0/610.50)	4,66,682/-	9,400/-	One month	350/-
13	Construction of Chindi Dachhain road Km. 0/00 to 8/435 (SH:- Widening of road in Km. 4/520 to 4/560, 4/845 to 4/880, 5/185 to 5/215, 5/275 to 5/295, 5/310 to 5/335, 5/540 to 5/560 and 5/640 to 5/690)	4,61,187/-	9,300/-	One month	350/-
14	R/R damages on Gharatha to Basol road km. 0/00 to 5/00 (SH:-Removal of slips at various RDs)	2,42,753/-	4,900/-	One month	350/-
15	R/R damages on Kenchi Mod to Mashog road km. 0/00 to 3/500 (SH:- C/o PCC R/wall at RD 0/610.50 to 0/616)	4,67,138/-	9,800/-	One month	350/-
16	R/R damages on Kenchi Mod to Mashog road km. 0/00 to 3/500 (SH:- C/o PCC R/wall at RD 1/720 ton 1/735)	4,85,299/-	9,800/-	One month	350/-
17	R/R damages on Chindi Bakhras road (SH:- Removal of slips at various reaches in km. 0/00 to 1/500)	1,18,756/-	2,400/-	One month	350/-
18	R/R damages on Kandi Dharkandlu road km. 0/00 to 6/150 (C/o R/wall at RD 4/450 to 4/464)	4,93,551/-	9,900/-	One month	350/-
19	R/R damages on Kotlu Nanj road km. 0/00 to 6/120 (Removal of slips at various RDs)	1,63,130/-	3,300/-	One month	350/-
20	R/R damages on Shakwa to Sarandi road Km. 0/0 to 6/0 (SH:- C/o unlined drain & Removal of slips at various RDs)	1,61,220/-	3,300/-	One month	350/-
21	R/R damages on Choldhar to Panaut Dehra road km. 0/00 to 2/700 (SH:- C/o unlined drain, maintenance of berm & removal of slips at various RDs)	1,83,752/-	3,700/-	One month	350/-
22	R/R damages on Nehra Bhadarnu road Km. 0/00 to 2/700 (SH:- C/o B/wall at RD 1/140 to 1/158)	4,05,215/-	8,200/-	One month	350/-
23	R/R damages on Chauridhar Kotlu road Km. 0/00 to 7/00 (SH:- C/o R/wall at RD 0/974 to 0/981)	3,69,571/-	7,400/-	One month	350/-
24	R/R damages on Shog to Majhas Chaloni road Km. 0/00 to 3/00 (SH: Removal of slips in various RDs)	1,38,654/-	2,800/-	One month	350/-
25	R/R damages on Mamail Mehandi road Km. 0/00 to 19/00 (SH: Removal of slips in various RDs)	2,33,974/-	4,700/-	One month	350/-
26	R/R damages on Katanda Pokhi road km. 0/00 to 10/00 (SH:- C/o R/wall at RD 8/630 to 8/642)	2,84,554/-	5,700/-	One month	350/-
27	R/R damages on Katanda to Pokhi road Km. 0/00 to 10/00 (SH:- C/o R/wall at RD 6/750 to 6/765)	4,08,225/-	8,200/-	One month	350/-
28	R/R damages on Katanda to Pokhi road Km. 0/00 to 10/00 (SH:- C/o R/wall at RD 4/555 to 4/570)	4,60,968/-	9,300/-	One month	350/-

29	R/R damages on Seri Shout road Km. 0/00 to 16/00 (SH:- C/o R/wall at RD 11/640 to 11/652)	4,28,095/-	8,600/-	One month	350/-
30	R/R damages on various road under Kotlu Section in Karsog Sub-Division (SH:- Removal of slips at various RDs)	4,52,110/-	9,100/-	One month	350/-
31	R/R damages on various road under Karsog Sub-Division (SH:- Removal of slips at various RDs) in Katanda Section	4,61,434/-	9,300/-	One month	350/-
32	R/R damages on Kotlu Katanda road km. 0/00 to 19/00 (SH:- C/o R/wall at RD 14/870 to 14/883) Kotlu Side	3,24,642/-	6,500/-	One month	350/-
33	R/R damages on Shakwa to Sarandi road Km. 0/00 to 6/00 (SH;- Removal of slips in various RDs)	4,56,558/-	9,200/-	One month	350/-
34	R/R damages on Kuther Rashog Deyom road km. 0/00 to 9/00 (SH:- removal of slips in various RDs)	4,73,450/-	9,500/-	One month	350/-
35	R/R damages on Thakurthana to Delag road km. 0/00 to 7/100 (SH:- C/o R/wall at RD 1/780 to 1/787)	2,70,523/-	5,500/-	One month	350/-
36	R/R damages on Chanyana Jassal road km. 0/00 to 2/200 (SH:-C/o R/wall at RD 1/547 to 1/555)	1,79,102/-	3,600/-	One month	350/-
37	R/R damages on Paralakashot to Sahal road (SH:- Removal of land slips at various reaches in Km. 0/00 to 1/500)	1,07,317/-	2,200/-	One month	350/-
38	R/R damages on Kelodhar to Chhatri road Km. 0/00 to 19/00 (SH;- C/o R/wall at RD 6/110 to 6/122)	3,38,549/-	6,800/-	One month	350/-
39	R/R damages on Mamail to Mehandi road Km. 0/00 to 19/00 (SH:- C/o R/wall at RD 12/360 to 12/370)	1,66,605/-	3,400/-	One month	350/-
40	R/R damages on Thakurthana to Delag road km. 0/00 to 7/100 (SH:C/o R/wall at RD 1/795 to 1/811)	4,05,445/-	8,200/-	One month	350/-
41	R/R damages on Mahog to Gawala road km. 0/00 to 19/00 (SH:- C/o R/wall at Rd 14/495 to 14/510)	4,09,885/-	8,200/-	One month	350/-
42	R/R damages on Mahog to Gawala road km. 0/00 to 19/00 (SH:- C/o R/wall at Rd 12/525 to 12/538)	3,75,714/-	7,600/-	One month	350/-
43	R/R damages on Mamail Mehandi road km. 0/00 to 19/00 (SH:- C/o R/wall at Rd 17/140 to 17/155)	3,50,895/-	7,100/-	One month	350/-
44	R/R damages on Mamail Mehandi road km. 0/00 to 19/00 (SH:- C/o R/wall at Rd 13/480 to 13/495)	3,44,809/-	6,900/-	One month	350/-
45	R/R damages on Mamail Mehandi road km. 0/00 to 19/00 (SH:- C/o R/wall at Rd 3/620 to 3/648)	4,93,430/-	3,400/-	One month	350/-

46	R/R damages on Kelodhar to Sainj road Km. 0/00 to 19/00 (SH:- C/o R/wall at RD 12/075 to 12/085)	4,43,610/-	8,900/-	One month	350/-
47	R/R damages on various road under Karsog Sub-Division (SH:- Removal of slips, C/o unlined drain & maintenance of berm at various RDs)	3,59,916/-	7,200/-	One month	350/-
48	R/R damages on Karsog to Dachain road km. 0/00 to 2/030 (SH:- C/o R/wall at RD 0/020 to 0/032)	4,73,198/-	9,500/-	One month	350/-
49	R/R damages on Karsog to Dachain road km. 0/00 to 2/030 (SH:- C/o R/wall at RD 0/140 to 0/152)	2,53,950/-	5,100/-	One month	350/-
50	R/R damages on Sanarli Bathar road km. 0/00 to 3/00 (C/o unlined drain, maintenance of berm & removal of slips at various RDS)	2,68,274/-	5,400/-	One month	350/-

TERMS & CONDITIONS:-


1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.


Executive Engineer
B&R Division
HPPWD Karsog,
Distt. Mandi(HP)

No. PW-E-Tender-NIT/23- 6128-33

Dated:- 28.09.23

1. Copy to the Director , Information & Publications Department, HP Shimla for favour of publication in one Regional Newspaper and one National Newspaper.
2. Copy to the Superintending Engineer, 1st Circle, HP,PWD, Mandi for information please.
3. The Sub-Divisional Officer (Civil) Karsog, Tehsil Karsog Distt. Mandi HP.
4. The Block Development Officer Karsog , Tehsil Karsog Distt. Mandi HP.
5. All the Assistant Engineers, working under this Division.
6. Copy to Drawing & Account Branch.
7. Notice board of this office.


Executive Engineer,
B&R Division,
HP PWD Karsog

Percentage Schedule Of Quantity

Estimated Cost 428247
 Earnest Money 8600
 Time One Month

Name of Work:- R/R Damages on Koltu to Katanda road Km. 0/00 to 19/00 (SH:- C/O RWall at RD 14/898 to 14/925) Koltu Side)

Sub-Head and Items of works.

Sr.No.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	17.01	Per Cubic Meter	379.90	6462.00	Rupees Six Thousand Four Hundred Sixty Two and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	73.24	Per Cubic Meter	5140.40	376483.00	Rupees Three Lakhs Seventy Six Thousand Four Hundred Eighty Three and Paise Zero Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	26.73	Per Cubic Meter	1277.55	34149.00	Rupees Thirty Four Thousand One Hundred Forty Nine and Paise Zero Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	30.00	Each	371.75	11153.00	Rupees Eleven Thousand One Hundred Fifty Three and Paise Zero Only
Total In Figures					428247.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Chauridhar Kotlu road Km. 0/00 to 7/00 (SH.: C/O R/Wall at RD 0/960 to 0/967)
Sub-Head and items of works.

Estimated Cost 369303
 Earnest Money 7400
 Time One Month

Sr.No.	Description	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	16.62	Per Cubic Meter	379.90	6314.00	Rupees Six Thousand Three Hundred Fourteen and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	64.68	Per Cubic Meter	5140.40	332481.00	Rupees Three Lakhs Thirty Two Thousand Four Hundred Eighty One and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) Towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	20.00	Each	371.75	7435.00	Rupees Seven Thousand Four Hundred Thirty Five and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	18.06	Per Cubic Meter	1277.55	23073.00	Rupees Twenty Three Thousand Seventy Three and Paise Zero Only
Total in Figures					369303.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 472068
 Earnest Money 9500
 Time One Month

Name of Work: R/R Damages on Shakelar to Tuman road Km. 0/00 to 2700 (SH:- Removal of slips at various RDs)		Sub-Head and items of works.					
Sr.No.		No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words	
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals.	3435.72	Per Cubic Meter	137.40	472068.00	Rupees Four Lakhs Seventy Two Thousand Sixty Eight and Paise Zero Only	
Total in Figures					472068.00		
Quoted Rate in Figures			Select		0.00		
Quoted Rate in Words		Zero and Paise Zero Only					


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 288541
 Earnest Money 5800
 Time One Month

Name of Work:- R/R Damages on various road under Kottu Section in Karsog Sub Division (SH:- Removal of slips at various RDS)						
Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	2100.01	Per Cubic Meter	137.40	288541.00	Rupees Two Lakhs Eighty Eight Thousand Five Hundred Forty One and Paise Zero Only
Total in Figures					288541.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words					Zero and Paise Zero Only	


Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Scheduled Quantity

Estimated Cost 141360
 Earnest Money 2900
 Time One Month

Name of work : - R/R Damages on Nehal to Kurupad Km 0/00 to 2/00 (SH :- Removal of slips at various RD's).


Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			In Figure	in words		
1	Construction of unlined surface drain of average cross-section area 0.40 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	900.00			Per Running Meter	
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	2275.50			Per Square Meter	
3	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock/slips in all king of soil including excavation of saturated soil, boulder & rocky portion requiring wherever blasting and loading in tipper and disposal and disposal of unreserviceable materials upto a distance of 1000 mtrs and stacking of all useful/ serviceable materials and neatly dressing the surface etc.l as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	310.90			Per Cubic Meter	
Total Amount						


Executive Engineer,
 Karsog Division,
 APPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 372813
 Earnest Money 7500
 Time One Month


Name of Work:- R/R Damages on Chauridhar Kollu road Km. 0/00 to 7/00 (SH:- C/O R/Wall at RD 0/967 to 0/974)		Sub-Head and Items of works.					
Sr.No.		No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	16.62	Per Cubic Meter	379.90	6314.00	Rupees Six Thousand Three Hundred Fourteen and Paise Zero Only	
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Noimnal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	64.68	Per Cubic Meter	5140.40	332481.00	Rupees Three Lakhs Thirty Two Thousand Four Hundred Eighty One and Paise Zero Only	
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	28.00	Each	371.75	10409.00	Rupees Ten Thousand Four Hundred Nine and Paise Zero Only	
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	18.48	Per Cubic Meter	1277.55	23609.00	Rupees Twenty Three Thousand Six Hundred Nine and Paise Zero Only	
Total in Figures					372813.00		
Quoted Rate in Figures			Select		0.00		
Quoted Rate in Words		Zero and Paise Zero Only					


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 370155
 Earnest Money 7500
 Time One Month

Name of Work:- R/R Damages on Chauridhar Kollu road Km. 0/00 to 7/00 (SH:- C/O RWall at RD 3/425 to 3/435)							
Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305. 1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	23.90	Per Cubic Meter	379.90	9080.00	Rupees Nine Thousand Eighty and Paise Zero Only	
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	61.06	Per Cubic Meter	5140.40	313873.00	Rupees Three Lakhs Thirteen Thousand Eight Hundred Seventy Three and Paise Zero Only	
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge Including carriage of materials within all leads and lifts and other incidentals.	28.00	Each	371.75	10409.00	Rupees Ten Thousand Four Hundred Nine and Paise Zero Only	
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204. 3. 8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	28.80	Per Cubic Meter	1277.55	36793.00	Rupees Thirty Six Thousand Seven Hundred Ninety Three and Paise Zero Only	
Total in Figures					370155.00		
Quoted Rate in Figures			Select		0.00		
Quoted Rate in Words				Zero and Paise Zero Only			


Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work: R/R Damages on Chauridhar Kotlu road Km. 0/00 to 7/00 (SH: C/O RWall at RD 3/390 to 3/400)
 Sub-Head and items of works.

Estimated Cost 284975
 Earnest Money 5700
 Time One Month

Sr.No.	Name of Work	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out mts dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mts depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	14.70	Per Cubic Meter	379.90	5585.00	Rupees Five Thousand Five Hundred Eighty Five and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10. (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	47.58	Per Cubic Meter	5140.40	244580.00	Rupees Two Lakhs Forty Four Thousand Five Hundred Eighty and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1 (v):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	28.00	Each	371.75	10409.00	Rupees Ten Thousand Four Hundred Nine and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	19.10	Per Cubic Meter	1277.55	24401.00	Rupees Twenty Four Thousand Four Hundred One and Paise Zero Only
Total in Figures					284975.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words					Zero and Paise Zero Only	


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 354085
 Earnest Money 7100
 Time One Month

Name of Work:- R/R Damages on Kelodhar to Sainj road Km. 0/00 to 19/00 (SH:- C/O R/Wall at RD 12/0990 to 12/0998)		Sub-Head and Items of works.		Estimated Cost	354085	
Sr.No.		No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	25.44	Per Cubic Meter	379.90	9665.00	Rupees Nine Thousand Six Hundred Sixty Five and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	60.90	Per Cubic Meter	5140.40	313050.00	Rupees Three Lakhs Thirteen Thousand Fifty and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	25.00	Each	371.75	9294.00	Rupees Nine Thousand Two Hundred Ninety Four and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	17.28	Per Cubic Meter	1277.55	22076.00	Rupees Twenty Two Thousand Seventy Six and Paise Zero Only
Total in Figures					354085.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Bill Of Quantity

Estimated Cost Rs.
Earnest Money cost Rs.

Time

475923
9600
One Month

Name of Work:- R/R Damages on Kench(mod to Mashog Road 0/00 to 5/500, Jachh Sarhi Road Km. 0/00 to 5/100 and Pangna Majhangan Road Km 0/00 to 8/00 (SH :-

Removal of land slides slips (Under Pangna Section)

Sr.No.	Description Work	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance: Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	3765.21	Per Cubic Meter	126.40	475923	Rupees Four Lakhs Seventy Five Thousand Nine Hundred Twenty Two and Paise Fifty Four Only
	Total Amount In Figure				475923	
	Quoted Rate In Figure					
	Quoted Rate In Words					


Executive Engineer,
Karsog Division,
HPWD, Karsog.

Bill Of Quantity

Estimated Cost Rs. 378383
 Earnest Money cost Rs. 7600
 Time One Month

Name of Work:- R/R Damages on Pangna Majhagan Road 0/00 to 8/00 (SH :- C/O P.C.C R/Wall at Rd 6/445 to 6/660)

Sr.No.	Description Work	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Excavation in soil in hilly area by mechanical mean including cutting and trimming of side slope and disposing of excavated earth with lift upto 1.50 mtr and a lead upto 20 mtr as per technical specification clause 1603.1 as per direction of engineer in charge with in all lead and lift As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	8.92	Per Cubic Meter	207.20	1848	Rupees One Thousand Eight Hundred Forty Eight and Paise Twenty Two Only
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	10.42	Per Cubic Meter	208.15	2169	Rupees Two Thousand One Hundred Sixty Eight and Paise Ninety Two Only
3	Providing and laying concrete for plain/reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	68.85	Per Cubic Meter	5140.40	353917	Rupees Three Lakhs Fifty Three Thousand Nine Hundred Sixteen and Paise Fifty Four Only
4	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3,7 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	21.00	Each	371.75	7807	Rupees Seven Thousand Eight Hundred Six and Paise Seventy Five Only
5	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3,8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	9.90	Per Cubic Meter	1277.00	12642	Rupees Twelve Thousand Six Hundred Forty Two and Paise Thirty Only
	Total Amount In Figure				378383	
	Quoted Rate In Figure					
	Quoted Rate In Words					


Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 466682
Earnest Money 9400
Time One Month

Name of Work:- R/R Damages on Kenchi Mod to Mashog road Km. 0/00 to 3/500 (SH:- C/O PCC R/Mail at RD 0/605 top 0/6/10.50)							
Sub-Head and Items of works.							
Sr.No.		No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words	
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with in upto any lead and technical specification clause 1603.1 as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	14.80	Per Cubic Meter	207.20	3067.00	Rupees Three Thousand Sixty Seven and Paise Zero Only	
2	Earth work in excavation by mechanical means (Hydrolic excavator) manual means in foundation trenches of drains (not exceeding 1.5 mtrs in width 10sqm on plan) including dressing of sides and remaining of bottoms lift upto 1.5 mtrs. including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead 50mtrs as per direction of engineer in charge with in all lead and lifts and other incidentals.	14.24	Per Cubic Meter	208.15	2964.00	Rupees Two Thousand Nine Hundred Sixty Four and Paise Zero Only	
3	Providing and laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	46.53	Per Cubic Meter	5457.80	253951.00	Rupees Two Lakhs Fifty Three Thousand Nine Hundred Fifty One and Paise Zero Only	
4	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202 and 1203 Nominal mix 1:5:10. (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	35.04	Per Cubic Meter	5140.40	180120.00	Rupees One Lakh Eighty Thousand One Hundred Twenty and Paise Zero Only	
5	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	20.00	Each	371.75	7435.00	Rupees Seven Thousand Four Hundred Thirty Five and Paise Zero Only	
6	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm (six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204, 3.8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	13.86	Per Cubic Meter	1381.34	19145.00	Rupees Nineteen Thousand One Hundred Forty Five and Paise Zero Only	
Total in Figures					466682.00		
Quoted Rate in Figures			Select			0.00	
Quoted Rate in Words						Zero and Paise Zero Only	


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- Construction of Chindi to Dachhain road Km. 0/00 to 8/435 (SH:- Widening of road In Km. 4/520 to 4/560, 4/845 to 4/880 , 5/185 to 5/215, 5/275 to 5/295, 5/310 to 5/335, 5/540 to 5/560 and 5/640 to 5/690)

Estimated Cost 461187.00
 Earnest Money 9300
 Time One Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blidge and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery of 216.40 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 421269/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1712.35	Per Cubic Meter	269.33	461187.00	Rupees Four Lakhs Sixty One Thousand One Hundred Eighty Seven and Paise Zero Only
Total In Figures					461187.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words					Zero and Paise Zero Only	


Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 242753
 Earnest Money 4900
 Time One Month


Name of Work:- R/R Damages on Gharatha to Basol road Km. 0/00 to 5/00 (SH:- Removal of slips at various RDs)							
Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words	
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals.	1766.76	Per Cubic Meter	137.40	242753.00	Rupees Two Lakhs Forty Two Thousand Seven Hundred Fifty Three and Paise Zero Only	
Total in Figures					242753.00		
Quoted Rate in Figures					0.00		
Quoted Rate in Words					Zero and Paise Zero Only		


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 467138
Earnest Money 9800
Time One Month

Name of Work:- R/R Damages on Kenchi Mod to Mashog road Km. 0/00 to 3/500 (SH:- C/O PCC R/Wall at RD 0/610.50 to 0/616)		Sub-Head and items of works.					
Sr.No.		No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words	
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with in upto any lead and technical specification clause 1603 1 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	14.19	Per Cubic Meter	207.20	2940.00	Rupees Two Thousand Nine Hundred Forty and Paise Zero Only	
2	Earth work in excavation by mechanical means (Hydraulic excavator) manual means in foundation trenches of drains (not exceeding 1.5 mtrs in width 10sqm on plan)including dressing of sides and remaining of bottoms, lift upto 1.5 mtrs including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead 50mtrs as per direction of engineer in charge with in all lead and lifts and other incidentals.	14.85	Per Cubic Meter	208.15	3091.00	Rupees Three Thousand Niney One and Paise Zero Only	
3	Providing and laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	46.53	Per Cubic Meter	5457.80	253951.00	Rupees Two Lakhs Fifty Three Thousand Nine Hundred Fifty One and Paise Zero Only	
4	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate and lifts and other incidentals) nominal size as per direction of engineer in charge including carriage of materials with in all lead lifts and other incidentals.	35.04	Per Cubic Meter	5140.40	180120.00	Rupees One Lakh Eighty Thousand One Hundred Twenty and Paise Zero Only	
5	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	20.00	Each	371.75	7435.00	Rupees Seven Thousand Four Hundred Thirty Five and Paise Zero Only	
6	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	14.19	Per Cubic Meter	1381.34	19601.00	Rupees Nineteen Thousand Six Hundred One and Paise Zero Only	
Total in Figures					467138.00		
Quoted Rate in Figures					0.00		
Quoted Rate in Words					Zero and Paise Zero Only		


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 485299
Earnest Money 9800
Time One Month

Name of Work:- R/R Damages on Kenchil Mod to Mashog road Km. 0/00 to 3/500 (SH:- C/O PCC R/Wall at RD 1/720 to 1/735)							
Sub-Head and Items of works.							
Sr.No.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words		
1	13.80	Per Cubic Meter	207.20	2859.00	Rupees Two Thousand Eight Hundred Fifty Nine and Paise Zero Only		
2	21.30	Per Cubic Meter	208.15	4434.00	Rupees Four Thousand Four Hundred Thirty Four and Paise Zero Only		
3	88.15	Per Cubic Meter	5140.40	453126.00	Rupees Four Lakhs Fifty Three Thousand One Hundred Twenty Six and Paise Zero Only		
4	21.00	Each	371.75	7807.00	Rupees Seven Thousand Eight Hundred Seven and Paise Zero Only		
5	12.36	Per Cubic Meter	1381.34	17073.00	Rupees Seventeen Thousand Seventy Three and Paise Zero Only		
Total in Figures				485299.00			
Quoted Rate in Figures				Select	0.00		
Quoted Rate in Words				Zero and Paise Zero Only			


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 118756
 Earnest Money 2400
 Time One Month

Name of Work:- R/R Damages on Chilandri to Bakhras road (SH:- Removal of land slips at various reaches in Km. 0/00 to 1/500)						
Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	939.53	Per Cubic Meter	126.40	118756.00	Rupees One Lakh Eighteen Thousand Seven Hundred Fifty Six and Paise Zero Only
Total in Figures					118756.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words		Zero and Paise Zero Only				


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages onKandi Dhar Kandlu road Km. 0/00 to 6/1500 (SH:- C/O RWall at RD 4/450 to 4/464)

Estimated Cost
Earnest Money
Time

493551
9900
One Month

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	43.40	Per Cubic Meter	379.90	16488.00	Rupees Sixteen Thousand Four Hundred Eighty Eight and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Noimnal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	85.68	Per Cubic Meter	5140.40	440429.00	Rupees Four Lakhs Forty Thousand Four Hundred Twenty Nine and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	36.00	Each	371.75	13383.00	Rupees Thirteen Thousand Three Hundred Eighty Three and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	18.20	Per Cubic Meter	1277.55	23251.00	Rupees Twenty Three Thousand Two Hundred Fifty One and Paise Zero Only
Total in Figures					493551.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Scheduled Quantity

Estimated Cost
Earnest Money
Time

163130
3300
One Month

Name of work : - R/R Damages on Kollu to Nanj road Km 0/00 to 6/120 (SH :- Removal of slips at various RD's).

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Construction of unlined surface drain of average cross-section area 0.40 sqm in soil specified line grade, level and dimension . Excavated material to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per direction of Engineer- in-charge with in all leads and lifts and other incidentals.	1065.00			Per Running Meter	
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	1231.50			Per Square Meter	
3	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock/slips in all kind of soil including excavation of saturated soil, boulder & rocky portion requiring wherever blasting and loading in tipper and disposal and disposal of unreserviceable materials upto a distance of 1000 mtrs and stacking of all useful/ serviceable materials and neatly dressing the surface etc.1 as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	686.00			Per Cubic Meter	
Total Amount						


Executive Engineer,
Karsog Division,
APPRWD, Karsog.

Scheduled Quantity

Estimated Cost 161220
 Earnest Money 3300
 Time One Month

Sr.No.	Name of work : - R/R Damages on Shakwa to Sarandi road Km 0/00 to 6/00 (SH :- C/O unlined drain & Removal of slips at various RD's).	Sub-Head and Items of works.	Qty.	Rate		Unit.	Amount.
				In Figure	in words		
1		Construction of unlined surface drain of average cross-section area 0.40 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	600.00			Per Running Meter	
2		Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	2638.50			Per Square Meter	
3		Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock/slips in all King of soil including excavation of saturated soil boulder & rocky portion requiring wherever blasting and loading in tipper and disposal and disposal of unreserviceable materials upto a distance of 1000 mtres and stacking of all useful serviceable materials and neatly dressing the surface etc:1 as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	427.43			Per Cubic Meter	
Total Amount							


 Executive Engineer,
 Karsog Division,
 HPF-WD, Karsog.

Scheduled Quantity

Estimated Cost
Earnest Money
Time

183752
3700
One Month

Name of work : - R/R Damages on Chholdhar to Panaut Dehra road Km. 0/00 to 2/700 (SH :- C/O unlined drain, maintenance of berm & Removal of slips at various RDs)

Sr.No.	Sub-Head and Items of works.	Qty.	Rate		Unit.	Amount
			In Figure	In words		
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	1305.00			Per Running Meter	
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1282.50			Per Square Meter	
3	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawing and technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1282.50			Per Square Meter	
4	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	575.50			Per Cubic Meter	
Total Amount						


 Executive Engineer,
 Karsog Division,
 HPPMD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Nehra Bhadarnu road km. 0/00 to 2/700 (SH.- C/O B/Wall at RD 1/140 to 1/158)
Sub-Head and Items of works.

Estimated Cost 405215
Earnest Money 8200
Time One Month

Sr.No.	Description	No. Of Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	46.08	Per Cubic Meter	379.90	17506.00	Rupees Seventeen Thousand Five Hundred Six and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	74.12	Per Cubic Meter	5140.40	381006.00	Rupees Three Lakhs Eighty One Thousand Six and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	18.00	Each	372.40	6703.00	Rupees Six Thousand Seven Hundred Three and Paise Zero Only
Total in Figures					405215.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog

Percentage Schedule Of Quantity

Estimated Cost 369571
Earnest Money 7400
Time One Month

Name of Work:- R/R Damages on Chauridhar Kotlu road Km. 0/00 to 7/00 (Sh:- C/O R/Wall at RD 0/974 to 0/981)

Sub-Head and items of works.

Sr.No.	Description	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes Including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	16.62	Per Cubic Meter	379.90	6314.00	Rupees Six Thousand Three Hundred Fourteen and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10. (one cement: five sand: ten graded stone aggregate and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all lead lifts and other incidentals.	64.68	Per Cubic Meter	5140.40	332481.00	Rupees Three Lakhs Thirty Two Thousand Four Hundred Eighty One and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	20.00	Each	371.75	7435.00	Rupees Seven Thousand Four Hundred Thirty Five and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	18.27	Per Cubic Meter	1277.55	23341.00	Rupees Twenty Three Thousand Three Hundred Forty One and Paise Zero Only
Total in Figures					369571.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words					Zero and Paise Zero Only	


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 138654
Earnest Money 2800
Time One Month

Name of Work:- R/R Damagus on Shog to Majhas Chaloni road Km. 0/00 to 3/00 (SH:- Removal of slips at various RDS)						
Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other Incidentals.	1009.13	Per Cubic Meter	137.40	138654.00	Rupees One Lakh Thirty Eight Thousand Six Hundred Fifty Four and Paise Zero Only
Total in Figures					138654.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words					Zero and Paise Zero Only	


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 233974
Earnest Money 4700
Time One Month

Name of Work:- R/R Damages on Mamail to Mehandi road Km. 0/00 to 19/00 (SH:- Removal of slips at various RDs)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST in Rs., P	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1702.87	Per Cubic Meter	137.40	233974.00	Rupees Two Lakhs Thirty Three Thousand Nine Hundred Seventy Four and Paise Zero Only
Total in Figures					233974.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 284554
Earnest Money 5700
Time One Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	36.60	Per Cubic Meter	379.90	13904.00	Rupees Thirteen Thousand Nine Hundred Four and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10. (one cement: five sand: ten graded stone aggregate and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	48.69	Per Cubic Meter	5140.40	250286.00	Rupees Two Lakhs Fifty Thousand Two Hundred Eighty Six and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment/wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	20.00	Each	371.75	7435.00	Rupees Seven Thousand Four Hundred Thirty Five and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	9.36	Per Cubic Meter	1381.34	12929.00	Rupees Twelve Thousand Nine Hundred Twenty Nine and Paise Zero Only
Total in Figures					284554.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Katanda to Pakhi road Km. 0/00 to 10/00 (SH:- C/O R/Wall at RD 6/750 to 6/765)
Sub-Head and items of works.

Estimated Cost
Earnest Money
Time

408225
8200
One Month

Sr.No.	Description	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	51.75	Per Cubic Meter	379.90	19660.00	Rupees Nineteen Thousand Six Hundred Sixty and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Noirimal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	71.09	Per Cubic Meter	5140.40	365431.00	Rupees Three Lakhs Sixty Five Thousand Four Hundred Thirty One and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	26.00	Each	371.75	9666.00	Rupees Nine Thousand Six Hundred Sixty Six and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204,3,8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	9.75	Per Cubic Meter	1381.34	13468.00	Rupees Thirteen Thousand Four Hundred Sixty Eight and Paise Zero Only
Total in Figures					408225.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words					Zero and Paise Zero Only	


Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Katanda to Pokhi road Km. 0/00 to 10/00 (SH:- C/O RWall at RD 4/555 to 4/570)
 Sub-Head and items of works.

Estimated Cost 460968
 Earnest Money 9300
 Time One Month

Sr.No.	Description	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	45.75	Per Cubic Meter	379.90	17380.00	Rupees Seventeen Thousand Three Hundred Eighty and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	81.27	Per Cubic Meter	5140.40	417760.00	Rupees Four Lakhs Seventeen Thousand Seven Hundred Sixty and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	26.00	Each	371.75	9666.00	Rupees Nine Thousand Six Hundred Sixty Six and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials within in all lead and lifts and other incidentals.	11.70	Per Cubic Meter	1381.34	16162.00	Rupees Sixteen Thousand One Hundred Sixty Two and Paise Zero Only
Total in Figures					460968.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 428095
Earnest Money 8600
Time One Month

Name of Work:- R/R Damages on Serl Shout road Km. 0/00 to 16/00 (SH:- C/O R/Wall at RD 11/640 to 11/652)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs., P	Total Amount with all taxes Including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	24.84	Per Cubic Meter	379.90	9437.00	Rupees Nine Thousand Four Hundred Thirty Seven and Paise Zero Only
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in-Charge including carriage of materials	73.27	Per Cubic Meter	5140.40	376637.00	Rupees Three Lakhs Seventy Six Thousand Six Hundred Thirty Seven and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	32.00	Each	371.75	11896.00	Rupees Eleven Thousand Eight Hundred Ninety Six and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204,3,8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	23.58	Per Cubic Meter	1277.55	30125.00	Rupees Thirty Thousand One Hundred Twenty Five and Paise Zero Only
Total in Figures					428095.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 452110
Earnest Money 9100
Time One Month

Name of Work:- R/R Damages on various road under Kottu Section in Karsog Sub Division (SH:- Removal of slips at various RDS)		Sub-Head and items of works.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1072.50	Per Square Meter	32.75	35124.00	Rupees Thirty Five Thousand One Hundred Twenty Four and Paise Zero Only		
2	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	3034.83	Per Cubic Meter	137.40	416986.00	Rupees Four Lakhs Sixteen Thousand Nine Hundred Eighty Six and Paise Zero Only		
Total in Figures					452110.00			
Quoted Rate in Figures					0.00			
Quoted Rate in Words					Zero and Paise Zero Only			


Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 461434
 Earnest Money -2880 9306
 Time One Month

Name of Work:- R/R Damages on various roads under Karsog Sub Division (SH:- Removal of slips at various RDs) in Katanda Section						
Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	3382.95	Per Cubic Meter	136.40	461434.00	Rupees Four Lakhs Sixty One Thousand Four Hundred Thirty Four and Paise Zero Only
Total in Figures					461434.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						Zero and Paise Zero Only



 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 324642
 Earnest Money 6500
 Time One Month

Name of Work:- R/R Damages on Kotlu to Katanda road Km. 0/00 to 19/00 (SH:- C/O RWall at RD 14/870 to 14/883) Kotlu Side

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	31.20	Per Cubic Meter	379.90	11853.00	Rupees Eleven Thousand Eight Hundred Fifty Three and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10. (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	54.35	Per Cubic Meter	5140.40	279381.00	Rupees Two Lakhs Seventy Nine Thousand Three Hundred Eighty One and Paise Zero Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204, 3, 8 as per direction of Engineer-in-Charge Including carriage of material within all leads and lifts and other incidentals.	17.42	Per Cubic Meter	1277.55	22255.00	Rupees Twenty Two Thousand Two Hundred Fifty Five and Paise Zero Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1 (v):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	30.00	Each	371.75	11153.00	Rupees Eleven Thousand One Hundred Fifty Three and Paise Zero Only
Total in Figures					324642.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


 Executive Engineer,
 Karsog Division,
 HPPW/D, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 456558.00
 Earnest Money 9200
 Time One Month

Name of Work:- R/R Damages on Shakwa to Sarandi road Km. 0/00 to 6/00 (SH:- Removal of slips at various RDs)						
Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	3322.84	Per Cubic Meter	137.40	456558.00	Ruppees Four Lakhs Fifty Six Thousand Five Hundred Fifty Eight and Paise Zero Only
Total in Figures					456558.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words		Zero and Paise Zero Only				


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 473450
 Earnest Money 9500
 Time One Month

Name of Work:- R/R Damages on Kurhed Rashog Deyom Road Km. 0/00 to 9/00 (SH:- Removal of slips at various RDs)						
Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	3745.65	Per Cubic Meter	126.40	473450.00	Rupees Four Lakhs Seventy Three Thousand Four Hundred Fifty and Paise Zero Only
Total In Figures					473450.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						
Zero and Paise Zero Only						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 270523
 Earnest Money 5500
 Time One Month

Name of Work:- R/R Damages on Thakurthana to Delag road Km. 0/00 to 7/100 (SH:- C/O RWall at RD 1/780 to 1/787)

Sub-Head and Items of works.

Sr.No.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	28.63	Per Cubic Meter	379.90	10877.00	Rupees Ten Thousand Eight Hundred Seventy Seven and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	49.86	Per Cubic Meter	5140.40	256300.00	Rupees Two Lakhs Fifty Six Thousand Three Hundred and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	9.00	Each	371.75	3346.00	Rupees Three Thousand Three Hundred Forty Six and Paise Zero Only
Total In Figures					270523.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 179102
Earnest Money 3600
Time One Month

Name of Work: - R/R Damages on Chanyana Jassal road Km. 0/00 to 2/200 (SH:- C/O R/Wall at RD 1/547 to 1/555)
Sub-Head and Items of Works.

Sr.No.	Description	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	14.48	Per Cubic Meter	379.90	5501.00	Rupees Five Thousand Five Hundred One and Paise Zero Only
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	30.80	Per Cubic Meter	5140.40	158324.00	Rupees One Lakh Fifty Eight Thousand Three Hundred Twenty Four and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	18.00	Each	371.75	6692.00	Rupees Six Thousand Six Hundred Ninety Two and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204, 3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	6.72	Per Cubic Meter	1277.55	8585.00	Rupees Eight Thousand Five Hundred Eighty Five and Paise Zero Only
Total in Figures					179102.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 107317
 Earnest Money 2200
 Time One Month

Sr.No.	Name of Work:- R/R Damages on Pralakashtot to Sahal road (SH:- Removal of land slips at various reaches in Km. 0/00 to 1/500) Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other Incidentals.	849.03	Per Cubic Meter	126.40	107317.00	Rupees One Lakh Seven Thousand Three Hundred Seventeen and Paise Zero Only
Total in Figures					107317.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 338549
 Earnest Money 6800
 Time One Month

Name of Work:- R/R Damages on Kelodhar to Chhatri road Km. 0/00 to 19/00 (SH:- C/O R/Wall at RD 6/110 to 6/122)		Sub-Head and items of works.					
Sr.No.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	19.32	Per Cubic Meter	379.90	7340.00	Rupees Seven Thousand Three Hundred Forty and Paise Zero Only	
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nonimnal mix 1:5:10. (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	57.09	Per Cubic Meter	5140.40	293465.00	Rupees Two Lakhs Ninety Three Thousand Four Hundred Sixty Five and Paise Zero Only	
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of (1v):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	24.00	Each	371.75	8922.00	Rupees Eight Thousand Nine Hundred Twenty Two and Paise Zero Only	
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	22.56	Per Cubic Meter	1277.55	28822.00	Rupees Twenty Eight Thousand Eight Hundred Twenty Two and Paise Zero Only	
Total in Figures					338549.00		
Quoted Rate in Figures					0.00		
Quoted Rate in Words					Zero and Paise Zero Only		


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 166605
Earnest Money 3400
Time One Month

Name of Work:- R/R Damages on Mamail to Mehandi road Km. 0/00 to 19/00 (SH:- C/O RWall at RD 12/360 to 12/370)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	15.00	Per Cubic Meter	379.90	5699.00	Rupees Five Thousand Six Hundred Ninety Nine and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	27.00	Per Cubic Meter	5140.40	138791.00	Rupees One Lakh Thirty Eight Thousand Seven Hundred Ninety One and Paise Zero Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	14.40	Per Cubic Meter	1277.55	18397.00	Rupees Eighteen Thousand Three Hundred Ninety Seven and Paise Zero Only
4	Providing weep holes in brck masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	10.00	Each	371.75	3718.00	Rupees Three Thousand Seven Hundred Eighteen and Paise Zero Only
Total in Figures					166605.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 405445
 Earnest Money 8200
 Time One Month

Name of Work:- R/R Damages on Thakurhana to Dalag road Km. 0/00 to 7/100(SH:- C/O R/Mail at RD 1/795 to 1/811)

Sub-Head and Items of works.

Sr.No.	Description	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	38.72	Per Cubic Meter	379.90	14710.00	Rupees Fourteen Thousand Seven Hundred Ten and Paise Zero Only
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nomininal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in-Charge including carriage of materials	72.09	Per Cubic Meter	5140.40	370571.00	Rupees Three Lakhs Seventy Thousand Five Hundred Seventy One and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment/wing wall./return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	24.00	Each	371.75	8922.00	Rupees Eight Thousand Nine Hundred Twenty Two and Paise Zero Only
4	Back filling behind abutment/wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	8.80	Per Cubic Meter	1277.55	11242.00	Rupees Eleven Thousand Two Hundred Forty Two and Paise Zero Only
Total in Figures					405445.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words					Zero and Paise Zero Only	


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 409885
 Earnest Money 8200
 Time One Month

Name of Work:- R/R Damages on Mahog Gawala road Km. 0/00 to 19/00 (SH:- C/O R/Wall at RD 14/495 to 14/510)
Sub-Head and Items of works.

Sr.No.	Description of Work	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	41.70	Per Cubic Meter	379.90	15842.00	Rupees Fifteen Thousand Eight Hundred Forty Two and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10, (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in-Charge including carriage of materials	71.73	Per Cubic Meter	5140.40	368721.00	Rupees Three Lakhs Sixty Eight Thousand Seven Hundred Twenty One and Paise Zero Only
3	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	11.70	Per Cubic Meter	1338.15	15656.00	Rupees Fifteen Thousand Six Hundred Fifty Six and Paise Zero Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	26.00	Each	371.75	9666.00	Rupees Nine Thousand Six Hundred Sixty Six and Paise Zero Only
Total in Figures					409885.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		



Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 375714
Earnest Money 7600
Time One Month

Name of Work:- R/R Damages on Mahog Gawala road Km. 0/00 to 19/00 (SH:- C/O RWall at RD 12/525 to 12/538)

Sr.No.	Sub-Head and Items of Works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	20.15	Per Cubic Meter	379.90	7655.00	Rupees Seven Thousand Six Hundred Fifty Five and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 Nominal mix 1:5:10. (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	66.65	Per Cubic Meter	5140.40	342608.00	Rupees Three Lakhs Forty Two Thousand Six Hundred Eight and Paise Zero Only
3	Providing weep holes in brck masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	22.00	Each	371.75	8179.00	Rupees Eight Thousand One Hundred Seventy Nine and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204,3,8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	13.52	Per Cubic Meter	1277.55	17272.00	Rupees Seventeen Thousand Two Hundred Seventy Two and Paise Zero
Total In Figures					375714.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Mamall to Mehandi road Km. 0/00 to 19/00 (SH.- C/O R/Wall at RD 17/140 to 17/155)
Sub-Head and Items of works.

Estimated Cost 350895
Earnest Money 7100
Time One Month

Sr.No.	Description	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305. 1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge Including carriage of material within all leads and lifts and other incidentals.	29.25	Per Cubic Meter	379.90	11112.00	Rupees Eleven Thousand One Hundred Twelve and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate and lifts and other incidentals as per direction of Engineer-in- Charge Including carriage of materials within all leads and lifts and other incidentals.	57.65	Per Cubic Meter	5140.40	296344.00	Rupees Two Lakhs Ninety Six Thousand Three Hundred Forty Four and Paise Zero Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	27.60	Per Cubic Meter	1277.55	35260.00	Rupees Thirty Five Thousand Two Hundred Sixty and Paise Zero Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	22.00	Each	371.75	8179.00	Rupees Eight Thousand One Hundred Seventy Nine and Paise Zero Only
Total in Figures					350895.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words					Zero and Paise Zero Only	


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 344809
 Earnest Money 6900
 Time One Month

Name of Work:- R/R Damages on Mamail to Mehandi road Km. 0/00 to 19/00 (SH:- C/O R/Wall at RD 13/480 to 13/495)
 Sub-Head and items of works.

Sr.No.	Description	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	29.25	Per Cubic Meter	379.90	11112.00	Rupees Eleven Thousand One Hundred Twelve and Paise Zero Only
2	Providing and laying concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	57.65	Per Cubic Meter	5140.40	296344.00	Rupees Two Lakhs Ninety Six Thousand Three Hundred Forty Four and Paise Zero Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	24.00	Per Cubic Meter	1277.55	30661.00	Rupees Thirty Thousand Six Hundred Sixty One and Paise Zero Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	18.00	Each	371.75	6692.00	Rupees Six Thousand Six Hundred Ninety Two and Paise Zero Only
Total in Figures					344809.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Mamail to Mehandri road Km. 0/00 to 19/00 (SH:- C/O R/Wall at RD 3/620 to 3/648)
Sub-Head and Items of works.

Estimated Cost 493430
Earnest Money 3400
Time One Month

Sr.No.	Description	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	42.00	Per Cubic Meter	379.90	15956.00	Rupees Fifteen Thousand Nine Hundred Fifty Six and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 Nonimimal mix 1:5:10. (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	81.13	Per Cubic Meter	5140.40	417041.00	Rupees Four Lakhs Seventeen Thousand Forty One and Paise Zero Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204,3,8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	40.32	Per Cubic Meter	1277.55	51511.00	Rupees Fifty One Thousand Five Hundred Eleven and Paise Zero Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	24.00	Each	371.75	8922.00	Rupees Eight Thousand Nine Hundred Twenty Two and Paise Zero Only
Total in Figures					493430.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words					Zero and Paise Zero Only	


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Kelodhar to Saini road Km. 0/00 to 19/00 (SH:- C/O RWall at RD 12/075 to 12/085)

Estimated Cost 443610
 Earnest Money 8900
 Time One Month

Sr.No.	Description	No. Of Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	31.85	Per Cubic Meter	379.90	12100.00	Rupees Twelve Thousand One Hundred and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10. (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	76.12	Per Cubic Meter	5140.40	391287.00	Rupees Three Lakhs Ninety One Thousand Two Hundred Eighty Seven and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	35.00	Each	371.75	13011.00	Rupees Thirteen Thousand Eleven and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	21.30	Per Cubic Meter	1277.55	27212.00	Rupees Twenty Seven Thousand Two Hundred Twelve and Paise Zero Only
Total in Figures					443610.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words					Zero and Paise Zero Only	


Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 359916
 Earnest Money 7200
 Time One Month

Name of Work:- RR Damages on various road under Karsog Sub Division (SH:- Removal of slips, C/ unlined drain & maintenance of berm at on various RD) Kelodhar Section Job No. II							
Sub-Head and Items of works.							
Sr.No.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words		
1	1628.70	Per Cubic Meter	137.40	223783.00	Rupees Two Lakhs Twenty Three Thousand Seven Hundred Eighty Three and Paise Zero Only		
2	2565.00	Per Running Meter	26.80	68742.00	Rupees Sixty Eight Thousand Seven Hundred Forty Two and Paise Zero Only		
3	2524.00	Per Square Meter	26.70	67391.00	Rupees Sixty Seven Thousand Three Hundred Ninety One and Paise Zero Only		
Total in Figures				359916.00			
Quoted Rate in Figures				0.00			
Quoted Rate in Words				Zero and Paise Zero Only			



 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Karsog To Dachhain road Km. 0/00 to 2/030 (SH:- C/O RWall at RD 0/020 to 0/032)

Estimated Cost 473198
 Earnest Money 9500
 Time One Month

Sr. No.	Sub-Head and items of works.	Qty.	Rate		Unit	Amount.
			in Figure	in words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	26.40			Per Cubic Meter	
2	Providing and laying concrete for plain/reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	79.20			Per Cubic Meter	
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	30.72			Per Cubic Meter	
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	40.00			Each	
Total Amount						


 Executive Engineer,
 Karsog Division,
 HRPWV Karsog.

SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Karsog To Dachhain road Km. 0/00 to 2/030 (SH:- C/O B/Wall at RD 0/140 to 0/152)

Estimated Cost 253950
 Earnest Money 5100
 Time One Month

Sr. No.	Sub-Head and items of works.	Qty.	Rate		Unit	Amount
			in Figure	in words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	21.12			Per Cubic Meter	
2	Providing and laying concrete for plain/reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802.803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	46.12			Per Cubic Meter	
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	24.00			Each	
Total Amount						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

DNT /SCHEDULE OF QUANTITY

Name of work : - R/R Damages on Sanarali to Bathar road Km. 0/00 to 3/00 (SH :- C/O unlined drain, maintenance of berm & Removal of slips at various RDs)

Estimated Cost 268274
 Earnest Money 5400
 Time One Month

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	1425.00			Per Running Meter	
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	1682.50			Per Square Meter	
3	Stripping excess soil from the shouldr surface to achive the approved level and compacting with plate compactor at OMC as per drawing and technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	1682.50			Per Square Meter	
4	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1009.03			Per Cubic Meter	
Total Amount						


Executive Engineer,
 Karsog Division,
 D.P.P.W.D, Karsog.