

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed items rate tender on form 6&8 are invited by the Executive Engineer HPPWD Kotla Behar Division Kotla Behar for the following works from the approved and eligible contractors enlisted with HPPWD Department so as to reach in this office on dated **9.10.2023 up to 10.30AM** and the same will be opened on the same day at **11.30 AM** in the presence of contractors /firms or their authorized representative. The application for purchase of tender forms will be received up to **2.00 PM** on dated **6.10.2023** and tender forms can be obtained from this office against cash payment (nonrefundable) on **7.10.2023 from 10.00 AM to 2.00 PM** and no tender form shall be issued by the post. The amount of earnest money in shape of FDR of any nationalized bank in HP duly pledged in the Name of Executive Engineer HPPWD Kotla Behar Division Kotla Behar

The conditional tender and tender received without earnest money (FDR) will be rejected and if holiday declared by the Govt. on the above date due to any reasons the tender shall be received and opened on the next working day. The undersigned reserved the right to rejected tender without assigned any reasons.

Sr No	Name of work	Estimated cost	Earnest money	Time Limit	Cost of tender form	Form No
1	Restoration of Rain damages on Kaloha Dhaliara Dada Siba Sansarpur Terrace Road Km 22/200 to 60/920 (SH:- C/O R/wall at Rd 26/835 to 26/850 & 26/840 to 26/844)	343463	7000	Two Month	350	6&8
2	Restoration of rain Damages On Bharwain to Dehi Pukhar Via karaa (SH:- C/O R/wall at Rd 6/800 to 6/812 7 7/200 to 7/206)	466282	9000	Two Month	350	6&8
3	Restoration of Rain Damages on Various Roads under Pragpur sub Division (SH:- Hiring of tractor with trolley for Removal of slips and Carriage of Material for filling of road depression in pragpur sub division)	288000	6000	Three Month	350	6&8
4	Restoration of damages due to OFC on Pucca Tiala Seul Mehra Road km 0/0 to 11/105 (SH:- P/L Interlocking paver block at Rd 8/300 to 8/345 and Construction of R/wall at Rd 7/930 to 7/945 & 7/950 to 7/956) Deposit work)	494163	10000	Three Month	350	6&8
5	Construction of Karsal to Didyan via mastial Road Km 0/0 to 3/500 (SH:- C/O R/wall at Rd 1/100 to 1/110,1/115 to 1/127 & 1/355 to 1/367 & Cement Concrete pavement at Rd 1/344 to 1/355) Under OTMNP	482165	10000	Three Month	350	6&8
6	C/O Jeepable Road from SH Harbans Lal House to Main Road S.C Basti Upper Behar in GP Kotla Behar (SH:- R/wall at Rd 0/150 to 0/165 & 0/220 to 0/232 (Under SCDP)	485069	10000	Three Month	350	6&8

1) Certified that tender of above works are being called in Exigency of public interest.

Executive Engineer,
Kotla Behar Division HPPWD.,
Kotla Behar

NO.PWD/KB/CB/TENDER 2023-24 -

3168-8106

DATED

28/9/2023

information please.

Copy to the F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla -2 for favour of

Copy to the Engineer-in-Chief HPPWD Shimla for information please.

Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of information please.

Copy to the Superintending Engineer 9th Circle HPPWD Nurpur for favour of information please.

Executive Engineer,
Kotla Behar Division HPPWD.,
Kotla Behar

JOB NO. 1

Estimate Cost :- Rs. 343463.00
Earnest Money :-Rs. 7000.00
Time Limit :- Two Month.

of work:- Restoration of Rain damage on Kaloha Dhaliara Dadasiba Sansarpur Terrace road Km. 22/200 to 60/920 (SH:- Const. of R/wall at RD. 26/835 to 26/850 & 26/840 to 26/844). Time Limit :- Two Month.

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to a original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and cutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and manning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	45.12 Cubic metre			Per Cubic metre	
providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand and isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD technical specification section 800, 900 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	90.41 Cubic metre			Per cubic metre	
back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	15.94 Cubic metre			Per Cubic metre	
providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204 3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	50.00 Number			Each	
TOTAL					

C

Executive Engineer,
Kotla Behar Division,
HPPWD-Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO. 2
Estimate Cost :- Rs. 466282.00
Earnest Money :-Rs. 9000.00
Time Limit :- Two Month.

Name of work:- Restoration of Rain damage on Bharwain to Dehi Pukhar via Karoa road (SH:- Const. of R/wall at RD. 6/800 to 6/812 & 7/200 to 7/206).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, abutments and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and bracing and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and including of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material in all leads, lifts and other incidentals.	58.78 Cubic metre			Per Cubic metre	
mixing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five parts of ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water), including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900,1200 and 1600 and as per entire satisfaction and directions of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	120.10 Cubic metre			Per cubic metre	
filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	35.80 Cubic metre			Per Cubic metre	
mixing and laying 100mm (one Hundred millimeter) dia ISI marked P V C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending in the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	50.00 Number			Each	
TOTAL					

Executive Engineer,
Kotla Behar Division,
HPPWD, Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO. 3

Estimate Cost :- Rs. 288000.00

Earnest Money :-Rs. 6000.00

Time Limit :- Three Month.

Name of work:- Restoration of Rain damage on Various roads under Pragnpur Sub Division (SH: Hiring of Tractor with Trolley for Removal of slips and Carriage of Material for filling of road depression in Pragnpur Sub Division).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Hiring of Tractor with Trolley Hydraulically equiped for Transportation / Shifting muck, debris, slips along the road on hourly basis including pol complete in periphery of sub Division on Various roads. All repair charges will be borne by the owner of Tractor. The work shall be carried out as directed by Engineer-in-Charge with in all leads and lifts, disposed earth to be levelled and neatly dressed including carriage of materials within all leads and lifts. The rate inclusive of Malkhana, royalty, octroi, toll tax, GST or any taxes imposed by the Government.	600.00 Hours			Per Hours	
TOTAL						


 Executive Engineer,
 Kolia Behar Division,
 HPPWD Kolia Behar.

JOB NO. 4
Estimate Cost :- Rs. 494163.00
Earnest Money :-Rs. 10000.00
Time Limit :- Three Month.

SCHEDULE OF QUANTITY

of work:- Restoration of damages due to OFC on Pucca Tiala Seul Mehra road Km. 0/0 to 11/105 (SH:- P/L Interlocking Paver Block at RD. 8/300 to 8/345 and Const. of R/wall at RD. 7/930 to 7/945 & 7/950 to 7/956) (Deposit work).

Description of item

Description of item	Quantity	Rate in		Unit	Amount
		Figures	Words		
work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, pits and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, removal of slumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and slush which may arise out during dewatering complete as per drawing and MORD Technical Specification 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material in all leads, lifts and other incidentals.	66.73 Cubic metre			Per Cubic metre	
ing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil) including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical Specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	67.34 Cubic metre			Per cubic metre	
filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	16.83 Cubic metre			Per Cubic metre	
ing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) concrete mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by Government.	8.33 Cubic metre			Per Cubic metre	
ing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	11.54 Cubic metre			Per Cubic metre	

6	Providing and laying of inter locking concrete paver blocks make of NTC/NTCO/HPPWD approved having thickness 80mm (eighty millimeter) Grade M-40 IS Code-15658:2006 and Technical Specification Clause 1504 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	115.44 Square metre					
7	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plinth reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical to twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709.1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	33.00 Number	Each				
TOTAL							


 Executive Engineer,
 Kotla Behar Division,
 HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO. 5
Estimate Cost :- Rs. 482165.00
Earnest Money :-Rs. 10000.00
Time Limit :- Three Month.
Pavement at RD. 1/344 to 1/355) (Under OTMNP)

Work:- Construction of Karsal to Didian via Mastial road km 0/0 to 3/500 (SH:- C/o R/wall at RD. 1/100 to 1/110 , 1/115 to 1/127 & 1/367 & Cement Concrete

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, pits, etc. in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and bracing and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and lining of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material in all leads, lifts and other incidentals.	51.09 Cubic metre			Per Cubic metre	
Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five parts of ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall, breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water), including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900,1200 and 1600 and as per entire satisfaction and directions of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	112.32 Cubic metre			Per cubic metre	
Filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	22.86 Cubic metre			Per Cubic metre	
Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and the entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	68.00 Number			Each	

5	Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M-Twenty five) design mix with minimum cement contents of 404 Kg (Four hundred four Kilogram) in open foundation as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	8.80 Cubic metre				Per Cubic metre	
TOTAL							

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO. 6
Estimate Cost :- Rs. 485069.00
Earnest Money :-Rs. 10000.00
Time Limit :- Three Month.
of work:- C/o Jeepable Road from Sh. Harbans Lal House to main road S.C. Basti upper Behar in G.P.Kotla Behar (SH:- C/o R/wall at RD. 0/150 to 0/165 & 0/220 to 0/232)
(Under SCDP)

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, pits, and other similar structures in all kinds and classification of soil, including saturated soil comprising of any mix soil, ordinary rock, hard rock, chiselling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and setting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and lining of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material in all leads, lifts and other incidentals.	80.85 Cubic metre			Per Cubic metre	
ing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five parts of ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water), including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical Specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, hana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	123.90 Cubic metre			Per cubic metre	
filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	31.77 Cubic metre			Per Cubic metre	
ing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	72.00 Number			Each	
TOTAL					


Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.