



Telephone No: 01782-233214

E-mail: eenh-ram-hp@nic.in

No. PW/EE/NH/RMP-CB-Tender /2023-24-
To

6925

Dated:- 21/10/2023

The Executive Engineer, (IT)
Nigam Vihar Shimla-2.

Subject: - Publication of tender notice

Enclosed, please find herewith copy of tender notice in
respect of tenders invited vide this office NIT No. PW/EE/NH/RMP/CB-Tender
Notice/ 2023-24- 6914-24 dated 21/10/2023 for uploading the same on
department website for wide publicity.

DA:- Copy of NIT


Executive Engineer,
NH Division HPPWD,
Rampur Bushahr.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed Item rate tender(s) on PWD form No.6 &8 are hereby invited by the Executive Engineer, NH- Division, HP.PWD, Rampur Distt. Shimla (H.P) on behalf of the Governor of H.P for the following works from the registered contractors/consultants in HP.PWD in appropriate class to reach in this office on 02.11.2023 up to 10.30 A.M. and will be opened on the same day at 11.00A.M. in the presence of Contractors/ consultants or their authorized representative who wish to be present at that time. The application for obtaining the tender form will be received on 01.11.2023 i.e. 11.00 AM to 1.00 PM and the tender form can be had from this office against this cash payment (Non- refundable) on the same day from 2.00P.M. to 5.00 P.M. No application shall be entertained without earnest money or through FAX.

Earnest money shall be in shape of NSC/FDR duly pledged in favour of Executive Engineer NH-Division HP.PWD Rampur Bushahr Distt. Shimla H.P. Ambiguous /Telegraphically/conditional tenders or tender through FAX shall not be entertained/ considered in any case.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time	Form No.	Cost of form
1	A/R & M/O on NH-305 Sainj Luhri Aut road Km 0/00 to 97/00 (SH:- C/O stone masonry B/wall or edge wall at RD 52/410 to 42/460).	496838/-	10000/-	One month	6&8	350/-
2	A/R & M/O on NH-305 Sainj Luhri Aut road Km 0/00 to 97/00 (SH:- C/O stone masonry R/wall at RD 52/800 to 52/825 and B/wall or edge wall at RD 42/460 to 52/474).	497986/-	10000/-	One month	6&8	350/-
3	A/R & M/O on NH-305 Sainj Luhri Aut road Km 0/00 to 97/00 (SH:- C/O PCC B/wall at RD 37/600 to 37/610 and 37/805 to 37/814.50).	488497/-	9800/-	One month	6&8	350/-
4	A/R & M/O on NH-305 Sainj Luhri Aut road Km 0/00 to 97/00 (SH:- C/O stone masonry R/wall at RD 52/462.80 to 52/480).	497374/-	10000/-	One month	6&8	350/-
5	A/R & M/O on NH-305 Sainj Luhri Aut road Km 0/00 to 97/00 (SH:- C/O PCC B/wall at RD 36/1100 to 36/1110 and 37/150 to 37/159).	486012/-	9800/-	One month	6&8	350/-
6	A/R & M/O on NH-305 Sainj Luhri Aut road Km 0/00 to 97/00 (SH:- C/O PCC R/wall at RD 28/790 to 28/801).	494140/-	9900/-	One month	6&8	350/-
7	A/R & M/O on NH-305 Sainj Luhri Aut road Km 0/00 to 97/00 (SH:- C/O PCC R/wall at RD 17/050 to 17/058.30 and stone masonry at RD 24/440 to 24/480).	494699/-	9900/-	One month	6&8	350/-
8	R/R damages on NH-305 Sainj Luhri Aut road Km 0/00 to 97/00 (SH:- Providing and laying WBM G-III in patches Km 0/00 to 23/00).	380203/-	7700/-	One month	6&8	350/-
9	R/R damages on NH-305 Sainj Luhri Aut road Km 0/00 to 97/00 (SH:- Repair of slab culvert at RD 0/490).	304126/-	6100/-	One month	6&8	350/-
10	R/R damages on NH-305 Sainj Luhri Aut road Km 0/00 to 97/00 (SH:- C/O wire crate B/wall at RD 24/400 to 24/418).	467046/-	9400/-	Two months	6&8	350/-
11	R/R damages on NH-05 Km 236/00 to 368/00 (SH:- Providing MS sheet safety panels for land slide at Nigulari from Bhabanagar side).	488328/-	9800/-	10 days	6&8	350/-
12	R/R damages on NH-305 Sainj Luhri Aut road Km 0/00 to 97/00 (SH:- C/O wire crate R/wall at RD 49/590 to 49/608).	467046/-	9400/-	Two months	6&8	350/-
13	R/R damages on NH-05 Km 236/00 to 368/00 (SH:- C/O B/wall in RR masonry at RD 279/340 to 279/350).	305391/-	6200/-	One month	6&8	350/-
14	R/R damages on NH-05 Km 236/00 to 368/00 (SH:- C/O PCC R/wall at RD 263/442 to 263/445.40).	435014/-	8800/-	Two months	6&8	350/-
15	R/R damages on NH-05 Km 236/00 to 368/00 (SH:- C/O B/wall in RR masonry over existing B/wall at RD 276/820 to 276/840).	276850/-	5600/-	One month	6&8	350/-
16	R/R damages on NH-05 Km 236/00 to 368/00 (SH:- C/O PCC R/wall at RD 263/448 to 263/452.20).	435014/-	8800/-	Two months	6&8	350/-
17	R/R damages on NH-05 Km 236/00 to 368/00 (SH:- Protection work to the existing abutment of Machada Bridge at RD 259/295 (U/S).	427639/-	8600/-	Two months	6&8	350/-

18	R/R damages on NH-05 Km 236/00 to 368/00 (SH:- C/O PCC R/wall at RD 296/746 to 296/754.70).	457760/-	9200/-	Two months	6&8	350/-
19	R/R damages on NH-05 Km 236/00 to 368/00 (SH:- C/O PCC R/wall at RD 298/569.50 to 298/577.50).	342827/-	6900/-	Two months	6&8	350/-
20	R/R damages on NH-05 Km 236/00 to 368/00 (SH:- C/O PCC R/wall at RD 298/560 to 298/569).	385681/-	6900/-	Two months	6&8	350/-
21	A/R & M/O on NH-305 Sainj Luhri Aut road Km 0/00 to 97/00 (SH:- C/O PCC R/wall at RD 35/710 to 35/720.80).	494560/-	9900/-	One month	6&8	350/-
22	R/R damages on NH-05 Km 236/00 to 368/00 (SH:- Providing MS sheet safety panels for land slide at Nigulari from Chaura side).	488328/-	9800/-	10 days	6&8	350/-
23	R/R damages on NH-05 Km 236/00 to 368/00 (SH:- C/O PCC R/wall at RD 296/277 to 296/287).	301532/-	6100/-	Two months	6&8	350/-
24	R/R damages on NH-05 Km 236/00 to 368/00 (SH:- Trapezoidal shape drain along with steel grating between Km 267/590 to 267/645).	477720/-	9600/-	Two months	6&8	350/-
25	R/R damages on NH-05 Km 236/00 to 368/00 (SH:- C/O PCC R/wall at RD 298/560 to 298/569).	454769/-	9100/-	Two months	6&8	350/-

SPECIAL CONDITIONS

- The material shall be arranged by the contractor/ consultants himself.
- The detail of documents to be attached with the application is given below.
 - Latest copy of renewal enlistment/empanelment.
 - Copy of Pan Card.
 - Copy of GST No.
- The offer of the tender shall be kept open for 90 days
- Tender received after the specified time/date shall not be opened.
- Executive Engineer NH-division HP.PWD Rampur Distt. Shimla H.P. reserves the right to reject any or all tender/s without assigning any reasons.
- If due to any unforeseen reasons the office of the Executive Engineer NH-Division HP.PWD Rampur remain closed on the notified date of sale and receipt of tender, tender will be sold and received/opened the next working day of same specified time.
- Tenderers may contact the Executive Engineer for any further information they may require during the working day/ office hours.
- The contractor/ consultants are requested to insert the rate of each in words as well as in figures failing which Executive Engineer reserves the right to reject any or all tenders.
- The labourcess shall allow/ deduction @ 2% TDS amount of GST (1% CGST and 1% SGST).
- The labour cess @ 1% will be deducted from the gross amount of the bill
- All the works are of urgent nature hence the contractor already having two works are not eligible to participate for the tendering.
- A contractor enlisted in a particular class shall be eligible to tender for his own class and one step below as per Govt. notification No.PBW (B) 22-1/2002 dated 26-05-2015.
- The Contractor/consultants will have to submit the proof of registration under Employees Provident Funds & Miscellaneous Provision Act. 1952 before award of work.
- Cement should be purchased from H.P. State Civil Supply Corporation
- GST will be deducted from each bill as per latest instruction of the Government.

Executive Engineer,
NH Division, H.P.PWD,
Rampur Bushahr.

No.PW/EE/NH/RMP/CB-Tender Notice/2023-24-
Copy forwarded for information to the:-

- Engineer-in-Chief, HP.PWD, Shimla
- Chief Engineer (NH) HP.PWD, Shimla-1
- Superintending Engineer, NH-Circle, HP.PWD, Shimla
- All the Assistant Engineer working under this division
- A/B & D/B in this office.
- Notice board of this office.

6914-24

Dated:- 21/10/2023

Executive Engineer,
NH Division, H.P.PWD,
Rampur Bushahr.

Certificate

Certified that the tenders of the works invited vide this office NIT No. PW/EE/NH/RMP/CB-tender/ 2023-24-6914-24 dated 21/10/2023 is of urgent nature in exigency of public interest.


Executive Engineer
NH Division HPPWD,
Rampur Bushahr.

SCHEDULE OF QUANTITY


Name of work:- A/R & M/O on NH -305 Saini Luhri Aut road Km 0/000 to 97/000 (SH:- C/O stone masonry B/wall or edge wall at RD 52/410 to 52/460)

Estimated cost:- 496838.00
Earnest money:- 10000.00

Time:- One month

Sr No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Earth work in excavation for structure in all depth as per drawing and technical specification Clause 304 of section 300 of MORTH specification in all kind of soils i.e pick work, Jumper work, blasting work in soft and hard rock and intermediate classification of soil including chiselling and wedging out of rock with in all depths and heights ,stacking the useful materials and disposal of unserviceable materials upto the indentified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	183.00			Per cubic metre	
2	Random Rubble/Stone masonry work in cement mortar 1:6 for substructure complete as per drawing and technical Specification (Random rubble masonry coursed/ uncoursed) including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	85.50			Per cubic metre	

3	Providing and laying mechanically mixed and vibrated cement concrete M-15 containing minimum contents of cement is 5.50 bags per cum in all heights and depth as per drawing and technical specifications in foundation of retaining walls complete as per MORTH specification No.1500,1700 & 2100 including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	1.32				Per cubic metre	
4	Providing and laying 100mm diameter (Hundred millimeter) P. V.C. pipe in weep holes in R/wall in requisite slopes for drainages as per the direction of the Engineer-in-charges including carriage of materials in all leads and lifts with mechanical means.	50.00				Per running metre	
						Total:-	


 Executive Engineer,
 NH Division HPPWD,
 Rampur Bsr.

SCHEDULE OF QUANTITY


Name of work:- A/R & M/O on NH -305 Sainj Luhri Aut road Km 0/000 to 97/000 (SH:- C/O stone masonry R/wall at RD 52/800 to 52/825 and B/wall or edge wall at RD 52/460 to 52/474)

Estimated cost:- 497986.00
Earnest money:- 10000.00

Time:- One month

Sr No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Earth work in excavation for structure in all depth as per drawing and technical specification Clause 304 of section 300 of MORTH specification in all kind of soils i.e pick work, Jumper work, blasting work in soft and hard rock and intermediate classification of soil including chiselling and wedging out of rock with in all depths and heights ,stacking the useful materials and disposal of unserviceable materials upto the indentified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	83.99			Per cubic metre	
2	Random Rubble/Stone masonry work in cement mortar 1:6 for substructure complete as per drawing and technical Specification (Random rubble masonry coursed/ uncoursed) including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	86.94			Per cubic metre	

3	Providing and laying mechanically mixed and vibrated cement concrete M-15 containing minimum contents of cement is 5.50 bags per cum in all heights and depth as per drawing and technical specifications in foundation of retaining walls complete as per MORTH specification No.1500,1700 & 2100 including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	1.71				Per cubic metre	
4	Providing and laying 100mm diameter (Hundred millimeter) P. V.C. pipe in weep holes in R/wall in requisite slopes for drainages as per the direction of the Engineer-in-charges including carriage of materials in all leads and lifts with mechanical means.	39.00				Per running metre	
5	Providing and laying back filling behind Retaining walls satisfying the requirement as per drawing and technical specifications in all heights and depths compacted to a firm condition complete including carriage of materials by mechanical transport in all leads and lifts and as per direction of the Engineer-in-Charge.	21.75				Per cubic metre	
						Total:-	


 Executive Engineer,
 NH Division HPPWD,
 Rampur Bsr.

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O on NH -305 Sainj Luhri Aut road Km 0/000 to 97/000 (SH:- C/O PCC B/wall at RD 37/600 to 37/610 and 37/805 to 37/814.50)

Estimated cost:- 488497.00
Earnest money:- 9800.00

Time:- One month

Sr No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Earth work in excavation for structure in all depth as per drawing and technical specification Clause 304 of section 300 of MORTH specification in all kind of soils i.e pick work, Jumper work, blasting work in soft and hard rock and intermediate classification of soil including chiselling and wedging out of rock with in all depths and heights, stacking the useful materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	59.48			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated cement concrete M-15 containing minimum contents of cement is 5.50 bags per cum in all heights and depth as per drawing and technical specifications in foundation of retaining walls complete as per MORTH specification No.1500,1700 & 2100 including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	72.79			Per cubic metre	

3	Providing and laying 100mm diameter (Hundred millimeter) P. V.C. pipe in weep holes in R/wall in requisite slopes for drainages as per the direction of the Engineer-in-charges including carriage of materials in all leads and lifts with mechanical means.	37.05				Per running metre	
						Total:-	


 Executive Engineer,
 NH Division HPPWD,
 Rampur Bsr.

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O on NH -305 Sainj Luhri Aut road Km 0/000 to 97/000 (SH:- C/O stone masonry R/wall at RD 52/462.80 to 52/480)				Estimated cost:- 497374.00		
				Earnest money:- 10000.00		
				Time:- One month		
Sr No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Earth work in excavation for structure in all depth as per drawing and technical specification Clause 304 of section 300 of MORTH specification in all kind of soils i.e pick work, Jumper work, blasting work in soft and hard rock and intermediate classification of soil including chiselling and wedging out of rock with in all depths and heights ,stacking the useful materials and disposal of unserviceable materials upto the indentified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	48.50			Per cubic metre	
2	Random Rubble/Stone masonry work in cement mortar 1:6 for substructure complete as per drawing and technical Specification (Random rubble masonry coursed/ uncoursed) including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	86.31			Per cubic metre	
3	Providing and laying 100mm diameter (Hundred millimeter) P. V.C. pipe in weep holes in R/wall in requisite slopes for drainages as per the direction of the Engineer-in-charges including carriage of materials in all leads and lifts with mechanical means.	38.70			Per running metre	

4	Providing and laying back filling behind Retaining walls satisfying the requirement as per drawing and technical specifications in all heights and depths compacted to a firm condition complete including carriage of materials by mechanical transport in all leads and lifts and as per direction of the Engineer-in-Charge.	14.10				Per cubic metre	
						Total:-	


 Executive Engineer,
 NH Division HPPWD,
 Rampur Bsr.

SCHEDULE OF QUANTITY

* SCHEDULE OF QUANTITY						
Name of work:- A/R & M/O on NH -305 Sainj Luhri Aut road Km 0/000 to 97/000 (SH:- C/O PCC B/wall at RD 36/1100 to 36/1110 and 37/150 to 37/159)				Estimated cost:- 486012.00		
				Earnest money:- 9800.00		
				Time:- One month		
Sr No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Earth work in excavation for structure in all depth as per drawing and technical specification Clause 304 of section 300 of MORTH specification in all kind of soils i.e pick work, Jumper work, blasting work in soft and hard rock and intermediate classification of soil including chiselling and wedging out of rock with in all depths and heights ,stacking the useful materials and disposal of unserviceable materials upto the indentified dumping site as per the direction of the Engineer-in-Charges with in all leads andlifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	59.17			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated cement concrete M-15 containing minimum contents of cement is 5.50 bags per cum in all heights and depth as per drawing and technical specifications in foundation of retaining walls complete as per MORTH specification No.1500,1700 & 2100 including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	72.42			Per cubic metre	

3	Providing and laying 100mm diameter (Hundred millimeter) P. V.C. pipe in weep holes in R/wall in requisite slopes for drainages as per the direction of the Engineer-in-charges including carriage of materials in all leads and lifts with mechanical means.	36.86				Per running metre	
						Total:-	


 Executive Engineer,
 NH Division HPPWD,
 Rampur Bsr.

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O on NH -305 Sainj Luhri Aut road Km 0/000 to 97/000 (SH:- C/O PCC R/wall at RD 28/790 to 28/801)

Estimated cost:- 494140.00
Earnest money:- 9900.00

Time:- One month

Sr No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Earth work in excavation for structure in all depth as per drawing and technical specification Clause 304 of section 300 of MORTH specification in all kind of soils i.e pick work, Jumper work, blasting work in soft and hard rock and intermediate classification of soil including chiselling and wedging out of rock with in all depths and heights ,stacking the useful materials and disposal of unserviceable materials upto the indentified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	44.66			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated cement concrete M-15 containing minimum contents of cement is 5.50 bags per cum in all heights and depth as per drawing and technical specifications in foundation of retaining walls complete as per MORTH specification No.1500,1700 & 2100 including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	71.15			Per cubic metre	


3	Providing and laying 100mm diameter (Hundred millimeter) P. V.C. pipe in weep holes in R/wall in requisite slopes for drainages as per the direction of the Engineer-in-charges including carriage of materials in all leads and lifts with mechanical means.	26.40				Per running metre	
4	Providing and laying back filling behind Retaining walls satisfying the requirement as per drawing and technical specifications in all heights and depths compacted to a firm condition complete including carriage of materials by mechanical transport in all leads and lifts and as per direction of the Engineer-in-Charge.	20.57				Per cubic metre	
						Total:-	


 Executive Engineer,
 NH Division HPPWD,
 Rampur Bsr.

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
Name of work:- A/R & M/O on NH -305 Sainj Luhri Aut road Km 0/000 to 97/000 (SH:- C/O PCC R/wall at RD 17/050 to 17/058.30 and stone masonry 24/440 to 24/480)				Estimated cost:- 494699.00		
				Earnest money:- 9900.00		
				Time:- One month		
Sr No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Earth work in excavation for structure in all depth as per drawing and technical specification Clause 304 of section 300 of MORTH specification in all kind of soils i.e pick work, Jumper work, blasting work in soft and hard rock and intermediate classification of soil including chiselling and wedging out of rock with in all depths and heights ,stacking the useful materials and disposal of unserviceable materials upto the indentified dumping site as per the direction of the Engineer-in-Charges with in all leads andlifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	23.41			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated cement concrete M-15 containing minimum contents of cement is 5.50 bags per cum in all heights and depth as per drawing and technical specifications in foundation of retaining walls complete as per MORTH specification No.1500,1700 & 2100 including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	41.65			Per cubic metre	

3	Providing and laying 100mm diameter (Hundred millimeter) P. V.C. pipe in weep holes in R/wall in requisite slopes for drainages as per the direction of the Engineer-in-charges including carriage of materials in all leads and lifts with mechanical means.	18.68				Per running metre	
4	Providing and laying back filling behind Retaining walls satisfying the requirement as per drawing and technical specifications in all heights and depths compacted to a firm condition complete including carriage of materials by mechanical transport in all leads and lifts and as per direction of the Engineer-in-Charge.	6.81				Per cubic metre	
5	Random Rubble/Stone masonry work in cement mortar 1:6 for substructure complete as per drawing and technical Specification (Random rubble masonry coursed/ uncoursed) including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	48.00				Per cubic metre	
						Total:-	


 Executive Engineer,
 NH Division HPPWD,
 Rampur Bsr.

8

Schedule of Quantity

Name of work:- R/R damages on NH-305 Sainj Luhri Aut road km 0/000 to 97/000 (Sub Head:- Providing and Laying WBM G-III in patches Km. 0/00 to 23/00)

Name of work:- R/R damages on NH-305 Sainj Luhri Aut road km 0/000 to 97/000 (Sub Head:- Providing and Laying WBM G-III in patches Km. 0/00 to 23/00)			Estimated Cost:-		380203.00	
			Earnest Money:-		7700.00	
			Time:-		One month	
S. No.	Descriptions	Qty.	In figure	Rate In words.	Unit	Amount
1	Providing , Laying Spreading and compacting stone aggregates of specific size (G-III) to water bound macadam specification i/c spreading in uniform thickness, hand packing rolling with 3 wheeled steel/ vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and vibroooming requiste type of screening/binding materials to fill up the intersices of course aggregate, watering and compacting to the required density.	137.63			Per cubic meter.	
Total Rs:-						


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on NH-305 Sainj Luhri Aut road km 0/000 to 97/000 (Sub Head:- Repair of Slab culvert at Rd. 0/490)

Name of work:- R/R damages on NH-305 Saini Luhri Aut road km 0/000 to 97/000 (Estimated Cost:-		304126.00	
Sub Head:- Repair of Slab culvert at Rd. 0/490)						Earnest Money:-		6100.00	
						Time:-		One month	
S. No.	Descriptions	Qty.	Rate		Unit	Amount			
			In figure	In words.					
1	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	46.62			Per cubic meter.				
Total Rs:-									


Executive Engineer,
N.H.Division, H.P. PWD,
Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on NH-305 Sainj Luhri Aut road km 0/000 to 97/000 (Sub Head:- C/O wire crate B/wall at RD. 24/400 to 24/418)

Name of work:- R/R damages on NH-305 Sainj Luhri Aut road km 0/000 to 97/000 (Sub Head:- C/O wire crate B/wall at RD. 24/400 to 24/418)		Estimated Cost:-		467046.00		
		Earnest Money:-		9400.00		
		Time:-		two months		
S. No.	Descriptions	Qty.	In figure	Rate In words.	Unit	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	93.60			Per cubic meter.	
2	Providing and laying of boulder apron laid in wire crate made with 4mm dia G.I. wire confirming to IS 280 and IS 4826 in 100x100mm mesh (weaved diagonally) including 10% extra for lapse and joints laid with stone boulder weighting not less than 40Kg.each. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	142.56			Per cubic meter.	
3	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	32.40			Per cubic meter.	
Total Rs:-						


 Executive Engineer,
 N.H.Division, HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- Providing MS sheet safety pannels for land slide at Nigulsari from Bhabanagar side)				Estimated Cost:-		488328.00
				Earnest Money:-		9800.00
				Time:-		Ten Days
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required complete as per specifications and direction of the engineer in charge.	2498.320			kg	
2	Providing and fixing MS/Plain or Chequered steel plates including cutting welding complete in pannel over steel frame work(Frame work to be paid seperately) including red lead steel primer as per direction of the engineer in charge.	1396.515			kg	


 Executive Engineer,
 N.H.Division, HP.PWD,
 Rampur Bst.

Schedule of Quantity

Name of work:- R/R damages on NH-305 Sainj Luhri Aut road km 0/000 to 97/000 (Sub Head:- C/O wire crate R/wall at RD. 49/590 to 49/608)

Name of work:- R/R damages on NH-305 Sainj Luhri Aut road km 0/000 to 97/000 (
Sub Head:- C/O wire crate R/wall at RD. 49/590 to 49/608)						
		Estimated Cost:-		467046.00		
		Earnest Money:-		9400.00		
		Time:-		two months		
S. No.	Descriptions	Qty.	In figure	Rate In words.	Unit	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	93.60			Per cubic meter.	
2	Providing and laying of boulder apron laid in wire crate made with 4mm dia G.I. wire confirming to IS 280 and IS 4826 in 100x100mm mesh (weaved diagonally) including 10% extra for lapse and joints laid with stone boulder weighing not less than 40Kg each. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	142.56			Per cubic meter.	
3	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	32.40			Per cubic meter.	
Total Rs:-						

Executive Engineer,
N.H.Division,HP.PWD,
Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O B/wall in R. R. Masonary at Rd. 279/340 to 279/350)

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O B/wall in R. R. Masonary at Rd. 279/340 to 279/350)						
S. No.	Descriptions	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:-			
			In figure	In words.		
1	Cutting in earth work in all kinds of soils such as pick work, jumper work, soft and hard rock i.e. chiselling and wedging out of rock if required and saturated soils and their intermediate classifications in all heights and depths.Stacking the useful stone/materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges including loading of truck for carrying the unserviceable materials. Any loss of Public/ private property during the course of execution shall be the sole responsibility of the contractor which shall have to be duly compensated by him at his own cost in all cases, the work shall be carried out as per clause 301 of section 300 of MORTH specifications to the entire satisfaction and direction of Engineer-in-Charge.	47.90			Per cubic meter.	
2	Random rubble masonry work in cement mortar 1:6 (1 Cement:6 Sand) for sub-structure complete as per drawing & technical specification (Random Rubble masonry coursed/uncoursed) including carriage of all materials within all leads and lifts with all modes of transportation and equipment required to complete the work to the satisfaction of the Engineer-in-Charge.	55.00			Per cubic meter.	
Total Rs:-						

164
Executive Engineer,
N.H.Division, HP.PWD,
Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O PCC R/wall at Rd. 263/442 to 263/445.40)		Estimated Cost:-		435014.00
		Earnest Money:-		8800.00
		Time:-		two months
		In figure	Rate In words.	Unit
S. No.	Descriptions	Qty.	Amount	
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	10.78	Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	64.50	Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	10.20	Per running meter.	

4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	15.30			Per cubic meter.	
Total Rs:-						

Executive Engineer,
N.H.Division,HP.PWD,
Rampur Bsr.

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O B/wall in R. R. Masonary over existing B/wall at Rd. 276/820 to 276/840)

Schedule of Quantity


Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O B/wall in R. R. Masonary over existing B/wall at Rd. 276/820 to 276/840)				Estimated Cost:-		276850.00
				Earnest Money:-		5600.00
				Time:-		One month
S. No.	Descriptions	Qty.	In figure	Rate	Unit	Amount
				In words.		
1	Cutting in earth work in all kinds of soils such as pick work, jumper work, soft and hard rock i.e. chiselling and wedging out of rock if required and saturated soils and their intermediate classifications in all heights and depths,Stacking the useful stone/materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges including loading of truck for carrying the unserviceable materials. Any loss of Public/ private property during the course of execution shall be the sole responsibility of the contractor which shall have to be duly compensated by him at his own cost in all cases, the work shall be carried out as per clause 301 of section 300 of MORTH specifications to the entire satisfaction and direction of Engineer-in-Charge.	33.00			Per cubic meter.	
2	Random rubble masonry work in cement mortar 1:6 (1 Cement:6 Sand) for sub-structure complete as per drawing & technical specification (Random Rubble masonry coursed/uncoursed) including carriage of all materials within all leads and lifts with all modes of transportation and equipment required to complete the work to the satisfaction of the Engineer-in-Charge.	50.20			Per cubic meter.	
Total Rs:-						


 Executive Engineer,
 N.H. Division, HP. PWD,
 Rampur Bsr.

Schedule of Quantity


Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O PCC R/wall at Rd. 263/448 to 263/452.20)		Estimated Cost:-		435014.00		
		Earnest Money:-		8800.00		
		Time:-		two months		
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	10.78			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	64.50			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	10.20			Per running meter.	

4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	15.30			Per cubic meter.	
Total Rs:-						


 Executive Engineer,
 N.H.Division, HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- Protection work to the existing Abutment of machada bridge at RD. 259/295 (U/S)						Estimated Cost:-		427639.00
						Earnest Money:-		8600.00
						Time:-		Two month
S. No.	Descriptions	Qty.	Rate		Unit	Amount		
			In figure	In words.				
1	Providing and fixing Dowel bar of 20mm dia including drilling holes and plugging in the bar with cement grouting including carriage of all materials within all leads and lifts with all modes of transportation and equipment required to complete the work to the satisfaction of the Engineer-in-Charge.	162.00			Per Running meter.			
2	Providing concrete for plain/reinforced cement concrete in open foudation complete as per drawings and technical specifications. PCC Grade M20 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compansated by him at his own cost.	13.00			Per cubic meter.			
3	Providing concrete for plain/reinforced cement concrete in open foudation complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compansated by him at his own cost.	40.56			Per cubic meter.			
Total Rs:-								



 Executive Engineer,
 N.H.Division, HP. PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O PCC R/wall at Rd. 296/746 to 296/754.70)

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O PCC R/wall at Rd. 296/746 to 296/754.70)						
S. No.	Descriptions	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:-			
			Time:-			
			In figure	Rate In words.	two months	
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	33.49			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	70.55			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	21.75			Per running meter.	

4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	7.30			Per cubic meter.	
Total Rs:-						



 Executive Engineer,
 N.H. Division, HP.PWD,
 Rampur Bsr.

Draft Schedule of Quantity

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O PCC R/wall at Rd. 298/569.50 to 298/577.50)

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O PCC R/wall at Rd. 298/569.50 to 298/577.50)				Estimated Cost:-		342827.00
				Earnest Money:-		6900.00
				Time:-		two months
S. No.	Descriptions	Qty.	In figure	Rate In words.	Unit	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	23.12			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	51.92			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	19.20			Per running meter.	

4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	9.76			Per cubic meter.	
Total Rs:-						


 Executive Engineer,
 N.H.Division, HP.PWD,
 Rampur Bsr.

Draft Schedule of Quantity

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O PCC R/wall at Rd. 298/560 to 298/569)

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O PCC R/wall at Rd. 298/560 to 298/569)							Estimated Cost:- 385681.00	
							Earnest Money:- 6900.00	
							Time:- two months	
S. No.	Descriptions	Qty.	Rate		Unit	Amount		
			In figure	In words.				
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	26.01			Per cubic meter.			
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	58.41			Per cubic meter.			
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	21.60			Per running meter.			

4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	10.98				Per cubic meter.	
Total Rs:-							



 Executive Engineer,
 N.H. Division, H.P. PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on NH-305 Sainj Luhri Aut road km 0/000 to 97/000 (Sub Head:- C/O PCC/wall at RD.35/710 to 35/720.80)


Name of work:- R/R damages on NH-305 Sainj Luhri Aut road km 0/000 to 97/000 (Sub Head:- C/O PCC/wall at RD.35/710 to 35/720.80)						
S. No.	Descriptions	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:-			
			Time:-			
			In figure	Rate In words.	two months	
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	31.75			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	69.85			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	25.92			Per running meter.	

4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	17.71			Per cubic meter.	
Total Rs:-						


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- Providing MS sheet safety pannels for land slide at Nigulsari from Chaura side)				Estimated Cost:-		488328.00
				Earnest Money:-		9800.00
				Time:-		Ten Days
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required complete as per specifications and direction of the engineer in charge.	2498.320			kg	
2	Providing and fixing MS/Plain or Chequered steel plates including cutting welding complete in pannel over steel frame work(Frame work to be paid seperately) including red lead steel primer as per direction of the engineer in charge.	1396.515			kg	


 Executive Engineer,
 N.H.Division, HP. PWD,
 Rampur Bsr.

Draft Schedule of Quantity

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O PCC R/wall at Rd. 296/277 to 296/287)

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O PCC R/wall at Rd. 296/277 to 296/287)							Estimated Cost:-		301532.00
							Earnest Money:-		6100.00
							Time:-		two months
S. No.	Descriptions	Qty.	Rate		Unit	Amount			
			In figure	In words.					
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	11.83			Per cubic meter.				
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	47.54			Per cubic meter.				
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	25.00			Per running meter.				
Total Rs:-									


Executive Engineer,
N.H.Division, HP.PWD,
Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O Trapezoidal shape drain along with Steel grating between Km. 267/590 to 267/645))

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O Trapezoidal shape drain along with Steel grating between Km. 267/590 to 267/645))						
S. No.		Descriptions	Qty.	Estimated Cost:-		
				Earnest Money:-		
				Time:-		
				In figure	Rate In words.	Unit
					two months	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	36.08			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	16.15			Per cubic meter.	
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	33.423			Per Qtl.	
Total Rs:-						

Executive Engineer,
N.H.Division, HP.PWD,
Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O PCC R/wall at Rd. 298/560 to 298/569)

Name of work:- R/R damages on NH-05 Km. 236/00 to 368/00 (Sub Head:- C/O PCC R/wall at Rd. 298/560 to 298/569)		Estimated Cost:-		454769.00		
		Earnest Money:-		9100.00		
		Time:-		two months		
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	43.20			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	64.70			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	24.00			Per running meter.	

4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	10.50			Per cubic meter.	
Total Rs:-						


 Executive Engineer,
 N.H.Division, HP.PWD,
 Rampur Bsr.