

NO/PW/TLD/Tender/2022:-
To

Himachal Pradesh
Public Works Department

8432-41

Dated:- 12/10/23

Executive Engineer IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2

Subject:- Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Principal Secretary (PW), to the Govt. of HP letter No. PBW (B) 1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- NIT.

Executive Engineer,
Thalout Division, HPPWD,
Thalout.

HPPWD Mandi for information please.

Copy is forwarded to Superintending Engineer, 1st Circle,

Division.

Copy to All the Assistant Engineers working under this

Copy to AB/DB in this office.

Copy to Notice board.

Executive Engineer,
Thalout Division, HPPWD,
Thalout.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDER"**

Scaled percentage rate tender on form No. 6&8 for the following works detailed in the table below hereby invited by the Executive Engineer, Thalout Division, HPPWD, Thalout on behalf of Governor of Himachal Pradesh from the eligible contractors of appropriate Class registered in HPPWD as per revised enlistment rule so as to reach in his office on 26.10.2023 at 11.00 A.M. The tenders shall be opened on the same date at 11.30 A.M. in the presence of intending contractors or their authorized representative who wish to be present. The request for issuing tenders form along with earnest money must reach in his office up to 3.00 P.M. on 23.10.2023 and that tender documents can be had from his office on cash payment noted against each (Non-Refundable) on 25.10.2023 up to 5.00 P.M on any working day. Notice Inviting Tender and other specification and conditions of the tender can be seen by the contractor in the office of the Executive Engineer, Thalout Division, HPPWD, Thalout during office hour on any working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Cost of form	Time Period for completion	Form No.	Eligibility of Contractors
1	RRD on Bali Thachi road km. 0/0 to 25/0 (SH :-C/O R/wall at RD. 5/550 to 5/560)	465243/-	10000/-	Rs. 350/-	One Month	6&8	Class D enlisted in HPPWD
2	RRD on Nauna to Sudhrani road km. 0/0 to 14/0 (SH :-C/O B/wall at RD. 12/395 to 12/414)	306435/-	6500/-	Rs. 350/-	One Month	6&8	-do-
3	RRD on Masad to Banoul road km. 0/0 to 4/500 (SH :-Hiring of JCB for removal of slips & Hiring of Tipper for removal of slips/muck debris in km. 0/0 to 4/500)	495200/-	10000/-	Rs. 350/-	One Month	6&8	-do-
4	RRD on Nauna to Sudhrani road km. 0/0 to 14/0 (SH :-C/O R/wall at RD. 12/736.60 to 12/744.90)	369399/-	8000/-	Rs. 350/-	One Month	6&8	-do-
5	RRD on Hanogi Bandhi road km. 0/0 to 17/0 (SH :-C/O crate R/wall at RD. 12/765 to 12/785)	481322/-	10000/-	Rs. 350/-	One Month	6&8	-do-
6	RRD on Hanogi Bandhi road km. 0/0 to 17/0 (SH :-C/O crate R/wall at RD. 12/800 to 12/820)	480182/-	10000/-	Rs. 350/-	One Month	6&8	-do-
7	RRD on Sharanallah Odidhar Barshi Drauli road km. 0/0 to 9/0 (SH :-C/O R/wall at RD. 2/225 to 2/240)	310684/-	6500/-	Rs. 350/-	One Month	6&8	-do-
8	C/O link road from ATP road to GSSS Kot Snore (BSP/2020/77 (SH :-C/O C/O crate B/wall & R/wall)	284821/-	6000/-	Rs. 350/-	One Month	6 & 8	-do-
9	RRD on Nauna to Sudhrani road km. 0/0 to 14/0 (SH :-C/O R/wall at RD. 13/136 to 13/152)	499520/-	10000/-	Rs. 350/-	One Month	6&8	-do-
10	RRD on Thach to Kashoud road km. 0/0 to 6/345 (SH :-C/O crate R/wall at RD. 6/007.50 to 6/015)	349819/-	7000/-	Rs. 350/-	One Month	6&8	-do-

11	RRD on Thach to Kashoud road km. 0/0 to 6/345 (SH :-C/O crate R/wall at RD. 6/00 to 6/007.50)	350233/-	7100/-	Rs. 350/-	One Month	6&8	-do-
12	RRD on Basan to Kalhani road km. 0/0 to 10/0 (SH :-C/O crate R/wall at RD.2/935 to 2/950)	400956/-	8100/-	Rs. 350/-	One Month	6&8	-do-
13	RRD on Hanogi to Bandhi road km. 0/0 to 10/0 (SH :-C/O crate R/wall at RD.7/285 to 7/300)	368360/-	7500/-	Rs. 350/-	One Month	6&8	-do-
14	RRD on Hanogi to Bandhi road km. 0/0 to 10/0 (SH :-C/O crate R/wall at RD.5/650 to 5/665)	497724/-	10000/-	Rs. 350/-	One Month	6&8	-do-
15	RRD on Hanogi to Bandhi road km. 0/0 to 10/0 (SH :-C/O crate B/wall at RD.11/615 to 11/645)	286916/-	6000/-	Rs. 350/-	One Month	6&8	-do-
16	RRD on Nauna to Sudhrani road km. 0/0 to 14/0 (SH :-C/O R/wall at RD.11/640 to 11/651)	499968/-	10000/-	Rs. 350/-	One Month	6 & 8	-do-
17	RRD on Karthach to Koon road km. 0/0 to 7/0 (SH :-C/O R/wall at RD. 1/685 to 1/695)	306296/-	6500/-	Rs. 350/-	One Month	6&8	-do-
18	RRD onBali Thachi road km. 0/0 to 25/0 (SH :-C/O R/wall at RD. 7/675 to 7/683)	378069/-	8000/-	Rs. 350/-	One Month	6&8	-do-
19	RRD on Bali Thachi road km. 0/0 to25/0 (SH :- C/O R/wall at RD. 3/725 to 3/737)	251264	5000	Rs. 350/-	One Month	6&8	-do-
20	RRD on Bali Thachi road km. 0/0 to 25/0 (SH :- C/O R/wall at RD. 14/888 to 14/893)	147559/-	3000/-	Rs. 350/-	One Month	6&8	-do-
21	C/O balance work of four rooms and one science lab in Govt, Senior Secondary School Farsh, Tehsil Aut Distt. Mandi (HP) (SH:- P/L brick masonary,plastering work and cement concrete flooring in 1st floor) Deposit	494247/-	10000/-	Rs. 350/-	One Month	6&8	-do-
22	RRD onHatoun Bhabas Bons Muthal road km. 0/0 to 7/0 (SH :- Removal of slips/muck debrisin various RDs.km. 3/500 to 7/0	498542/	10000/-	Rs. 350/-	One Month	6&8	-do-
23	RRD on Sudharani Thatta road km. 0/0 to 5/500 (SH :- C/O R/wall at RD. 4/205 to 4/215)	489520	10000	Rs. 350/-	One Month	6&8	-do-
24	RRD on Dhunju to Kareri road km. 0/0 to2/500 (SH :- C/O R/wall at RD. 2/410 to 2/417)	267190	5400	Rs. 350/-	One Month	6&8	-do-

25	RRD on Bakhali to Kholanal road km. 0/0 to 18/500(SH :- C/O R/wall at RD. 0/280 to 0/296)	499079/-	10000/-	Rs. 350/-	One Month	6&8	-do-
26	RRD on Nauna to Sudharani road km. 0/0 to 14/00(SH :- C/O R/wall at RD. 12/600 to 12/606)	234660	4800	Rs. 350/-	One Month	6&8	-do-
27	RRD on Bakhali to Kholanal road km. 0/0 to 18/500(SH :- C/O R/wall at RD. 1/650 to 1/668)	498241/-	10000/-	Rs. 350/-	One Month	6&8	-do-
28	Repair and maintenance of Pandoh Dam to Rest House Pandoh road km. 0/0 to 1/200 to connect the NH-003 (SH :- Providing and laying 50 mm. thick BM and tack coat in km. 0/0 to 0/200)	495630/-	10000	Rs. 350/-	One Month	6&8	-do-
29	RRD on Nauna to Sudharani road km. 0/0 to 14/00(SH :- C/O R/wall at RD. 12/955 to 12/963.50)	238091	4800	Rs. 350/-	One Month	6&8	-do-
30	RRD on Nauna to Sudharani road km. 0/0 to 14/00(SH :- C/O B/wall at RD. 0/715 to 0/730)	351212	7000	Rs. 350/-	One Month	6&8	-do-
31	RRD on Mani to Shegali road km. 0/0 to 6/0 (SH :- C/O R/wall at RD. 0/697 to 0/707) under SCDP	455631	9200	Rs. 350/-	One Month	6&8	-do-
32	RRD on Lambathach, Shilibagi, Kalhani Pandoh road km.36/0 to 62/0 (SH :- C/O crated R/wall at RD. 49/555 to 49/562)	191247/-	4000/-	Rs. 350/-	One Month	6&8	-do-
33	RRD on Sudharani to Thatta road km. 0/0 to 5/500 (SH :- C/O R/wall at RD. 4/215 to 4/217.50)	130055	3000	Rs. 350/-	One month	6&8	-do-
34	RRD on Bali Thachi road km. 0/0 to 25/0 (SH :- C/O RCC hume pipe culvert at RD. 14/840)	484780	9700	Rs. 350/-	One Month	6&8	-do-
35	RRD on Bali Thachi road km. 0/0 to 25/0 (SH :- C/O R/wall at RD. 16/604.50 to 16/609)	330038	6600	Rs. 350/-	One month	6&8	-do-
36	RRD on Lambathach, Shilibagi, Kalhani Pandoh road km.36/0 to 62/0 (SH :- C/O crated R/wall at RD. 49/580 to 49/592)	453316/-	9100/-	Rs. 350/-	One Month	6&8	-do-
37	RRD on Bali Thachi road km. 0/0 to 25/0 (SH :- C/O R/wall at RD. 16/600 to 16/604.50)	329768	6600	Rs. 350/-	One Month	6&8	-do-

38	RRD on Nauna to Sudharani road km. 0/0 to 14/00 (SH :- C/O R/wall at RD. 11/680 to 11/689.50)	458512	9200	Rs. 350/-	One Month	6&8	-do-
39	RRD on Bouchari to Kandha road km. 0/0 to 12/0 (SH :- C/O RCC hume pipe culvert at RD. 9/180)	139862	2800	Rs. 350/-	One Month	6&8	-do-
40	RRD on Bali Thachi road km. 0/0 to 25/0 (SH :- C/O R/wall in wire crate at RD. 14/990 to 15/006.80)	332491	6600	Rs. 350/-	One Month	6&8	-do-
41	RRD on Nagwain Balu road km. 0/0 to 12/500 (SH :- C/O R/wall at RD. 6/308 to 6/320)	312535/-	6500	Rs. 350/-	One Month	6&8	-do-
42	RRD on Bhurah to Panjain road km. 0/0 to 11/0 (SH :- C/O R/wall at RD. 1/480 to 1/500 and R/wall at RD 1/650 to 1/670)	433619	8700	Rs. 350/-	One Month	6&8	-do-
43	RRD on Thalout Panjain Thachi Shetadhar road km. 0/0 to 40/0 (SH :- C/O B/wall at RD. 3/925 to 3/940 and R/wall at RD. 3/915 to 3/935)	499408	10000	Rs. 350/-	One Month	6&8	-do-
44	RRD on Thalout Panjain Thachi Shetadhar Chet Chiuni Lambathach road km. 0/0 to 75/0 (SH :- C/O R/wall at RD 11/038 to 11/050)	334169	6700	Rs. 350/-	One Month	6&8	-do-
45	RRD on Bakhali to Kholanal road km. 0/0 to 18/5000 (SH :- C/O R/wall at RD 1/735 to 1/744)	482510/-	10000	Rs. 350/-	One Month	6&8	-do-
46	Repair and maintenance of Pandoh Dam to Rest House Pandoh road km. 0/0 to 1/200 to connect the NH-003 (SH :- Providing and laying 50 mm. thick BM and tack coat in km. 0/200 to 0/400)	495630/-	10000	Rs. 350/-	One Month	6&8	-do-
47	RRD on Bakhali to Kholanal road km. 0/0 to 18/5000 (SH :- C/O R/wall at RD 0/355 to 0/365)	418583/-	9000/-	Rs. 350/-	One Month	6&8	-do-
48	RRD on Thalout Kalhanl road km. 0/0 to 10/0 (SH :- C/O R/wall at RD 3/360 to 3/376.80)	388616	8000/-	Rs. 350/-	One Month	6&8	-do-
49	RRD on Chhakidhar to Dobha via Malai road km. 0/0 to 5/0 (SH :- C/O R/wall at RD. 1/037.80 to 1/044)	499942/-	10000/-	Rs. 350/-	One Month	6&8	-do-

50	RRD on Thalout Kalhani road km. 0/0 to 10/0 (SH :- C/O R/wall at RD 0/355 to 0/370)	498368	10000	Rs. 350/-	One Month	6&8	-do-
51	Repair and maintenance of Pandoh Dam to Rest House Pandoh road km. 0/0 to 1/200 to connect the NH-003 (SH :- Providing and laying 50 mm. thick BM and tack coat in km. 0/600 to 0/800)	495630/-	10000	Rs. 350/-	One Month	6&8	-do-
52	RRD on Chhakidhar to Dobha via Malai road km. 0/0 to 5/0 (SH :-C/O R/wall at RD. 1/031.80 to 1/037.80)	493325/-	10000/-	Rs. 350/-	One Month	6&8	-do-
53	R/R Damages onThalout to Kalhani road up to Dhunju km. 0/0 to 10/0 (SH:- Removal of slips at various RDs. in km. 5/0 to 10/00)	498561/-	10000	Rs. 350/-	One Month	6&8	-do-
54	Repair and maintenance of Pandoh Dam to Rest House Pandoh road km. 0/0 to 1/200 to connect the NH-003 (SH :- Providing and laying 50 mm. thick BM and tack coat in km. 0/400 to 0/600).	495630/-	10000	Rs. 350/-	One Month	6&8	-do-

TERMS & CONDITIONS: -

1. The Tender form will not be issued to those contractors whose performance is not found satisfactory.
2. The Contractor whose rates are abnormally low may be asked to furnish the full justification of his rate failing which he will be debarred to complete in tendering for four months.
3. The Contractor must be ensured that he is not having more than two works in hand and their detail must be prescribed in the proforma & attached with the application and only upto completion of work satisfactory including adherence to quality parameters further work will be awarded to him & two jobs shall be considered in one application subject to above.
4. The rates beyond the limit over +5% will be rejected besides this the Additional Performance security will have to borne @ 20 % & 30 % for unbalanced bid in case the rates is lower than 10 % but upto 20 % & lower than 20 % upto 30 % respectively. The tender will be accepted beyond the limit of -30 % also.

Executive Engineer,
Thalout Division,
HPPWD Thalout

NO/PW/TLD/Tender/2023:-8412-31

Dated:- 12.10.2023


Copy forwarded to the following for information and necessary action:-

1. The Engineer-in-Chief HPPWD Shimla.
2. The Deputy Commissioner Mandi Distt. Mandi HP.
3. The Sub Divisional Officer Balichowki, Distt. Mandi HP.
4. The Chief Engineer, (MZ) HPPWD Mandi.
5. The Superintending Engineer, Ist Circle, HPPWD Mandi HP.
6. The Distt. Panchayat Officer Mandi HP.
7. All AEs under this Division.
8. The President of Contractor's Association.
9. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies.

Executive Engineer,
Thalout Division,
HPPWD Thalout

Certificate

Certified that the tender called vide this office letter NO.
PW/TLD/Tender/2023-8412-31 dated 12.10.2023 is emergent nature and in Public interest.


Executive Engineer,
Thalout Division, HPPWD,
Thalout.

SCHEDULE OF QUANTITY

Name of work: R.E.H. on Thal Thuchl road Km 0/0 to 23/0 (S.N. C/30 H/wall at 000 17/550 to 0/560)

Estimated Cost: Rs. 465243.00
 Earned Money: Rs. 9400.00

Time: One Month

Sl. No.	Description of item	Qty	In figure	Unit		Amount
				In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and erecting, removal of slumps and other obstructions material and disposal upto in all level (disposing of sides and bottom and backfilling in latter with gravel) suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	30.00	3501.20	Rupees Three hundred ninety eight and paise twenty only	Per Cubic Metre	12249.60
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 plain cement concrete 1:0.12 (one cement six sand twelve graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	4.00	4400.60	Rs. Four thousand four hundred and paise sixty only	Per Cubic Metre	21123.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 plain cement concrete 1:4:8 (one cement four sand eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	70.60	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	389371.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	20.05	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	25331.00
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical is to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	44	391.20	Rupees Three hundred ninety one and paise twenty only	Each	17213.00
Rate Quoted by contractor (+/-)					Total	465243.00
Quoted rate in figures						
Quoted rate in words						

Executive Engineer,
 Thalout Division,
 HPPWD, Thalout

2

SCHEDULE OF QUANTITY

Name of work:- RRD on Nouna to Sudhrani road Km. 0/0 to 14/0 (SH:- C/O B/wall at RD 12/395 to 12/414)

Estimated Cost:- Rs. 306435.00
Earnest Money :- Rs. 6200.00
Time :- One Month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.50 metre in width as well as 10 sqm. on plan) including getting out and disposal of excavated earth lead up to 50 metre and lift up to 1.50 metre including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	81.32	139.40	Rupees One hundred thirty nine and paise forty only.	Per Cubic Metre	11336.00
2	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	17.67	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	7036.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802, 803, 1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	56.81	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	277892.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	26	391.20	Rupees Three hundred ninety one and paise twenty only	Each	10171.00
					Total	306435.00
	Rate Quoted by contractor (+/-)					
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HPPWD, Thalout

3

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
Name of work:- Restoration of damages on Masard to Banoul road km 0/0 to 4/500 (SH:- Hiring of JCB for removal of slips & Hiring of Tipper for removal of slips/ muck debris in km. 0/00 to 4/500)				Estimated Cost:- 495200.00		
				Earnest Money:- 10000.00		
				Time:- One Month		
S.No.	Description of item		Figure	Rate in	Unit	Amount
				Words		
1	Hiring of JCB Machine to be deployed for snow/cutting excavation/filling removal on cost of fuel oil Lubricants and wages of operating staff any repair during operation will be carried out by the owner on his risk and cost of the shifting of machinery from one place to other at required location actual working hours will be accounted for the payment. Excavation in all kind of soil and loading in truck during the process of removal of debris if required at site complete in all respect as per direction of Engineer-in Charge.	370.00	1200.00	Rs. One thousand two hundred only	Per Hour	444000.00
2	Hiring of Tipper for carriage of debris/ muck / unserviceable material from the various reaches of the road including all leads, lifts and unloading of material at suitable places as per entire satisfaction of Engineer-in-Charge (9.00 am to 5.00 pm) Terms and conditions:- 1. The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge. 2. During working hours any type of accident the owner is responsible.	16.00	3200.00	Rupees Three thousand two hundred only	Per day	51200.00
Total						495200.00

Executive Engineer,
Thalout Division (B&R)
HP PWD Thalout.

Executive Engineer,
Thalout Division (B&R),
HP PWD Thalout.

1

SCHEDULE OF QUANTITY

Name of work:- RRD on Nauna Sudhrani road Km 0/00 to 14/00 (SH:- C/O R/wall at Rd 12/736.60 to 12/744.90)

Estimated Cost:- 369399.00
Earnest Money :- 7500.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 metre (fifty meter) dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge	28.22	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	11237.00
2	Providing and laying concrete for plain/reinforced concrete in 1:6:12 (one cement: six sand: Twelve crushed / stone aggregate) 40 mm (forty millimeter) nominal size open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge	3.32	4400.60	Rs. four Thousand four hundred and paise Sixty only	Per Cubic Metre	14610.00
3	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone aggregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge	64.07	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	313405.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204. 3.8 including all lead and lift and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	16.43	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	20758.00
5	Providing weepholes in brick masonry/stone masonry /plain reinforced cement abutment wing wall, return wall with 100 mm (hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One vertical: twenty horizontal) with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	24	391.20	Rs. Three hundred ninety one and paise twenty only	Each	9389.00
					Total	369399.00

Executive Engineer,
Tbalout Division,
R.P.W.D. Thalcutty

5

SCHEDULE OF QUANTITY

Name of work:- RRD on Hanogi to Bandhl, Kandha road Km 0/0 to 17/00 (SH:- C/O R/wall in wire crate at RD 12765 to 12785)

Estimated Cost: 481322.00
 Earnest Money :- 10000.00
 Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other detritious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	56.40	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	22458.00
2	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone ssgregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	28.80	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	140878.00
3	Providing and laying of Boulder upron laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less then 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts, carriage of materials and other incidental complete.	96.77	3098.00	Rs. Three thousand ninety eight and paise seventy only	Per Cubic Metre	299793.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	14.40	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	18193.00
Total in figures					Total	481322.00
Rate quoted by contractor +/-						
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
 Thaloout Division,
 PWD, Thaloout

SCHEDULE OF QUANTITY

Name of work:- RRD on Hanogj Bandhl, Kandha road Km 0/0 to 17/00 (SH:- C/O B/wall in wire crate at RD 12/800 to 12/820).

Estimated Cost: 480182.00
Earnest Money :- 10000.00

Time :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre (One point five meter) and a lead upto 20 metre (Twenty meter) as per technical specification clause 1603.1 + 1603.2 and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	54.00	140.20	Rs. one hundred forty and paise twenty only	Per Cubic Metre	7571.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	57.60	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	22936.00
3	Providing and laying of Boulder upon laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less then 25 kg each as per drawing and technical specifications clause 1301 within all leads, lifts,carriage of materials and other incidental complete.	145.15	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	449675.00
Total in figures					Total	480182.00
	Quoted rate in figure				Rate quoted by contractor +/-	
	Quoted rate in words					

Executive Engineer,
Thalout Division,
H.P.W.D. Thalour

57

SCHEDULE OF QUANTITY

Name of work:- RRD on Shara Odidhar Barshi Draunil road km 0/00 to 9/00 (SH:- C/o R/wall at RD 2/225 to 2/240)

Estimated Cost:- 310684.00
Earnest Money :- 6500.00
Time :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	46.50	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	18516.00
2	Providing and laying concrete for plain/reinforced concrete in 1:6:12 (one cement six sand: Twelve crushed / stone aggregate) 40 mm (forty millimetre) nominal size open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	6.45	4400.60	Rs. four Thousand four hundred and paise Sixty only	Per Cubic Metre	28384.00
3	Stone masonry work in Random Rubble masonry in cement mortar 1:6 (one cement: 6 sand) in foundation complete as per drawing and technical specifications Clause 702.704.1202 and 1203 including all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	22.65	5197.20	Rs. Five thousand one hundred ninety seven and paise twenty only	Per Cubic Metre	117717.00
4	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub structure complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer-in-Charge.	34.20	3751.20	Rs. Three thousand Seven hundred fifty one and paise twenty only	Per Cubic Metre	128291.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	14.07	1263.40	Rs One thousand two hundred sixty three and paise forty only	Per Cubic Metre	17776.00
Total in figures						310684.00
Rate quoted by contractor +/-				Percent		
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
Thaloul Division,
H.B. P.W.O. Thaloul,
9

Name of work:- Construction of link road from Aut Takoll Parashar road to GSSS Kot Snore.
(SH:- C/O Crated B/wall and PCC R/wall). (BSP/2020/77) Deposit

SCHEDULE OF QUANTITY

Estimated Cost:- 2,84,821.00
Earnest Money :- 6000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	63.92	213.45	Rs. Two hundred thirteen and paise forty five only.	Per Cubic Metre	13644.00
2	Providing and laying of Boulder upon laid in wire crates with 4 mm (Four millimetre) dia G.I. wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm (one hundred millimetre x one hundred millimetre) mesh (woven) diagonally) including 10 (Ten) percent extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	41.48	2628.95	Rs. Two thousand six hundred twenty eight and paise ninety five only	Per Cubic Metre	109049.00
3	Providing and laying in position cement concrete 1:6:12 (one cement: six sand :twelve graded stone aggregate) bedding of specified grade including shuttering complete within all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	2.59	4400.60	Rs. Four thousand four hundred and paise sixty only	Per Cubic Metre	11398.00
4	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre size) as per entire satisfaction and direction of Engineer-in-Charge.	28.39	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	138873.00
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204,3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	12	391.20	Rupees Three hundred ninety one and paise twenty only	Each	4694.00
6	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204,3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	5.67	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	7163.00
Total in Figures			Percent			284821.00
Rate Quoted by contractor +/-						
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
Thalout Division (B&R),
HPPWD, Thalout

9

SCHEDULE OF QUANTITY

Name of work:- RRD on Nauna Sudhranal road Km 0/00 to 14/00 (SH:- C/O R/wall at Rd 13/136 to 13/152)

Estimated Cost:- 499520.00
Earnest Money :- 10000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dig. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 metre (fifty meter) dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge	50.08	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	19942.00
2	Providing and laying concrete for plain/reinforced concrete in 1:6:12 (one cement: six sand: Twelve crushed / stone aggregate) 40 mm (forty millimetre) nominal size open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	6.08	4400.60	Rs. four Thousand four hundred and paise Sixty only	Per Cubic Metre	26736.00
3	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone aggregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	84.64	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	414025.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204. 3.8 including all lead and lift and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	20.80	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	26279.00
5	Providing weepholes in brick masonry/stone masonry /plain reinforced cement abutment wing wall, return wall with 100 mm (hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One vertical: twenty horizontal) with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	32	391.20	Rs. Three hundred ninety one and paise twenty only	Each	12518.00
					Total	499520.00

Executive Engineer,
Talout Division,
P.W.D., Thalout.

SCHEDULE OF QUANTITY

Name of work:- RRD on Thach to Kashoud road Km. 0/0 to 6/345 (SH:-C/O R/wall in wire crates at RD 6/007.50 to 6/015)

Estimated Cost :- Rs. 349819.00
Earnest Money :- Rs. 7000.00
Time :- One Month

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	34.61	398.20	Rs. Three hundred ninety eight and paise twenty only.	Per Cubic Metre	13782.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 plain cement concrete 1:4:8 (one cement four Sand: eight graded stone aggregate 40mm (forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	43.88	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	214643.00
3	Providing and laying of Boulder upon laid in wire crates with 4 mm (Four millimetre) dia G.I. wire conforming to IS : 280 and IS-4826 in 150 mm x 150 mm (one hundred fifty millimetre x one hundred fifty millimetre) mesh (woven) diagonally) including 10 (Ten) percent extra for laps and joints laid with stones boulders weighing not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	35.16	2769.40	Rs. Two thousand seven hundred sixty nine and paise forty only	Per Cubic Metre	97372.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	16	391.20	Rupees Three hundred ninety one and paise twenty only	Each	6259.1
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	14.06	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	1776
	Total					349819


 Executive Engineer
 Thachout Divisi
 HPPWD, Thach

SCHEDULE OF QUANTITY

Name of work:- RRD on Thach to Kashoud road Km. 0/0 to 6/345 (SH:- C/O R/wall in wire crates at RD 6/0 to 6/007.50)

Estimated Cost :- Rs. 3,50,233.00
Earnest Money :- Rs. 7100.00

Time :- One Month

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	29.21	398.20	Rs. Three hundred ninety eight and paise twenty only.	Per Cubic Metre	11631.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate 40mm (forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	43.88	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	214643.00
3	Providing and laying of Boulder upon laid in wire crates with 4 mm (Four millimetre) dia G.I. wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm (one hundred fifty millimetre x one hundred fifty millimetre) mesh (woven) diagonally including 10 (Ten) percent extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	35.16	2769.40	Rs. Two thousand seven hundred sixty nine and paise forty only	Per Cubic Metre	97372.00
4	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	16	391.20	Rupees Three hundred ninety one and paise twenty only	Each	6259.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	16.09	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	20328.00
	Total					350233.00


 Executive Engineer,
 Thalout Division,
 HPPWD, Thalout

12

SCHEDULE OF QUANTITY

Name of work:- RRD on Basan Kalthani road Km. 0/0 to 0/0 (SH:- C/O wire crated R/wall at RD 2/935 to 2/950)

Estimated Cost :- Rs. 400956.00
 Earnest Money :- Rs. 8100.00
 Time :- One Month

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shorting and bracing, removal of stumps and other deleterious material and disposal upto all lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	18.00	398.20	Rs. Three hundred ninety eight and paise twenty only.	Per Cubic Metre	7168.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate 40mm (forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	22.50	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	110061.00
3	Providing and laying of Boulder upon laid in wire crates with 4 mm (Four millimetre) dia G.I. wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm (one hundred fifty millimetre x one hundred fifty millimetre) mesh (woven) diagonally) including 10 (Ten) percent extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	93.76	2769.40	Rs. Two thousand seven hundred sixty nine and paise forty only	Per Cubic Metre	259659.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	19.05	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	24068.00
					Total	400956.00
	Rate Quoted by contractor (+/-)					
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
 Thalout Division,
 BPWD, Thalout

13

SCHEDULE OF QUANTITY

Name of work:- RRD on Hanogi to Bandhi, Kandha road Km 0/0 to 17/00 (SH:- C/O R/wall in wire crate at RD 7/285 to 7/300)

Estimated Cost: 368360.00
Earnest Money :- 7500.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	104.40	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	41572.00
2	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone ssgregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	21.60	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	105659.00
3	Providing and laying of Boulder upron laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less than 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete. (Rate with out wire).	103.69	2001.00	Rs. Two thousand one and paise zero only	Per Cubic Metre	207484.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	10.80	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	13645.00
Total in figures					Total	368360.00
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
H.P.W.D, Thalou

SCHEDULE OF QUANTITY

Name of work:- RRD on Hanogl to Bandhl, Kandha road Km 0/0 to 17/00 (SH:- C/O R/wall in wire crate at RD 5/650 to 5/665)

Estimated Cost: 497724.00
Earnest Money :- 10000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	86.40	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	34404.00
2	Providing and laying of Boulder upron laid in wire crates with 4 mm dia G.I. wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally including 10 percent extra for laps and joints laid with stones boulders weighting not less than 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts, carriage of materials and other incidental complete.	145.15	3098.00	Rs. Three thousand ninty eight and paise zero only	Per Cubic Metre	449675.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	10.80	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	13645.00
Total in figures					Total	497724.00
	Rate quoted by contractor +/-					
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
H.P. PWD, Thalout

SCHEDULE OF QUANTITY

Name of work:- RRD on Hanogi Bandhi, Kandha road Km 0/0 to 17/00 (SH:- C/O B/wall in wire crate at RD 11/615 to 11/645).

Estimated Cost: 286916.00
Earnest Money :- 6000.00

Time :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre (One point five meter) and a lead upto 20 metre (Twenty meter) as per technical specification clause 1603.1 + 1603.2 and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	55.50	140.20	Rs. one hundred forty and paise twenty only	Per Cubic Metre	7781.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	28.80	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	11468.00
3	Providing and laying of Boulder upon laid in wire crates with 4 mm dia G.I. wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less than 25 kg each as per drawing and technical specifications clause 1301 within all leads, lifts, carriage of materials and other incidental complete.	86.40	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	267667.00
Total in figures					Total	286916.00
	Quoted rate in figure				Rate quoted by contractor +/-	
	Quoted rate in words					

Executive Engineer,
Talabot Division,
F.P.W.D. Talabot

(16)

SCHEDULE OF QUANTITY

Name of work:- RRD on Nauna to Sudhrani road Km. 0/0 to 14/0 (SH: C/O R/wall at RD 11/640 to 11/651)

Estimated Cost:- Rs.	499968.00
Earnest Money :- Rs.	10000.00

Time :- One Month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	50.05	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	19930.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 plain cement concrete 1:6:12 (one cement: six sand: twelve graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	5.28	4400.60	Rs. Four thousand four hundred and paise sixty only	Per Cubic Metre	23235.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	87.56	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	428308.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	17.60	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	22236.00
5	Providing weep hole in brick masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical is to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	16	391.20	Rupees Three hundred ninety one and paise twenty only	Each	6259.00
Rate Quoted by contractor (+/-)					Total	499968.00
Quoted rate in figures						
Quoted rate in words						

Executive Engineer,
Thalout Division
HPPWD, Thalout

17

SCHEDULE OF QUANTITY

Name of work:- RRD on Kartthach to Koon road Km. 0/0 to 7/0 (SH:- C/O R/wall at RD 1/685 to 1/695)

Estimated Cost:- Rs. 306296.00
Earnest Money :- Rs. 6200.00
Time :- One Month

Sr. No.	Description of Item	Qty.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	22.80	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	9079.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	19.64	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	96071.00
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 random rubble masonry in cement mortar 1:6 (one cement: six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	16.90	5197.20	Rupees Five thousand one hundred ninety seven and paise twenty only	Per cubic metre	87633.00
4	Construction of Random Rubble dry stone masonry as per MORO specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	21.00	3751.20	Rupees Three thousand seven hundred fifty one and paise twenty only	Per Cubic Metre	78775.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	16.50	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	20846.00
6	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	35	391.20	Rupees Three hundred ninety one and paise twenty only	Each	13692.00
					Total	306296.00
	Rate Quoted by contractor (+/-)					
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,

Thalout Division,

Alleppey, Thalout.

18

SCHEDULE OF QUANTITY

Name of work: RRD on Ball Thachl road km. 0/0 to 25/0 (SH: C/0 R/wall at RD 7/675 to 7/683)

Estimated Cost: Rs.	378069.00
Earnest Money: Rs.	7600.00
Time :- One Month	

Sr. No.	Description of item	Qnys	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	18.00	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	7168.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	11.06	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	54101.00
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702.704.1202 & 1204 random rubble masonry in cement mortar 1:6 (one cement: six sand) complete within all leads. lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	30.32	5197.20	Rupees Five thousand one hundred ninety seven and paise twenty only.	Per cubic metre	157579.00
4	Construction of Random Rubble dry stone masonry as per MORC specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	33.82	3751.20	Rupees Three thousand seven hundred fifty one and paise twenty only	Per Cubic Metre	126866.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	16.32	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	20619.00
6	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical iso twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709.1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	30	391.20	Rupees Three hundred ninety one and paise twenty only	Each	11736.00
Rate Quoted by contractor (+/-)					Total	378069.00
Quoted rate in figures						
Quoted rate in words						

Executive Engineer,
Thalout Division
HPWD, Thaloudky

(19)

SCHEDULE OF QUANTITY

Name of work:- RRD on Ball Thachil road Km. 0/0 to 25/0 (SH:- C/O R/wall at RD 3/725 to 3/737)

Estimated Cost:- Rs.	251264.00
Earnest Money :- Rs.	5000.00
Time :- One Month	

Sr. No.	Description of item	Qlys.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.4 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	14.16	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	5639.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 plain cement concrete 1:6:12 (one cement: six sand: twelve graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	3.40	4400.60	Rs. Four thousand four hundred and paise sixty only	Per Cubic Metre	14962.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	39.72	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	194294.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	17.64	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	22286.00
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709.1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	36	391.20	Rupees Three hundred ninety one and paise twenty only	Each	14083.00
Rate Quoted by contractor (+/-)					Total	251264.00
Quoted rate in figures						
Quoted rate in words						

Executive Engineer,
Thalout Division
MPPWD, Thalout

SCHEDULE OF QUANTITY

Estimated Cost:- 147559.00
Earnest Money :- 3000.00

Executive Engineer,
Thalout Division,
H.P., P.W.D., Thalout.

(21)

/32

before work

SCHEDULE OF QUANTITY

Name of work:- C/O Four rooms and One Science Lab in Govt. Senior Secondary School Farsh, Tehsil Aut, Dist. Mandi (H.P.) (S.H.-: Providing and laying brick masonry, plastering work and cement concrete flooring in first Floor

Estimated Cost:- 494247.00
 Earnest Money:- 9900.00
 Time:- One Month

Sr. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in all shapes and sizes in cement mortar 1:6 (One cement : six coarse sand) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	18.04	14103.70	Rs. Forteen thousand one hundred three and paise seventy only.	Per Cubic Metre	254431.00
2	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in cement mortar 1:3 (one cement : three coarse sand) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	55.68	1679.70	Rs. Sixteen hundred seventy nine and paise seventy only.	Per Cubic Metre	93526.00
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	670.00	150.00	Rs. One hundred fifty and paise zero only.	Per Kilogram	100500.00
4	15mm cement plaster on rough side of single or half brick wall of mix complete in all respect including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	147.90	309.60	Rs. Three hundred nine and paise sixty only.	Per Square meter	45790.00
Total in Figures			Percent			494247.00
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
 Thalout Division (B&R),
 P.P.W.D, Thalout.

SCHEDULE OF QUANTITY

Estimated Cost:-	498542.00
Earnest Money:-	10000.00

Time:- One Month

Executive Engineer,
Thalout Division (B&R),
H/P PWD Thalout.

23

SCHEDULE OF QUANTITY

Name of work:- RRD on Sudhant Thatta road Km 0/00 to 5/500 (SH - C/O R/wall at Rd 4/205 to 4/215)

Estimated Cost: 489520.00
Earnest Money :- 10000.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dfg. and technical specification clause 305 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 metre (fifty meter) dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge	34.60	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	13778.00
2	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed stone aggregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge	46.26	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	226285.00
3	Stone masonry work in cement mortar 1:6 (One cement: six sand) in foundation complete as per drawing and technical specifications Clause 702.704.1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge	21.45	5197.20	Rs. Five thousand one hundred ninety seven and paise twenty only	Per Cubic Metre	109921
4	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub structure complete as per drawing and technical specification Clause 704.6 and 1302.5 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge	29.12	3751.20	Rs. Three thousand Seven hundred twenty one and paise twenty only	Per Cubic Metre	109235
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge	10.05	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	12697.00
6	Providing weepholes in brick masonry/stone masonry /plain reinforced cement abutment wing wall, return wall with 100 mm (hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One vertical: twenty horizontal) with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge	45	391.20	Rs. Three hundred ninty one and paise twenty only	Each	17604.00
		Total				489520.00

Executive Engineer,
Thalour Division,
P.W.D. Thalour

SCHEDULE OF QUANTITY

Name of work:- RRD on Dhunju to Kareel road Km. 0/0 to 2/500 (SH: C/O R/wall at RD 2/410 to 2/417)

240

Estimated Cost:- Rs. 267190.00
Earnest Money :- Rs. 5400.00
Time :- One Month

Sr. No.	Description of item	Qty's	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	25.41	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	10118.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 plain cement concrete 1:6:12 (one cement: six sand: twelve graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	5.04	4400.60	Rs. Four thousand four hundred and paise sixty only	Per Cubic Metre	22179.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	3.01	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	14724.00
4	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702.704.1202 & 1204 random rubble masonry in cement mortar 1:6 (one cement : six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	23.24	5197.20	Rupees Five thousand one hundred ninety seven and paise twenty only.	Per cubic metre	120783.00
5	Construction of Random Rubble dry stone masonry as per MORD specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	20.33	3751.20	Rupees Three thousand seven hundred fifty one and paise twenty only	Per Cubic Metre	76262.00
6	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	12.11	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	15300.00
7	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709.1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	20	391.20	Rupees Three hundred ninety one and paise twenty only	Each	7824.00
Total						267190.00
Rate Quoted by contractor (+/-)						
Quoted rate in figures						
Quoted rate in words						

Executive Engineer,
Tolout Division,
PPWD, Thalout

25

BILL OF QUANTITY

Name of work:- RRD on Bakhtali to Khoulal road Km 0/00 to 18/500 (SH:- C/o PCC Rdwall at RD 0/280 to 0/296)

Estimated Cost:- 499079.00
Earnest Money :- 10000.00
Time :- One Month

S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dty. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	25.10	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	9995.00
2	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone aggregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 with in 3x lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	97.04	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	474681.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	11.40	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	14403.00
Total in figures						499079.00
Quoted rate in figure				Percent		
Quoted rate in words						

Bill of quantity approved for Rs 499079/-only

Executive Engineer,
Thalout Division
RTP PWD, Thalout

820

SCHEDULE OF QUANTITY

Name of work:- RRD on Nouna to Sudhrani road Km. 0/0 to 14/0 (SH:- C/O R/wall at RD 12/600 to 12/606)

Estimated Cost:- Rs. 234660.00

Earnest Money :- Rs. 4600.00

Time :- One Month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	15.69	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	6248.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 plain cement concrete 1:6:12 (one cement: six sand: twelve graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	2.58	4400.60	Rs. Four thousand four hundred and paise sixty only	Per Cubic Metre	11354.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	39.36	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	192533.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	12.60	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	15919.00
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical iso twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	22	391.20	Rupees Three hundred ninety one and paise twenty only	Each	8606.00
Total						234660.00
Rate Quoted by contractor (+/-)						
Quoted rate in figures						
Quoted rate in words						

Executive Engineer,

Thalout Division ,

PPWD, Thalout

27

81

BILL OF QUANTITY

Name of work:- RRD on Bakhal to Kholanal road Km 0/00 to 18/500 (SH:- C/O PCC Rdwall at RD 1/650 to 1/668)

Estimated Cost:- 498241.00
Earnest Money :- 10000.00
Time :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In Figure	In word		
1	Earth work in excavation for structure as per dry. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a head of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	42.12	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	16772.00
2	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement four sand eight crushed/ stone ssgregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	95.22	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	465778.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	12.42	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	15691.00
Total in figures						498241.00
	Quoted rate in figure		Rate quoted by contractor +/-		Percent	
	Quoted rate in words					

Bill of quantity approved for Rs. 4,98,241/- only

Executive Engineer,
Raibout Division,
P.W.D. Thalout

28

SCHEDULE OF QUANTITY

Name of work:- Repair and maintenance of Pandoh Dam to Rest House Pandoh road Km. 0/0 to 1/200 to connect the NH-03 (SH :- Providing and laying 50mm thick BM and tack coat in Km 0/00 to 0/200).

Estimated Cost:- 495630.00
Earnest Money :- 10000.00
Time :- One Month

Sr.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Providing and laying bituminous macadam using crushed stone aggregates of specified grading premixed with bituminous binder, transported to site by tippers, laid over a previously prepared surface with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge 50 to 100 mm (Fifty to one hundred millimetre) average compacted thickness with bitumen of grade VG-30 @ 3.50% (At the rate of three point five zero percent) (percentage by weight of total mix) prepared in Batch Type Hot Mix Plant of 100-120 TPH capacity including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	32.02	14391.60	Rs.Forteen thousand three hundred ninety one and paise sixty only	Per Cubic Metre	460819.00
2	Providing and applying tack coat using hot straight run bitumen of grade VG - 10, including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications on bituminous surface @ 0.50 Kg / sqm (At the rate of zero point five zero kilogram per square metre) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	640.50	54.35	Rs.Fifty four and paise thirty five only	Per Cubic Metre	34811.00
Total in figures						495630.00
	Quoted rate in figure		Rate quoted by contractor +/-			
	Quoted rate in words		Percent			

Executive Engineer,
Thalout Division,
H.P.W.D, Thalout

29

SCHEDULE OF QUANTITY

Name of work:- RRD on Nauna Sudhrani road Km 0/00 to 14/00 (SH:- C/O R/wall at Rd 12/955 to 12/953.50)

Estimated Cost:- 238091.00
Earnest Money :- 4800.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dty. and technical specification clause 305.1 w/c setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal up to a lead of 50 metre (fifty meter) dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge	19.25	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	7665.00
2	Providing and laying concrete for plain/reinforced concrete in 1:6:12 (one cement: six sand: Twelve crushed / stone aggregate) 40 mm (forty millimetre) nominal size open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	4.17	4400.60	Rs. four Thousand four hundred and paise Sixty only	Per Cubic Metre	18351.00
3	Stone masonry work in cement mortar 1:6 (One cement: six sand) in foundation complete as per drawing and technical specifications Clause 702.704.1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	17.36	5197.20	Rs. Five thousand one hundred ninety seven and paise twenty only	Per Cubic Metre	90223
4	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification Clause 704.6 and 1302.5 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	25.38	3751.20	Rs. Three thousand Seven hundred twenty one and paise twenty only	Per Cubic Metre	95205
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204. 3.8 including all lead and lift and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	14.28	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	18041.00
6	Providing weepholes in brick masonry/stone masonry /plain reinforced cement abutment wing wall, return wall with 100 mm (hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One vertical: twenty horizontal) with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	22	391.20	Rs. Three hundred ninety one and paise twenty only	Each	8606.00
Total						238091.00

Executive Engineer,
Thalout Division,
P.W.D., Thalout

30

SCHEDULE OF QUANTITY

Name of work:- RRD on Nouna Sudhrami road Km. 0/0 to 14/0 (SH:- C/O R/wall at RD 0/715 to 0/730)

Estimated Cost:- Rs.	351212.00
Farrest Money :- Rs.	7000.00

Time :- One Month

Sr. No.	Description of item	Qty's	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth. 1.50 metre in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead up to 50 metre and lift up to 1.50 metre including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	71.55	140.20	Rupees One hundred forty and paise twenty only	Per Cubic Metre	10031.00
2	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	24.68	398.20	Rupees Three hundred ninety eight and paise twenty only	Per Cubic Metre	9828.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	65.34	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	319617.00
4	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709.1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	30	391.20	Rupees Three hundred ninety one and paise twenty only	Each	11736.00
					Total	351212.00
	Rate Quoted by contractor (+/-)					
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division
RPPWD, Thalout

(31)

247

SCHEDULE OF QUANTITY

Name of work:- C/O road from Mani to Shegali Km. 0/0 to 6/0 (SIH:- C/O R/wall at RD 0/697 to 0/707) under SCDP

Estimated Cost:- Rs. 455631.00
 Earnest Money :- Rs. 9200.00
 Time :- One Month

Sr. No	Description of item	Qty	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	55.85	398.20	Rupees Three hundred ninety eight and paise twenty only	Per Cubic Metre	22239.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802, 803, 1202 and 1203 plain cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	7.98	4400.60	Rs Four thousand four hundred and paise sixty only	Per Cubic Metre	35117.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802, 803, 1202 and 1203 plain cement concrete 1:4:8 (one cement four Sand: eight: graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	4.70	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	22991.00
4	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 random rubble masonry in cement mortar 1:6 (one cement six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge	37.90	5197.20	Rupees Five thousand one hundred ninety seven and paise twenty only	Per Cubic Metre	196974.00
5	Construction of Random Rubble dry stone masonry as per MORD specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	42.28	3751.20	Rupees Three thousand seven hundred fifty one and paise twenty only	Per Cubic Metre	158601.00
6	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3 & 6 and as per the entire satisfaction and direction of Engineer-in-Charge.	15.60	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	19709.00
Total						455631.00
Rate Quoted by contractor (+/-)						
Quoted rate in figures						
Quoted rate in words						

Executive Engineer,
 Balout Division,
 P.P.W.D. Thalour,
 [Signature]

322

SCHEDULE OF QUANTITY

Name of work:- RRD on Lambathach, Shillibagi, Kalhani Pandoh road Km. 36/0 to 62/0 (SH:- C/O R/wall at RD 49/555 to 49/562)

Estimated Cost:- Rs. 191247.00
Earnest Money :- Rs. 4000.00
Time :- One Month

Sr. No.	Description of item	Qty's.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	18.69	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	7442.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 plain cement concrete 1:6:12 (one cement: six sand: twelve graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	3.43	4400.60	Rs. Four thousand four hundred and paise sixty only	Per Cubic Metre	15094.00
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702.704, 1202 & 1204 random rubble masonry in cement mortar 1:6 (one cement : six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	16.05	5197.20	Rupees Five thousand one hundred ninety seven and paise twenty only.	Per cubic metre	83415.00
4	Construction of Random Rubble dry stone masonry as per MORD specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	19.14	3751.20	Rupees Three thousand seven hundred fifty one and paise twenty only	Per Cubic Metre	71798.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	5.11	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	6456.00
6	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	18	391.20	Rupees Three hundred ninety one and paise twenty only	Each	7042.00
Rate Quoted by contractor (+/-)					Total	191247.00
Quoted rate in figures						
Quoted rate in words						

Executive Engineer,
Thalout Division,
RPPWD, Thalout

SCHEDULE OF QUANTITY

Name of work:- RRD on Sudhrani to Thatta road Km. 0/0 to 5/500 (SH:- C/O R/wall at RD 4/215 to 4/217.50)

Estimated Cost:- Rs. **130055.00**
 Earnest Money :- Rs. **2000.00**

Time :- One Month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	8.40	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	3345.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	11.69	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	57183.00
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 random rubble masonry in cement mortar 1:6 (one cement : six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	7.16	5197.20	Rupees Five thousand one hundred ninety seven and paise twenty only.	Per cubic metre	37212.00
4	Construction of Randum Rubble dry stone masonry as per MORD specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	5.41	3751.20	Rupees Three thousand seven hundred fifty one and paise twenty only	Per Cubic Metre	20294.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.5 and as per the entire satisfaction and direction of Engineer-in-Charge.	5.18	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	6544.00
6	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical is to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	14	391.20	Rupees Three hundred ninety one and paise twenty only	Each	5477.00
	Rate Quoted by contractor (+/-)				Total	130055.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
 Talout Division,
 MPWD, Talout

24

SCHEDULE OF QUANTITY

Name of work:- RRD on Bali Thachhi road Km. 0/0 to 25/0 (SH:- Construction of RCC Hume pipe culvert at RD 14/840)									
Estimated Cost:- Rs. 484780.00									
Earnest Money :- Rs. 9700.00									
Time :- One Month									
Sr. No.	Description of item	Quantity	Rate		Unit	Amount			
			In figure	In word					
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means over areas (exceeding 30 cm in depth, 1.50 metre in width as well as 10 sqm. on plan) including getting out and disposal of excavated earth lead up to 50 metre and lift up to 1.50 metre including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	13.98	140.20	Rupees One hundred forty and paise twenty only.	Per Cubic Metre	1960.00			
2	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	72.29	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	28786.00			
3	Providing and laying in position cement concrete 1:6:12 (one cement: six sand :twelve graded stone aggregate) bedding of specified grade including shuttering complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	3.42	4400.60	Rupees Four thousand four hundred and paise sixty only	Per Cubic Metre	15050.00			
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802.803, 1202 and 1203 in cement concrete 1:3:6 (one cement: three sand : six graded stone aggregate 20mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	66.14	5771.80	Rupees Five thousand seven hundred seventy one and paise eighty only.	Per Cubic Metre	381747.00			
5	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	7.50	3622.80	Rupees Three thousand six hundred twenty two and paise eighty only	Per running metre	27171.00			
6	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303 complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	0.49	2599.05	Rupees Two thousand five hundred ninety nine and paise zero five only	Per Cubic Metre	1274.00			
7	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	13.50	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	17056.00			

(34)

8	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	30	391.20	Rupees Three hundred ninety one and paise twenty only	Each	11736.00
					Total	484780.00
	Rate Quoted by contractor (+/-)					
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division
FPWD, Thalout

35

244

SCHEDULE OF QUANTITY

Name of work:- RRD on Bail Thachl road Km. 0/0 to 25/0 (SH:- C/O R/wall at RD 16/604.50 to 16/609)

Estimated Cost:- Rs.	330038.00
Earnest Money :- Rs.	6600.00
Time :- One Month	

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.50 metre in width as well as 10 sqm. on plan) including getting out and disposal of excavated earth lead up to 50 metre and lift up to 1.50 metre including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	10.80	140.20	Rupees One hundred forty and paise twenty only.	Per Cubic Metre	1514.00
2	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	7.20	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	2867.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	13.55	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	66281.00
4	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 random rubble masonry in cement mortar 1:6 (one cement : six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	27.72	5197.20	Rupees Five thousand one hundred ninety seven and paise twenty only.	Per cubic metre	144066.00
5	Construction of Random Rubble dry stone masonry as per MORO specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	25.95	3751.20	Rupees Three thousand seven hundred fifty one and paise twenty only	Per Cubic Metre	97344.00
6	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	6.17	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	7795.00
7	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical iso twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	26	381.20	Rupees Three hundred ninety one and paise twenty only	Each	10171.00
Total						330038.00
Rate Quoted by contractor (+/-)						
Quoted rate in figures						
Quoted rate in words						

Executive Engineer
Structure Division
P.W.D. Thachl Road

36

SCHEDULE OF QUANTITY

Name of work:- RRD on Lambathach, Shillibagl, Kallant Pandoh road Km. 36/0 to 62/0 (Silt:- C/O R/wall at RD 49/580 to 49/592)

Estimated Cost:- Rs. 453316.00
Earnest Money:- Rs. 9100.00
Time :- One Month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	31.44	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	12519.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 plain cement concrete 1.6:12 (one cement: six sand: twelve graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	8.64	4400.60	Rs Four thousand four hundred and paise sixty only	Per Cubic Metre	38021.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 plain cement concrete 1.4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	5.16	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	25241.00
4	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702.704.1202 & 1204 random rubble masonry in cement mortar 1:6 (one cement : six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	37.56	5197.20	Rupees Five thousand one hundred ninety seven and paise twenty only.	Per cubic metre	195207.00
5	Construction of Random Rubble dry stone masonry as per MORD specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	37.13	3751.20	Rupees Three thousand seven hundred fifty one and paise twenty only	Per Cubic Metre	139282.00
6	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	26.64	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	33657.00
7	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical is to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709.1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	24	391.20	Rupees Three hundred ninety one and paise twenty only	Each	9389.00
Rate Quoted by contractor (+/-)					Total	453316.00
Quoted rate in figures						
Quoted rate in words						

Executive Engineer,
Tiraput Division,
HPWD, Thalouga

27

243

SCHEDULE OF QUANTITY

Name of work:- RRD on Bali Thachi road Km. 0/0 to 25/0 (SH:- C/O R/wall at RD 16/600 to 16/604.50)

Estimated Cost:- Rs. 329768.00
 Earnest Money:- Rs. 6600.00
 Time :- One Month

Sr. No.	Description of item	Oys	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation by mechanical means (Hydraulic excavator) (manual means over areas (exceeding 30 cm in depth, 1.50 metre in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead up to 50 metre and lift up to 1.50 metre including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	11.93	140.20	Rupees One hundred forty and paise twenty only	Per Cubic Metre	1673.00
2	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in benches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	7.20	352.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	2557.00
3	Providing and laying concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 plain cement concrete 1:4:8 (one cement four Sand, eight graded stone aggregate forty millimetre nominal size) including form work, and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	13.55	4291.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	55231.35
4	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702.704, 1202 & 1204 random rubble masonry in cement mortar 1:6 (one cement : six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	27.72	5197.20	Rupees Five thousand one hundred ninety seven and paise twenty only.	Per Cubic Metre	144055.00
5	Construction of Random Rubble dry stone masonry as per MORD specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	25.95	3751.20	Rupees Three thousand seven hundred fifty one and paise twenty only	Per Cubic Metre	97344.00
6	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	5.83	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	7366.00
7	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	26	391.20	Rupees Three hundred ninety one and paise twenty only	Each	10171.00
Total						329768.00

Rate Quoted by contractor (+/-)

Quoted rate in figures

Quoted rate in words

Executive Engineer,
 Tbalout Division,
 HEPWD, Thalout, Dist

38

SCHEDULE OF QUANTITY

Name of work:- RRD on Nouna to Sudhrani road Km. 0/0 to 14/0 (Sit:- C/O R/wall at RD 11/680 to 11/689.50)

Estimated Cost:- Rs. 458512.00

Earnest Money :- Rs. 9200.00

Time :- One Month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means over areas (exceeding 30 cm in depth, 1.50 metre in width as well as 10 sqm. on plan) including getting out and disposal of excavated earth lead up to 50 metre and lift up to 1.50 metre including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	35.58	140.20	Rupees One hundred forty and paise twenty only.	Per Cubic Metre	4988.00
2	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	10.45	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	4161.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	42.56	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	208186.00
4	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702.704, 1202 & 1204 random rubble masonry in cement mortar 1:6 (one cement : six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	20.72	5197.20	Rupees Five thousand one hundred ninety seven and paise twenty only.	Per cubic metre	107686.00
5	Construction of Random Rubble dry stone masonry as per MORD specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	27.04	3751.20	Rupees Three thousand seven hundred fifty one and paise twenty only	Per Cubic Metre	101432.00
6	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	12.68	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	16020.00
7	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	41	391.20	Rupees Three hundred ninety one and paise twenty only	Each	16039.00
Rate Quoted by contractor (+/-)					Total	458512.00
Quoted rate in figures						
Quoted rate in words						

Executive Engineer,

Tolait Division

HPPWD, Malout

39

SCHEDULE OF QUANTITY

Name of work:- RRD on Bounchhari to Kandtha road Km. 0/0 to 12/0 (SH:- Construction of RCC Hume pipe culvert at RD 9/180)

Estimated Cost :- Rs. 139862.00
Earnest Money :- Rs. 2800.00

Time :- One Month

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.50 metre in width as well as 10 sqm. on plan) including getting out and disposal of excavated earth lead up to 50 metre and lift up to 1.50 metre including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	5.38	140.20	Rupees One hundred forty and paise twenty only.	Per Cubic Metre	754.00
2	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	40.81	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	16251.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802, 803, 1202 and 1203 in cement concrete 1:3:6 (one cement: three sand : six graded stone aggregate 20mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	4.51	5771.80	Rupees Five thousand seven hundred seventy one and paise eighty only.	Per Cubic Metre	26031.00
4	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 coursed rubble masonry in cement mortar 1:5 (One cement : five sand) complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	11.32	6153.30	Rupees Six thousand one hundred fifty three and paise thirty only.	Per cubic metre	69655.00
7	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	7.50	3622.80	Rupees Three thousand six hundred twenty two and paise eighty only	Per running metre	27171.00
Rate Quoted by contractor (+/-)					Total	139862.00
Quoted rate In figures						
Quoted rate in words						

Executive Engineer,
Tolout Division
HPWD, Thalout

40

SCHEDULE OF QUANTITY

Name of work:- RRD on Ball Thachhi road Km. 0/0 to 25/0 (SH:- C/O R/wall in wire crate at RD 14/990 to 15/006.80)

Estimated Cost :- Rs.	332491.00
Earnest Money :- Rs.	6600.00
Time :- One Month	

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	20.83	398.20	Rs. Three hundred ninety eight and paise twenty only.	Per Cubic Metre	8295.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate 40mm (forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	19.53	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	95533.00
3	Providing and laying of Boulder upon laid in wire crates with 4 mm (Four millimetre) dia G.I. wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm (one hundred fifty millimetre x one hundred fifty millimetre) mesh (woven) diagonally) including 10 (Ten) percent extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	72.58	2769.40	Rs. Two thousand seven hundred sixty nine and paise forty only	Per Cubic Metre	201003.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	16.63	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	21010.00
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709.1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	17	391.20	Rupees Three hundred ninety one and paise twenty only	Each	6550.00
Rate Quoted by contractor (+/-)					Total	332491.00
Quoted rate in figures						
Quoted rate in words						

Executive Engineer,
Tolour Division
R.P.W.D. Thakour

617

SCHEDULE OF QUANTITY

Name of work:- RRD on Nagwain to Balu road km 0/00 to 12/500 (SH:- C/O R/Wall at RD 6/308 to 6/320)

Estimated Cost:- 3,12,535.00
Earnest Money :- 6500.00

Time :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dty. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal up to a lead of 50 metre (fifty meter) dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge	44.76	140.20	Rs. One hundred forty and paise twenty only	Per Cubic Metre	6275.00
2	Providing and laying concrete for plain/reinforced concrete in 1:6:12 (one cement: six sand: Twelve crushed / stone aggregate) 40 mm (forty millimetre) nominal size open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	5.88	4400.60	Rs. four thousand four hundred and paise Sixty only	Per Cubic Metre	25676.00
3	Stone masonry work in Random Rubble masonry in cement mortar 1:6 (one cement: 6 sand) in foundation complete as per drawing and technical specifications Clause 702, 704, 1202 and 1203 including all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	22.44	5197.20	Rs. Five thousand one hundred ninety seven and paise twenty only	Per Cubic Metre	116625.00
4	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub stuctur and super structure complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer in-Charge.	35.64	3721.20	Rs. Three thousand Seven hundred twenty one and paise twenty only	Per Cubic Metre	132624.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	13.68	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	17283.00
6	Providing and laying concrete for plain in open foundations complete as per drawing and technical specification Clause 802.803, 1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm nominal size) and curing complete including shuttering and carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge. (For parapets)	2.40	5771.80	Rs. Five thousand seven hundred seventy one and paise eighty only	Per Cubic Metre	13852.00
Total in figures						312535.00
Quoted rate in figure				Percent		
Quoted rate in words						

Executive Engineer,
Thalout Division,
HP, PWD, Thalout

42

SCHEDULE OF QUANTITY

Name of work:- RRD on Bhurath to Panjath road Km. 0/0 to 11/0 (SH:- C/O II/wall at RD 1/430 to 1/500 and R/wall at RD 1/650 to 1/670)

Estimated Cost :- Rs. 433619.00
 Earnest Money :- Rs. 8700.00
 Time :- One Month

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means over areas (exceeding 30 cm in depth, 1.50 metre in width as well as 10 sqm. on plan) including getting out and disposal of excavated earth lead up to 50 metre and lift up to 1.50 metre including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	56.40	140.20	Rupees One hundred forty and paise twenty only.	Per Cubic Metre	7907.00
2	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	22.20	398.20	Rs. Three hundred ninety eight and paise twenty only.	Per Cubic Metre	8840.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate 40mm (forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	47.00	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	229905.00
4	Providing and laying of Boulder upron laid in wire crates with 4 mm (Four millimetre) dia G.I.wire conforming to IS : 280 and IS-4826 in 150 mm x 150 mm (one hundred fifty millimetre x one hundred fifty millimetre) mesh (woven) diagonally) including 10 (Ten) percent extra for laps and joints laid with stones boulders weighting not less than 25 kg. (Twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	55.30	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	171319.00
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204,3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	40	391.20	Rupees Three hundred ninety one and paise twenty only	Each	15648.00
Rate Quoted by contractor (+/-)					Total	433619.00
Quoted rate in figures						
Quoted rate in words						

Executive Engineer,
 Talacut Division,
 PWD, Talacut

(43)

SCHEDULE OF QUANTITY

Name of work:- RRD on Thalout Panjain Trachi Shetadhar Chet Chinni Lambathach road Km. 0/0 to 75/0 (SH:- C/O B/wall at RD 3/925 to 3/940 and R/wall at RD 3/915 to 3/935)

Estimated Cost :- Rs. 499408.00

Earnest Money :- Rs. 10000.00

Time :- One Month

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means over areas (exceeding 30 cm in depth, 1.50 metre in width as well as 10 sqm. on plan) including getting out and disposal of excavated earth lead up to 50 metre and lift up to 1.50 metre including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	24.00	140.20	Rupees One hundred forty and paise twenty only.	Per Cubic Metre	3365.00
2	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	37.50	398.20	Rs. Three hundred ninety eight and paise twenty only.	Per Cubic Metre	14933.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 plain cement concrete 1:4:8 (one cement four Sand: eight graded stone aggregate 40mm (forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	63.57	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	310959.00
4	Providing and laying of Boulder upon laid in wire crates with 4 mm (Four millimetre) dia G.I.wire conforming to IS : 280 and IS-4826 in 150 mm x 150 mm (one hundred fifty millimetre x one hundred fifty millimetre) mesh (woven) diagonally) including 10 (Ten) percent extra for laps and joints laid with stones boulders weighing not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	51.84	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	160600.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	7.56	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	9551.00
	Rate Quoted by contractor (+/-)				Total	499408.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
BPPWD, Thalout

44

SCHEDULE OF QUANTITY

Name of work:- RRD on Thalout Panjain Thuchi Shetadhar Chet Chulul Lambathach road Km. 0/0 to 75/0 (SIII:- C/O R/wall at RD 11/038 to 11/050)

Estimated Cost :- Rs. 334169.00
Earnest Money :- Rs. 6700.00

Time :- One Month

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shorting and bracing, removal of stumps and other deleterious material and disposal upto all lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	15.72	398.20	Rs. Three hundred ninety eight and paise twenty only.	Per Cubic Metre	6260.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate 40mm (forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	41.04	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	200751.00
3	Providing and laying of Boulder upon laid in wire crates with 4 mm (Four millimetre) dia G.I.wire) conforming to IS : 280 and IS-4826 in 150 mm x 150 mm (one hundred fifty millimetre x one hundred fifty millimetre) mesh (woven) diagonally) including 10 (Ten) percent extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	31.10	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	96348.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204,3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	9	391.20	Rupees Three hundred ninety one and paise twenty only	Each	3521.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	21.60	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	27289.00
					Total	334169.00
	Rate Quoted by contractor (+/-)					
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HPPWD, Thalout

SCHEDULE OF QUANTITY

Name of work: **RRD on Bakhtali to Kholanai road Km. 0/0 to 10/0 (SH- C/0 R/wall at RD 1/735 to 1/744)**

Estimated Cost:- Rs. **482510.00**

Fareest Money :- Rs. **19000.00**

Time :- One Month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	25.56	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	10178.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand, eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	24.24	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	118572.00
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702.704, 1202 & 1204 random rubble masonry in cement mortar 1:6 (one cement : six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	35.92	5197.20	Rupees Five thousand one hundred ninety seven and paise twenty only.	Per cubic metre	186683.00
4	Construction of Random Rubble dry stone masonry as per MORD specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	36.24	3751.20	Rupees Three thousand seven hundred fifty one and paise twenty only	Per Cubic Metre	135943.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	10.40	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	13139.00
6	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	46	391.20	Rupees Three hundred ninety one and paise twenty only	Each	17995.00
Rate Quoted by contractor (+/-)					Total	482510.00
Quoted rate in figures						
Quoted rate in words						

Executive Engineer,

Thalout Division,

HPPWD, Talou,

26

SCHEDULE OF QUANTITY

Name of work:- Repair and maintenance of Pandoh Dam to Rest House Pandoh road Km. 0/0 to 1/200 to connect the NH-03 (SH :- Providing and laying 50mm thick BM and tack coat in Km 0/200 to 0/400).

Estimated Cost:- 495630.00
Earnest Money :- 10000.00
Time :- One Month

Sr.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Providing and laying bituminous macadam using crushed stone aggregates of specified grading premixed with bituminous binder, transported to site by bippers, laid over a previously prepared surface with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge 50 to 100 mm (Fifty to one hundred millimetre) average compacted thickness with bitumen of grade VG-30 @ 3.50% (At the rate of three point five zero percent) (percentage by weight of total mix) prepared in Batch Type Hot Mix Plant of 100-120 TPH capacity including cartage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	32.02	14391.60	Rs Fourteen thousand three hundred ninety one and paise sixty only	Per Cubic Metre	460819.00
2	Providing and applying tack coat using hot straight run bitumen of grade VG - 10, including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications on bituminous surface @ 0.50 Kg / sqm (At the rate of zero point five zero kilogram per square metre) including cartage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	640.50	54.35	Rs Fifty four and paise thirty five only	Per Cubic Metre	34811.00
		Total in figures				495630.00
		Rate quoted by contractor +/-		Percent		
		Quoted rate in figure				
		Quoted rate in words				

Executive Engineer,
Dakout Division,
P.W.D. Talicut

47

Name of work: RRD on Pakhal to Kholanar road Km. 0/0 to 10/0 (SIH: C/O R/wall at RD 0/355 to 0/365)

SCHEDULE OF QUANTITY

Sr. No.	Description of item	Qty's	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	22.25	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	8860.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	20.79	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	101696.00
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702.704, 1202 & 1204 random rubble masonry in cement mortar 1:5 (one cement : six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	31.30	5197.20	Rupees Five thousand one hundred ninety seven and paise twenty only.	Per cubic metre	162672.00
4	Construction of Random Rubble dry stone masonry as per MORD specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	30.94	3751.20	Rupees Three thousand seven hundred fifty one and paise twenty only	Per Cubic Metre	116062.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	10.80	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	13645.00
6	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	40	391.20	Rupees Three hundred ninety one and paise twenty only	Each	15648.00
Rate Quoted by contractor (+/-)					Total	418583.00
Quoted rate in figures						
Quoted rate in words						

Executive Engineer,
Thalput Division
PPWD, Thalput

SCHEDULE OF QUANTITY

Name of work:- RRD on Thalout to Kalliani road Km. 0/0 to 10/0 (SH:- C/O R/wall at RD 3/360 to 3/376.80)

Estimated Cost :- Rs. 388616.00

Earnest Money :- Rs. 7800.00

Time :- One Month

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	40.32	398.20	Rs. Three hundred ninety eight and paise twenty only.	Per Cubic Metre	16055.00
2	Providing and laying of Boulder upon laid in wire crates with 4 mm (Four millimetre) dia G.I. wire conforming to IS : 280 and IS-4826 in 150 mm x 150 mm (one hundred fifty millimetre x one hundred fifty millimetre) mesh (woven) diagonally) including 10 (Ten) percent extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	120.96	2769.40	Rs. Two thousand seven hundred sixty nine and paise forty only	Per Cubic Metre	334987.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	29.74	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	37574.00
					Total	388616.00
	Rate Quoted by contractor (+/-)					
	Quoted rate in figures					
	Quoted rate in words					


 Executive Engineer,
 Thalout Division
 HPRWD, Thalout

Estimated Cost:-	Rs.	499942.00
------------------	-----	-----------

499942.00
100000.00

Executive Engineer,
Thalout Division,
HPPWD, Thalout

56

SCHEDULE OF QUANTITY

Name of work:- RRD on Thalout to Kallhani road Km. 0/0 to 10/0 (SH:-C/O R/wall at RD 0/355 to 0/370)

Estimated Cost :- Rs. 498368.00

Earnest Money :- Rs. 10000.00

Time :- One Month

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	29.85	398.20	Rs. Three hundred ninety eight and paise twenty only.	Per Cubic Metre	11886.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate 40mm (forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	72.90	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	356598.00
3	Providing and laying of Boulder upon laid in wire crates with 4 mm (Four millimetre) dia G.I. wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm (one hundred fifty millimetre x one hundred fifty millimetre) mesh (woven) diagonally) including 10 (Ten) percent extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	27.65	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	85660.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	44	391.20	Rupees Three hundred ninety one and paise twenty only	Each	17213.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	21.38	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	27011.00
	Rate Quoted by contractor (+/-)				Total	498368.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
H.P.W.D. Thalout.

(51)

SCHEDULE OF QUANTITY

Name of work:- Repair and maintenance of Pandoh Dam to Rest House Pandoh road Km. 0/0 to 1/200 to connect the NH-03 (SH :- Providing and laying 50mm thick BM and tack coat in Km 0/600 to 0/800).

Estimated Cost:- 495630.00
 Earnest Money :- 10000.00
 Time :- One Month

Sl.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Providing and laying bituminous macadam using crushed stone aggregates of specified grading premixed with bituminous binder, transported to site by tippers, laid over a previously prepared surface with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge 50 to 100 mm (Fifty to one hundred millimetre) average compacted thickness with bitumen of grade VG-30 @ 3.50% (At the rate of three point five zero percent) (percentage by weight of total mix) prepared in Batch Type Hot Mix Plant of 100-120 TPH capacity including carriage of material with in all loads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	32.02	14391.60	Rs. Fourteen thousand three hundred ninety one and paise sixty only	Per Cubic Metre	460819.00
2	Providing and applying tack coat using hot straight run bitumen of grade VG - 10, including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications on bituminous surface @ 0.50 Kg / sqm (At the rate of zero point five zero kilogram per square metre) including carriage of material with in all loads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	640.50	54.35	Rs. Fifty four and paise thirty five only	Per Cubic Metre	34811.00
		Total in figures				495630.00
		Rate quoted by contractor +/-		Percent		
		Quoted rate in figures				
		Quoted rate in words				

Executive Engineer,
 Thalout Division,
 AP PWD, Thalout.

SCHEDULE OF QUANTITY

Name of work: RRD on Chhakhidhar to Dobha road via Mallic Km. 0/0 to 5/0 (SII: C/O R/wall at RD 1/031.80 to 1/037.80)

Estimated Cost:- Rs. 493325.00
Earnest Money :- Rs. 10000.00

Time :- One Month

Sr No.	Description of item	Qyts.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	38.88	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	15482.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	91.62	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	448168.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	12.96	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	16374.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709.1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	34	391.20	Rupees Three hundred ninety one and paise twenty only	Each	13301.00
	Rate Quoted by contractor (+/-)				Total	493325.00
	Quoted rate in figures					
	Quoted rate in words					


 Executive Engineer,
 Thalout Division,
 HPPWD, Thalout.

53

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Thalout to Kalhani road up to Dhunju km. 0/0 to 10/0 (SH:- Removal of slips at various RDs. in km. 5/0 to 10/00)

Estimated Cost:- 498561.00
Earnest Money:- 10000.00
Time:- One Month

S.No.	Description of item	Qty.	Figure	Rate in Words	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any leads and lifts as per technical specification 302.3.5 and 1611 including carriage of material and other incidentals in all leads and lifts and as per the direction of the Engineer-in Charge.	3985.30	125.10	Rs. One hundred twenty five and paise ten only	Per cubic metre	498561.00
	Total in figures					498561.00
	Rate quoted by contractor +/-		Percent			
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division (B&R).
HP PWD Thalout

54

SCHEDULE OF QUANTITY

Name of work:- Repair and maintenance of Pandoh Dam to Rest House Pandoh road Km. 0/0 to 1/200 to connect the NH-03 (SH :- Providing and laying 50mm thick BM and tack coat in Km 0/400 to 0/600).

Estimated Cost:- 495630.00
Earnest Money :- 10000.00
Time :- One Month

Sr.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Providing and laying bituminous macadam using crushed stone aggregates of specified grading premixed with bituminous binder, transported to site by tippers, laid over a previously prepared surface with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge 50 to 100 mm (Fifty to one hundred millimetre) average compacted thickness with bitumen of grade VG-30 @ 3.50% (At the rate of three point five zero percent) (percentage by weight of total mix) prepared in Batch Type Hot Mix Plant of 100-120 TPH capacity including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	32.02	14391.60	Rs. Forteen thousand three hundred ninety one and paise sixty only	Per Cubic Metre	460819.00
2	Providing and applying tack coat using hot straight run bitumen of grade VG - 10, including heating the bitumen, spraying the bitumen with mechanically operated spray unit filled on bitumen boiler, cleaning and preparing the existing road surface as per specifications on bituminous surface @ 0.50 Kg / sqm (At the rate of zero point five zero kilogram per square metre) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	640.50	54.35	Rs. Fifty four and paise thirty five only	Per Cubic Metre	34811.00
Total in figures						495630.00
Rate quoted by contractor +/-						
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
Talout Division,
FP PWD, Talout