



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Tel.01899-299219.

eepwd-chowari@hp.gov.in

No. PWD-CHW/Tender /2023-24-

To

8344-46

Dated:- 31/10/23

**The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2**

Subject: - Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.

**Executive Engineer,
Chowari Division,
HPPWD, Chowari.**

Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

**Executive Engineer,
Chowari Division,
HPPWD, Chowari.**

Certificate

Certified that the tenders called vide this office letter No. PWD-CHW/Tender /2023-24-~~8444-16~~ dated. ~~31-10-23~~ is emergent nature and in Public interest.

Executive Engineer,
Chowari Division,
HPPWD, Chowari.



Tel.01899-299219.
cepwd-chowari@hp.gov.in

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed percentage/item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Chowari Division, HPPWD, Chowari on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

- 1 Date of receipt of application for the tender
Form a/w requisite documents: -
- 2 Date of issued/sale of tender form against
Cash payment (non refundable).

07/11/2023

08/11/2023

The tender shall be received upto 11.00 AM on 09/11/2023 and will be opened on the same day at 12.00 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on 09/11/2023.

The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Chowari Division, HPPWD, Chowari must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1	Restoration of rain damage on Shahpur Sihunta Chowari road Km 40/0 to 76/00 (SH:- C/o R/wall at Rd 49/975 to 49/984).	491599/-	9900/-	Rs. 350/-	Three Month	Class-D & C
2	Restoration of rain damage on Chowari to Kainthly road Km 0/0 to 12/570 (SH:- C/o (HP Culvert at Rd 2/090 to alongwith wing wall).	486133/-	9725/-	Rs. 350/-	Three Month	Class-D & C
3	Restoration of rain damage on Shahpur Sihunta Chowari road Km 48/00 to 53/00 (SH:- Hiring of excavator cum loader for removal of slips).	493200/-	9865/-	Rs. 350/-	Three Month	Class-D & C
4	Restoration of rain damage on Shahpur Sihunta Chowari Jot road Km 54/200 to 73/00 (SH:- Hiring of excavator cum loader and Tipper for carriage of material).	491100/-	9822/-	Rs. 350/-	Three Month	Class-D & C
5	Restoration of rain damage on various roads under Sihunta Sub Division (SH:- Hiring of excavator cum loader for removal of slips).	299250/-	6000/-	Rs. 350/-	Three Month	Class-D & C
6	Restoration of rain damage on Balana to Balli road (SH:-C/o R/wall in wire crate at Rd 2/820 to 2/849.60).	496483/-	9920/-	Rs. 350/-	Three Month	Class-D & C
7	Protection work for Govt. Senior Secondary School at Sahla (SH:- C/o B/wall at Rd 0/0 to 0/015).	248486/-	5000/-	Rs. 350/-	Three Month	Class-D & C
8	A/R & M/O various roads under Sihunta Sub Division (SH:- Painting and lettering).	183822/-	3660/-	Rs. 350/-	Three Month	Class-D & C
9	Restoration of rain damage on Shahpur Sihunta Chowari road Km 40/00 to 76/00 (SH:- Pustha for R/wall at Rd 51/820 to 51/830).	490903/-	9900/-	Rs. 350/-	Three Month	Class-D & C
10	Restoration of rain damage on Shahpur Sihunta Chowari road Km 40/00 to 76/00 (SH:- Pustha for R/wall at Rd 51/800 to 51/810).	495519/-	10000/-	Rs. 350/-	Three Month	Class-D & C

11	Restoration of rain damage on Shahpur Sihunta Chowari road Km 53/00 to 76/00 (SH:- Hiring of Pocklain for removal of slips/Debris/boulder etc).	498825/-	10000/-	Rs. 350/-	Three Month	Class-D & C
12	Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti road Km 18/00 to 25/00 (Sh:- Hiring of excavator cum loader and Tipper for shifting of material).	495300/-	10000/-	Rs. 350/-	Three Month	Class-D & C
13	Restoration of rain damage Shahpur Sihunta Chowari road Km 42/00 to 44/00 (SH:- Hiring of excavator cum loader and Tipper for shifting of material	492150/-	9800/-	Rs. 350/-	Three Month	Class-D & C
14	Restoration of rain damage on various road under Sihunta Sub Division HPPWD, Sihunta (SH:- Hiring of Pocklain for removal of slips /Debris/boulder etc.	498825/-	10000/-	Rs. 350/-	Three Month	Class-D & C
15	Restoration of rain damage on various road under Sihunta Sub Division (SH:- Hiring of excavator cum loader for removal of slip).	498750/-	10000/-	Rs. 350/-	Three Month	Class-D & C
16	Restoration of rain damage on various road under Sihunta Sub Division (SH:- Hiring of excavator cum loader for removal of slips).	497700/-	9800/-	Rs. 350/-	Three Month	Class-D & C

- 1 The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
- 2 The Contractor should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.
- 3 GST No/Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
- 4 Application without all documents will not be entertained.
- 5 Proxy application will not be entertained.

Executive Engineer,
Chowari Division,
HPPWD, Chowari.

Dated:- 31-10-2023

No. PWD-CHW/Tender /2023-24-

8347-97

Copy forwarded to the following for information and necessary action please:-

- 1 Engineer-in-Chief, HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 The BDO Bhattiyat.
- 7 Sub Divisional Magistrate/B.D.O/Tehsildar Chowari.
- 8 Notice Board of this office.


Executive Engineer,
Chowari Division,
HPPWD, Chowari.

Schedule of Quantity

Name of work:- Restoration of Rain Damage on Shahpur Silhunta Chowari Jot Chamba Road km 40/0 to 76/00 (SH:- C/o R/wall at RD 49/975 to 49/984)

Estimated Cost	Rs.491559/-
Earnest Money	Rs.9831/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	39.90			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	93.60			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (IV); 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614,709,1204.3.7 as per the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	28.00			Each	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	19.31			Per cubic metre	
Total						


Executive Engineer
 Chowari Division
 Hpqwd Chowari

Schedule of Quantity

Estimated Cost	Rs.486133/-
Earnest Money	Rs. 9723/-
Time Limit	Three months

NAME OF WORK:- Restoration of rain damage on Chowari to Kainthly Road km 0/0 to 12/570 (SIH:- C/o H.P. Culvert at RD 2/090 along with wing walls)

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt	49.99			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:3:6) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt	2.20			Per cubic metre	
3	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2:5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt	0.38			Per cubic metre	
4	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2:4) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt	0.37			Per cubic metre	
5	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2:5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt	19.56			Per cubic metre	
6	Providing and laying (to level or slope) 900mm dia (Nine thousand millimeters) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete or first class bedding and masonry work in head walls and parapets as per drawing and MORD technical specifications section 11080, including hauling of materials in all leads and lifts and other incidental. The rate including Octroi, Royalty, Malkana, Toll Tax, Sale Tax, GST and other taxes imposed by the Government	2.50			Per running metre	
7	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt	58.80			Per cubic metre	

8	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V) : 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614,709,1204.3.7 as per the directions of the Engineer-in-charge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt	24			Each	
9	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	12.45			Per cubic metre	


 Executive Engineer,
 Chowari Division,
 H.P.D. Chowari

(3)

Schedule of Quantity

Name of work:- Restoration of rain damages on Shahpur Sihunta Chowari Jot Chamba Road km 48/0 to 53/0 (SH:-Hiring of Excavator cum loader and Tipper)

Estimate Cost :- Rs.	493200/-
Earnest Money	9864/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	372.00			Per hour	
2	Hiring of Tipper having capacity 5.5 (five decimal five zero) cubic meter for carriage of all type of material upto any leads and lifts as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also are borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	200.00			Per hour	

Executive Engineer
Chowari Division
HPWD, Chowari

4

Schedule of Quantity

Name of work:- Restoration of rain damages on Shahpur Sihunta Chowari Jot Chamba Road km 54/200 to 73/0 (SH:-Hiring of Excavator cum loader and Tipper)

Estimate Cost :- Rs.	491100/-
Earnest Money	9822/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	370.00			Per hour	
2	Hiring of Tipper having capacity 5.5 (five decimal five zero) cubic meter for carriage of all type of material upto any leads and lifts as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also are borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	200.00			Per hour	

Executive Engineer
Chowari Division
HPWD, Chowari

5

Schedule of Quantity

Name of work:- Restoration of rain damages on Various Roads under Sihunta Sub-Division (SH:- Hiring of Excavator cum loader for removal of slips)

Estimate Cost :- Rs.	299250/-
Earnest Money	5985/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	285.00			Per hour	

Executive Engineer
 Chowari Division
 HPBVD, Chowari


6

Schedule of Quantity

Name of work:- Restoration of Rain Damage on Balana to Balli Road (SH:- C/o R/wall in wire crate at RD 2/820 to 2/849.60)

Estimated Cost	Rs.496483/-
Earnest Money	Rs.9930/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	65.42			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 40kg (Fortykilogram) each as per drawing and technical specification Clause 1301 and as per directions of including the octroi, royalty Malkana, Toll tax Sales tax, GST or any taxes imposed by the Govt.	170.50			Per cubic metre	
3	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	20.72			Per cubic metre	
Total						


Executive Engineer
Chowari Division
Hppyd Chowari

(7)

Schedule of Quantity

Name of work:- Protection work for Govt. SSS Shalla (under RMISA) (SIH:- C/o B/wall at RD 0/0 to 0/015)

Estimated Cost	Rs. 248468
Earnest Money	Rs. 6970/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	22.93			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	45.30			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V); 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-in-charge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	18.00			Each	
Total						

Executive Engineer
Chowari Division
HPWD Chowari

Schedule of Quantity

Name of work:- A/R & M/O to various roads under Sihunta Sub-Division (Sub head:- Painting and lettering)

Estimate Cost :- Rs.	183822
Earnest Money	3680/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Remolding old paint from steel and other metal surface even with paint removal of approved brand and manufacture including carriage of material with all leads and lifts and as per direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental .The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	160.00			Per square metre	
2	Painting one coat excluding priming coat on previously painted steel and other metal surface of all dirt ,dust and other matter with ready mixed paint including carriage of material with all leads ,lifts and as per direction of Engineer-in-Charge. The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	160.00			Per square metre	
3	Painting one coat excluding priming coat on previously painted concrete/ masonry /plastered surface with enamel paint of approved brand and manufacture for use on floors to give an even shade including cleaning of all dirt dust and other foreign matter and sand papering as required. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	210.00			Per square metre	
4	Writing letters of figures on any surface with synthetic enamel including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt. mel paint (other than white) stop , comas, hyphens and the like not to be measured and paid separately) block letters ,indian letters,/figures within all leads lifts of within all leads ,lifts of materials and other incidentals.	40250.0			Per centimetre	


Executive Engineer
 Chowari Division
 HPWD, Chowari


(2)

Schedule of Quantity

Name of work:- Restoration of Rain Damage on Shahpur Sihunta Chowari Road km 40/0 to 76/00 (SH:- C/o Pusta for R/wall at RD 51/820 to 51/830)

Estimated Cost	Rs. 490903/-
Earnest Money	Rs. 9818/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	63.35			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	33.60			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V) : 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or any other taxes imposed by the Govt.	60.00			Per cubic metre	
4	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	20.00			Each	
Total						


Executive Engineer
 Chowari Division
 Hppwd Chowari

10

Schedule of Quantity

Name of work:- Restoration of Rain Damage on Shahpur Sihunta Chowari Jot Chamba Road km 40/0 to 76/00 (SH:- C/o Pusta for R/wall at RD 51/800 to 51/810)

Estimated Cost	Rs.495519/-
Earnest Money	Rs.9910/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	55.80			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Normal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	67.20			Per cubic metre	
3	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Normal size 1:4:8) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	28.80			Per cubic metre	
4	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of (1V); 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	19.00			Each	
Total						

Executive Engineer
 Chowari Division
 Hppwd Chowari

Schedule of Quantity

Name of work :- Restoration of rain damages undwer Sihunta Sub-Division (Sub head:- Hiring of Poclain for removal of Slip/Debris/boulder etc)

Estimated Cost	Rs. 498825/-
Earnest Money	Rs. 10000/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of Poclain ofr removal of lips /Debris/Boulder in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be lave to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	135.00			Per Hours	
Total						


Executive Engineer
Chowari Division
Hppmd Chowari

12

Schedule of Quantity

Name of work:- Restoration of rain damages on Nurpur Sanjhi Nallah Lahru Tunuhatti Road km 18/0 to 25/0 (SH:-Hiring of Excavator cum loader and Tipper)

Estimate Cost :- Rs.	495300/-
Earnest Money	9906/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	374.00			Per hour	
2	Hiring of Tipper having capacity 5.5 (five decimal five zero) cubic meter for carriage of all type of material upto any leads and lifts as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also are borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	200.00			Per hour	

Executive Engineer
Chowari Division
HPWD, Chowari

Schedule of Quantity

Name of work:- Restoration of rain damages on Shahpur Sihunta Chowari Jot Chamba Road km 42/0 to 44/0 (SH:-Hiring of Excavator cum loader and Tipper)

Estimate Cost :- Rs. 492150/-
Earnest Money 9843/-
Time Limit Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be laved to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	371.00			Per hour	
2	Hiring of Tipper having capacity 5.5 (five decimal five zero) cubic meter for carriage of all type of material upto any leads and lifts as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be laved to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also are borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	200.00			Per hour	

Executive Engineer
Chowari Division
HPRWD, Chowari

14

Schedule of Quantity

Estimated Cost	Rs. 498825/-
Earnest Money	Rs. 10000/-
Time Limit	Three months

Name of work :- Restoration of rain damages on Shahpur Sihunta Chowari Jot Chamba Road km 53/0 to 76/0 (Sub head:- Hiring of Poclain for removal of Slip/Debris/boulder etc)

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of Poclain of removal of lips /Debris/Boulder in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	135.00			Per Hours	
Total						

Executive Engineer
 Chowari Division
 Hppwd Chowari

(15)

Schedule of Quantity

Name of work:- Restoration of rain damages on Various Roads under Sihunta Sub-Division (SH:-Hiring of Excavator cum loader for removal of slips)

Estimate Cost :- Rs.	498750
Earnest Money	9975/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	475.00			Per hour	

Executive Engineer
 Chowari Division
 HPPWD, Chowari

Schedule of Quantity

Name of work:- Restoration of rain damages on Various Roads under Sihunta Sub-Division (SH:-Hiring of Excavator cum loader for removal of slips)

Estimate Cost :- Rs. 497700/-
 Earnest Money 9954/-
 Time Limit Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be laved to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	474.00			Per hour	

Executive Engineer
Chowari Division
HPWD, Chowari